


UC RIVERSIDE | THE BARN EXPANSION PROJECT | DETAILED PROJECT PROGRAM UPDATE



FERNAU & HARTMAN ARCHITECTS

AUGUST 9, 2012

TABLE OF CONTENTS

I. INTRODUCTION			V. COST PLAN	
Participants	2		Preliminary Budget Estimate	188
Executive Summary	4			
Process	7		VI. IMPLEMENTATION	
Project Goals	9		Project Schedule	240
Barn Area Study: Site Analysis	10		Phasing and Implementation Diagrams	241
II. FUNCTIONAL CONCEPTS			VII. APPENDIX	
Composite Site Organization Plan	14		Campus Supporting Documents	244
Site Diagrams	15		2012 - Meeting Notes, Action Items presented at:	
III. PROGRAM			Workshop #1	248
Project Area Summary	28		Workshop #2	260
Site and Building Adjacency Diagrams	36		Cost Conference Call	268
Comprehensive Space Plans	41		2012 - Correspondence	271
Room Data Sheets and Conceptual Room Layouts			2010 - Participants	304
Cottage	46		2010 - Meeting Notes, Action Items, and/or Site Plan Alternatives presented at:	
The Barn	59		Workshop #1	305
East Courtyard Restrooms	94		Workshop #2	318
Barn Stable	96		KUCR Conference Call	333
Faculty / Staff Dining	107		Workshop #3	334
IV. SUPPORT DOCUMENTS			Performances Issues Conference Call	352
System Narratives	128		DRB Presentation	355
LEED Checklist	158		Workshop #4	358
LEED Matrix	162		2010 - Correspondence	367

I. INTRODUCTION

Program Revisions to the Barn Project Phase 1 & 2 have made it necessary to update the Detailed Project Program (DPP) of May 28, 2010. The update is necessary to incorporate the Faculty / Staff Dining Facility into the project and to remove KUCR. Only those pages and sections that are affected by these program changes are modified or added. This Detailed Project Program Update (DPP Update) document replaces the original report.

Executive Summary outlines: the changes made to the DPP in more detail; the project vision; methodology; site; and scope. *Process* describes the series of workshops that included the many stakeholders' input to arrive at the DPP and the DPP Update. *Project Goals* states the guiding principles and *Site Analysis* describes the key elements of the 2009 Barn Area Study that were reviewed as part of the DPP.

Appreciation is given to all who participated in the development of the 2010 Barn Project Phases 1 & 2 DPP and the 2012 Barn Expansion Project DPP Update.

Participants

UNIVERSITY OF CALIFORNIA, RIVERSIDE - PARTICIPANTS FOR DPP UPDATE 2012

PROJECT MANAGEMENT TEAM

Tim Ralston	Associate Vice Chancellor, Capital and Physical Planning
Jon Harvey	Principal Education Facilities Planner, Capital Resource Management
Richard Racicot	Assistant Vice Chancellor, Design and Construction
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Andy Plumley	Assistant Vice Chancellor, Housing, Dining and Residential Services
Susan L. Marshburn	Executive Director of Housing Services
Yun Baird	Director of Capital Projects
Cheryl Garner	Executive Director of Dining, Conference and Catering Services

STEERING COMMITTEE

Andy Plumley	Assistant Vice Chancellor, Housing, Dining and Residential Services
Susan L. Marshburn	Executive Director of Housing Services
Cheryl Garner	Executive Director, Conference and Catering Services
Professor John Ganim	Academic Senate Physical Resources Planning Committee Representative
David Henry	Director of Residential Dining
Albert Esquada	General Manager for Retail Dining
Catalina Zavala	Graduate Student Association

CAMPUS REPRESENTATIVES

Scott Corrin	Fire Marshal
Weston Lewis	Office of Sustainability
Uma Ramasubramanian	Senior Physical Planner

Note: Participants and Consultant Team Members for the DPP 2010 are found in Section VII. Appendix

Participants

CONSULTING TEAM MEMBERS

ARCHITECT (DPP 2010 and DPP Update 2012)

Fernau & Hartman Architects

2512 Ninth Street No. 2
Berkeley, CA 94710

Richard Fernau	Design Principal
Laura Hartman	Principal in Charge
Laura Boutelle	Project Architect
Jason Wilkinson	Project Manager (2010 only)
Cindy Liu	Junior Designer
Anastasia Yee	Junior Designer (2012 only)
Ryan Metcalf	Junior Designer (2010 only)

CIVIL ENGINEER (DPP 2010)

Sherwood Design Engineers

1 Union Street, Second Floor
San Francisco, CA 94111

John Leys	Principal
Bry Sarte	Principal Engineer

LANDSCAPE ARCHITECT (DPP 2010)

Lutsko Associates

2815 18th Street
San Francisco, CA 94110

Ron Lutsko	Principal
Terri McFarland	Senior Associate

STRUCTURAL ENGINEER (DPP 2010 and DPP Update 2012)

Tipping Mar

1906 Shattuck Ave
Berkeley, CA 94704

David Mar	Principal
-----------	-----------

MECHANICAL / ELECTRICAL / PLUMBING ENGINEER (DPP 2010)

Timmons Design Engineers

901 Market Street, Suite 480
San Francisco, CA 94103

Sean Timmons	Principal
John Rozeluk	Associate Principal

FOOD SERVICE CONSULTANT (DPP 2010 and DPP Update 2012)

Laschober + Sovich Inc.

20301 Ventura Blvd, Suite 338
Woodland Hills, CA 91364

Larry Lanier	President
--------------	-----------

COST ESTIMATOR (DPP 2010 and DPP Update 2012)

Oppenheim Lewis Inc.

2742 17th Street
San Francisco, CA 94110

Scott Lewis	President
-------------	-----------

THEATER CONSULTANT (DPP Update 2012)

The Shalleck Collaborative, Inc.

400 Montgomery St., Ste. 500
San Francisco, CA 94104

Adam Shalleck	Principal
---------------	-----------

ACOUSTICAL AND A/V CONSULTANT (DPP 2010 and DPP Update 2012)

Charles M. Salter Associates, Inc.

130 Sutter Street, Suite 500
San Francisco, CA 94104

Charles M. Salter	President
Thomas A. Schindler	Vice President

GREEN BUILDING CONSULTANT (DPP 2010)

Simon & Associates, Inc.

200 Brannan Street #204
San Francisco, CA 94107

Lynn Simon	President
Marian Keeler	Senior Consultant

BEVERAGE CONSULTANT (DPP Update 2012)

Alcoholic Beverage Consulting Service

26023 Jefferson Street
Murrieta, CA 92562

Mike Brewer	Principal Consultant
-------------	----------------------

Executive Summary

In September of 2011, UCR requested that the Barn Project Phase 1 & 2 DPP of May 28, 2010 be revised to respond to new programmatic changes by developing a concise Detailed Project Program Update (DPP Update) document that replaces the original report. The programmatic changes that UCR requested are as follows:

- Retain the Cottage, Barn Dining & Kitchen Addition, Barn Stable, Barn Theater, and the overall site framework as presented in the DPP.
- Verify and update the Barn Kitchen Addition program to service the Faculty / Staff Dining and the Barn Dining. Remove Bar Program from Barn Dining / Kitchen.
- Remove KUCR from the plan.
- Program a new Faculty / Staff Dining space, including:
 - Determining foodservice and support requirements.
 - Increasing indoor dining capacity to a size that is similar to the former Arroyo Vista Café.
 - Incorporating a Buffet Serving Area.
 - Providing a place for soft seating, and a private dining room.
 - Relocating the Bar to serve the Faculty / Staff Dining (indoor) and the West Courtyard (outdoor) dining spaces.

- Expand program to Provide support of the Bar that includes a secure area that contains an office, dry storage, refrigerator / wine cooler and a walk-in.
- Providing back-of-the-house functions such as Beverage Service (Non Alcoholic), Set Up Area (glasses, utensils, place sets, bussing station), storage (catering, and dining room), and Food Staging Area.
- Incorporating a Green Room (adjacent to the stage), storage, and restrooms.
- Improve West Courtyard to support outdoor events in all kinds of weather, and provide acoustic control that limit disruptions to the surrounding area, including:
 - Incorporating a flexible outdoor area near the Bar that can accommodate approximately 25% of the entertainment area seating capacity.
 - Locating BBQ adjacent to the Bar.
 - Evaluating Stage location based upon proposed program revisions.
 - Retain service access along West Campus Drive as shown in the DPP.
 - Retain all other parts of the DPP to remain as previously presented.

PROJECT VISION

The Barn Expansion Project offers the opportunity to strengthen the connection between the historic roots of the region and the future identity of the UCR campus. The Barn Group has the possibility of becoming a hub of indoor / outdoor activity and diversity that anchors and brands the image of UCR through a respectful integration of old and new. The Barn Expansion Project will:

- Provide a unique dining and entertainment center.
- Enhance awareness of the Campus's agrarian heritage.
- Serve as a gateway / link between the East Campus and the West Campus.
- Integrate indoor and outdoor spaces to support dining and entertainment programs.
- Provide a model of sustainable adaptive reuse that can serve to both instruct and demonstrate principles of sustainability.



Executive Summary

METHODOLOGY

The 2012 Barn Expansion Project DPP Update was realized through two on-site workshops which included the UCR Project Team, Steering Committee, and the design consultant team. This team included: Capital Resource Management, Architects and Engineers, and Housing, Dining & Residential Services. The working sessions included detailed input from Housing, Dining, and Residential Services to define the requirements for the Faculty / Staff Dining Facility.

The 2010 Barn Project Phases 1 & 2 DPP was realized through a series of four on-campus workshops which included the UCR Project Management Team, Steering Committee, and the design consultant team. This team included: Capital Resource Management (formerly the Offices of Capital and Physical Planning), Architects and Engineers (formerly the Office of Design and Construction) and Housing, Dining & Residential Services. The working sessions included detailed input from KUCR, as well as the College of Humanities, Arts, and Social Sciences (CHASS), University Club, and other campus representatives. The preferred alternative was presented and favorably reviewed by the Campus Design Review Board (DRB).

Previous campus planning documents were used as a point of departure. They include:


- 1993 Historical Resources Inventory, The Barn Theater and The Barn Group
- 2002 East Campus Infrastructure Detailed Project Program
- 2005 Long Range Development Plan, Amendment 2
- 2006 East / Southeast Campus Area Study
- 2007 Campus Design Guidelines
- 2008 Campus Aggregate Master Planning Study (CAMPS)
- 2009 Barn Area Study
- 2010 Historic Resources Assessment--The Barn Group and University Cottage

The 2010 Historical Resources Assessment did not encounter any “historical resources” as defined by CEQA within the project area. However, because the buildings are associated with the earliest history of the campus, the buildings should be given special consideration in planning and design. This could include keeping the buildings together as a group and preserving their rustic feel by retaining features that contribute to their historic character.

The program elements were defined and located based on campus and user requirements and standards, as well as design consultant input.

PROJECT SITE

The project is located in the southwest Carillon Mall District near the intersection of West Campus Drive with the Barn Walk and the western terminus of the Eucalyptus Walk.



Executive Summary

PROJECT SCOPE: BARN EXPANSION PROJECT

The Barn Expansion Project will be developed in two phases. Phase 1A will include bringing major utility connections to the site. Phase 1B will include: the renovation of The Barn and construction of the Kitchen Addition; the relocation, renovation, and addition to the Barn Stable; the relocation and renovation of the Cottage; the East Courtyard; the Cottage South Patio; Loading Dock Area and Drive Aisle along West Campus Drive, as well as the construction of the new Faculty / Staff Dining Facility and the West Courtyard, the Campus Walk and minor improvements to the Barn Theater as it interfaces with the Campus Walk. This DPP Update addresses these two phases in detail. A future Phase 2 would complete a Barn Theater Addition and Renovation as identified in the 2009 Barn Area Study. This DPP Update locates and provides design guidelines for the future development of the Barn Theater, but does not include detailed programming for this phase.

The Program for the 2012 Barn Expansion Project Phases 1B is organized in four categories with the following Assigned Square Footage (ASF):

The 6,400 ASF of The Barn (Barn Dining and Kitchen Addition) includes:

- Production kitchen
- Ware washing
- Back of house support
- Servery
- Indoor seating and Indoor Stage

The 1,870 ASF of the Barn Stable Relocation, Renovation and Addition includes:

- Meeting Room
- Bar
- Lobby
- Kitchen
- Storage

The 739 ASF of the Cottage Relocation and Renovation includes:

- Servery
- Back of house support

The 3,086 ASF of Faculty / Staff Dining includes:

- Lobby
- Dining Room
- Food Service Staging and Setup
- Bar and Bar Support
- Office
- Storage
- Restrooms
- Green Room
- Backstage space

PROGRAMMABLE OUTDOOR SPACE

Additional programmable space not included in the ASF totals above include outdoor spaces organized into five categories with the related Square Footage (SF):

The 1,080 SF of the Cottage South Patio includes:

- 54 café style dining seats
- Condiment Counter and Bussing Station

The 3,160 SF of the East Courtyard includes:

- 100 café style dining seats
- Condiment Counter and Bussing Station

The 875 SF of the Barn Stable Patio includes:

- 44 café style dining seats

The 5,448 SF of the West Courtyard includes:

- 162 table dining seats
- 3,000 SF shade structure
- 80 SF Outdoor BBQ
- Condiment Counter and Bussing Station

The 600 SF of the Outdoor Stage at Faculty / Staff Dining includes:

- Outdoor Stage and roof

SITE BASED PROJECT SCOPE

In addition to the enclosed ASF and the Programmable Outdoor Space outlined above, the project has considerable site-based scope of work. This includes hardscape, softscape, shade structures associated with the courtyards, and portions of the Barn Walk. Work at Sprout Loading Dock was also studied and is viewed as part of a future project. This includes alterations to roadway, near dock structure, landscaping and some utility alterations. The project also includes primary and secondary pedestrian paths, 3 parking spaces, and Loading Dock Area and Drive Aisle off West Campus Drive. See project scope of work as identified in the Phasing and Implementation diagram on page 241.



INTRODUCTION

Process

OVERVIEW OF PROCESS - 2012

Two workshops were held on the UC Riverside campus along with several conference calls. Information was presented via large-scale drawings, sketches, and PowerPoint presentations. The workshops were held in February and April 2012.

**WORKSHOP 1:
PROGRAM REVIEW AND REFINEMENT,
SITE REQUIREMENTS**

- Review and discussion of UCR's responses to Programming questions.
- Report on Beverage Consultant's description of basic parameters for alcoholic beverage service at this facility.
- Review and discussion of draft Project Area Summary for new Faculty / Staff Dining Facility—finalize.
- Review and discussion of the Barn Kitchen Addition program revisions needed to service the Faculty / Staff Dining and the Barn Dining—finalize.
- Review and discussion of the program revisions for the outdoor and indoor stages and the kinds of performances and entertainment anticipated. (Theater Consultant--Adam Shalleck, via conference call)
- Review of LEED checklist

CONFERENCE CALL: WITH BEVERAGE CONSULTANT

- Discussion of third party sale of alcoholic beverages and their requirements
- Discussion of the parameters of a club license and membership

- Discussion of where alcoholic beverages are to be served and consumed
- Review of ABC's requirements for containment of alcoholic beverages

**MEETING WITH BEVERAGE CONSULTANT,
ABC & UCR PMT (F&H NOT PRESENT)**

- Representatives from the Department of Alcoholic Beverage Control (ABC) were open to the idea of creating a club / entertainment venue at the Barn
- Discussion of barriers required to clearly identify areas where beer and wine can be consumed
- Discussion of options for what areas are included in the license and how to deal with the Campus Walk passing through the project
- Discussion that the Campus Walk would be closed for West Courtyard concerts, but the area would be off-limits for alcohol consumption.
- Discussion on the types of alcoholic licenses that would be required to cover the program planned for the space

WORKSHOP 2: CHARRETTE TO FINALIZE SITE PLAN & COMPREHENSIVE SPACE PLANS & PREPARE FOR COST ESTIMATE

- Review of Site Plan for the West Courtyard and Comprehensive Space Plans: West Courtyard; Loading Dock; Faculty / Staff Dining; Barn and Kitchen Addition; & Restrooms
- Review of Site Plan in relation to campus facilities and infrastructure requirements
- Review of Room Data Sheets

- Review of System Narratives
- Review of Site and Building Adjacency Diagrams
- Review of Project Area Summaries with Scott Lewis via conference call
- Provided guidance and approval on materials presented on documentation needed for Cost
- Discussion of Estimate and DPP Update, including: Site Plan Alternative; Comprehensive Space Plans; Phasing & Implementation Diagram
- Discussion of parameters for project schedule and implementation plan for design through construction.
- Review of costing parameters and methods with Scott Lewis via conference call

CONFERENCE CALL: WITH COST CONSULTANT

- Goal of Conference Call: to obtain feedback on cost plan, schedule, phasing and implementation
- Review of Cost Plan
- Review of Project Schedule

INTRODUCTION

Process

OVERVIEW OF PROCESS - 2010

A series of four workshops and a presentation to the Design Review Board were held on the UC Riverside campus along with several conference calls. Information was presented via large-scale drawings, sketches, and PowerPoint presentations. The workshops were held from early February through mid-April 2010.

WORKSHOP 1:**PROGRAM REVIEW AND REFINEMENT; SITE PLAN ANALYSIS; ESTABLISH PROJECT GOALS**

- Review 2009 Barn Area Study
- Interview campus and program representatives
- Discuss site plan options / opportunities / constraints
- Discuss building and site character
- Review program for building and site

WORKSHOP 2:**SITE PLAN OPTIONS; BUILDING SYSTEMS; SUSTAINABILITY**

- Review building systems options
- Discuss sustainability strategies and LEED
- Review site plan
- Review program

WORKSHOP 3:**FINALIZE ELEMENTS OF DPP; PREPARE FOR COST ESTIMATE**

- Review space program and room requirements
- Review site plan and space plans
- Discuss parameters for project schedule and implementation plan for design through construction
- Review building systems narratives, including LEED
- Discuss costing parameters and methods

WORKSHOP 4:**REVIEW DPP AND COST PLAN**

- Review and approve Draft DPP
- Review and approve Draft Cost Plan

DESIGN REVIEW BOARD PRESENTATION

- Review project vision, campus precedents, and supporting documents
- Review project milestones
- Review and discuss preferred scheme

CONFERENCE CALL:**KUCR**

- Discuss program elements and space allocation for KUCR

CONFERENCE CALL:**PERFORMANCE ISSUES**


- Review types of performances
- Discuss A/V and theatrical design and equipment criteria
- Discuss requirements for Ticket Booth and support spaces
- Review outdoor seating Shade Structure
- Discuss opportunities for shared program areas



INTRODUCTION

Project Goals

- Provide a unique dining and entertainment center.
- Enhance awareness of the Campus's agrarian heritage.
- Serve as a gateway / link between the East Campus and the West Campus.
- Integrate indoor and outdoor spaces to support dining and entertainment programs.
- Provide a well organized, welcoming, secure, and efficient group of buildings.
- Design the buildings to function as a group or independently.
- Achieve a minimum LEED Silver USGBC certification.
- Develop an architectural design that clearly communicates sustainability. Develop aspects of the sustainable design so this project can serve as an instructional / demonstration facility.



INTRODUCTION

Site Analysis of 2009 Barn Area Study

OVERVIEW

A detailed analysis of the 2009 Barn Area Study (BAS) was completed at the start of the project. The purpose of the review was to obtain a common understanding of the site, and identify areas that needed further attention during the DPP. The site analysis diagram and supporting text illustrate the key issues to test and verify in the 2009 BAS site plan.

FLOW & CIRCULATION

The Barn Group, located northwest of the intersection of West Campus Drive and the termination of Eucalyptus Walk, is a gateway site from the community into the core of the East Campus. The Barn Walk links the perimeter to the core of the campus and provides an important service access to Sproul Hall.

A strong pedestrian corridor enters The Barn Group site through the Humanities & Social Sciences Building, and connects to the Barn Walk from the west, while the walkway that runs along the south of Sproul and Watkins Hall connects to the Barn Walk from the east. This linkage must be maintained.

West Campus Drive is a major peripheral Campus loop. Proposed realignment to the road is considered a future project (note: the illustration shows the future road realignment as proposed in the 2009 BAS). The project must be planned to work with both the current and the future road.

Within the site, easy flow from indoor to outdoor should be enhanced to support dining and entertainment and to activate the outdoor spaces.

OUTDOOR SPACES

The project will make a significant contribution to the existing and very successful outdoor spaces on the campus. Two major courtyards (East and West) furnish seating areas that support the Barn's primary activities. A third outdoor space at the termination of Eucalyptus Walk, the South Cottage Patio, could offer an inviting entry to the Barn Walk.

IMPLEMENTATION


Phase 1A and 1B construction can be completed via a series of coordinated projects. Also access to the Theater needs to be maintained during construction and ticketed West Courtyard events. Site planning will need to consider how the Barn Theater can be accessed for future development.

HISTORIC CHARACTER—DIMENSIONS AND PROPORTIONS

The character of the existing barn structures should be maintained. Additions should support their character but be distinctly different, while being compatible with the re-purposed barn structures. The dimensions and proportions, as well as the materials and roof configurations, will need to be carefully studied in the design phases.

INTRODUCTION

Site Analysis of 2009 Barn Area Study



SITE ANALYSIS OF 2009 BARN AREA STUDY 

II. FUNCTIONAL CONCEPTS

From the 2010 DPP, the Composite Site Organization Plan and site diagrams were developed through the exploration of alternatives, that built upon the 2009 Barn Area Study and the goals for the project. These were then revised in the 2012 DPP Update to reflect Faculty/Staff Dining program addition which replaced KUCR.

Maintaining the character of the existing structures to be repurposed and developing the synergy between the indoor and outdoor spaces for dining and entertainment were the touchstones for the development of the preferred concept.

A series of diagrams present the preferred concept, and show how operational issues (including service access and security) are addressed. Two site organization plans show: site Build-out of the Barn Group including completion of the Barn Theater Expansion; and site after completion of the Barn Expansion. The site build-out is part of the Barn Area Study. A study of potential improvements to the Sproul Hall loading dock was also done.

Composite Site Organization Plan

BUILDINGS

THE BARN

Barn Dining

- Indoor dining and entertainment venue (renovation)

Kitchen Addition

- Main Kitchen supporting The Barn Group (new construction)

COTTAGE

- Coffee house with some limited food service (renovation and relocation)

BARN STABLE

- Multipurpose event venue (renovation of relocated structure and new construction)

BARN THEATER

- Rehearsal and performance space for CHASS (future phase renovation and addition)
- Relocation of ramp on the West and moving the South exit to the North side (will be part of Phase 1A)

FACULTY / STAFF DINING FACILITY

- Indoor dining with Bar and Food Services Staging and Setup (new construction)

OUTDOOR SPACES

EAST COURTYARD

- Quiet dining courtyard

WEST COURTYARD

- Outdoor entertainment and dining venue including covered Outdoor Stage and Shade Structure
- Outdoor access to the Bar which provides service to the Faculty / Staff Dining Facility and the West Patio

BARN STABLE PATIO

- Outdoor dining area

SOUTH COTTAGE PATIO

- Outdoor dining area

THE CAMPUS WALK

- Major cross axis, allows for expansion of West Courtyard and Barn Theater activities.

FUNCTIONAL CONCEPTS

Composite Site Organization Plan - Barn Group Build-out

OVERVIEW

Project site is located at the southwest edge of the campus core, and is crisscrossed by vibrant pedestrian pathways.

The site plan organizes the buildings and landscape to frame a series of outdoor rooms, while enhancing the pedestrian pathways throughout.

The East Courtyard will provide for quiet outdoor dining and is framed by two historically significant buildings; the relocated Cottage, a coffeehouse and entrance marker for the East Campus; and The Barn, a cultural dining and entertainment venue.

The West Courtyard will host a variety of live performances as well as provide space for outdoor dining. It is framed by The Barn, the Barn Theater, and Faculty / Staff Dining.

The relocated Barn Stable frames a patio providing a more intimate indoor / outdoor venue for various events including Campus special events, gatherings and weddings.

Service for the Kitchen Addition and Faculty / Staff Dining is screened by the landscape strip along West Campus Drive.



COMPOSITE SITE ORGANIZATION PLAN - BARN GROUP



NOTE: The conceptual vertical control points shown are based on topography received from Capital Resource Management April 8, 2012. They are to be verified, during design, once a site survey is available.

FUNCTIONAL CONCEPTS

Composite Site Organization Plan - Barn Expansion Project

The Barn Expansion Project of 2012 includes only minor changes to ramps and fire exiting at the Barn Theater.



COMPOSITE SITE ORGANIZATION PLAN -
BARN EXPANSION PROJECT




FUNCTIONAL CONCEPTS

Site Diagrams

OUTDOOR SEATING

OPTION A: WEST COURTYARD DINING TABLE SEATING

West Courtyard capacity varies with use, and this diagram shows a possible configuration for dining seating that provides 136 seats. These areas are based on somewhat greater than the minimum of 20 SF per seat.



OUTDOOR SEATING DIAGRAM - DINING SEATING OPTION




FUNCTIONAL CONCEPTS

Site Diagrams

OUTDOOR SEATING

OPTION B: WEST COURTYARD DINING TABLE SEATING MAXIMUM

West Courtyard capacity varies with use, and this diagram shows a possible configuration for dining seating that provides 162 seats (maximum allowable). These areas are based on approximately 20 SF per seat.



OUTDOOR SEATING DIAGRAM - DINING SEATING OPTION




FUNCTIONAL CONCEPTS

Site Diagrams

OUTDOOR SEATING

OPTION C: WEST COURTYARD
EVENT ROW SEATING

West Courtyard capacity varies with use, and this diagram shows a possible configuration for event row seating that provides 217 seats (maximum allowable). These areas are based on approximately 15 SF per seat.



OUTDOOR SEATING DIAGRAM - EVENT SEATING



FUNCTIONAL CONCEPTS


Site Diagrams

SECURITY

The goal is to secure the three courtyards while allowing through-site access between the Barn Walk and CHASS, via the Campus Walk.

The West Courtyard has three points of access. Its primary entrance is to the East, where tickets will be sold and people will queue for events. All gates, including the sliding gate to the North which has two 3'-0" wide man doors, meet emergency exit swing requirements.

The East Courtyard and Barn Stable Patio can both be independently isolated and secured.



SECURITY DIAGRAM


FUNCTIONAL CONCEPTS

Site Diagrams

ON-SITE SERVICE CIRCULATION

The majority of service circulation will be accomplished on-site with carts pushed by hand.

The Kitchen Addition serves as the service core for dining operations on-site. It will provide food storage and preparation for Barn Dining, East and West Courtyards, Barn Stable, the Cottage, and Faculty / Staff Dining. It will also serve as an area of preparation for catered events elsewhere on the campus (see food service narrative) and general commissary products.



ON-SITE SERVICE CIRCULATION DIAGRAM



FUNCTIONAL CONCEPTS

Site Diagrams

SITE CIRCULATION

SERVICE VEHICLES


West Campus Drive is a major peripheral campus loop road and provides access to The Barn Group. This service access is separated from West Campus Drive by a landscaped median that will screen the facilities. Service access to The Barn will be from the Loading Dock at the southwest corner of the Kitchen Addition. This service lane also provides access to Faculty / Staff Dining's three parking spaces. Service access to the Sproul Hall Loading Dock will be from a service road that parallels the Barn Walk.

BICYCLES

UCR is currently in the initial stages of developing a bike lane plan. A bicycle lane should be provided along West Campus Drive and connect to East Campus via the Barn Walk service road.

PEDESTRIANS

The Barn Walk links the perimeter to the core of the East Campus. It is the terminus of both Eucalyptus Walk and the walk just south of Sproul Hall and Watkins Hall. A strong pedestrian corridor enters the Barn Group through the College of Humanities, Arts, and Social Sciences (CHASS) Building from the northeast, and connects to the Barn Walk via the Campus Walk. Should entertainment events close the West Courtyard to through traffic, pedestrians can walk through the orange grove just south of CHASS. West Campus Drive is a major peripheral campus loop road for pedestrians as well as vehicles.



SITE CIRCULATION DIAGRAM




FUNCTIONAL CONCEPTS

Site Diagrams

TRUCK TURNING

Truck turning for the largest delivery truck was studied with the following goals:

- Allow for a drive aisle to also serve Faculty / Staff Dining parking
- Allow clearance for a car to pass alongside a delivery vehicle
- Provide a strong pedestrian experience along West Campus Drive



TRUCK TURNING DIAGRAM




FUNCTIONAL CONCEPTS

Site Diagrams

UTILITY POINTS OF CONNECTION

See civil narrative for information on utility points of connection.

All Utility Points of Connection remain as was presented in the 2010 DPP.



UTILITY POINTS OF CONNECTION



FUNCTIONAL CONCEPTS

Site Diagrams

ALTERNATE FOR SPROUL LOADING DOCK

The 2009 Barn Area Study proposed major modifications to the Sproul Hall Loading Dock to address several issues. One of the issues identified with the existing loading dock is the need for the front-loading trash collection vehicles to back up to West Campus Drive when exiting. The costs for any work associated with the Sproul Hall Loading Dock (east of the curb at the Barn Walk) are included in the budget below-the-line as an alternate and are viewed as part of a future project. Three options were explored for this report:

- Maintain the existing configuration.
- Reconfigure the service vehicle spaces and screen the recycling/trash bins within a new enclosure (as illustrated in the Composite Site Organization Plan, page 13.)
- Provide a new loading dock between the Sproul Hall buildings as well as the modifications mentioned in option 2 above (as illustrated in the diagram on this page).

Each option will need to allow for through access to the Carillon Mall by Fire Department vehicles.



ALTERNATE FOR SPROUL LOADING DOCK DIAGRAM

III. PROGRAM

The unique dining and entertainment opportunities offered by the facilities, and the site's rich agrarian and cultural heritage were emphasized throughout the planning process.

The identity and character of the project—within the campus, within the Riverside community, and within the UC system—are addressed in relation to the unique functional requirements that are the basis of the program. The Project Area Summary and the Room Data Sheets summarize these requirements.

In the 2012 DPP Update, Basic Gross Totals are rounded up to the next 10 SF for simplicity. Two Project Area Summaries show: site Build-out of

the Barn Group including completion of the Barn Theater Expansion; and site after completion of the Barn Expansion. The site build-out is part of the Barn Area Study.

Per the California Building Code 2010, the maximum allowable area on site is 28,317 SF (see Code Narrative for assumptions). To meet this requirement, the covered portion of the West Courtyard is changed from a solid roof in the 2010 DPP to a stand-alone, non-solid shade structure in the 2012 DPP Update, which minimizes overall square footage on the site, lowers cost, and eliminates the need for sprinklers.

PROGRAM

Project Area Summary - Barn Group Build-out 2012 DPP Update

BUILDING AND ASSOCIATED OUTDOOR AREAS	ASF	NON-ASF	BASIC GROSS TOTAL	Covered Area (SF)	OGSF100	OGSF50	SF ¹	Indoor Dining Seating	Outdoor Dining Seating
COTTAGE	739	26	880	610	1,490	1,185			
THE BARN: BARN DINING & KITCHEN ADDITION	6,400	728	8,200	1,320	9,520	8,860		94	
EAST COURTYARD RESTROOMS	0	792	910	170	1,080	995			
BARN STABLE	1,870	322	2,530	470	3,000	2,765		42	
FACULTY / STAFF DINING ²	3,082	1,010	4,710	1,800	6,180	5,445		58	
BARN THEATER ³	3,013	0	3,470	0	3,470	3,470			
SOUTH COTTAGE PATIO (OUTDOOR) ⁴							1,080		54
EAST COURTYARD (OUTDOOR) ⁵							3,160		98
WEST COURTYARD (OUTDOOR UNCOVERED DINING) ⁶							255		
WEST COURTYARD (OUTDOOR SHADE STRUCTURE OVER DINING) ⁷							3,000		162
WEST COURTYARD (OUTDOOR CIRCULATION + BBQ/SERVING)							2,193		
BARN STABLE PATIO (OUTDOOR)							875		44
TOTAL	15,104	2,878	20,700	4,370	24,740	22,720	10,563	194	358

¹ Outdoor areas are calculated in square feet (SF).

² Faculty/Staff Dining covered area includes an estimate of 870 SF for non-programmable roof overhangs including covered front and back entry porches + 930 SF for the covered Stage and Stage Roof Overhang at the Outdoor Stage (600 SF) adjacent to Faculty/Staff Dining.

³ The Barn Theater areas per the 2009 Barn Area Study (BAS). Barn Theater is not included as part of the Barn Expansion Project (see separate Project Area Summary.)

⁴ The South Cottage Patio has outdoor café seating adjacent to the Cottage.

⁵ East Courtyard includes combined area of the East Courtyard Seating, Circulation and Condiment Counter (2,160 SF) + Cottage (1,000 SF) = 3,160 SF. The outdoor dining seating in the East Courtyard includes the combined seating for the Barn Dining (48 seats) + the Cottage (50 seats) = 98 seats.

⁶ West Courtyard includes 2,093 SF Outdoor Circulation + 100 SF BBQ and Condiment Counter + 3,255 SF available for Outdoor Dining Seating. 3,000 SF of Dining Seating is covered by Outdoor Shade Structure, and the remaining 255 SF Dining Seating is uncovered.

⁷ Assumes stand-alone shade structure, not a solid roof.

PROGRAM

Project Area Summary - Barn Expansion Project 2012 DPP Update

BUILDING AND ASSOCIATED OUTDOOR AREAS	ASF	NON-ASF	BASIC GROSS TOTAL	Covered Area (SF)	OGSF100	OGSF50	SF ¹	Indoor Dining Seating	Outdoor Dining Seating
COTTAGE	739	26	880	610	1,490	1,185			
THE BARN: BARN DINING & KITCHEN ADDITION	6,400	728	8,200	1,320	9,520	8,860		94	
EAST COURTYARD RESTROOMS	0	792	910	170	1,080	995			
BARN STABLE	1,870	322	2,530	470	3,000	2,765		42	
FACULTY / STAFF DINING ²	3,082	1,010	4,710	1,800	6,180	5,445		58	
BARN THEATER ³	0	0	0	0	0	0			
SOUTH COTTAGE PATIO (OUTDOOR) ⁴							1,080		54
EAST COURTYARD (OUTDOOR) ⁵							3,160		98
WEST COURTYARD (OUTDOOR UNCOVERED DINING) ⁶							255		
WEST COURTYARD (OUTDOOR SHADE STRUCTURE OVER DINING) ⁷							3,000		162
WEST COURTYARD (OUTDOOR CIRCULATION + BBQ/SERVING)							2,193		
BARN STABLE PATIO (OUTDOOR)							875		44
TOTAL	12,091	2,878	17,230	4,370	21,270	19,250	10,563	194	358

¹ Outdoor areas are calculated in square feet (SF).

² Faculty/Staff Dining covered area includes an estimate of 870 SF for non-programmable roof overhangs including covered front and back entry porches + 930 SF for the covered Stage and Stage Roof Overhang at the Outdoor Stage (600 SF) adjacent to Faculty/Staff Dining.

³ Barn Theater is not included as part of the Barn Expansion Project.

⁴ The South Cottage Patio has outdoor café seating adjacent to the Cottage.

⁵ East Courtyard includes combined area of the East Courtyard Seating, Circulation and Condiment Counter (2,160 SF) + Cottage (1,000 SF) = 3,160 SF. The outdoor dining seating in the East Courtyard includes the combined seating for the Barn Dining (48 seats) + the Cottage (50 seats) = 98 seats.

⁶ West Courtyard includes 2,093 SF Outdoor Circulation + 100 SF BBQ and Condiment Counter + 3,255 SF available for Outdoor Dining Seating. 3,000 SF of Dining Seating is covered by Outdoor Shade Structure, and the remaining 255 SF Dining Seating is uncovered.

⁷ Assumes stand-alone shade structure, not a solid roof.

PROGRAM

Project Area Summary - Cottage

AREA DESCRIPTION	NEW CONSTRUCTION	RENOVATION OF EXISTING BUILDING	TOTAL
COTTAGE			
ASSIGNABLE (ASF): SERVING			
Lobby		151	151
Serving Area		150	150
Customer Queuing		120	120
Self-Serve Condiment Counter & Queuing		24	24
SUBTOTAL	0	445	445
ASF: BACK OF HOUSE SUPPORT			
Dry Storage		64	64
Refrigerated Storage - Bulk		36	36
Storage		55	55
Office		55	55
Ware-washing		60	60
Ice Making/Prep/Misc Support		24	24
SUBTOTAL	0	294	294
ASSIGNABLE TOTAL	0	739	739
NON-ASSIGNABLE (NON-ASF) SPACES			
Telecom/Electrical		26	26
NON-ASSIGNABLE TOTAL	0	26	26
NET TOTAL ASF & NON-ASF	0	765	765
Grossing Factor (15%)	0	115	115
BASIC GROSS TOTAL	0	880	880
ASF to GSF Ratio	0%	84%	84%
PROGRAMMABLE COVERED OUTDOOR SPACE			
Entrance Arcade		46	46
Front Porch		136	136
Back Porch		164	164
Existing Building Overhangs		264	264
PROGRAMMABLE COVERED OUTDOOR TOTAL	0	610	610
OGSF100	0	1,490	1,490
OGSF50	0	1,185	1,185
PROGRAMMABLE OUTDOOR SPACE¹			
Outdoor Seating - East Courtyard ²	1,000		1,000
Outdoor Seating - South Cottage Patio	1,080		1,080
TOTAL OUTDOOR SPACE	2,080	0	2,080
¹ Outdoor areas are calculated in square feet (SF).			
² Assume 20 SF / Person for outdoor seating:			
Outdoor Seating - East Courtyard	1,000 / 20 =	50	
Outdoor Seating - South Cottage Patio	1,080 / 20 =	54	
Total Outdoor Cottage Seating		104	

PROGRAM

Project Area Summary - Barn Dining / Kitchen Addition

AREA DESCRIPTION	NEW CONSTRUCTION	RENOVATION OF EXISTING BUILDING	TOTAL
THE BARN: BARN DINING/ KITCHEN ADDITION			
ASSIGNABLE (ASF): PRODUCTION KITCHEN			
Cold Prep	579		579
Soda Room / Ice Machine	82		82
Hot Production (Cook Line & Grille)	408	153	561
Refrigerated Storage - Bulk Food	120		120
Refrigerated Storage - Finished Product Cooler	120		120
Frozen Storage	120		120
Dry Storage - Food	340		340
Catering Storage	63		63
Receiving, Recycling and Outbound Staging	160		160
SUBTOTAL	1,992	153	2,145
ASF: WARE-WASHING			
Dishwashing & Pot-washing Combined	127		127
Janitor's Closet for Kitchen	32		32
SUBTOTAL	159	0	159
ASF: BACK OF HOUSE SUPPORT			
Unisex Changing Room & Lockers	77		77
Manager's + Production Office	123		123
Storage - West Courtyard Tables + Chairs	160		160
Stage Power & Dimmers for Outdoor Stage	45		45
SUBTOTAL	405	0	405
ASF: SERVING			
Serving Area		800	800
Customer Queuing		360	360
Self-Serve Beverage Counter & Queuing		65	65
Self-Serve Condiment Counter & Queuing		65	65
SUBTOTAL	0	1,290	1,290
ASF: INDOOR SEATING & STAGE			
Indoor Seating ¹		1,870	1,870
Indoor Stage ²	105	160	265
Stage Audio Equipment + Storage ²	40		40
Green Room ²	55	75	130
Ticket Booth ²	40	56	96
SUBTOTAL	240	2,161	2,401
ASSIGNABLE TOTAL	2,796	3,604	6,400
NON-ASSIGNABLE (NON-ASF) SPACES			
Mechanical	200		200
Telecom Closet	120		120
Electrical Room	66		66
Public Restrooms (2)	300		300
Janitor's Closets for Restroom	42		42
NON-ASSIGNABLE TOTAL	728	0	728
NET TOTAL ASF & NON-ASF	3,524	3,604	7,128
Grossing Factor (15%)	526	546	1072
BASIC GROSS TOTAL	4,050	4,150	8,200
ASF TO GSF RATIO	69%	87%	78%

AREA DESCRIPTION	NEW CONSTRUCTION	RENOVATION OF EXISTING BUILDING	TOTAL
THE BARN: BARN DINING/ KITCHEN ADDITION (continued)			
NON-PROGRAMMABLE COVERED OUTDOOR SPACE			
Covered Loading Dock Area	603		603
Building Overhang	167	550	717
NON-PROGRAMMABLE COVERED OUTDOOR TOTAL	770	550	1,320
OGSF100	4,820	4,700	9,520
OGSF50	4,435	4,425	8,860
PROGRAMMABLE OUTDOOR SPACE³			
Outdoor Dining Seating - East ⁴	960		960
Outdoor Gathering/Circulation - East	1,180		1,180
Outdoor Dining Seating - West ⁵	3,255		3,255
Outdoor Circulation - West	2,093		2,093
Outdoor BBQ	80		80
Outdoor Condiment Counter - West	20		20
Outdoor Condiment Counter - East	20		20
SUBTOTAL (SF)	7,608	0	7,608
NON-PROGRAMMABLE OUTDOOR SPACE			
Loading Dock ⁶	3,465		3,465
Campus Walk	3,670		3,670
SUBTOTAL (SF)	7,135	0	7,135
TOTAL OUTDOOR SPACE	14,743	0	14,743
¹ Assume 20 SF / Person for indoor dining seating: Indoor Seating 1,870 ASF / 20 = 94			
² The Indoor Stage, Stage Audio Equipment & Storage, Green Room, and Ticket Booth include both existing space and new construction (on the North edge of Barn Dining.) In the cost estimate, the new construction area is covered under Kitchen Addition.			
³ Outdoor areas are calculated in square feet (SF). East and West Courtyard Programmable Outdoor Space is covered in this summary because the Barn Kitchen serves the East Courtyard Dining and West Courtyard Dining.			
⁴ For the East Courtyard, assume 20 SF / Person for outdoor dining seating: East Courtyard 960 SF / 20 = 48 people			
⁵ For the West Courtyard, maximum capacity varies depending on use: West Courtyard 3,255 SF / 20 = 162 people dining seating (max. lunch capacity) 3,255 SF / 15 = 217 people row seating 3,255 SF / 7 = 466 people standing (max. event capacity)			
⁶ Loading Dock includes space for truck and/or vehicle parking and is adjacent to Covered Loading Dock Area.			

PROGRAM

Project Area Summary - East Courtyard Restrooms

AREA DESCRIPTION	NEW CONSTRUCTION	RENOVATION OF EXISTING BUILDING	TOTAL
EAST COURTYARD RESTROOMS			
NON-ASSIGNABLE (NON-ASF) SPACES			
Janitor's Closets for Restroom	32		32
Public Restrooms (2) ¹	760		760
NON-ASSIGNABLE TOTAL	792	0	792
NET TOTAL ASF & NON-ASF	792	0	792
Grossing Factor (15%)	118	0	118
BASIC GROSS TOTAL	910	0	910
Building Overhang	170	0	170
NON-PROGRAMMABLE COVERED OUTDOOR TOTAL	170	0	170
OGSF100	1,080	0	1,080
OGSF50	995	0	995
¹ East Courtyard Restrooms are expanded to provide additional restrooms needed to support the larger program in the DPP Update.			

PROGRAM

Project Area Summary - Barn Stable

AREA DESCRIPTION	NEW CONSTRUCTION	RENOVATION OF EXISTING BUILDING	TOTAL
BARN STABLE (formerly known as "Barn Annex")			
ASSIGNABLE (ASF)			
Meeting Room ¹		868	868
Bar		100	100
Lobby	328		328
Kitchen		254	254
Storage		70	70
Storage for tables and chairs	250		250
ASSIGNABLE TOTAL	578	1,292	1,870
NON-ASSIGNABLE (NON-ASF) SPACES			
Mechanical	100		100
Telecom Closet	52		52
Public Restrooms (2) ²	150		150
Janitor's Closet for Restrooms	20		20
NON-ASSIGNABLE TOTAL	322	0	322
NET TOTAL ASF & NON-ASF	900	1,292	2,192
Grossing Factor (15%)	140	198	338
BASIC GROSS TOTAL	1,040	1,490	2,530
ASF to GSF Ratio	56%	87%	74%
OUTDOOR SPACE³			
Covered Outdoor Space	100		100
Existing Building Overhangs	0	370	370
NON-PROGRAMMABLE COVERED OUTDOOR TOTAL	100	370	470
OGSF100	1,140	1,860	3,000
OGSF50	1,090	1,675	2,765
OUTDOOR SPACE³			
Barn Stable Patio ⁴	875		875
TOTAL OUTDOOR SPACE	875	0	875
¹ Assume 20 SF / Person for indoor dining seating: Meeting Room 868 ASF / 20 = 42			
² Increase in Restrooms SF is due to code analysis done for the DPP Update of 2012.			
³ Outdoor areas are calculated in square feet (SF).			
⁴ Assume 20 SF / Person for outdoor dining seating: Barn Stable Patio 875 / 20 = 44			

PROGRAM

Project Area Summary - Faculty / Staff Dining Facility

AREA DESCRIPTION	NEW CONSTRUCTION	RENOVATION OF EXISTING BUILDING	TOTAL
FACULTY / STAFF DINING			
ASF: DINING			
Indoor Faculty / Staff Dining--for 50	1,300		1,300
Buffet Serving Area	192		192
<i>Back of house support for Dining:</i>			
Beverage Service (non-alcoholic)	80		80
Storage (Catering and Dining Room)	150		150
Food Staging (warmers, refrigerators) + Set Up Area (glasses, utensils, place sets, bussing)	200		200
Dishwashing	150		150
Entry /Lobby	100		100
SUBTOTAL	2,172	0	2,172
ASF: OTHER SPACES			
Bar ¹	270		270
<i>Support spaces for the Bar:</i>			
Office + Packaging	100		100
Dry Storage	80		80
Walk-in Refrigerator / Wine Cooler	150		150
Janitor's Closet for Kitchen	40		40
<i>Support Spaces for Stage</i>			
Green Room	150		150
Outdoor Performance Equipment Storage	120		120
SUBTOTAL	910	0	910
ASSIGNABLE TOTAL	3,082	0	3,082

AREA DESCRIPTION	NEW CONSTRUCTION	RENOVATION OF EXISTING BUILDING	TOTAL
FACULTY / STAFF DINING			
NON-ASSIGNABLE (NON-ASF) SPACES			
Circulation	500		500
Mechanical/Electrical	200		200
Telecom Closet	100		100
Public Restrooms (2)	110		110
Restroom for Green Room	50		50
Janitor's Closet for Restrooms	50		50
NON-ASSIGNABLE TOTAL	1,010	0	1,010
NET TOTAL ASF & NON-ASF			
Grossing Factor (15%)	618	0	618
BASIC GROSS TOTAL	4,710	0	4,710
ASF TO GSF RATIO	65%	0%	19%
OGSF100			6,180
OGSF50			5,445
PROGRAMMABLE UNCOVERED OUTDOOR SPACE			
			0
PROGRAMMABLE COVERED OUTDOOR SPACE			
Outdoor Stage	600		600
PROGRAMMABLE COVERED OUTDOOR TOTAL	600		600
COVERED AREA			
Outdoor Stage Roof and Stage Roof Overhang ²	930		930
COVERED AREA TOTAL	930		930
NON-PROGRAMMABLE COVERED OUTDOOR SPACE			
Building Overhang	870		870
NON-PROGRAMMABLE COVERED OUTDOOR TOTAL	870		870
COVERED PROG. + NON-PROG. OUTDOOR AREA TOTAL	1,470		1,470
¹ Bar would be run by a third party operator. ² Covered Area includes the area of roof which covers the stage (600 SF) + the additional roof overhang that extends past the stage (330 SF) = 930 s.f. total.			


PROGRAM

Project Area Summary - Barn Theater (Future)

AREA DESCRIPTION	2009 BAS
BARN THEATER¹	
ASF SPACES	
Rehearsal 01	1,140
Office	288
Rehearsal 02	765
Locker/Restroom	313
Storage	507
ASSIGNABLE TOTAL	3,013
NON-ASSIGNABLE (NON-ASF) SPACES	
Circulation (included above)	
Mechanical	
Public Restrooms	
NON-ASSIGNABLE TOTAL	0
NET TOTAL ASF & NON-ASF	3,013
Grossing Factor (15%)	457
BASIC GROSS TOTAL	3,470
ASF TO GSF RATIO	87%
OGSF100	3,470
OGSF50	3,470
OUTDOOR SPACE²	
Exterior Stage ³	670
TOTAL OUTDOOR SPACE	670
<p>¹ The Barn Theater is not part of the Barn Expansion Project. Barn Theater areas are per the 2009 Barn Area Study (BAS). 1,651 SF will be used for Barn Theater Entry Modifications in the Cost Estimate.</p> <p>² Outdoor areas are calculated in square feet (SF).</p> <p>³ Exterior Stage at Barn Theater combined with Outdoor Stage adjacent to Faculty/Staff Dining</p>	

Site & Building Adjacency Diagrams


COTTAGE



Site & Building Adjacency Diagrams



THE BARN: BARN DINING / KITCHEN ADDITION

EAST COURTYARD RESTROOMS




Site & Building Adjacency Diagrams

BARN STABLE




Site & Building Adjacency Diagrams

FACULTY / STAFF DINING



Site & Building Adjacency Diagrams



SITE



Comprehensive Space Plans

COTTAGE



SCALE




Comprehensive Space Plans

THE BARN

SCALE





EAST COURTYARD RESTROOMS (NON-ASF)



Comprehensive Space Plans

BARN STABLE

SCALE



Room Data Sheets

ABBREVIATIONS

A/V	Audio/Visual
CFM	Cubic feet per minute (ventilation)
FC	Foot-candles
FRP	Fiberglass-reinforced plastic
FSC	Forest Stewardship Council
HVAC	Heating, Ventilation, and Air Conditioning
NA	Not applicable
NC	Noise Criteria
POS	Point of sale
STOR	Storage
U/C	Under-counter
V	Volts
WAP	Wireless Access Point

PROGRAM


Room Data Sheets

COTTAGE: SERVING LOBBY

GENERAL INFORMATION

Area for customers to gather.

TOTAL ASF	151
NUMBER OF OCCUPANTS	25 (maximum)
ADJACENCIES	Serving Area, Office, Front and Back Porch
VIEWS	East Courtyard, Cottage South Patio
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Wood or other high-end finish
WALLS / BASE	Gypsum board with wood wainscotting
FLOORS	Wood, wood tile or epoxy -- will be determined during design
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible. Self-closing exterior doors.
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT

BUILT-IN	Bar counters, existing fireplace (repair)
FIXED	NA
MOVABLE	Trash and recycling containers
OTHER	Repair fireplace as necessary for structural integrity to allow for operation

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Downlights, ceiling mount linear fluorescents, architectural sconces, 20-30 FC. Controlled via a central time clock system and provided with an override switch
MECHANICAL	HVAC. Individual zone control/thermostat. Self-closing exterior doors
PLUMBING	NA
SECURITY	Rough-in for cameras above each POS, key access, Window sash locks, Magnetic contacts at exterior doors and windows
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	WAP
MEDIA	Sound system and ceiling loudspeakers

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM

Room Data Sheets

COTTAGE: SERVING SERVING AREA

GENERAL INFORMATION

Area for serving customers.

TOTAL ASF	150
NUMBER OF OCCUPANTS	5
ADJACENCIES	Lobby, Service access
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES


CEILING	Wood or other high-end finish
WALLS / BASE	Gypsum board, epoxy coving
FLOORS	Epoxy poured floor
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible Self-closing exterior doors.
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT

BUILT-IN	
FIXED	Point of sale (POS) (2), pick-up counter, coffee counter, blender counter, hand sink, floor sink for espresso machine
MOVABLE	Trash and recycling containers
OTHER	Espresso and coffee machines, blenders, bakery display case (2 sections: ambient and refrigerated), oven, ice bin, grinders, under-counter refrigerator (2)

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	
ELECTRICAL	120/208 V / 3 Phase, Quad receptacle at each POS
LIGHTING	Ceiling mount linear fluorescent with acrylic lens, 40-50 FC. Controlled via Occupancy Sensor/Switch
MECHANICAL	HVAC. Exhaust air at kitchen hoods with interlocked tempered make-up air. Self-closing exterior doors
PLUMBING	Hot and cold water, sanitary sewer for equipment as required, gas
SECURITY	Rough-in for cameras above each POS, Panic alarm, Card key access ext. door, Window sash locks, Magnetic contacts at exterior door and windows
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	1 phone / 2 data (1 phone/1 data at each POS, separate data for credit cards) as well as at least one data on each wall
MEDIA	NA
ACOUSTICS	
ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-45



PROGRAM


Room Data Sheets

COTTAGE: SERVING CUSTOMER QUEUING

GENERAL INFORMATION

Serpentine queue system (next available cashier). Seating will not be provided.

TOTAL ASF	120
NUMBER OF OCCUPANTS	4
ADJACENCIES	Lobby, Servery
VIEWS	East Courtyard, Cottage South Patio
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Wood or other high-end finish
WALLS / BASE	Gypsum board with wood wainscotting
FLOORS	Wood, wood tile or epoxy -- will be determined during design
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible Self-closing exterior doors.
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Downlights, Ceiling mount linear fluorescents, 30-40 FC. Controlled via central time clock system with override switches.
MECHANICAL	HVAC self-closing exterior doors
PLUMBING	NA
SECURITY	Rough-in for cameras over each POS, key access, Window sash locks, Magnetic contacts at exterior doors and windows
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	WAP
MEDIA	Sound system and ceiling loudspeakers

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM


Room Data Sheets

COTTAGE: SERVING SELF-SERVE CONDIMENT COUNTER & QUEUING

GENERAL INFORMATION

Located away from Serving counter.

TOTAL ASF	24
NUMBER OF OCCUPANTS	1
ADJACENCIES	Lobby, Servery
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Wood or other high-end finish
WALLS / BASE	Gypsum board with wood wainscotting
FLOORS	Wood, wood tile or epoxy -- will be determined during design
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible Self-closing exterior doors.
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT

BUILT-IN	Millwork condiment counter with stone top, built in condiment rail with insets and built in napkin dispensers
FIXED	NA
MOVABLE	Trash container below counter
OTHER	For milk, toppings, napkins, lids, stirrs, and straws, sugars (3), knives, forks and spoons

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V convenience receptacles (2)
LIGHTING	Downlights, Ceiling mount linear fluorescents, 30-40 FC. Controlled via central time clock system with override switches.
MECHANICAL	HVAC. Self-closing exterior doors
PLUMBING	NA
SECURITY	Rough-in for cameras over each POS, key access, Window sash locks, Magnetic contacts at exterior doors and windows
FIRE PROTECTION	Sprinkler
VOICE/DATA	WAP
MEDIA	Sound system and ceiling loudspeakers

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM

Room Data Sheets

COTTAGE: BACK OF HOUSE SUPPORT DRY STORAGE

GENERAL INFORMATION

Storage of dry goods.

TOTAL ASF	64
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Servery, Service entrance
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board with FRP, epoxy coving
FLOORS	Epoxy poured floor
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT


BUILT-IN	NA
FIXED	NA
MOVABLE	Stainless steel shelving
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Ventilation
PLUMBING	NA
SECURITY	Window sash locks, Magnetic contacts at exterior window
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55



PROGRAM

Room Data Sheets

COTTAGE: BACK OF HOUSE SUPPORT REFRIGERATED STORAGE - BULK

GENERAL INFORMATION

Storage of bulk refrigerated goods.

TOTAL ASF	36
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Servery, Service entrance
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board with FRP, epoxy coving
FLOORS	Epoxy poured floor
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT


BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch. Factory-installed (included with refrigerator)
MECHANICAL	Ventilation
PLUMBING	NA
SECURITY	Window sash locks, Magnetic contacts at exterior window
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55



PROGRAM


Room Data Sheets

COTTAGE: BACK OF HOUSE SUPPORT STORAGE

GENERAL INFORMATION

General storage.

TOTAL ASF	55
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Office, open to Telecom/Electrical Closet
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Wood or other high-end finish
WALLS / BASE	Gypsum board with FRP, epoxy coving
FLOORS	Epoxy poured floor
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	Stainless steel shelving
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch
MECHANICAL	Ventilation
PLUMBING	NA
SECURITY	Card key access, Window sash locks, Magnetic contacts at exterior window, Camera at entry door
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

Room Data Sheets

COTTAGE: BACK OF HOUSE SUPPORT OFFICE

GENERAL INFORMATION

Space for managers to work and place their belongings and for cash counting.


TOTAL ASF	55
NUMBER OF OCCUPANTS	1
ADJACENCIES	Open to Storage, Telecom/electrical Closet
VIEWS	Exterior
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Wood or other high-end finish
WALLS / BASE	Gypsum board with FRP, epoxy coving
FLOORS	Epoxy poured floor
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT

BUILT-IN	Desk, computer table and safe
FIXED	NA
MOVABLE	Chair and file cabinet
OTHER	NA



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Direct/Indirect linear pendants, 10-20 FC. Task lights 30-40 FC. Controlled via Occupancy Sensor/Switch.
MECHANICAL	HVAC
PLUMBING	NA
SECURITY	Card key access, Window sash locks, Magnetic contacts at exterior window, Camera over cash counting area
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 1 data, at least one on each wall
MEDIA	Lobby/Porch audio source equipment, sound system for all of Cottage

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM


Room Data Sheets

COTTAGE: BACK OF HOUSE SUPPORT WARE-WASHING

GENERAL INFORMATION

Space for washing.

TOTAL ASF	60
NUMBER OF OCCUPANTS	1
ADJACENCIES	Servery
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board with FRP; epoxy, stainless steel or ceramic tile coving -- to be determined during design
FLOORS	Epoxy poured floor
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT

BUILT-IN	Stainless steel backsplash for sinks
FIXED	3-compartment sink, handsink with enclosure
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	30 FC, Occupancy sensors
MECHANICAL	Ventilation required at chem stor
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	Window sash locks, Magnetic contacts at exterior window
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55


PROGRAM

Room Data Sheets

COTTAGE: BACK OF HOUSE SUPPORT ICE MAKING / PREP / MISC. SUPPORT

GENERAL INFORMATION

TOTAL ASF	24
NUMBER OF OCCUPANTS	1
ADJACENCIES	Servery, Service Entrance
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board with FRP; epoxy, stainless steel or ceramic tile coving -- to be determined during design
FLOORS	Epoxy poured floor
WINDOWS	Wood -- double glaze, match existing
DOORS	Wood -- refinish existing where possible
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Ice machine, prep counters
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120/208 V / 1 Phase
LIGHTING	48" recessed fluorescent fixtures with plastic lens covers
MECHANICAL	Ventilation, ice machine and refrigerator heat rejection of 11.2 MBTU
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	Window sash locks, Magnetic contacts at exterior window
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS


ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

Room Data Sheets

COTTAGE: NON-ASSIGNABLE SPACES TELECOM / ELECTRICAL CLOSET

GENERAL INFORMATION

Area for telecom and electrical equipment that is open to Storage.
Access to the equipment will need to be maintained (approach TBD during design). Code-required clearances will need to be provided for the electrical dimensions of equipment TBD during design.



TOTAL NON-ASF	26
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Open to Storage
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Fire resistant plywood / wood and gypsum board; epoxy, stainless steel or ceramic tile coving -- to be determined during design
FLOORS	Resilient or epoxy
WINDOWS	NA
DOORS	Wood -- refinish existing where possible
DOOR FRAMES	Wood -- refinish existing where possible

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust
PLUMBING	NA
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 1 data
MEDIA	Telecom equipment will need physical protection

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM


Room Data Sheets

COTTAGE: PROGRAMMABLE COVERED OUTDOOR SPACE FRONT PORCH / ENTRANCE ARCADE

GENERAL INFORMATION

The front porch/entrance arcade is the front door for the cottage

TOTAL SF	182
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Lobby, Barn Walk, Cottage South Patio
VIEWS	Barn Walk, West Campus Drive, Eucalyptus Walk
MINIMUM CEILING HEIGHT	7'-6"
ACCESSIBILITY	Per code, 5' wide 1:12 ramp, possible ADA conflict at entry door (see diagram). Accessibility issues will be addressed during design.
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Wood, painted
WALLS / BASE	Wood siding, painted
FLOORS	Wood decking and colored concrete
WINDOWS	Wood painted
DOORS	Wood painted, self-closing exterior door
DOOR FRAMES	Wood painted

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase, Lockable outdoor outlet
LIGHTING	Outdoor Lighting
MECHANICAL	Self-closing exterior door
PLUMBING	NA
SECURITY	NA
FIRE PROTECTION	Sprinklers at covered areas
VOICE/DATA	NA
MEDIA	Outdoor loudspeakers

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-45

PROGRAM


Room Data Sheets

COTTAGE: PROGRAMMABLE COVERED OUTDOOR SPACE BACK PORCH

GENERAL INFORMATION

Primarily an exterior circulation space, this area is the public “back door” to the cottage.

TOTAL SF	164
NUMBER OF OCCUPANTS	NA
ADJACENCIES	East Courtyard, Lobby
VIEWS	East Courtyard, Lobby
MINIMUM CEILING HEIGHT	7'-6"
ACCESSIBILITY	Per code , 5' wide, 1:12 ramp
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Wood, painted
WALLS / BASE	Wood siding, painted
FLOORS	Wood decking and colored concrete
WINDOWS	Wood, painted
DOORS	Wood, painted, self-closing exterior door
DOOR FRAMES	Wood, painted

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase, Lockable outdoor outlet
LIGHTING	Outdoor Lighting
MECHANICAL	Self-closing exterior doors
PLUMBING	NA
SECURITY	NA
FIRE PROTECTION	Sprinklers at covered areas
VOICE/DATA	NA
MEDIA	Outdoor loudspeakers

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-45

PROGRAM

Room Data Sheets

BARN DINING: PRODUCTION KITCHEN COLD PREP

GENERAL INFORMATION

Cold production for Barn, Barn/University Club catering, and 425 pieces packaged grab-and-go products daily.

SEE *HOT PRODUCTION* FOR DIAGRAM

TOTAL ASF	579
NUMBER OF OCCUPANTS	5
ADJACENCIES	Hot Production, Dishwashing, Refrigerated Storage, Frozen Storage, Dry Storage
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	Aluminum
DOORS	Hollow metal painted door with viewing panel
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Stainless steel counters, undercounter prep refrigerator (2), work tables with sinks, hand sink, vegetable prep sinks
MOVABLE	Mobile pan racks, double overselves, trash containers, hot and cold catering carts
OTHER	20-quart mixer, slicer, vegetable processor, food chopper, salad dryer

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	North facing clerestory windows
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	48" recessed fluorescent fixtures with plastic lens covers, occupancy sensors
MECHANICAL	HVAC / Exhaust / Chilled water supply and return; HVAC maintains internal temperature of 75°F DB summer and 70°F DB winter, conditioned primarily by make-up air; air curtains with door actuation switches at exterior doors
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required, Grease interceptor
SECURITY	Card key access at exterior door, Window sash locks, Magnetic contacts at exterior door and windows
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-50

PROGRAM



Room Data Sheets

BARN DINING: PRODUCTION KITCHEN SODA ROOM / ICE MACHINE

GENERAL INFORMATION

Area for soda equipment and ice machine.

TOTAL ASF	82
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Receiving
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP with epoxy coving
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Soda carbonator
MOVABLE	Soda shelving, water filter, CO2 regulators, ice machine, and ice bin with mobile ice carts
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	HVAC; 0.15 cfm/sf ventilation, humidity sensor.
PLUMBING	Cold water, floor trough drain
SECURITY	Key access for Soda room
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

PROGRAM

Room Data Sheets

BARN DINING: PRODUCTION KITCHEN HOT PRODUCTION (COOK LINE & GRILLE)

GENERAL INFORMATION:

Grill line adjacent to Servery with pass-through window for finished products;
Bulk hot production line to include finish baking capability.

DIAGRAM ON FOLLOWING PAGE

TOTAL ASF	561
NUMBER OF OCCUPANTS	3
ADJACENCIES	Cold Prep, Servery, Refrigerated Storage, Frozen Storage
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	Aluminum
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	36" clamshell grill (2), exhaust hoods, double-stacked combi-oven (2), double-stacked convection oven, 6-burner range with oven
FIXED	Pot racks, sheet pan storage, fryer (4) with filter and pump to oil collection tank, freezer, under counter prep refrigerator, expediter counter with crumb rail, 3-pan hot food well
MOVABLE	Bun racks
OTHER	Chef's counter, 40-gallon tilting skillet, 25-gallon tilting kettle, pressure fryer (2), vertical toaster

BUILDING SYSTEMS

DAYLIGHTING	North facing clerestory windows.
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	48" recessed fluorescent fixtures with plastic lens covers, occupancy sensors; exhaust hoods will have internal lighting
MECHANICAL	HVAC / Exhaust / Chilled water supply and return; HVAC maintains internal temperature of 75°F DB summer and 70°F DB winter, make-up air will be tempered; air curtains with door actuation switches at exterior doors
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required, Grease interceptor
SECURITY	Card key access at exterior door, Window sash locks, Magnetic contacts at exterior doors and windows
FIRE PROTECTION	R-102 / UL-300, cooking fire protection system
VOICE/DATA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-50

PROGRAM


Room Data Sheets

BARN DINING: PRODUCTION KITCHEN

COLD PREP & HOT PRODUCTION (COOK LINE & GRILLE)

SCALE 1/8" = 1'-0"

- ① WORK COUNTER, FOOD PROCESSOR, SALAD DRYERS, DOUBLE SINKS, DOUBLE WALL SHELVES, MOBILE PAN RACK
- ② DOUBLE SIDED WORK COUNTER, DOUBLE OVERSHELVES, SLICER, FOOD CHOPPER, MIXER, 20 QT, SINK, TRASH CONTAINER, MOBILE PAN RACKS
- ③ DOUBLE SIDED WORK COUNTER, DOUBLE OVERSHELVES, DOUBLE UNDERCOUNTER, REFRIGERATOR WITH COLD PAN RAIL, TRASH CONTAINER, HAND SINK
- ④ PARTIAL DOUBLE SIDED WORK COUNTER, DOUBLE OVERSHELVES, OVERHEAD POT RACK, SINKS, CATERING CART (6)
- ⑤ DOUBLE COMBI OVEN, DOUBLE CONVECTION OVEN, PRESSURE FRYER (2), TILTING SKILLET, 40 GAL, TILTING KETTLE, 40 GAL, SIX BURNER RANGE WITH OVEN, EXHAUST HOOD WITH FIRE SUPPRESSION SYSTEM
- ⑥ CLAM SHELL GRILL (2 TRIPLE PLATEN), FRYER (3), FRYER DUMP STATION (2), BUN TOASTER, BUN RACK, HAND SINK
- ⑦ DOUBLE SIDED EXPEDITOR COUNTER, OVER SHELF, DOUBLE UNDERCOUNTER REFRIGERATOR WITH COLD PAN RAIL, HOT FOOD WELL, 3 PAN, FREEZER



PROGRAM


Room Data Sheets

BARN DINING: PRODUCTION KITCHEN REFRIGERATED STORAGE - BULK FOOD

GENERAL INFORMATION

Walk-in refrigerated storage.

TOTAL ASF	120
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Receiving, Cold Prep
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Insulated panels
WALLS / BASE	Insulated panels
FLOORS	Insulated panels, stainless steel with stainless steel Diamond plate flooring
WINDOWS	NA
DOORS	Insulated with windows
DOOR FRAMES	Part of Cold Room

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Walk-in cooler / evaporator coil
MOVABLE	Shelving, Dunnage Racks
OTHER	Remote compressor, temperature alarm, temperature and door monitoring system

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Ventilation
PLUMBING	Waste -- indirect, 36" trench drain outside of door
SECURITY	NA
FIRE PROTECTION	Sprinkler with freeze protection
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

PROGRAM

Room Data Sheets


BARN DINING: PRODUCTION KITCHEN

REFRIGERATED STORAGE - FINISHED PRODUCT COOLER

GENERAL INFORMATION

Walk-in refrigerated storage.

TOTAL ASF	120
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Receiving, Cold Prep
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Insulated panels
WALLS / BASE	Insulated panels
FLOORS	Insulated panels, stainless steel with stainless steel Diamond plate flooring
WINDOWS	NA
DOORS	Insulated with windows
DOOR FRAMES	Part of Cold Room

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Ventilation
PLUMBING	Waste -- indirect, 36" trench drain outside of door
SECURITY	NA
FIRE PROTECTION	Sprinkler with freeze protection
VOICE/DATA	NA
MEDIA	NA

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Walk-in cooler / evaporator coil
MOVABLE	Adjustable, Washable Plastic Shelving (Cambro) and Dunnage racks
OTHER	Remote compressor, temperature alarm, temperature and door monitoring system

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

PROGRAM


Room Data Sheets

BARN DINING: PRODUCTION KITCHEN FROZEN STORAGE

GENERAL INFORMATION

Walk-in frozen storage

TOTAL ASF	120
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Receiving, Cold Prep
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Insulated panels
WALLS / BASE	Insulated panels
FLOORS	Insulated panels, stainless steel with stainless steel Diamond plate flooring
WINDOWS	NA
DOORS	Insulated with windows
DOOR FRAMES	Part of Cold Room

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Walk-in freezer / evaporator coil
MOVABLE	Shelving and Dunnage racks
OTHER	Remote compressor, temperature alarm, temperature and door monitoring system

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Ventilation
PLUMBING	Waste -- indirect, 36" trench drain outside of door
SECURITY	NA
FIRE PROTECTION	Sprinkler with freeze protection
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

PROGRAM

Room Data Sheets

BARN DINING: PRODUCTION KITCHEN DRY STORAGE - FOOD

GENERAL INFORMATION

Dry storage for bulk food items.

TOTAL ASF	340
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Receiving
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP
FLOORS	Epoxy with coving
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT


BUILT-IN	NA
FIXED	NA
MOVABLE	Adjustable, Washable Plastic Shelving (Cambro)
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase convenience receptacle
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	HVAC; 0.15 cfm/sf ventilation, humidity sensor
PLUMBING	Floor drain
SECURITY	Key access
FIRE PROTECTION	Sprinkler with freeze protection
VOICE/DATA	1 phone/ 1 data (for desk and work station to be added later)
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55



Room Data Sheets


BARN DINING: PRODUCTION KITCHEN

CATERING STORAGE

GENERAL INFORMATION

Storage for catering equipment.

TOTAL ASF	63
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Receiving
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-INNA	
FIXED	NA
MOVABLE	Adjustable, Washable Plastic Shelving (Cambro) and Dunnage racks
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase, Quad receptacle at POS
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.v
MECHANICAL	HVAC; 0.15 cfm/sf ventilation, humidity sensor.
PLUMBING	Floor drain
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

PROGRAM


Room Data Sheets

BARN DINING: PRODUCTION KITCHEN RECEIVING, RECYCLING, AND OUTBOUND STAGING AREA

GENERAL INFORMATION

Receiving; outbound cart marshalling.

TOTAL ASF	160
NUMBER OF OCCUPANTS	1
ADJACENCIES	Loading Dock
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Epoxy poured floor
WINDOWS	NA
DOORS	Hollow metal painted door, Vision panels
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	Food waste and compostable bins (exterior), compactor
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Recessed downlights rated for outdoor use or ceiling mounted linear fluorescents, 20-30 FC. Controlled via switch and Occupancy Sensor.
MECHANICAL	HVAC, Exhaust, Air curtains with door actuation switches at exterior doors
PLUMBING	NA
SECURITY	Card key access, Magnetic contacts at exterior doors, Camera at dock, interior and exterior doors
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA
ACOUSTICS	
ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

PROGRAM

Room Data Sheets

BARN DINING: WAREWASHING DISHWASHING AND POT-WASHING COMBINED

GENERAL INFORMATION

Space includes chemical storage.

TOTAL ASF	127
NUMBER OF OCCUPANTS	2
ADJACENCIES	Cold Prep
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, stainless steel flashing, epoxy coving
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT


BUILT-IN	NA
FIXED	Conveyor dishmachine, scrap collector, utensil sinks with Power Soak, hand sink, wall shelves, eye wash station
MOVABLE	Tray dollies, trash containers
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	North facing clerestory windows
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	48" recessed fluorescent fixtures with plastic lens covers, occupancy sensors
MECHANICAL	HVAC. Provide exhaust air at a rate of at least 0.7 cfm/sf with stainless steel duct, sloped down towards appliance. Make-up air from adjoining spaces.
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required, Eye wash station
SECURITY	Key access for chemical storage
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-50



PROGRAM

Room Data Sheets

BARN DINING: WAREWASHING JANITOR'S CLOSET FOR KITCHEN

GENERAL INFORMATION

Storage of cleaning and janitorial supplies.

TOTAL ASF	32
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Cold Prep
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Epoxy
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT


BUILT-IN	NA
FIXED	Mop sink, mop rack, cleaning equipment storage also includes chemical storage, eye wash station
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust 6 air changes per hour, meet LEED requirement for indoor chemical control; require full height partitions
PLUMBING	Hot / cold water, waste, eye wash station
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA



PROGRAM

Room Data Sheets

BARN DINING: BACK OF HOUSE SUPPORT CHANGING ROOM & LOCKERS (UNISEX)

GENERAL INFORMATION

TOTAL ASF	77
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Receiving
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Paint or lay-in
WALLS / BASE	Paint, epoxy coving
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT


BUILT-IN	(18) 36" lockers (2-tier) for staff and (16) 18" lockers (4-tier) for students
FIXED	NA
MOVABLE	Changing bench, mirror
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Surface mounted linear fluorescent with acrylic lens. Controlled via Occupancy Sensor/Switch.
MECHANICAL	HVAC, exhaust at minimum 0.5 CFM/sf per code
PLUMBING	NA
SECURITY	Card key access, padlock type lockers
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 1 data
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-45



PROGRAM

Room Data Sheets

BARN DINING: BACK OF HOUSE SUPPORT MANAGER'S & PRODUCTION OFFICE

GENERAL INFORMATION

3 work stations shared by: 1 Senior Mgr., 1 Entertainment Mgr., 1 Principal Supervisor (Barn), and 1 Principal Cook (Barn).


TOTAL ASF	123
NUMBER OF OCCUPANTS	See above
ADJACENCIES	Receiving
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Paint or lay-in
WALLS / BASE	Paint, epoxy coving
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	Aluminum or skylight
DOORS	Hollow metal painted door Vision panel
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	Safe, desk and upper shelving
FIXED	Desks, storage cabinet
MOVABLE	Copy Machine, printer
OTHER	NA



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows where possible
ELECTRICAL	120 V / 1 Phase
LIGHTING	Direct/Indirect linear pendants, 10-20 FC. Task lights 30-40 FC. Controlled via Occupancy Sensor/Switch.
MECHANICAL	HVAC; group offices on a common zone for temperature control independent from Kitchen prep area.
PLUMBING	NA
SECURITY	Key access, Window sash locks, Magnetic contacts at safe and exterior windows, Camera over cash counting area
FIRE PROTECTION	Sprinkler
VOICE/DATA	3 phone (at least one at each work station) / 4 data (at least one on each wall)
MEDIA	Intercom station

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM


Room Data Sheets

BARN DINING: BACK OF HOUSE SUPPORT STORAGE - WEST COURTYARD TABLES & CHAIRS

GENERAL INFORMATION

Furniture storage for West Courtyard Dining Seating. Required size pending type of furniture to be used; furniture storage for west Courtyard was considered in the DPP Update and will be further studies during the design phases.

TOTAL ASF	160
NUMBER OF OCCUPANTS	NA
ADJACENCIES	West Courtyard, BBQ, Restrooms
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Exterior grade plywood
FLOORS	Concrete
WINDOWS	NA
DOORS	FSC certified solid-core wood door painted
DOOR FRAMES	Hollow metal painted

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	NA
PLUMBING	NA
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	Carts for chair storage
OTHER	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

PROGRAM


Room Data Sheets

BARN DINING: BACK OF HOUSE SUPPORT STAGE POWER & DIMMERS FOR OUTDOOR STAGE

GENERAL INFORMATION

Serves Outdoor Stage at West Courtyard.

TOTAL SF	45
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Indoor Stage, Outdoor Stage, away from acoustically sensitive spaces
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Open to structure
WALLS / BASE	Gypsum board; epoxy, stainless steel or ceramic tile coving -- to be determined during design
FLOORS	Sealed concrete
WINDOWS	NA
DOORS	Wood or hollow metal
DOOR FRAMES	Hollow metal

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Lighting and electrical equipment
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120/208 V / 3 Phase power breakers, relays, processor and dimmers
LIGHTING	Surface mounted fluorescents with acrylic lens. 30-40 FC. Occupancy Sensor/Switch.
MECHANICAL	Exhaust air and ventilation
PLUMBING	NA
SECURITY	Card key access, Magnetic contacts at exterior doors
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	Dimmers and racks for Outdoor Stage

ACOUSTICS

ACOUSTICAL MEASURES	Vibration isolation
BACKGROUND NOISE CRITERIA	NA
AUDIOVISUAL	NA

PROGRAM

Room Data Sheets

BARN DINING: SERVING SERVING AREA

GENERAL INFORMATION

Exhibition kitchen and servery, 4 exhibition production platforms (salad / cold sandwich, hot sandwich / specialty, grill, pizza / woodstone oven).


TOTAL ASF	800
NUMBER OF OCCUPANTS	5
ADJACENCIES	Dining, Kitchen
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Drop; washable
WALLS / BASE	Washable; epoxy, stainless steel or ceramic tile coving -- to be determined during design
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-IN	Serving counter with lighted sneeze/breath guard, heat lamps, stainless steel cabinets with decorative inset panels
FIXED	Counters, pizza oven, refrigerator, large ceiling fans, hand sink, pizza prep refrigerator, heated shelf, refrigerated open display case, salad mixing station with cold rail, sink, bread drawers, undercounter heated cabinet, hot/cold well (2), hot well (3), carving station with lamp, plate shelves, undercounter refrigerator. All front counter equipment on curbs.
MOVABLE	Racks, pizza dough rack, trash cans
OTHER	Orange juice machine, glove box holders



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Roof monitors at Dining
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	Ceiling mount linear fluorescent with acrylic lens, 40-50 FC. Controlled via Occupancy Sensor/Switch
MECHANICAL	HVAC, Exhaust air at kitchen hoods with interlocked tempered make-up air; Air curtains with door actuation switches at exterior doors.
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	NA
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	2 data
MEDIA	Servery/Dining/Courtyard audio source equipment or control, LED menus at each station mounted from overhead or back walls

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-45

PROGRAM

Room Data Sheets

BARN DINING: SERVING CUSTOMER QUEUING

GENERAL INFORMATION

Serpentine queue system (next available cashier), 4 POS stations


TOTAL ASF	360
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Serving Area, Self-serve Condiments and Beverages
VIEWS	NA
MINIMUM CEILING HEIGHT	Open to existing structure
ACCESSIBILITY	Per code, angle columns require cane detection area.
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Open to trusses above
WALLS / BASE	Wood; epoxy, stainless steel or ceramic tile coving -- to be determined during design
FLOORS	Colored concrete
WINDOWS	Wood painted
DOORS	FSC certified solid-core wood door painted
DOOR FRAMES	Wood painted

FURNITURE + EQUIPMENT

BUILT-IN	POS (4)
FIXED	Large ceiling fans
MOVABLE	NA
OTHER	NA



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Roof monitors at Dining
ELECTRICAL	120 V / 1 Phase, Quad receptacle at each POS
LIGHTING	Downlights, Ceiling mount linear fluorescents, 30-40 FC. Controlled via central time clock system with override switches.
MECHANICAL	HVAC; air curtains with door actuation switches at exterior doors
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	Key access, Window sash locks, Magnetic contacts at exterior doors and windows, Camera at each POS
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	1 phone / 1 data at each POS, WAP
MEDIA	Speakers, Ceiling loudspeakers
ACOUSTICS	
ACOUSTICAL MEASURES	Sound absorbing ceiling treatment; remote refrigeration (i.e. no display cases with built-in condensers)
BACKGROUND NOISE CRITERIA	NC-40

PROGRAM

Room Data Sheets

BARN DINING: SERVING SELF-SERVE BEVERAGE COUNTER & QUEUING

GENERAL INFORMATION

TOTAL ASF	65
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Part of Customer Queuing at Servery, adjacent to Double-Sided Service Bar
VIEWS	NA
MINIMUM CEILING HEIGHT	Open to existing structure
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

SEE *CUSTOMER QUEUING* ROOM DATA SHEET FOR DIAGRAM OF SPACE

MATERIALS AND FINISHES

CEILING	Open to trusses above
WALLS / BASE	Washable
FLOORS	Colored concrete
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Counter, beverage equipment, large ceiling fans, stainless steel cabinets with decorative inset panels
MOVABLE	Soda/ice dispenser, double coffee machine, iced tea brewer, refrigerated grab-and-go display case

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Roof monitors at Dining
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	Downlights, Ceiling mount linear fluorescents, 30-40 FC. Controlled via central time clock system with override switches.
MECHANICAL	HVAC; air curtains with door actuation switches at exterior doors
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	NA
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	WAP
MEDIA	Ceiling loudspeakers

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment; remote refrigeration (i.e. no display cases with built-in condensers)
BACKGROUND NOISE CRITERIA	NC-40

PROGRAM

Room Data Sheets

BARN DINING: SERVING

SELF-SERVE CONDIMENT COUNTER & QUEUING

GENERAL INFORMATION

TOTAL ASF	65
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Part of Customer Queuing at Servery
VIEWS	NA
MINIMUM CEILING HEIGHT	Open to existing structure
ACCESSIBILITY	Per code

SEE *CUSTOMER QUEUING* ROOM DATA SHEET FOR
DIAGRAM OF SPACE

MATERIALS AND FINISHES

CEILING	Open to trusses above
WALLS / BASE	Themed
FLOORS	Colored concrete
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Counter, basket/tray return station, large ceiling fans, stainless steel counter/cabinets with decorative inset panels and built in condiment rail, condiment dispensing system and napkin dispensers. Cut outs for trash below as well as storage for back up condiments. Solid top such as corian or stone.
MOVABLE	Trash and recycling containers, oven, condiment pan, napkin dispensers
OTHER	Storage

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Roof monitors at Dining
ELECTRICAL	120 V / 1 Phase
LIGHTING	Downlights, Ceiling mount linear fluorescents, 30-40 FC. Controlled via central time clock system with override switches.
MECHANICAL	HVAC
PLUMBING	NA
SECURITY	Key access, Window sash locks, Magnetic contacts at exterior doors and windows
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	WAP
MEDIA	Ceiling loudspeakers

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment; remote refrigeration (i.e. no cases with built-in condensers)
BACKGROUND NOISE CRITERIA	NC-40

PROGRAM

Room Data Sheets

BARN DINING: INDOOR SEATING + STAGE INDOOR SEATING

GENERAL INFORMATION

Main interior dining area with 94 cafe style seats

TOTAL ASF	1,870
NUMBER OF OCCUPANTS	94
ADJACENCIES	Indoor Stage, Servery, West and East Courtyards
VIEWS	West and East Courtyards
MINIMUM CEILING HEIGHT	Open to existing structure
ACCESSIBILITY	Per code

MATERIALS AND FINISHES

CEILING	Open to trusses above
WALLS / BASE	Wood
FLOORS	Colored concrete
WINDOWS	Wood painted
DOORS	FSC certified solid-core wood door painted
DOOR FRAMES	Wood painted

FURNITURE + EQUIPMENT

BUILT-IN	Indoor Stage
FIXED	Audio speakers, television screens, oversized ceiling fans, station for trash, recycling and dish bussing for reuseable plastic baskets, limited serving vehicles.
MOVABLE	94 seats (cafe style), sound & lighting control
OTHER	NA

AUGUST 9, 2012

DIAGRAM OF SPACE FOUND ON FOLLOWING PAGE

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Roof monitors
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	50 - 60 FC, Photocell sensors to be used in rooms with abundant daylight. These are not mandated by T-24 but add to energy efficiency.
MECHANICAL	HVAC. Natural ventilation could cause music-to-exterior noise issues if area can separate from Food Service. Otherwise, mechanical ventilation. All 3 MEP options (see MEP programming narrative) apply here, but would prefer Option 2 for energy efficiency and overall sustainability. Air curtains with door actuation switches at exterior doors.
PLUMBING	NA
SECURITY	Key access, Window sash locks, Magnetic contacts at exterior doors and windows, Camera at location TBD
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	NA
MEDIA	Indoor Stage performance audio system similar to existing, reuse existing where feasible; manual pull-down projection screen at downstage edge; Audio presentation capability (e.g. one to four mics, audio for video) without deployment of large mixer or operator; Installed video projector; Background music for non-performance times

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM


Room Data Sheets

BARN DINING: INDOOR SEATING + STAGE

INDOOR SEATING

SCALE

1/8" = 1'-0"



PROGRAM


Room Data Sheets

BARN DINING: INDOOR SEATING + STAGE INDOOR STAGE

GENERAL INFORMATION

Stage open to interior Barn Seating Area for live performances. Includes a non-permanent location for sound mixing and lighting control. Sitalines will require further review during design.

TOTAL ASF	265
NUMBER OF OCCUPANTS	per code
ADJACENCIES	Indoor Seating, Green Room, Stage Audio Equipment & Storage
VIEWS	Indoor Seating
MINIMUM CEILING HEIGHT	Determined by existing structure, approx. 7' - 6"
ACCESSIBILITY	Per code, 1:12 sloped walkway
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Open to structure
WALLS / BASE	Architectural "backdrop"
FLOORS	Hardwood
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-IN	Stage lighting and sound
FIXED	Equipment attachment pipes at ceiling
MOVABLE	Stage lighting and sound
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Roof monitors at dining
ELECTRICAL	120/208 V / 3 Phase - see Production Systems Narrative
LIGHTING	see Production Systems Narrative
MECHANICAL	HVAC
PLUMBING	NA
SECURITY	Camera at location tbd
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	1 phone / 4 data, at least one on each wall
MEDIA	A/V feed to KUCR, roll down projection screen, ceiling mounted projector and speakers, performance audio system (possible reuse of existing), intercom station

ACOUSTIC

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM


Room Data Sheets

BARN DINING: INDOOR SEATING + STAGE STAGE AUDIO EQUIPMENT & STORAGE

GENERAL INFORMATION

For storage of equipment for Indoor Stage.

TOTAL ASF	40
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Outdoor Stage
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board, plywood impact protection to +4' - 0" A.F.F., backing for storage racks
FLOORS	Hardwood or linoleum
WINDOWS	NA
DOORS	FSC certified solid-core wood door painted or sliding
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Surface mounted downlights or direct fluorescent (depending on ceiling), 40-60 FC. Controlled via Switch/Occupancy Sensor
MECHANICAL	Exhaust air
PLUMBING	NA
SECURITY	Card key access, Magnetic contacts at exterior door, Camera
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	Study needed for possible equipment noise
BACKGROUND NOISE CRITERIA	NA

PROGRAM

Room Data Sheets

BARN DINING: INDOOR SEATING + STAGE GREEN ROOM

GENERAL INFORMATION

Space for performers before and after after a show.


TOTAL ASF	130
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Exterior, Indoor Stage, Indoor Dining
VIEWS	Secure
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board
FLOORS	Carpet
WINDOWS	NA
DOORS	FSC certified solid-core wood door with lite, painted, with one-way viewing window into Indoor Dining
DOOR FRAMES	Hollow metal

FURNITURE + EQUIPMENT

BUILT-IN	Counter, hand sink
FIXED	Lockers with built-in locks, low refrigerator
MOVABLE	Mirror, chairs and/or couch, coat rack
OTHER	NA



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase all walls; above/below counter
LIGHTING	Direct/indirect pendants, specialty lighting – lights around mirror, 30-50 FC. Occupancy Sensor/Switch.
MECHANICAL	HVAC, Individual zone control/thermostat.
PLUMBING	Hot and cold water
SECURITY	Card key access, Magnetic contacts at exterior door, Camera at exterior door
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 4 data, at least one on each wall
MEDIA	Intercom station, wall-mounted monitor for performance monitor use (feed from stage camera)

ACOUSTICS

ACOUSTICAL MEASURES	Carpet or sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM


Room Data Sheets

BARN DINING: INDOOR SEATING + STAGE TICKET BOOTH

GENERAL INFORMATION

Area for ticket sales and distributing performance information.

TOTAL ASF	96
NUMBER OF OCCUPANTS	2
ADJACENCIES	Barn interior, West and East Courtyards
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Open to trusses above
WALLS / BASE	Wood
FLOORS	Wood
WINDOWS	Wood painted
DOORS	FSC certified solid-core wood door painted
DOOR FRAMES	Wood painted

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Controlled Daylight
ELECTRICAL	120 V / 1 Phase, Quad receptacle at each POS
LIGHTING	Direct/indirect pendants with downlight above counter, 35-50 FC. Occupancy Sensor/ Switch.
MECHANICAL	HVAC. Individual temperature control.
PLUMBING	NA
SECURITY	Window sash locks, Magnetic contacts at exterior windows, Security camera at each POS
FIRE PROTECTION	Sprinkler
VOICE/DATA	2 phone / 4 data, at least one on each wall
MEDIA	Intercom station

FURNITURE + EQUIPMENT

BUILT-IN	Sales desk with cable grommets, ticket windows (2)
FIXED	Safe, POS (2), Ticketmaster terminals (2)
MOVABLE	File cabinets
OTHER	Floor safe

ACOUSTICS

ACOUSTICAL MEASURES	Carpet or sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35


Room Data Sheets

BARN DINING: NON-ASSIGNABLE SPACES MECHANICAL

GENERAL INFORMATION

Main mechanical room for the entire complex.

TOTAL NON-ASF	200
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Exterior
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Metal decking
WALLS / BASE	Plywood
FLOORS	Colored concrete
WINDOWS	NA
DOORS	Hollow metal painted
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120/208 V, 3 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Heat exchange equipment, pumps, expansion tanks, metering for Barn Dining
PLUMBING	Drains, gas, water
SECURITY	Key access, Magnetic contacts at exterior doors
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 1 data, at least one on each wall
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA


PROGRAM

Room Data Sheets

BARN DINING: NON-ASSIGNABLE SPACES TELECOM CLOSET/ELECTRICAL ROOM

GENERAL INFORMATION

TOTAL NON-ASF	120 SF Telecom and 66 SF Electrical
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Mechanical Room, Transformer
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Metal decking
WALLS / BASE	Plywood
FLOORS	Colored concrete
WINDOWS	NA
DOORS	Hollow metal painted
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust
PLUMBING	NA
SECURITY	Key access, Magnetic contacts at exterior doors
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 1 data
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM

Room Data Sheets

BARN DINING: NON-ASSIGNABLE SPACES PUBLIC RESTROOMS (2)

GENERAL INFORMATION

Restroom for public as well as Barn Dining employees.


TOTAL NON-ASF	300 SF
NUMBER OF OCCUPANTS	NA
ADJACENCIES	West Courtyard, Kitchen Addition
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Metal decking
WALLS / BASE	Tile
FLOORS	Colored concrete
WINDOWS	Aluminum skylights
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	Restroom fixtures and accessories.
FIXED	NA
MOVABLE	NA
OTHER	NA



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Skylights or Roof monitors, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Surface mounted fluorescents above mirrors, downlights in the aisle ways with acrylic lens. 30-40 FC. Occupancy Sensor/Switch.
MECHANICAL	Exhaust air and ventilation, heating, fan
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	Key access, Magnetic contacts at exterior doors
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-45

PROGRAM

Room Data Sheets

BARN DINING: NON-ASSIGNABLE SPACES JANITOR'S CLOSET FOR RESTROOMS

GENERAL INFORMATION

Storage of cleaning and janitorial supplies.

TOTAL NON-ASF	42
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Loading Dock, West Courtyard
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Epoxy
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT


BUILT-IN	NA
FIXED	Mop sink, mop rack, cleaning equipment storage also includes chemical storage, eye wash station
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust 6 air changes per hour, meet LEED requirement for indoor chemical control; require full height partitions
PLUMBING	Hot / cold water, waste, eye wash station
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA



PROGRAM

Room Data Sheets

BARN DINING: PROGRAMMABLE OUTDOOR SPACE EAST COURTYARD

GENERAL INFORMATION

Dining, circulation, and gathering space east of Barn Dining (48 seats) and north of the Cottage (50 seats); 98 seats total. Cafe-style seating, Bussing Stations.

TOTAL SF	3,140 SF Combined with South Cottage Patio
NUMBER OF OCCUPANTS	TBD
ADJACENCIES	Barn Dining, Cottage, Barn Walk, Barn Annex
VIEWS	NA
MINIMUM CEILING HEIGHT	NA
ACCESSIBILITY	Per code
SCALE	1" = 30'-0"

MATERIALS AND FINISHES

CEILING	NA
WALLS / BASE	NA
FLOORS	NA
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT


BUILT-IN	Shade structures / trellis, fences and gates
FIXED	Station for trash, recycling and dish bussing for reusable plastic baskets and limited serving vehicles
MOVABLE	Tables and chairs, condiment counter for patio with built in condiment dispensing system, condiment rail, napkin dispensers, cut-out for trash containers below and lockable storage below
OTHER	Landscape planters

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	
ELECTRICAL	Outdoor electrical outlets for special events
LIGHTING	Outdoor lighting
MECHANICAL	Heaters
PLUMBING	NA
SECURITY	Key access at gates, Cameras at location TBD
FIRE PROTECTION	Sprinklers at covered areas
VOICE/DATA	WAP
MEDIA	Outdoor loudspeakers

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA



PROGRAM

Room Data Sheets

BARN DINING: PROGRAMMABLE OUTDOOR SPACE WEST COURTYARD

GENERAL INFORMATION

Dining and circulation space west of Barn Dining. Mix of standing, seating, and table seating, BBQ and Condiment Counter (see separate room data sheets), A/V and Stage Control Movable Platform (location to be studied during design).

TOTAL SF	5,348 SF total (3,255 SF available Dining Seating) 162 people at 20sf/p at table seating for dining (max. lunch capacity) 217 people at 15sf/p at row seating for a show 460 people at 7sf/p standing (max. event capacity) Potential seating arrangement for 72 people dining as shown
NUMBER OF OCCUPANTS	Maximum 460 people standing
ADJACENCIES	Outdoor Stage, Faculty/Staff Dining Facility, Barn
VIEWS	NA
MINIMUM CEILING HEIGHT	14' - 0" clearance for shade structure
ACCESSIBILITY	Per code
SCALE	1" = 30' - 0"

MATERIALS AND FINISHES

CEILING	NA
WALLS / BASE	NA
FLOORS	NA
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA


FURNITURE + EQUIPMENT

BUILT-IN	14' - 0" high clearance for shade structure
FIXED	Trash, recycling, dish bussing station
MOVABLE	Stage control movable, foldable platform, condiment counter
OTHER	Landscape planters, seat walls, ramps, steps

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	Outdoor electrical outlets for special events
LIGHTING	Outdoor lighting
MECHANICAL	Heaters
PLUMBING	NA
SECURITY	Key access at gates, cameras at locations tbd
FIRE PROTECTION	Sprinklers at covered areas
VOICE/DATA	WAP
MEDIA	See Outdoor Stage room data sheet for additional requirements

ACOUSTICS--see Acoustical Systems Narrative



PROGRAM


Room Data Sheets

BARN DINING: PROGRAMMABLE OUTDOOR SPACE OUTDOOR BBQ

GENERAL INFORMATION

Outdoor area for the preparation and sales of BBQ and other food items.

TOTAL SF	80
NUMBER OF OCCUPANTS	NA
ADJACENCIES	West Courtyard, service entrance to Kitchen Addition
VIEWS	NA
MINIMUM CEILING HEIGHT	NA
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	NA
WALLS / BASE	NA
FLOORS	Colored concrete
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Counter, BBQ, hand sink, POS (1), sneeze guard with heat lamps under counter refrigerator, undercounter shelving / bread racks. Hood and flue may not be needed, will be studied further during design phases.
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120/208 V / 3 Phase, Quad receptacle at POS, outlet at front counter
LIGHTING	Outdoor
MECHANICAL	Exhaust
PLUMBING	Hot / cold water, gas, waste
SECURITY	Key access for equipment and POS, Camera at POS, panic (may be remote)
FIRE PROTECTION	Cooking fire protection system
VOICE/DATA	1 phone / 2 data for POS and Credit Cards
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM

Room Data Sheets

BARN DINING: PROGRAMMABLE OUTDOOR SPACE OUTDOOR CONDIMENT COUNTER

GENERAL INFORMATION


TOTAL SF	20
NUMBER OF OCCUPANTS	NA
ADJACENCIES	West Courtyard
VIEWS	NA
MINIMUM CEILING HEIGHT	NA
ACCESSIBILITY	Per code

MATERIALS AND FINISHES

CEILING	NA
WALLS / BASE	NA
FLOORS	Colored concrete
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-IN	Stainless steel with solid top. Condiment dispensing system, condiment rail, napkin dispensers, lockable storage
FIXED	Counter, basket/tray return station, large ceiling fans
MOVABLE	Trash and recycling containers, oven, condiment pan, napkin dispensers
OTHER	Storage



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Roof monitors at Dining
ELECTRICAL	120 V / 1 Phase
LIGHTING	Downlights, Ceiling mount linear fluorescents, 30-40 FC. Controlled via central time clock system with override switches.
MECHANICAL	NA
PLUMBING	NA
SECURITY	NA
FIRE PROTECTION	NA
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM

Room Data Sheets

BARN DINING: NON-PROGRAMMABLE OUTDOOR SPACE COVERED LOADING DOCK AREA & LOADING DOCK

GENERAL INFORMATION

TOTAL SF	3,465
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Production Kitchen / Storage
VIEWS	NA
MINIMUM CEILING HEIGHT	NA
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	NA
WALLS / BASE	NA
FLOORS	Concrete slab at covered area, asphalt
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT


BUILT-IN	3 bays: 2 vehicle, 1 trash/recycling (compactor, trash dumpster, recycling cotainers for oil waste, paper, compostables); mat/cart washing area
FIXED	Space for Food Digester and electrical require ments required to operate. Bulk CO ² . Remote Oil Waste Collection System. Hose Reel Assembly
MOVABLE	Space for soiled linens, beverage and milk crates, minimal food service equipment and carts, bread racks, Waste Caddy
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	Area light
MECHANICAL	NA
PLUMBING	Hot/cold water, grease waste
SECURITY	Locking gates, Camera's overhead aimed at doors
FIRE PROTECTION	NA
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA



PROGRAM

Room Data Sheets

EAST COURTYARD RESTROOMS: NON ASSIGNABLE SPACES PUBLIC RESTROOMS (2)

GENERAL INFORMATION

Restroom for public as well as Barn Dining employees. See separate sheet for Janitor's Closet (Non-ASF).

TOTAL NON-ASF	760 SF
NUMBER OF OCCUPANTS	NA
ADJACENCIES	East Courtyard, Barn Walk
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Metal decking
WALLS / BASE	Tile
FLOORS	Colored concrete
WINDOWS	Aluminum skylights
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT


BUILT-IN	Restroom fixtures and accessories.
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Skylights or Roof monitors, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Surface mounted fluorescents above mirrors, downlights in the aisle ways with acrylic lens. 30-40 FC. Occupancy Sensor Switch
MECHANICAL	Exhaust air and ventilation, heating, fan
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	Key access, Magnetic contacts at exterior doors
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-45



PROGRAM


Room Data Sheets

EAST COURTYARD RESTROOMS: NON-ASSIGNABLE SPACES JANITOR'S CLOSET FOR RESTROOMS

GENERAL INFORMATION

Storage of cleaning and janitorial supplies.

TOTAL NON-ASF	32
NUMBER OF OCCUPANTS	NA
ADJACENCIES	East Courtyard, Barn Walk
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Epoxy
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Mop sink, mop rack, cleaning equipment storage also includes chemical storage, eye wash station
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust 6 air changes per hour, meet LEED requirement for indoor chemical control; require full height partitions
PLUMBING	Hot / cold water, waste, eye wash station
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM


Room Data Sheets

BARN STABLE MEETING ROOM

GENERAL INFORMATION

50 seats; flexible multipurpose room for weddings, parties, meetings, and lectures.

TOTAL ASF	868
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Barn Stable Patio, Lobby, Bar, Kitchen
VIEWS	Barn Stable Patio
MINIMUM CEILING HEIGHT	10'-0"
ACCESSIBILITY	Per code
SCALE	1/16" = 1'-0"



MATERIALS AND FINISHES

CEILING	Exposed existing wood structure and reinforced original metal roofing
WALLS / BASE	Wood slats over acoustical cloth
FLOORS	Wood
WINDOWS	Wood; operable
DOORS	FSC certified solid-core wood door painted with vision glazing
DOOR FRAMES	Wood painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Sunshade, projection screen in ceiling
MOVABLE	Tables and chairs
OTHER	Sliding barn door

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Direct/indirect pendants. Downlights above any presentation wall. 40-50 FC. Occupancy Sensor/Switch.
MECHANICAL	HVAC. Individual zone control/thermostat. Ventilation at 15 CFM / person; room to be on own zone control; CO2 sensors for demand control ventilation; Air curtains with door actuation switches at exterior doors
PLUMBING	NA
SECURITY	Card key access, Window sash locks, Magnetic contacts at exterior doors and windows
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	1 phone / 4 data, at least one on each wall, WAP
MEDIA	Ceiling loudspeakers; roll-down projection screen; ceiling-mounted video projector

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment, acoustical wall treatment
BACKGROUND NOISE CRITERIA	NC-25


Room Data Sheets

BARN STABLE BAR

GENERAL INFORMATION

Full service bar with ability to secure, with lockable shutters.

TOTAL ASF	100
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Meeting, Lobby, Kitchen
VIEWS	Meeting
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Exposed existing wood structure and reinforced original metal roofing; possible wood slats overhead
WALLS / BASE	Painted gypsum board
FLOORS	Epoxy
WINDOWS	NA
DOORS	FSC certified solid-core wood door painted
DOOR FRAMES	Wood painted

FURNITURE + EQUIPMENT

BUILT-IN	Bar top and die with beer taps, POS (1), undercounter ice maker; back bar to include undercounter refrigeration, undercounter dishwasher and bar sink, wire rack for liquor storage (secure)
FIXED	NA
MOVABLE	Wood shutters for locking bar when not in use
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL LIGHTING	120 V / 1 Phase, Quad receptacle at POS Downlights, Ceiling mount linear fluorescents, 30-40 FC. Controlled via central time clock system with override switches.
MECHANICAL HVAC	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
PLUMBING SECURITY	Key access shutters, Magnetic contacts at shutters and door to kitchen, Camera over POS, panic alarm
FIRE PROTECTION VOICE/DATA	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe 1 phone / 2 data (1 phone/ 1 data at POS, separate data for Credit Cards), not at each wall
MEDIA	Audio source (music) for Meeting Room loudspeakers
ACOUSTICS	
ACOUSTICAL MEASURES	Sound absorbing ceiling treatment; remote refrigeration (i.e. no display cases with built-in condensers)
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM

Room Data Sheets

BARN STABLE LOBBY

GENERAL INFORMATION


TOTAL ASF	328
NUMBER OF OCCUPANTS	
ADJACENCIES	Meeting, Bar, Restrooms
VIEWS	Barn Stable Patio
MINIMUM CEILING HEIGHT	10'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Acoustical wood slats
WALLS / BASE	Wood / gypsum board
FLOORS	Wood
WINDOWS	Aluminum
DOORS	Aluminum door with vision glazing at exterior, wood at interior
DOOR FRAMES	Aluminum, Wood painted at interior

FURNITURE + EQUIPMENT

BUILT-IN	Bench, coat check, reception
FIXED	NA
MOVABLE	Soft chairs
OTHER	NA



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Downlights, ceiling mount linear fluorescents, architectural sconces, 20-30 FC. Controlled via a central time clock system and provided with an override switch.
MECHANICAL	HVAC. Individual zone control/thermostat
PLUMBING	NA
SECURITY	Card key access, Window sash locks, Magnetic contacts at exterior doors and windows, Cameras at doors
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	1 phone / 1 data, at least one on each wall, wireless access point
MEDIA	Speakers

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM

Room Data Sheets

BARN STABLE KITCHEN

GENERAL INFORMATION

Finishing kitchen only, supported by Barn Dining Kitchen. Allows for catering events, including those held at Barn Stable.

TOTAL ASF	254
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Bar, Meeting
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES


CEILING	Vinyl-faced lay-in panels
WALLS / BASE	FRP
FLOORS	Epoxy
WINDOWS	Wood painted
DOORS	Wood painted
DOOR FRAMES	Wood painted

FURNITURE + EQUIPMENT

BUILT-IN	Cook line: exhaust hood, 1 two-basket fryer, 24" range and 24" griddle with oven below
FIXED	3-compartment sink, soiled pot shelving, clean pot shelving, 8-10' work counter with undercounter dishmachine for glassware, 1 wire rack shelf / lockable liquor storage, dry storage, 1 hand sink
MOVABLE	Plating table, 1-section roll-in refrigerator
OTHER	Cart parking area with electrical outlets

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	Ceiling mount linear fluorescent with acrylic lens, 40-50 FC. Controlled via Occupancy Sensor/Switch.
MECHANICAL	Exhaust air at kitchen hoods with interlocked tempered make-up air; control humidity with humidity sensors; air curtains with door actuation switches at exterior doors
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required, Gas, Grease waste
SECURITY	Card key access at exterior door, Window sash locks, Magnetic contacts at exterior door and windows, Camera at exterior door
FIRE PROTECTION	Cooking fire protection system, 120 V hard wired smoke detector, fire alarm mini-horn and strobe fire alarm mini-horn and strobe
VOICE/DATA MEDIA	1 phone / 1 data, at least one on each wall NA
ACOUSTICS	
ACOUSTICAL MEASURES	Dedicated in and out doors (single-swing with stops) to provide adequate door seals between Kitchen and Meeting
BACKGROUND NOISE CRITERIA	NC-45



PROGRAM


Room Data Sheets

BARN STABLE STORAGE

GENERAL INFORMATION

For storage of miscellaneous kitchen items and equipment.

TOTAL ASF	70
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Meeting, Kitchen
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	FRP
FLOORS	Epoxy
WINDOWS	NA
DOORS	Wood painted
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	Shelving
FIXED	NA
MOVABLE	Carts
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	0.15 CFM/sf ventilation
PLUMBING	NA
SECURITY	NA
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

PROGRAM


Room Data Sheets

BARN STABLE STORAGE FOR TABLES AND CHAIRS

GENERAL INFORMATION

For storage of round tables and folding chairs.

TOTAL ASF	250
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Meeting, Lobby
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	FRP
FLOORS	Epoxy
WINDOWS	NA
DOORS	FSC certified solid-core wood door painted
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	Carts for chair storage
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	HVAC; 0.15 CFM/sf ventilation
PLUMBING	NA
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS


ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

Room Data Sheets

BARN STABLE: NON-ASSIGNABLE SPACES MECHANICAL (TBD)

GENERAL INFORMATION

TOTAL NON-ASF	100
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Exterior
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board
FLOORS	Sealed concrete
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

BUILDING SYSTEM REQUIREMENTS


DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch
MECHANICAL	HVAC; 0.15 CFM/sf ventilation
PLUMBING	TBD
SECURITY	Key access, Magnetic contacts at exterior door
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 data
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

Room Data Sheets

BARN STABLE: NON-ASSIGNABLE SPACES TELECOM CLOSET



GENERAL INFORMATION

TOTAL NON-ASF	52
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Exterior
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board
FLOORS	Sealed concrete
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch
MECHANICAL	HVAC; 0.15 CFM/sf ventilation
PLUMBING	NA
SECURITY	Key access, Magnetic contacts at exterior door
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 1 data
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA



PROGRAM

Room Data Sheets

BARN STABLE: NON-ASSIGNABLE SPACES PUBLIC RESTROOMS (2)

GENERAL INFORMATION

TOTAL NON-ASF	150
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Lobby
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Tile
FLOORS	Tile
WINDOWS	Aluminum, Obscured
DOORS	FSC certified solid-core wood door painted
DOOR FRAMES	Hollow metal painted

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Surface mounted fluorescents above mirrors, downlights in the aisle ways with acrylic lens. 30-40 FC. Occupancy Sensor/Switch.
MECHANICAL	HVAC, exhaust air
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	Latch and closer
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

FURNITURE + EQUIPMENT

BUILT-IN	Restroom fixtures and accessories, provide shower in one restroom
FIXED	NA
MOVABLE	NA
OTHER	NA


ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-45

PROGRAM

Room Data Sheets

BARN STABLE: NON-ASSIGNABLE SPACES JANITOR'S CLOSET FOR RESTROOMS



GENERAL INFORMATION

Storage of cleaning and janitorial supplies.

TOTAL NON-ASF	20
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Restrooms, Lobby
VIEWS	NA
MINIMUM CEILING HEIGHT	8'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Epoxy
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Mop sink, mop rack
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust 6 air changes per hour, meet LEED requirement for indoor chemical control; require full height partitions
PLUMBING	Hot / cold water, waste
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM


Room Data Sheets

BARN STABLE: PROGRAMMABLE OUTDOOR SPACE PATIO

GENERAL INFORMATION

Dining, circulation, and gathering space outside Barn Stable. 44 seats; cafe-style seating, Bussing Stations.

TOTAL SF	875
NUMBER OF OCCUPANTS	TBD
ADJACENCIES	Lobby, Meeting
VIEWS	NA
MINIMUM CEILING HEIGHT	NA
ACCESSIBILITY	Per code
SCALE	1/16" = 1'-0"



MATERIALS AND FINISHES

CEILING	NA
WALLS / BASE	NA
FLOORS	NA
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	Electrical outlets for special events
LIGHTING	Outdoor lighting
MECHANICAL	Heaters
PLUMBING	NA
SECURITY	Fencing, gates with keyed entry
FIRE PROTECTION	NA
VOICE/DATA	Wireless access point
MEDIA	Outdoor speakers

FURNITURE + EQUIPMENT

BUILT-IN	Shade structures
FIXED	Trash, recycling and dish bussing station
MOVABLE	NA
OTHER	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM

Room Data Sheets

FACULTY/STAFF DINING DINING ROOM

GENERAL INFORMATION

Main interior dining area with 50 seats that includes a mixture of dining and soft seating.

TOTAL ASF	1,300
NUMBER OF OCCUPANTS	58 (including Bar seating)
ADJACENCIES	Food staging & set-up, Bar, Lobby (in space), Buffet (in space)
VIEWS	West Courtyard, view of minor importance
MINIMUM CEILING HEIGHT	10' - 0"
ACCESSIBILITY	Per code
SCALE	1/16" = 1'-0"

MATERIALS AND FINISHES

CEILING	Open to trusses above
WALLS / BASE	Wood slats over acoustical cloth
FLOORS	Wood, wood tile or epoxy -- to be determined during design
WINDOWS	Wood operable
DOORS	FSC certified solid-core wood doors and french doors painted
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT


BUILT-IN	Booths and benches
FIXED	Sunshade at clerestory windows on West wall, protection screens on lower windows
MOVABLE	Tables and chairs
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Clerestory windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Direct/indirect pendants. Downlights above any presentation wall. 40-50 FC. Occupancy Sensor/Switch.
MECHANICAL	HVAC. Individual zone control/thermostat. Ventilation at 15 CFM / person; room to be on own zone control; CO2 sensors for demand control ventilation; Air curtains with door actuation switches at doors to Back of House.
PLUMBING	NA
SECURITY	Card key access, Window sash locks, Magnetic contacts at exterior doors and windows
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	1 phone / 4 data, at least one on each wall, WAP
MEDIA	Projection screen; possible ceiling mounted projector, or portable would also work. Audio playback; laptop presentation support.

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment, acoustical wall treatment
BACKGROUND NOISE CRITERIA	NC-30



Room Data Sheets

FACULTY/STAFF DINING BUFFET SERVING AREA

GENERAL INFORMATION

Area for serving customers.


TOTAL ASF	192
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Dining Room, Food staging and set-up
VIEWS	Dining Room
MINIMUM CEILING HEIGHT	10' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Open to trusses above
WALLS / BASE	Wood slats over acoustical cloth
FLOORS	Wood, wood tile or epoxy -- to be determined during design
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-IN	Serving counter
FIXED	Hot / cold buffet counters
MOVABLE	30" - 36" by 80' - 0" Buffet serving table / sneeze guards required
OTHER	Possibly induction warmers and chafers



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Direct/indirect pendants. Downlights above any presentation wall. 40-50 FC. Occupancy Sensor/Switch.
MECHANICAL	HVAC. Individual zone control/thermostat. Ventilation at 15 CFM / person; room to be on own zone control; CO2 sensors for demand control ventilation
PLUMBING	NA
SECURITY	Card key access, Window sash locks, Magnetic contacts at exterior doors and windows
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	1 phone / 4 data, at least one on each wall, wireless access point
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-40 (open to dining room)

PROGRAM

Room Data Sheets

FACULTY/STAFF DINING: BACK OF HOUSE SUPPORT BEVERAGE SERVICE

GENERAL INFORMATION

Area for non-alcoholic beverages, soda equipment, and ice machine.

TOTAL ASF	80
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Dining Room, Food staging and set-up, service access
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 6"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Gypsum board painted or vinyl faced lay-in
WALLS / BASE	White FRP
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT


BUILT-IN	NA
FIXED	Soda carbonator, bag-in-box rack, soda shelving, water filter, ice machine, ice bin
MOVABLE	CO2 regulators, mobile ice carts
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	HVAC; 0.15 cfm/sf ventilation, humidity sensor.
PLUMBING	Cold water, floor trough drain
SECURITY	Key access for Soda room
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55



PROGRAM


Room Data Sheets

FACULTY/STAFF DINING: BACK OF HOUSE SUPPORT STORAGE

GENERAL INFORMATION

Storage for catering equipment.

TOTAL ASF	150
NUMBER OF OCCUPANTS	0
ADJACENCIES	Food staging and set-up, service access
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 6"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	White washable
WALLS / BASE	FRP, cove tile
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	NA
DOORS	Hollow metal, painted
DOOR FRAMES	Hollow metal

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	HVAC; 0.15 cfm/sf ventilation, humidity sensor.
PLUMBING	NA
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Storage shelving 3-tier, 18" d. x 54", 66", 78" h
MOVABLE	NA
OTHER	Carts (transport)

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-45


PROGRAM

Room Data Sheets

FACULTY/STAFF DINING: BACK OF HOUSE SUPPORT FOOD STAGING AND SET UP AREA

GENERAL INFORMATION

TOTAL ASF	200
NUMBER OF OCCUPANTS	2
ADJACENCIES	Service Corridor and Dining Room
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 6"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	White washable
WALLS / BASE	FRP / cove tile
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	Aluminum
DOORS	Hollow metal, painted
DOOR FRAMES	Hollow metal

FURNITURE + EQUIPMENT

BUILT-IN	Work counters with sink, wall cabinets, stainless steel work counters
FIXED	Refrigerator, hand sink, ice machine, ice/soda tower
MOVABLE	Carts, heated cabinet, mobile table
OTHER	Coffee machine, ice tea machine, glass/cup dollies, POS

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	North facing clerestory windows
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	48" recessed fluorescent fixtures with plastic lens covers, occupancy sensors
MECHANICAL	HVAC / Exhaust / Chilled water supply and return; conditioned primarily by make-up air
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required, Grease interceptor
SECURITY	Card key access at exterior door, Window sash locks, Magnetic contacts at exterior door and windows, Camera over POS
FIRE PROTECTION	Sprinkler
VOICE/DATA	2 phone / 2 data (1 phone / 2 data at POS)
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-45
AUDIOVISUAL	NA

PROGRAM

Room Data Sheets

FACULTY/STAFF DINING: BACK OF HOUSE SUPPORT DISHWASHING

GENERAL INFORMATION

Space includes chemical storage.

TOTAL ASF	150
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Dining Room, service access
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 6"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in, gypsum board painted, or ACT
WALLS / BASE	White FRP, stainless steel flashing
FLOORS	Anti-slip epoxy or Silikal
WINDOWS	Aluminum
DOORS	Hollow metal
DOOR FRAMES	Hollow metal

FURNITURE + EQUIPMENT


BUILT-IN	NA
FIXED	Dishmachine, scrap collector, utensil sinks, hand sink, wall shelves, eye wash station, 4-tier shelf, exhaust hood
MOVABLE	Dish dollies, trash containers
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	48" recessed fluorescent fixtures with plastic lens covers, occupancy sensors
MECHANICAL	HVAC. Provide exhaust air at a rate of at least 0.7 cfm/sf with stainless steel duct, sloped down towards appliance. Make-up air from adjoining spaces.
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required, Eye wash station, soft water for dishwasher
SECURITY	Key access for chemical storage
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTIC

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-50



PROGRAM

Room Data Sheets

FACULTY/STAFF DINING LOBBY

GENERAL INFORMATION

Entry and transition area into dining and soft seating.

TOTAL ASF	100
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Main Entrance/Dining Room, Restrooms
VIEWS	to North
MINIMUM CEILING HEIGHT	8' - 6"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Open to trusses above
WALLS / BASE	Wood slats over acoustical cloth
FLOORS	Wood
WINDOWS	Wood
DOORS	FSC certified solid-core custom wood door
DOOR FRAMES	Wood

FURNITURE + EQUIPMENT


BUILT-IN	Bench
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase
LIGHTING	Downlights, ceiling mount linear fluorescents, architectural sconces, 20-30 FC. Controlled via a central time clock system and provided with an override switch.
MECHANICAL	HVAC. Individual zone control/thermostat
PLUMBING	NA
SECURITY	Card key access, Window sash locks, Magnetic contacts at exterior doors and windows, cameras at door
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe
VOICE/DATA	1 phone / 1 data, at least one on each wall, Wireless Access Point
MEDIA	Speakers, possibly some digital signage for menus, events, etc.

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35



PROGRAM

Room Data Sheets

FACULTY/STAFF DINING BAR

GENERAL INFORMATION

Serves both interior and exterior; both have beer taps and bottled wine, with 10-15 beer taps on the exterior section and hard liquor on the interior; airtight barrier divides interior from exterior; staffed by one bartender. Includes Beer Supplies Closet.


TOTAL ASF	270 SF
NUMBER OF OCCUPANTS	1-2 bartenders (8 seats on interior bar included in Faculty/Staff Dining Room)
ADJACENCIES	Faculty/Staff Dining Room, Bar Support, West Courtyard
VIEWS	NA
MIN. CEILING HT.	8' - 6"
ACCESSIBILITY	Per code

MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in (or themed) or ACT
WALLS / BASE	Gypsum board or tile with tile or epoxy coving
FLOORS	Epoxy poured floor
WINDOWS	Aluminum or wood
DOORS	Hollow metal or aluminum
DOOR FRAMES	Hollow metal

FURNITURE + EQUIPMENT

BUILT-IN	POS (3)
FIXED	Hand sink, (3) 4-tap beer towers, glass storage, lockable wine / liquor storage, back bar refrigerator, (2) ice bin / soda guns, cup dispensers, espresso machine on dining side
MOVABLE	Trash containers, interior bar seating
OTHER	NA



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows, exterior sun shading where applicable
ELECTRICAL	120 V / 1 Phase, Quad receptacle at each POS
LIGHTING	Downlights, Ceiling mount linear fluorescents, 30-40 FC. Controlled via central time clock system with override switches.
MECHANICAL	HVAC; air curtains with door actuation switches at exterior windows
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	Window sash locks, Magnetic contacts at exterior windows, Camera at each POS, Lockable when building is open
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 2 data at each POS
MEDIA	Ceiling loudspeakers
ACOUSTICS	
ACOUSTICAL MEASURES	possible ACT ceiling as order-takers need a reasonable noise environments.
BACKGROUND NOISE CRITERIA	NC-40

PROGRAM

Room Data Sheets

FACULTY/STAFF DINING: BAR SUPPORT OFFICE & PACKAGING

GENERAL INFORMATION

Two workstations for Bar operations staff and shared safe.


TOTAL ASF	100
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Bar, Storage, service access
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 6"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Paint or lay-in
WALLS / BASE	Gypsum board, painted; Epoxy coving
FLOORS	Epoxy
WINDOWS	Aluminum or skylight
DOORS	Hollow metal painted door Vision panel
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	Safe, desk, shelving above
FIXED	Desks, storage cabinet
MOVABLE	Printer
OTHER	NA



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	Windows where possible
ELECTRICAL	120 V / 1 Phase
LIGHTING	Direct/Indirect linear pendants, 10-20 FC. Task lights 30-40 FC. Controlled via Occupancy Sensor/Switch.
MECHANICAL	HVAC; group offices on a common zone for temperature control independent from Kitchen prep area.
PLUMBING	NA
SECURITY	Key access, Window sash locks, Magnetic contacts at safe and exterior windows, Camera over cash counting area
FIRE PROTECTION	Sprinkler
VOICE/DATA	2 phone / 4 data, at least one on each wall
MEDIA	Intercom station at Production Office

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM


Room Data Sheets

FACULTY/STAFF DINING: BAR SUPPORT DRY STORAGE

GENERAL INFORMATION

Dry storage for bulk food items.

TOTAL ASF	80
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Bar, service access
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 6"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Epoxy poured floor
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	Lockers
FIXED	NA
MOVABLE	Washable, adjustable shelving (Cambro)
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase convenience receptacle
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	HVAC; 0.15 cfm/sf ventilation, humidity sensor
PLUMBING	NA
SECURITY	Key access
FIRE PROTECTION	Sprinkler with freeze protection
VOICE/DATA	1 voice/ 2 data
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55

PROGRAM

Room Data Sheets

FACULTY/STAFF DINING: BAR SUPPORT WALK-IN REFRIGERATOR & WINE COOLER

GENERAL INFORMATION

Walk-in refrigerated storage and wine cooler. Capacity for (12) 15.5-gallon kegs on dollies.

TOTAL ASF	150
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Bar, service access
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Insulated panels
WALLS / BASE	Stainless Steel insulated panels
FLOORS	Diamond plate insulated panels
WINDOWS	NA
DOORS	Insulated with windows
DOOR FRAMES	Part of Cold Room

FURNITURE + EQUIPMENT


BUILT-IN	NA
FIXED	Walk-in cooler / evaporator coil, wine storage
MOVABLE	Shelving
OTHER	Remote compressor, temperature alarm, beer refrigerator unit

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Ventilation
PLUMBING	Waste -- indirect, 36" trench drain outside of door
SECURITY	Lockable
FIRE PROTECTION	Sprinkler with freeze protection
VOICE/DATA	NA
MEDIA	NA

ACOUSTIC

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-55



PROGRAM

Room Data Sheets


FACULTY/STAFF DINING: BAR SUPPORT

JANITOR'S CLOSET FOR KITCHEN AND BAR

GENERAL INFORMATION

Storage of cleaning and janitorial supplies.

TOTAL ASF	40
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Dining Support
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 6"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in or gypsum Board
WALLS / BASE	White FRP; epoxy coving
FLOORS	Epoxy
WINDOWS	NA
DOORS	Hollow metal painted door, with vent at bottom
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Mop sink, mop rack, cleaning equipment storage also includes chemical storage, eye wash station
MOVABLE	Cleaning Caddy (22" x 24")
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust 6 air changes per hour, meet LEED requirement for indoor chemical control; require full height partitions
PLUMBING	Hot / cold water, waste, eye wash station
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM

Room Data Sheets

FACULTY/STAFF DINING: STAGE SUPPORT GREEN ROOM

GENERAL INFORMATION

Space for performers before and after a show.


TOTAL ASF	150
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Outdoor Stage, West Courtyard, Restroom
VIEWS	Secure
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"

MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board with rubber or wood base
FLOORS	Carpet
WINDOWS	NA
DOORS	FSC certified solid-core wood door with lite, painted
DOOR FRAMES	Wood

FURNITURE + EQUIPMENT

BUILT-IN	Counter
FIXED	Lockers, lockable safe, low refrigerator
MOVABLE	Mirror, chairs and/or couch, coat rack
OTHER	NA



BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase all walls; above/below counter
LIGHTING	Direct/indirect pendants, specialty lighting – lights around mirror, 30-50 FC. Occupancy Sensor/Switch.
MECHANICAL	HVAC, Individual zone control/thermostat.
PLUMBING	NA
SECURITY	Card key access, Magnetic contacts at exterior door, Camera at exterior door
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 4 data, at least one on each wall
MEDIA	Intercom station, wall-mounted monitor for performance monitor use (feed from stage camera)

ACOUSTICS

ACOUSTICAL MEASURES	Carpet or sound absorbing ceiling treatment
BACKGROUND NOISE CRITERIA	NC-35

PROGRAM


Room Data Sheets

FACULTY/STAFF DINING: STAGE SUPPORT OUTDOOR PERFORMANCE EQUIPMENT STORAGE

GENERAL INFORMATION

For storage of equipment for the Outdoor Stage.

TOTAL ASF	120
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Outdoor Stage
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board or open to structure
WALLS / BASE	Gypsum board, plywood impact protection to +4' - 0" A.F.F., backing for storage racks
FLOORS	Sealed concrete or linoleum
WINDOWS	NA
DOORS	FSC certified solid-core wood door painted or sliding
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Surface mounted downlights or direct fluorescent (depending on ceiling), 40-60 FC. Controlled via Switch/Occupancy Sensor
MECHANICAL	HVAC
PLUMBING	NA
SECURITY	Card key access, Magnetic contacts at exterior door, Camera
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 2 data, at least one near entry door
MEDIA	Intercom station

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM


Room Data Sheets

FACULTY/STAFF DINING: NON-ASSIGNABLE SPACES MECHANICAL / ELECTRICAL

GENERAL INFORMATION

Room to house HVAC and electrical equipment. Exterior access ok.

TOTAL NON-ASF	200
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Exterior
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board
FLOORS	Sealed concrete
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120/208 V / 3 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust
PLUMBING	TBD
SECURITY	Key access, Magnetic contacts at exterior doors
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 1 data
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	Possible sound-insulating construction to adjacent spaces.
BACKGROUND NOISE CRITERIA	NA

PROGRAM


Room Data Sheets

FACULTY/STAFF DINING: NON-ASSIGNABLE SPACES TELECOM CLOSET

GENERAL INFORMATION

Room to house telecommunications equipment. Exterior access ok.

TOTAL NON-ASF	100
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Exterior
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Gypsum board
FLOORS	Sealed concrete
WINDOWS	NA
DOORS	Hollow metal painted
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust, HVAC tbd
PLUMBING	NA
SECURITY	Key access, Magnetic contacts at exterior door
FIRE PROTECTION	Sprinkler
VOICE/DATA	1 phone / 1 data
MEDIA	NA

ACOUSTIC

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM


Room Data Sheets

FACULTY/STAFF DINING: NON-ASSIGNABLE SPACES PUBLIC RESTROOMS (2) + RESTROOM FOR GREEN ROOM

GENERAL INFORMATION

Unisex restrooms, one to be accessible only from Backstage Space. See separate Room Data Sheet for Janitor's Closet (Non-ASF).

TOTAL NON-ASF	110 SF Public Restrooms and 50 SF dedicated restroom for Green Room
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Lobby, Green Room, Exterior
VIEWS	NA
MINIMUM CEILING HEIGHT	8' - 0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Gypsum board
WALLS / BASE	Tile
FLOORS	Tile or colored concrete
WINDOWS	NA
DOORS	FSC certified solid-core wood doors painted
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	Restroom fixtures and accessories: 1 WC, 1 lav each
FIXED	NA
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Surface mounted fluorescents above mirrors, downlights in the aisle ways with acrylic lens. 30-40 FC. Occupancy Sensor/Switch.
MECHANICAL	HVAC, exhaust air
PLUMBING	Floor drain, Cold and hot water, Sanitary sewer for equipment as required.
SECURITY	Key access, shared Restroom to be lockable from both outside and the Green Room.
FIRE PROTECTION	Sprinkler, 120 V hard wired smoke detector, fire alarm mini-horn and strobe in shared area
VOICE/DATA	NA
MEDIA	NA
ACOUSTIC	
ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NC-45

PROGRAM


Room Data Sheets

FACULTY/STAFF DINING: NON-ASSIGNABLE SPACES JANITOR'S CLOSET FOR RESTROOMS

GENERAL INFORMATION

Storage of cleaning and janitorial supplies.

TOTAL NON-ASF	50
NUMBER OF OCCUPANTS	NA
ADJACENCIES	Public Restrooms, Lobby
VIEWS	NA
MINIMUM CEILING HEIGHT	9'-0"
ACCESSIBILITY	Per code
SCALE	1/8" = 1'-0"



MATERIALS AND FINISHES

CEILING	Vinyl faced lay-in
WALLS / BASE	White FRP, epoxy coving
FLOORS	Epoxy
WINDOWS	NA
DOORS	Hollow metal painted door
DOOR FRAMES	Hollow metal painted

FURNITURE + EQUIPMENT

BUILT-IN	NA
FIXED	Mop sink, mop rack, cleaning equipment storage also includes chemical storage, eye wash station
MOVABLE	NA
OTHER	NA

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	120 V / 1 Phase
LIGHTING	Utilitarian surface mounted linear fluorescents, 20-30 FC with acrylic lens. Controlled with Occupancy Sensor/Switch.
MECHANICAL	Exhaust 6 air changes per hour, meet LEED requirement for indoor chemical control; require full height partitions
PLUMBING	Hot / cold water, waste, eye wash station
SECURITY	Key access
FIRE PROTECTION	Sprinkler
VOICE/DATA	NA
MEDIA	NA

ACOUSTICS

ACOUSTICAL MEASURES	NA
BACKGROUND NOISE CRITERIA	NA

PROGRAM


Room Data Sheets

FACULTY/STAFF DINING: PROGRAMMABLE OUTDOOR SPACE OUTDOOR STAGE & STAGE CONTROL - LIGHTING (LT) & SOUND (SD)

GENERAL INFORMATION

Outdoor Stage for performances.

TOTAL SF	600
NUMBER OF OCCUPANTS	Per code
ADJACENCIES	West Courtyard, Equipment Storage, Green Room
VIEWS	West Courtyard
MINIMUM CEILING HEIGHT	10' - 0" at rear to 14' - 0" at front of stage
ACCESSIBILITY	Per code
SCALE	1" = 30' - 0"



MATERIALS AND FINISHES

CEILING	Open to structure
WALLS / BASE	Architectural backdrop
FLOORS	Sealed concrete
WINDOWS	NA
DOORS	NA
DOOR FRAMES	NA

FURNITURE + EQUIPMENT

BUILT-IN	Stage lighting and sound
FIXED	Foldable/rollable drum risers
MOVABLE	Stage lighting and sound, rental wood floor used for dance
OTHER	Equipment attachment points within ceiling canopy

BUILDING SYSTEM REQUIREMENTS

DAYLIGHTING	NA
ELECTRICAL	Outdoor electrical outlets for special events (see Production Systems Narrative)
LIGHTING	Truss-mounted moveable theatrical lighting (see Production Systems Narrative)
MECHANICAL	Some wired signal paths and pathways for temporary cabling from stage to mix position.
PLUMBING	NA
SECURITY	See West Courtyard room data sheet
FIRE PROTECTION	Sprinkler at covered areas
VOICE/DATA	1 phone / 4 data at LT & SD Booth, WAP
MEDIA	Large installed audio system, Roll-down projection screen, Truss-mounted Speakers and Projector, Camera for video feed. One or two 22" wide x 28" deep equipment racks required for audio/production equipment. Must be in an air-conditioned space (ductless OK).

ACOUSTICS

ACOUSTICAL MEASURES	Sound absorbing wall and canopy treatment, some level of sound insulating construction to Faculty/Staff Dining Room
---------------------	---

BACKGROUND NOISE CRITERIA NA

IV. SUPPORT DOCUMENTS

The architectural narrative begins to develop the character and materials of the buildings. Narratives that describe the systems that support the buildings are provided for civil, landscape, structural, food service, acoustical, mechanical, electrical, plumbing and code. Sustainability has been integrated with the discussions of building character, materials, and systems. The project will obtain at minimum a LEED Silver rating with the goal of being LEED Gold. Furthermore, the design phase should explore opportunities to demonstrate sustainable principles where possible.

System Narratives

ARCHITECTURAL

OVERVIEW

The Barn Project offers the opportunity to demonstrate that these well-used (and well-loved) existing structures have utility beyond being part of the historical record. Part found object, part new intervention, the Barn Project can be a model for sustainable adaptive reuse. This project should explore an unromantic attitude toward these structures, one that retains their integrity while addressing contemporary needs and sensibilities. To that end, the development should express what is new as new, and allow the spirit of the old to remain.

This project is conceived of as a compound of three existing historic barns (each to be renovated and added to), an historic cottage (to be relocated and renovated), and a new Faculty / Staff Dining Space. These buildings are to be interconnected through three significant new outdoor rooms. In order to be perceived as a compound of related structures and activities, it is very important that the material choices, massing strategies and connecting tertiary structures be thought of as a whole. To organize the various structures on the site, a coordinated hierarchy of building elements is proposed.

PRIMARY ELEMENTS

The three barns (called “The Barn”, “Barn Stable,” and “Barn Theater”) and the Cottage were part of the original Citrus Research Station that has become UCR. The Barn has a long history as an important performance venue on the campus. The overall character of this project is driven by a

desire to revive and repurpose these four buildings as the central elements in this new dining and entertainment compound.

The goal is to update these existing structures in the spirit of their original design. The vernacular and material strategies employed in the existing structures will be the basis for material decisions. It is desirable to maintain the essential character of each structure as it is repurposed, and in several cases relocated. The buildings are to be treated as working farm structures that are being given a new life.

The existing three barns are wood frame structures on concrete slabs, with painted wood siding (predominantly board and batten and some horizontal wood siding). The Cottage has painted horizontal wood siding. They are predominantly rectangular structures that vary in width and height, with overhangs on four sides. They have wood windows and doors and either asphalt shingle or corrugated metal roofs.

In the renovation of these structures the exterior siding will be repaired and re-used as much as possible. New double-glazed wood windows, with true divided lights, will replace existing windows. New wood doors in various configurations will replace existing and there will be a few large sliding barn doors with glazing. Additional openings will be added to provide daylight to the spaces that are frequently occupied. The roofs will be replaced with either new asphalt shingles or corrugated metal roofing. Cool roof materials will be utilized to minimize the site’s heat-island effect.

SECONDARY ELEMENTS

Significant additions are to be made to each barn, in some cases nearly equal in size to the original structures. These additions should be secondary and recessive in relation to the barns. They should be compatible with the barns, but distinct as additions. They should be developed as a “family” of additive elements, which relate to each other within the compound. All should have the same siding material. To contrast with the barns, horizontal metal or wood siding is recommended. Doors and windows should be metal (or wood if affordable). In order to address the varying eave heights of the existing structures they will most likely have flat roofs, with a durable, light colored single-ply membrane.

TERTIARY ELEMENTS

There are a variety of elements that are essential to knit the project into the site, to meet the functional requirements of the hybrid program, and to address the uniqueness of the existing buildings while still conveying an overall sense of place. The most significant of these is the shade structure in the West Courtyard. Also included are four trellises, fences, gates, bathrooms, a mechanical / electrical support structure, a canopy over the kitchen service area, and the connecting elements between the existing barns and their additions. These should be developed as a family of elements with agrarian character. The shade structures should be a mixture of steel and wood, as should the fences and gates. The small buildings (bathrooms and mechanical /

System Narratives

ARCHITECTURAL (CONTINUED)

electrical support structure) should be very recessive and closely woven in with the landscape elements. They should be “planted-out” with vine armatures on their walls over fiber reinforced composite or metal siding. Most are windowless, so skylights and solar tubes in the bathrooms are desirable. They should have low roofs, most likely flat, that could be planted if determined to be appropriate.

THE NEW BUILDING— FACULTY / STAFF DINING FACILITY

As the only new building in the project, the Faculty / Staff Dining Facility has several roles to play in the Barn Compound. It has three major components: the Faculty / Staff Dining Room and its supporting spaces; the Bar (which will be run by a third party operator) and its supporting spaces; and the Stage, and its supporting spaces, which will be a major entertainment venue for the West Courtyard. To some extent this should be a background building, a visual and acoustical buffer separating the West Courtyard from West Campus Drive and the freeway. The building should also promote the identity of the Barn Compound as an entertainment and performance venue.

The design should employ composite strategies, using the hierarchy of elements outlined above. The Stage on the West Courtyard is part of the entertainment program for The Barn. The Stage roof will be fairly high on its east side to allow for adequate sight lines. It should relate to the agrarian character of the existing barn structures (the Primary Elements above)--in either form or structure (or both).

The Faculty / Staff Dining Facility is seen as an inward facing program or a retreat and does not need a strong connection to the West Courtyard. The main part of the new building should also relate to the agrarian character, if not form, of the Primary Elements outlined above. In this case, a simple shed roof, lower toward the courtyard and higher toward the freeway, may make the most sense. Acoustical analysis will occur early on to confirm that the massing is helping both to exclude freeway noise and to contain sound related to performances within the West Courtyard. Finally, the supporting elements on the West and South should relate to the Secondary Elements outlined above. A covered open walkway will link the Faculty / Staff Dining Space to the Barn Kitchen Addition and needs to relate to the Tertiary Elements outlined above.

FLEXIBILITY / ADDRESSING CHANGE

The programmed spaces allow for flexibility by creating wide open space, not encumbered by structural supports, so that many of the spaces could be adapted (if need be) over time. Whether tailored for the specific needs of performance or dining, the buildings should be designed to respond to a variety of formal and informal activities that change over time.

SUSTAINABILITY

An integrated design approach will be needed to achieve sustainable design. Concentration on “first principles”--orientation, shading, natural ventilation, and other passive strategies--will go a long way toward achieving sustainable design in this climate.

Among the most important concepts are durability and consideration of the life cycle impact of these buildings. All materials need to be long-lasting and low maintenance. Materials that can be reused, contain recycled content and produced regionally will be given priority over exotic and virgin materials. In addition to selecting materials which have decreased environmental impacts, low emitting materials will be selected to promote optimal indoor air quality.

In addition to “first principles” of sustainable design, an emphasis will be placed on creating a well-insulated and air sealed facility. By controlling thermal conductivity through insulation and minimizing air infiltration through air sealing, the facility’s net heating and cooling loads will be decreased providing a quick return on investment. Spray foam insulation should be considered for its additional benefit of air sealing.

Additional steps will be taken to promote high performance sustainable construction by installing ENERGY STAR products, low-flow fixtures, LED or high-efficient florescent lighting and mechanical systems. Solar PV and hot water systems will be considered due to Riverside’s high solar potential.”

The goal is to create comfortable, energy-, water-, and resource-efficient facility with measurable sustainable performance meeting the University’s mission on sustainability. As mandated by the UC Office of the President, all UC LEED eligible construction must have a minimum LEED certification level of Silver. In addition to meeting Silver, it is University policy to outperform CBC energy-efficiency standards by at least 20%. In an

System Narratives

ARCHITECTURAL (CONTINUED)

effort to outperform current standards, LEED Gold is targeted for project certification. LEED certification at the level of Gold is deemed achievable with little cost impact. Designing the buildings and landscape to reveal their sustainable systems and to educate their users about “green” principles should be a fundamental aspect of the design. Education strategies can include a combination of signage for sustainable features, a central building dashboard, website and tours. Building dashboards provide users with an opportunity to learn about the buildings sustainability features, energy performance, and could present other information such as event calendars, menu, and Barn history.

BUILDING AND LANDSCAPE

The Riverside campus has a number of very successful outdoor spaces. These are a key part of the campus character and identity. This project is committed to contributing to and extending the outdoor spaces on the campus. The potential for integration of indoor and outdoor spaces is deeply imbedded in the building program. In the development of the design, the building and landscape should be seen as inseparable partners, so that in the end the project has as much to say about successful outdoor spaces as it does about successful interiors. These outdoor spaces will be able to support a variety of activities. An effort has been made to program the outdoor spaces with as much specificity and flexibility as the interior spaces. These spaces can work with the buildings to establish the character of the Barn Project compound and engage the natural cycles of the site with the theater of everyday life.



System Narratives

CIVIL

**Note: See “Utility Points of Connection” Diagram in Section II (Functional Concepts)*

GENERAL SITE WORK

The majority of the site work for the Barn Expansion will be completed during Phase 1A and 1B of construction. Underground utility work, grading, the majority of the drainage systems, and primary paving should be incorporated by the end of Phase 1B construction activities. Final landscape and hardscape treatments for areas around the Barn Theater are within the project boundaries as identified in the Phasing and Implementation diagram on page 241.

GENERAL UTILITY ISSUES

Utility design and construction practices shall follow UC Riverside standards. Where UC Riverside standards do not exist, appropriate local, state, and federal regulations shall be followed. For utilities such as graywater and rainwater, where local codes may inhibit standard green building design practices, the University shall support the design team’s use of codes from other municipalities within the State of California as precedents that may help the campus further their green building practices.

Specific design related items include:

- Provide a minimum five (5) foot separation between outside edge of building foundations and centerline of nearest underground utility line.
- Provide separate meters for each building to allow for effective commissioning and long-term use monitoring for gas, water, power, hot water, and electricity.

WATER

Domestic water will require new points of connection for the proposed buildings within The Barn Group. At this time the civil engineer assumes that there will be three new connection points as per the utility diagram. The existing 12” water line running to the west of the Barn Stable conflicts with the proposed location for the Faculty / Staff Dining Facility and will need to be relocated further to the west. The point of this relocation shall serve as one of the water points of connection (see utility diagram).

A three valve cluster will be installed at each point of connection; one isolation valve on the service lateral, and two valves at each tee head. Each building will require the installation of a separate meter on this service lateral. Size of water service laterals will be provided by the MEP.

Fire suppression water supply is combined in the same piped network as potable water. Location of a new fire hydrant, if required, will be coordinated with the campus Fire Marshall.

A water softener will need to be installed for the Kitchen Addition and Faculty / Staff Dining and Bar area. This should be located within the Kitchen Addition and Faculty / Staff Dining Facility.

SANITARY SEWER

At least one new sanitary sewer point of connection will be required for The Barn Group. This connection will occur to the southwest of The Barn Group as per the utility diagram. At this new point of connection a sanitary sewer manhole will be constructed. During the schematic design

phase the civil engineer may evaluate the option of including an alternative point of connection for the Cottage and proposed outdoor Public Restroom at the East Courtyard (see utility diagram). The capacity of the existing sewer service will need to be reviewed before design work begins. Size of sewer service laterals will be provided by the MEP. A grease interceptor from the kitchen will be required.

GRAYWATER

There is no recycled water system on campus and as such alternative reclaimed water resources would have to be derived from onsite sources. The most viable water reuse source on site is the graywater generated within the Kitchen Addition. In order to tap this source, the Kitchen Addition will need to be dual plumbed so as to separate graywater from blackwater. Graywater is defined as wash water that typically comes from sinks, showers, and laundry facilities; while blackwater is defined as water that is exposed to organic material. Within the Kitchen Addition it is assumed that graywater would be generated through water sources that have minimal-to-no contact with organics. Sinks used to clean soiled items will be connected directly to the sanitary sewer. Kitchen sink layout and type of use will be provided by the Foodservice Consultant and MEP.

Graywater collected from the Kitchen Addition should be treated through filtration and disinfection, and used immediately for toilet flushing or irrigation. Graywater shall not be stored longer than 24 hours without treatment. Graywater system design will follow the Uniform Plumbing Code. Construction of a graywater system is estimated

System Narratives

CIVIL (CONTINUED)

to cost between \$25,000 and \$40,000 (actual cost will depend on length of piping installed, filtration system specified, disinfection system specified, and type reuse). Given the relatively low cost of water in Riverside, this system is not expected to pay for itself within its design lifespan. This system would however provide an exceptional opportunity for demonstration by the University and help the project meet UC Riverside's sustainability goals.

ELECTRICAL

The electrical point of connection will occur at Vault 3 (see "Utility Points of Connection" diagram), allowing connection to the 12kV substation. This project will require that the existing transformer and 800 amp service be replaced with a new 480kVa transformer and 600 amp service that meets the project demands as per the MEP. The existing service will be replaced with new copper conduit for all new service connections. New electric meters shall be installed at each building. The existing transformer will need to be replaced in order to accommodate the 600 amp service; and may be pad-mounted as per UC Riverside standards.

The conduit between MH 12 and MH 13 is currently out of use but should be reserved if possible for reuse with data / telecommunications.

The line to the west of the current Barn Stable location (feed to CHASS) can be slurry capped and spanned with a bridge foundation in order to avoid moving the line.

The old 800 amp service and transformer shall be retained by the University.

NATURAL GAS

The Kitchen Addition and Barn Stable will have connections to natural gas. This point of connection will occur along the existing line running to the south of the site at the location shown on the utility diagram. The project shall reuse the existing service lateral and gas meter if approved by the provider, Southern California Gas.

FIBER OPTIC

A fiber optic line will be run from Sproul Hall for fire communication. If the compound is connected to the central plant for chilled water, fiber will be needed for EMS controls for the Central Plant to monitor.

TELECOMMUNICATIONS

Existing telecommunications conduits run along the western and southern side of The Barn Group. New runs will be required for some of the buildings. Feed to the Faculty / Staff Dining Facility will come from the conduits running to the west. Feed to the Cottage will come from the vault to the south. Reusing the existing conduit to feed the Kitchen Addition is a possibility. The Telecommunications infrastructure is to be designed by the Telecommunications consultant.

A new AV switching mechanism will be placed outside Vault 3A.

STEAM / CHILLED WATER

The point of connection for steam and chilled water is in Tunnel Vault 15 to the south of Watkins Recital Hall. See utility diagram and the MEP narrative for more information.

STORMWATER

Stormwater shall be managed in order to meet LEED Credits 6.1 and 6.2 for stormwater runoff quality and quantity. Impervious areas will be minimized and stormwater will be treated as close as possible to the point at which it falls. Drainage design shall minimize piped flow and maximize overland surface flow to treatment areas. Permeable, interlocking pavers shall be used for hardscape surfaces wherever possible and configured for onsite infiltration. Softscape treatments, such as rain gardens and bioswales, shall be integrated into the landscape design where feasible. During the design phase, effort should be made to keep stormwater management facilities visible, thereby enhancing The Barn Area as a demonstration project. Additional UC Riverside stormwater requirements, if more stringent than LEED, shall be met.

GRADING / EARTHWORK

Grading and earthwork will be minimized onsite and an effort will be made to balance cut and fill across the project.

CIRCULATION

Circulation will be improved via changes to the loading bay areas. The kitchen approach will be adjusted so that trucks approach from the south and pull into a new parking lane, allowing parking and unloading without traffic lane obstruction.

CARBON

CO2 emissions for the facility will be minimized through design and infrastructure selection, helping UCR meet its Climate Action goals. Additional vegetation will further offset carbon emissions across the project.

System Narratives

LANDSCAPE

The outdoor spaces of the Barn Expansion Project are a series of interconnected courtyards shaped by the surrounding buildings. A strong connection between indoor and outdoor spaces is achieved through large doors and wide exterior corridors. The landscape (layout, plantings, hardscape, and shade elements) will be designed to reflect the rich agricultural heritage of the region and The Barn Group.

The Barn Walk, the main pedestrian route from the site to East Campus, is separated from the Sproul Hall service drive with a planted corridor of orange trees that tie into the existing orange grove to the north of the project. This citrus allée will also function to screen the Sproul Hall loading dock from the project site. Bike traffic will use the service road with pavement striping to separate a bike lane.

The Eucalyptus Walk, which approaches the project site from the east, terminates at the intersection with the Barn Walk. This important intersection will be studied during design so that it functions in several ways: as circulation, as a visual endpoint of the two walks, and as a courtyard garden / meeting place. One possible reference may be the historic rancho garden, with a courtyard of decomposed granite inset with informal plantings.

The East Courtyard at The Barn and Cottage will be shaded by the large existing shade trees. This courtyard will have moveable furniture for dining and gatherings.

The West Courtyard will be shaded by a large shade structure and used for dining and outdoor performances. An area in front of the Outdoor Stage will be used as a flexible space for everyday

dining or as seating / standing for performances. Moveable furniture and other landscape elements will accommodate a variety of formal and informal seating.

The Barn Stable will have its own patio enclosed by low walls or fences accessed by gates and will be separated from the rest of The Barn Group by plantings.

Fencing and gates will be designed with transparency and security in mind. Wood and steel will be the primary construction materials. The design of the fences and gates will be integrated into the tertiary shade structures and planted trellises. The operable gates will allow for a variety of possibilities for enclosing the Barn Stable Patio and the West and East Courtyards. For instance, access to the West Courtyard performance area can be controlled by rolling gates to completely enclose this area for alcohol and ticketing control. All gates will have swing capacities for exiting.

The hardscape will be durable and light-colored to minimize the heat island effect. The design will consider areas of permeable paving to reduce runoff. Planted bio-swales, where feasible, will retain, clean, and slow down storm water before it reaches the storm water drainage system. Rainwater collection for onsite usage (toilet flushing, irrigation) will be considered. Other ornamental planting areas will feature drought-tolerant perennials and shrubs and will add softness, color, and aroma.

The plant palette--consistent with the Campus Design Guidelines (December 2007)--will include shade trees such as Sycamores and Oaks; citrus and possibly other fruit or nut trees (avocado, walnut); drought-tolerant native or Mediterranean perennials, featuring flowers suitable for cutting for

use in dining table arrangements; shrubs; vines (grape or kiwi as potential edible vines.) There is also the possibility of an herb garden to be used by the Kitchen Addition.

The approach to exterior lighting is a subtle integration of lighting fixtures into the proposed built structures: recessed wall lights at steps and ramps; dimmable down lights from the West Courtyard Shade Structure; down lights from existing trees at the East Courtyard; downlights from the trellises at the Barn Stable Patio. Low path lights in planting areas adjacent to walkways will supplement where needed for circulation safety.

Future site work (not part of this project) will include the necessary service access for Sproul Hall with a revised layout of parking spots and 3 dumpsters. Truck exiting this Loading Dock will back out onto West Campus Drive as they currently do; no turn around will be provided. Screening of the Sproul Hall Loading Dock will be achieved as mentioned above with a citrus allée running along the Barn Walk. Expected cost for these improvements is included as an alternate in the Cost Plan.

The design of the landscape will play a key role in ensuring a pleasant experience along West Campus Drive at the western edge of the project, which is largely a service area. The Drive Aisle that runs parallel to West Campus Drive allows for: truck delivery to the Kitchen Addition, access to Faculty / Staff Dining Facility parking, and a more continuous pedestrian experience. A carefully designed strip of plantings and trees will provide screening of this area, all per the Campus Design Guidelines (See Campus Supporting Documents in Section VII. Appendix).

System Narratives

STRUCTURAL

THE BARN DINING FACILITY

The gravity load resisting system appears to be adequate for its intended use. We do not anticipate needing to do any significant work to the framing to resist vertical gravity loads. However, in many areas the existing framing and siding appears to be near or in contact with the exterior grade. The building should be surveyed for water damage and repaired as needed.

Based on a review of the available structural information, the Barn Dining Facility will most likely require a seismic upgrade as part of a comprehensive renovation. The structure is both too weak and too flexible in its current state, relative to modern safety standards. Fortunately, upgrading can be relatively straightforward and cost-effective.

The existing straight-sheathed roof diaphragm is inadequate to transfer seismic loads to the walls. It can be easily upgraded by adding a layer of plywood sheathing directly to the existing structure. This work would be integral with improving the insulation and re-roofing the building. The proposal is to work above existing sheathing and keep in tact the structure as exposed from the inside. Once the existing roof has been removed to bare structure, the new plywood would be nailed directly to the framing. Because the building is currently not insulated, a layer of rigid insulation would be added over the new plywood. The insulation would change the appearance of the building by raising the roof by around six inches. To maintain the look

of the exposed rafter-tails and roof overhang, the existing rafter-tails would be removed flush with the wall line. A new set of false tails would be set on top of the new plywood and overhang past the walls. The new framing would exist above the diaphragm, but within the layer of insulation. The overall appearance of the building would be made similar, except that the building would be taller by the height of the new insulation. The roof framing forms a low monitor at the ridge, the full length of the building. The insulation layer would also be added to the monitor. To preserve the roof appearance similar to its current state, the exposed rafter framing at the monitor would be removed and replaced in kind. The new position would be higher due to the insulation. Like the rafter-tails of the main roof, the final appearance of the monitor would be similar to the current state.

The most cost-effective and straightforward way to improve the seismic strength of the structure is to add new plywood sheathing to the existing wood stud framing. The wall locations best suited for new plywood are at the ends of the structure. In plan, the walls would appear as bookends. Both transverse wall elevations would be sheathed. Additionally, one segment of wall would be sheathed at each end of each longitudinal elevation. This placement of sheathing works well with existing walls, and would not disrupt the function of the building. The sheathing will be placed on the inside of the stud framing once gypboard finishes have been removed. This placement preserves the existing historic wood siding.

The kitchen addition could be framed economically with steel light gauge construction or wood stud framing. If steel framing is selected, the walls would be steel studs in bearing and the roof would be framed with steel joists and steel beams. Because metal studs and joists have problems with thermal bridging, a layer of rigid insulation would most likely be needed outside of the walls and over the roof to get satisfactory insulation. The roof sheathing would be shallow gauge metal deck. The wall sheathing would be a structural panel made of gypboard laminated with light gauge steel. The foundations would be shallow wall footings and the ground floor would be a slab on grade. The new construction would be seismically separated from the existing Barn Dining structure.

If wood stud framing were used, the construction would be similar to the light gauge steel. The walls would be wood studs and the roof joists would be either solid lumber or engineered I-joist. The roof sheathing and wall sheathing would be plywood. Because both new and existing framing would be wood, no seismic joint is needed. Other differences are that no additional rigid insulation is needed.

Several issues should be considered in the selection of the framing system. The metal stud framing is considered to be more durable with respect to moisture resistance and straighter. The wood framing has advantages in addition to not requiring rigid insulation and a seismic joint. Wood framing is architecturally in keeping with the existing Barn complex. It is also the most appropriate material from the prospective of

System Narratives

STRUCTURAL (CONTINUED)

environmental sustainability – especially if Forrest Stewardship Council (FSC) certified wood is used. Often wood framing is less expensive than other forms of construction. Finally, the issues of longevity can be addressed with good detailing practices that are supported by good maintenance.

THE BARN STABLE

The Barn Stable is proposed to be relocated. The new site would be prepared with a new foundation supporting a concrete perimeter curb. Presently, areas of framing and siding appear to be in contact with the exterior grade. The building should be surveyed for water damage and repaired as needed. The lower portions of the stud framing and siding should be removed (approx. 6") to have the building positioned on the new curb above grade.

Like the Barn Dining Facility, the Barn Stable will most likely require a seismic upgrade as part of a comprehensive renovation. In a similar fashion, the structure can be strengthened and stiffened with plywood sheathing to meet modern standards.

The existing roof diaphragm of corrugated metal sheathing is inadequate to transfer seismic loads to the walls. A layer of plywood sheathing can be added over the metal sheathing and fastened to the existing structure. This work would be integral with adding new rigid insulation and re-roofing the building. Working above the existing corrugated sheathing will keep the exposed structure in tact from the inside. Like the Dining Facility, the added insulation would change the appearance of the building by raising the roof by around six inches.

However, a similar strategy of false exposed rafters would keep the overall appearance of the building similar to its present state.

The seismic strength would be improved by adding new plywood sheathing to the existing wood stud framing. The sheathing would be placed on the inside of the stud framing. This placement removes the existing poor quality interior finishes and preserves the existing historic wood siding.

New framing that is part of the stable building could be either light gauge metal or wood stud. The same issues noted for the kitchen addition apply here.

THE COTTAGE

The Cottage is proposed to be relocated. The new site would be prepared with a new foundation. The structure presently has a wood framed floor that would be preserved. By altering the design of the perimeter curb and foundation, the final height of the building could be set at various levels. The building could possibly be set relatively lower than its current state. This change would reduce the length and appearance of the new exterior ramp.

The improvements to the seismic capacity of the building would be made by adding new plywood sheathing. The roof structure would be sheathed above the existing sheathing and the roof replaced. Because the cottage has flat ceilings, additional insulation would be placed in the cavity above the ceiling and below the roof. No changes to the eave framing would be needed. New wall plywood sheathing would be added to the interior face of

existing stud framing, once interior finishes have been removed and replaced as needed.

Additionally, the chimney anchorage would be improved for seismic resistance.

THE FACULTY / STAFF DINING FACILITY AND STAGE STRUCTURE

The Faculty / Staff Dining Facility and stage structure is expected to be one building of three parts. They are the main dining room, the adjacent support spaces, and the open stage structure. These spaces would be structurally tied together with no seismic joints.

The main dining room may consist of a single volume rectangular in plan. The framing would be five exposed trusses made with glulam timbers or built-up 2x's and custom steel connections. The shape may be a long shed, but other forms are possible. Some steel members may also be incorporated in the trusses. The trusses may be spaced around on 12' center. They would be supported on exposed glulam timber or built-up 2x columns. Spanning between the trusses would be 2x12 wood joists at 24" oc. There will also be exposed wood eaves. The roof diaphragm would be plywood structural sheathing. A ceiling is expected to be below the joists and the joist cavity filled with insulation. Rigid insulation may also occur above the roof sheathing. The walls of the dining space could be made of wood studs (engineered at tall walls) with plywood sheathing, metal studs with steel / gypboard sheathing or concrete block masonry. The issues of cost,

System Narratives

STRUCTURAL (CONTINUED)

environmental impact, and durability discussed for the Barn Dining Facility also apply to these walls.

The adjacent support spaces may be flat roof structures with no exposed framing. The spaces could be framed in several ways. One would be with wood stud bearing walls with plywood sheathing that support engineered wood I-joist. In a similar way metal studs with steel / gypboard sheathing and metal joists could be used. If concrete block masonry is used, then the roof could be framed with either engineered wood I-joist or metal joists.

The foundations for both areas would be shallow concrete footings and the ground floor would be a slab on grade. The support under the columns in the dining room would be individual spread footings. The support at the bearing walls would be spread footings.

The stage structure will be structurally connected at the roof to the dining facility. The framing is expected to consist of an exposed steel girder truss (around 36" deep) that spans the length of the stage. The steel girder truss supports 6 perpendicular exposed glulam timber or built-up 2xs (top chord) and steel (bottom chord and webs) trusses spaced a 6' oc. The glulam timber or built-up 2x/steel trusses also are supported on exposed glulam timber or built-up 2x columns. Between these trusses would be 3x wood decking with plywood sheathing above.

The steel girder truss would be supported by steel wide flanged columns at each end. The columns

are both the vertical support and the lateral support of the stage. Assume 14" wide flange with 120 lbs/ft steel beams (W14x120s) for estimating. The columns will be supported by a large grade beam that runs under the stage. Assume a section of 2' x 3' with 150 lbs/cy of reinforcement. The stage platform would be wood framed or metal stud construction supported on a perimeter concrete footing. The stage floor is concrete: either a topping slab on plywood (if wood framed); or metal decking (if metal studs); or a concrete slab on sand with perimeter concrete walls.

SHADE STRUCTURE

The open shade structure may be framed by steel columns (assume HSS 5x5x1/4s) that support four light steel trusses that span around 50'. The steel truss may consist of welded tubes, with two tube top chords and a single tube bottom chord, to form a triangular section. Spanning between the trusses would be the shade cloth. The columns would be supported on concrete piers (assume 18" dia. x 15' deep). Another option for the shade structure is to use a tension fabric structure. the shade structure will need to support lighting equipment.

System Narratives

FOODSERVICE + BEVERAGE

FACULTY / STAFF DINING FACILITY

The Faculty / Staff Dining Facility and beverage program is to serve a limited buffet lunch with beverage and bar service. The food program will be supported by the new Barn Dining Kitchen where all food whether cold or hot will be prepared and transported in enclosed refrigerated, hot or ambient carts to the food set up room in the Faculty / Staff Dining Facility. It will be placed in serving ware and placed on the buffet counter in the Dining Room. There will be furniture / fixture(s) in the Dining Room for table top components easily accessible to dining staff.

The Faculty / Staff Dining Facility will have its own china and glassware which will be washed and stored within the facility. Storage rooms are provided for buffet service ware and other food and beverage service requirements.

The Bar will be operated by a third party and will have service to the West Courtyard through an open front counter with a closure to secure it during non-operating hours. The Bar will also have service to the Dining Room and the two areas will be separated by a double action café style door designed to be air tight to maintain conditioned space inside the dining room. The Courtyard counter will serve draft beer, wine and sodas and the club side will serve draft and bottled beer, wine, soda, hard liquor and espresso based beverages. The Bar will have dedicated office, dry and refrigerated storage support.

THE BARN

The Dining Master Planning Study (DMPS) determined potential foodservice demand of 320 meals per hour as opposed to the current 120 meals per hour, an increase of 2.5 times.

The Barn foodservice demands require The Barn Kitchen to provide meals for The Barn and support for the Cottage, Barn Stable functions, pre-packaged food items for Ivan's and other locations (commissary operations) and a barbeque on the West Courtyard. Day part service is lunch, happy hour, dinner and potentially breakfast. Dining areas include interior seating with a small Indoor Stage at Barn Dining, outdoor eating at the West Courtyard with a large Outdoor Stage, and quiet courtyard on the east side of The Barn.

The DMPS assigned area requirements by function for The Barn to support these foodservice requirements. This recent study and the earlier 2009 Barn Area Study (BAS) presented the need to expand the kitchen and servery. The 2009 BAS proposed an addition to the west side of The Barn to support the requirements but did not address the potential dining demand presented in the DMPS. Accordingly, additional kitchen expansion is necessary to support the anticipated foodservice demands.

The DMPS proposed an operational style of order and pre-payment of meals with the customers recalled to the servery when the meals are ready, putting double circulation requirements on the servery. Thus the decision was made to change to a post-pay system in order to eliminate half of the required circulation space demand. It was also decided to forgo the use of china ware and instead use disposables, re-usable trays, and self-bussing stations located in each of the three dining areas.

The servery has 4 food stations (Pizza, Salad / Cold Sandwich, Hot Sandwich / Specialty and Grill), as well as a self-serve beverage counter and two double sided dual tandem Point of sale (POS) counters. The condiment counter is to be located

behind the beverage counter facing Indoor Seating.

All finish food preparation is "on stage" to promote fresh food, freshly prepared.

The Kitchen functions include dry storage, catering storage, cold storage, cold food prep, hot food prep, catering staging, ware-washing, ice machine, soda system room, change room and one shared office.

The Service area is to support deliveries and house the storage of: empty vendor racks / bottles, a refillable CO2 tank, a trash compactor, recycling bins, and a used cooking oil tank. Access to staff restrooms is through the service area. It is anticipated that a remote compressor rack will be located on the roof.

COTTAGE

The Cottage is located east of The Barn and programmed to be a coffee house serving coffee-based beverages, hot tea, cold blended beverages, pastries, self-serve cold bottled beverages, pre-packaged salads and sandwiches. Day part service is breakfast, lunch, afternoon, and evening. Some exterior seating will be provided at the South Cottage Patio and the East Courtyard. It will be supported by The Barn kitchen with bulk storage and food prep.

BARN STABLE

This facility is located northeast of The Barn and will host occasional lunches, teas, dinner, meetings and banquet functions. A small pantry kitchen with grill, warming oven and dishwashing will be supported by The Barn Kitchen and will have a full service bar in a multi-function room and a patio. It is not programmed to operate as a restaurant on a daily basis.

System Narratives

ACOUSTICAL

OVERVIEW

The acoustical design issues include room acoustics, sound isolation, mechanical equipment noise and vibration control, and sound reinforcement.

WEST COURTYARD

The main outdoor courtyard space will be used for both dining and outdoor entertainment. Freeway noise and possibly mechanical system noise are potential issues in this space. To optimize the acoustical quality in the space as it is developed, the following should be considered:

To the extent feasible, building massing should be used to block freeway noise into the outdoor use space.

The building surfaces facing into the outdoor area space should be made sound absorbing to the extent feasible so as to mitigate echoes and reverberation.

Overhead canopies, trellises, and other feasible design elements could work together to mitigate freeway noise intrusion into the outdoor area space, as well as to provide shading.

OUTDOOR STAGE SOUND PROPAGATION

Stage sound will propagate from the stage area to adjacent buildings in proportion to the source sound levels (how loud the sources are), the degree of directional control of those sound sources, and the presence of sound-reflecting

surfaces. The actual impact on building occupants will also be governed by the distance from the stage, sound-insulating properties of the building they are in (e.g. non-operable versus operable windows), and the background noise level in the occupied space (i.e. HVAC background noise).

The facility design can regulate the directional nature of the audio system, reducing the sound source level at a limited number of loudspeaker locations by distributing loudspeakers across the seating area, providing automatic control of the maximum sound output of the installed audio system, and treating any problematic reflecting surfaces with acoustically absorptive material. The design cannot regulate the “stage-volume” of amplified musical instruments on-stage or the noise produced by the crowd.

The intent of the above described sound mitigation methods is to maximize the acceptable daytime uses of the stage, however there is no assurance that some performance may adversely impact a neighboring activity given the factors involved that are beyond the control of the facility design.

STAGE - FACULTY / STAFF DINING ROOM ADJACENCY

The current space layout will likely allow compatibility of stage performances with dining functions depending on the type of stage performance and what wall / window / door constructions are chosen for the final design. The compatibility of conducting presentations in

the Faculty / Staff Dining Room while stage performances occur is questionable however, given the requirement for much greater sound insulation for a presentation versus dining. Given the current space adjacencies, scheduling coordination of presentations and stage performances will be needed.

BARN AND BARN STABLE ROOM ACOUSTICS

Controlling excessive reverberation in dining and serving areas is important to the overall quality of the spaces. The sound absorbing material selected for these spaces need to be reconciled with the interest in having an exposed ceiling / roof structure.

MECHANICAL EQUIPMENT NOISE AND VIBRATION CONTROL

When designing controls for mechanical equipment noise and vibration both inside and outside the buildings, the recommended criteria will vary depending on the use of the space. A conference room may require a background noise level of NC 25, where as an appropriate background noise level for a dining facility would be NC 40 to NC 45. The typical design noise limit for mechanical equipment is 40 dBA in outdoor-use areas such as dining.

System Narratives

AUDIOVISUAL

OUTDOOR STAGE AUDIO SYSTEM

With properly selected equipment, a production sound system at the stage could support regional and live touring acts, providing an easy load-in / out scenario as touring or locally rented audio and lighting would not be required. To maintain the loudspeaker locations and orientations in a precise enough manner to address the sound propagation issues, the loudspeakers should be permanently mounted and highly weatherized so that they do not need to be deployed and stored seasonally.

The loudspeaker system should be directional (concentrating the sound output in the direction of the audience) and at least partially distributed over the audience area so that an adequate minimum sound level across the audience area can be maintained without the need for exceptionally high loudspeaker sound levels at only one end of the audience area (i.e. the stage), as would otherwise be the case in a conventional stage sound system.

OUTDOOR STAGE VIDEO PROJECTION

The outdoor stage could include a manual large-fixed roll-down screen for movie projection, or if movie use is infrequent enough, this type of screen could be provided on a rental basis. Given the high capital and maintenance costs associated with a video projector the size of that which would be required for a venue of this size, it is recommended

that video projection be provide on a per-event rental basis.

BARN DINING SPACE AUDIOVISUAL

The Barn Dining Space existing audio and lighting equipment may be reusable in the renovated space. However given the overhead costs associated with removing, storing, and redeploying this equipment, the University may wish to investigate other uses for this equipment on campus and include new audio / video equipment in the project for the Barn Dining space.

A roll-down projection screen and ceiling mounted projector would be very useful in this venue. It is recommended, but not currently included in the cost estimate. Some level of digital signage for menus and events could also be considered.

MEETING SPACE AUDIOVISUAL

The Barn Stable and Faculty / Staff Dining Spaces will likely be usable for audiovisual presentations and as such, audio and video projections systems should be considered. The need for any audio-conferencing and/or teleconferencing should be evaluated. The audio and video systems in any of these spaces can be configured for these purposes, however in most cases, smaller rooms will work better as remote presentation / conferencing sites.

Some video display and digital menu / event signage should also be considered for the Barn Dining facility.

System Narratives

THEATER

The following narrative describes our recommended approach for the venue characteristics and technical systems related to the performance facilities at the Barn Expansion Project. The musicians and their audiences are aided and supported by the facilities in which they work. The ultimate goal is to focus on the architectural design, technical operation and what it takes for audiences to have rich and captivating experiences, what it takes to inspire and support students, faculty, artists and musicians, what it takes to maintain financial viability for the project and the working facility, and what it takes to design and build a successful arts education and performance venue.

These recommendations are further based conversations with the User's committee, our interpretations made from experience on similar projects of this type, and incorporating new directions in production technology.

OUTDOOR AND INDOOR STAGES: VENUE CHARACTERISTICS

Circulation & Access

The following routes must be provided for proper and code compliant circulation between the various areas:

- Gracious and universal route(s) shall connect the pre-function spaces to the seating areas.
- Per the CA Building Code and the 2010 ADA, wheelchair positions shall be integral to the general seating area and dispersed and different heights (which is to say front to back) and left and right within the room. In a venue where the floor is en-

tirely flat, this is solely an operational issue.

- A path shall be provided from the audience areas and the performance platforms. This will facilitate performer circulation into the audience area, audience circulation to the platform as may be the case for award ceremonies, and for rolling equipment access to/from the audience chamber from storage.
- There shall be smooth access between the loading and backstage areas to the performance platforms, of a width sufficient for the movement of instruments and equipment. This operational circulation shall neither pose a risk to valuable instruments nor cause undue operational personnel efforts or time.
- Seating in rows or at tables shall comply with governing codes.
- Technical access shall be provided to all locations for lighting and audio / video devices for the adjustment and servicing thereof. It shall be viable to access all components (drives, tracks and control system elements) for installation, commissioning, servicing and replacement.
 - o Where performance or architectural lighting is placed over flat floor areas, it shall be no higher than 30'-0" a.f.f. and with sufficient clear floor area for a personnel lift with its outriggers fully extended. Long life lamps shall not be considered a substitute for safe and efficient access.

Illumination

Several systems shall be employed to suit the various use needs:

- For performance use, provide a minimum average 20 fc even coverage for house lights. CRI no less than 94. The selection of appropriate sources and a high quality dimming system and configuration shall provide smooth, flicker-free performance with a completely uniform ignite / extinguish, to and from 0% with no margin of tolerance.
- Provide compliant emergency lighting
- Performance lighting shall be accomplished by the use of a flexible performance lighting systems described below. Mounting positions will be provided over the platforms and front lighting positions at +/-45 degrees vertical and from left and right to each area on the platform, with no gaps.
- It is assumed that these venues will not be used for classroom functions, which precludes the need for higher lighting levels.

GENERAL APPROACH TO SYSTEMS

The Indoor and Outdoor venues will be used for both general assembly and entertainment functions. Because of the wide variety of performances anticipated, flexible production systems are key to proper functionality.

Production Lighting Control – Indoor and Outdoor Stages

A complete control system consists of a control console, control electronics, dimmers and circuit outlet boxes ("distribution").

Performance lighting and house lighting will be controlled by a single integrated and comprehensive system of a single manufacturer. Three means

System Narratives

THEATER (cont.)

of lighting control would be provided. For simple events, a lighting system touchscreen LCD panel at the performance platform control position would be provided. This would allow for preset recall, and basic dimming control. For more advanced events, a portable lighting control console would be provided with connection points both on the performance platform and at a technical position within the audience areas. Control locations would be set up on a per-event basis on temporary elevated platforms at the rear of the audience.

A data network would provide the means to run effects as well as providing control integration of the house lights. Lighting control data output and constant power will be provided at all lighting positions for advanced lighting effects such as color scrollers and moving lights. Simple one-button preset recall panels would be provided at entries.

Outdoor Stage: The system would include all of the control elements described above and (96) 20A, 2.4kw dimmers for production & house lighting. Dimmers are housed in (1) full installation rack of (96) 2.4kw dimmers within an electrical room located remotely from the performance platform to provide acoustical isolation between the racks and the noise sensitive areas.

Performance and house lighting dimmers shall be fed with a dedicated isolation transformer. The transformer shall be K-13 type or HMT type. Provide a dedicated 600A, 3-phase breaker in the same room as the dimmers. Feeders shall be copper with neutrals oversized as a current carrying conductor, configured per dimming manufacturer's recommendations.

The dimmers would be located where convenient and accessible to technicians, close to the primary locations of circuits to minimize voltage drop and the cost of wiring. Dimmer room shall be sized for installation and maintenance clearances per code, with room enclosure construction, assembly and equipment mounting techniques that prevent the emanation of noise and vibration to critical areas as stipulated by the acoustical consultant.

Indoor Stage: The system would include all of the control elements described above and (24) 10A, 1.2kw dimmers for production. In order to provide flexible locations and high quality dimming without the need for a dedicated dimmer room, packaged, distributed, IGBT-style dimmers will be used and located in groups of (6) circuits at several lighting positions. The dimmer product shall be Philips-Strand S21 Dimmer Strip powered by standard, constant 20A, 3-phase power at the lighting positions. The data network will tie the dimmers to the control system.

For House Lighting dimmers are housed in (1) wall mounted installation rack of (24) 2.4kw dimmers within an electrical room located remotely from the performance platform to provide acoustical isolation between the racks and the noise sensitive areas.

Circuit distribution would entail wiring in conduit from the dimmers to 3-pin wiring devices strategically placed at lighting positions. The wiring device types will vary depending upon the specific lighting position. Multi-pin, pigtail or flush receptacle boxes and connector strips will be used for overhead positions.

An inventory of extension cable would be used to augment circuit distribution.

Architectural lighting circuiting shall provide control to logical use areas in the venues, ordered front-to-back in the room (not left to right), and organized within the dimmer rack and addresses logically. Dimmer capacities and assignment for architectural circuits shall be selected to provide high loading to the circuit as another component to control filament noise.

Production Lighting Fixtures and Cable (Group II equipment)

An inventory of approximately 75 theatrical lighting fixtures (typically ellipsoidals, fresnels and pars) plus accessories would be provided.

Accommodation for the integration of advanced devices such as color changers or moving yokes will be provided within the control system, but the initial budgets established will likely not include those types of fixtures and accessories.

Performance Overhead Support – Outdoor Stage

Performance lighting will be supported by two means: a "house" system will be in place to support the ready use of the venue with a minimum of set-up. This will be attached to overhead stage lighting pipes of industry standard dimension that are integrated within the structure of the overhead canopy and that have weight supporting capacity. The weight capacity and configuration will also make these pipes useful for the attachment of scenic elements such as banners and stage draperies.

System Narratives

THEATER (cont.)

For the performances where more elaborate lighting or scenic configuration is necessary using a temporary road “rig”, a series of rigging points of heavy load capacity will be provided. A total of ten one-ton-rated rigging points on a grid above the platform. These points would be used with motorized chain hoists to suspend portable production devices, such as lighting truss, portable loudspeakers, and other portable production equipment.

Performance Overhead Support – Indoor Stage

Performance lighting will be supported by a “house” system that will be in place to support the ready use of the venue with a minimum of set-up. This will be attached to overhead stage lighting pipes of industry standard dimension that are integrated within the structure of the overhead canopy and that have weight supporting capacity. The weight capacity and configuration will also make these pipes useful for the attachment of scenic elements such as banners and stage draperies.

Production Power

Outdoor Stage: One 200A, 3-phase, 120/208VAC “company switch” power source will be provided at platform level for supplemental temporary dimmers or other variable power needs. The 200A company switch will be a purpose built device including a breaker, indicator lights, a “Camlok” connection panel with double neutrals.

Indoor Stage: One 100A, 3-phase, 120/208VAC “company switch” power outlet will provide a generic power source to temporary systems. The “pin and sleeve” connector will mate with that of a portable distribution panel that will provide breakered

power outlets of the various kinds typically used in theatre. The 100A company switch will be provided at the performance platform level.

Additional power sources may be provided for other event functions such as steam tables and exhibits.

Refer to AV Narrative for AV power requirements

Temporary Wiring Infrastructure

Since the production lighting and AV control consoles will be portable and in some cases brought in by guest users, recessed and out-of-the-way temporary cable routes need to be provided so the cables do not pose tripping hazards to the audience. The cable route would allow connection between the performance platforms and the control areas.

At an Outdoor Stage this is typically accomplished with a recessed trench with a robust yet easily removable cover to lie in the cable.

At the Indoor Stage this would be accomplished with 8” minimum diameter empty PVC conduits with double length pull ropes inside. If bends are necessary it is critical that have a very wide radius so pulling cable is not onerous.

System Narratives

MEP

INTRODUCTION

The mechanical systems for the Barns Expansion Project will be designed to optimize performance, and minimize maintenance and energy use. Three distribution options are proposed, all of which take advantage of the central campus chilled water and steam utilities. A central mechanical room located in the Barn will then distribute heating hot water and chilled water to the other buildings on site. Energy conservation will also be achieved by optimizing natural daylight, selecting energy efficiency lighting, and using lighting controls such as occupancy sensors, photocells and dimmers. Low flow fixtures are recommended for use throughout the site to reduce overall water use by at least 30%.

HEATING VENTILATION AND AIR CONDITIONING (HVAC)

Systems Design Philosophy:

HVAC system components and distribution layouts will have the following characteristics:

1. Modular approach.
2. Energy and resource efficient.
3. Flexibility for future changes.
4. Durability.
5. Ease of maintenance.
6. Reliability.
7. Redundancy of critical components.

Codes and Standards

- NFPA Codes, current editions, as applicable
- ASHRAE Standard 62-2004 Ventilation for Acceptable Indoor Air Quality
- ASHRAE Handbooks, current editions
- SMACNA Duct Construction Standards

HVAC Design Criteria

Location: Riverside CA

Latitude: 34.0° N 117.4° W

Elevation: 1007 ft.

Outside Design Conditions:

Summer: 110°FDB/68°FWB (per UCR standards)

Winter: 34°F DB

Interior Design Conditions:

Occupancy	Summer	Winter
Conference/Meeting Rooms:	75°F DB, 50% RH*	70°F DB
Offices:	75°F DB, 50% RH*	70°F DB
Dining Areas:	75°F DB, 50% RH*	70°F DB
Kitchen:	75°F DB, 50% RH*	70°F DB
Telecom/Data Equip Rooms:	70°F DB, 35%-55% RH	70°F DB, 35%-55% RH
Mech/Elec:	95°F DB max	65°F min

* Humidity control is not required in General Occupied Spaces, but may be necessary in Telecom / Data Equip Rooms, as recommended by equipment manufacturers.

* Where radiant cooling is used comfort conditions will be maintained by designing to the operative temperature which incorporates both air temperature (DB) and mean radiant temperature.

Outdoor Air Ventilation:

- Minimum Outdoor Air Ventilation rate will be 15 cfm / occupant, as recommended by Title-24 as it exceeds ASHRAE for dining spaces, based on maximum number of people in each space taken from Project Room Data Sheets, whichever is higher. Where the LEED EQ Credit dictates a higher air flow will be used.

- Internal Heat Gains: Heat gain from occupants will be calculated according to ASHRAE guidelines for maximum number of people in each space taken from Project Room Data Sheets.
- Heat gain from lighting will be calculated based on the actual layouts and fixture types obtained from the electrical drawings. For energy efficiency the lighting design will employ lower ambient lighting levels with task lighting.
- Heat gain from equipment will be based on information received from specialty consultants (i.e kitchen consultant, telecom, etc.) and project cut sheets.

Energy Efficiency

The UC system mandates that all new buildings are required to outperform Title 24 by at least 20%. The building will need to incorporate sustainable design measures to meet the requirement of LEED® Silver Rating.

The building envelope shall be designed to outperform the T-24 minimum requirements by at least 20%. T-24 prescriptive envelope requirements for California Climate Zone 10 are given below:

- Roof R19
- Wall R13
- Floor R11
- Glazing U factor 0.47
- RSHG

	Non-North	North	U
0-10% WWR	0.47	0.61	U
11-20% WWR	0.36	0.51	U
21-30% WWR	0.36	0.47	U
31-40% WWR	0.31	0.47	U

System Narratives

MEP (CONTINUED)

Glazing systems shall be selected to provide optimum Shading Coefficients / Solar Heat Gain Coefficients and U-factors on each exposure of the building. External shading is recommended where possible for non-north exposures.

- Glazed areas shall be optimized to maximize effective use of natural day-lighting and allow views to the exterior and to the interior.
- Operable windows will provide natural ventilation of rooms in perimeter zones (where applicable by program). Operable windows shall be under the control of occupants and the users will maintain the windows in the appropriate position when supplemental heating or cooling is provided from the mechanical system.

HVAC systems will incorporate energy conserving features known to be economically feasible. The design will first focus on passive systems such as thermal mass and natural ventilation (where applicable by program) which provide the most energy benefit at the least cost. Once the cooling and heating loads have been minimized then the most efficient active systems will be explored. Technologies to be explored include, radiant cooling and heating, chilled beams, active thermal mass, heat recovery, dedicated 100% outside air economizer cooling cycle for air handling systems, CO2 sensors utilized to control minimum outdoor air, variable frequency drives for control of fans, and premium efficiency motors. Additional energy conserving features, such as variable speed drives for pumps, indirect evaporative cooling of outdoor air, and heat recovery from exhaust systems will be evaluated during the Schematic phase and provided if shown to be economically feasible.


Utilization of renewable energy sources, such as solar panels for water heating, wind power and/ or photo-voltaic power for supplemental power generation will be evaluated during the Schematic phase and incorporated into the project if shown to be economically feasible. Three (3) additional LEED® credits are available for renewable energy.

HVAC Systems

The graph below shows an annual plot of temperature in Riverside as it relates to human comfort. As can be seen there is a defined heating and cooling season. In the peak of the cooling season there is a 15°F diurnal variation which allows for a night time purge cycle however there are periods where the night time temperature is above interior comfort conditions so the purge cycle would be limited in these months.

Thus the buildings will need to be conditioned (heating and cooling) but will be done in a mixed mode fashion so that natural ventilation can be used in periods where conditions allow.

Three ventilation and air conditioning systems appropriate for the building are being proposed for evaluation during the Schematic Design phase. The evaluation will be based on a life-cycle analysis considering capital first cost, projected energy / operating costs, and maintenance cost.



System Narratives

MEP (CONTINUED)

Option 1 is a base case design of a single duct over head variable air volume (VAV) systems, with hot water reheat. Based on current thinking for building organization this is likely to be split into a single air handling unit per building.

This system has the following characteristics:

Benefits	Cons
Conventional system with known installation and maintenance procedures.	VAV boxes create noise. A ceiling is often used to limit noise transfer, adding cost to the system. Acoustical tile or gypsum board ceilings, whether installed for acoustic or aesthetic reasons also limit the opportunity to use exposed structure as a thermal mass that would moderate the temperature swings.
The users may prefer finished ceilings below mechanical equipment for aesthetic and acoustic reasons.	Added cost to provide individual control at each perimeter office per LEED® IEQ Credit 6.2.
	Higher fan pressure reduces energy efficiency. Estimate system performance between 10-15% below ASHRAE 90.1 Achieving the mandatory 20% below T-24 is a challenge with this system.
	Reduced IAQ (Interior Air Quality) and comfort compared to other systems described below.
	Higher floor to floor heights required, increasing cost for building structure and envelope.

Option 2 is a Dedicated Outside Air System with radiant floors. For costing purposes 1/2" tubing on 6" centers may be assumed for radiant floors, with combined heating and cooling zones in a 15 foot perimeter band. The interior zones would be cooling only. Individual control of the office and the enclosed spaces (Faculty / Staff Dining Room) would be provided. The ventilation system would be 1/3 the size of the all system described in Option 1 above. The optimum location for the ventilation air is at low level so the displacement effect can be used.

The radiant floor assembly will consist of a topping slab with a total thickness of 3 inches. This includes 1 inch for insulation between the slab and topping slab, and a 2 inch thick topping slab.

This system has the following characteristics:

Benefits	Cons
Excellent IAQ.	Unconventional system with which some subcontractors are unfamiliar.
Excellent control.	Limited load capacity. Must be comprehensively designed to balance demand with capacity. May require building occupants to moderate heat gain from lighting, computers, equipment, etc.
Excellent comfort.	Require exposed thermal mass to allow passive cooling.
Reduced floor to floor height.	
Very responsive system	
Can work in tandem with natural ventilation with control monitoring.	
Very energy efficient. Both hydronic cooling and displacement AHUs run at higher chilled water higher temps allowing the central plant to run at its maximum efficiency.	

Option 3 is a dedicated outside air system with active chilled beams. The active beam density at the perimeter would be one 6 foot beam per 100 sq.ft. Individual control of offices would be provided.

This system provides:

Benefits	Cons
Very good IAQ. The system is not displacement but the dedicated outside air system provides constant rates of outside air.	Unconventional system with which some subcontractors are unfamiliar.
Very good control.	Limited load capacity. Must be comprehensively designed to balance demand with capacity. May require building occupants to moderate heat gain from lighting, computers, equipment, etc.
Excellent comfort.	Works best with exposed thermal mass to allow passive cooling.
Night time cooling with low energy. This option allows more ceiling to be exposed	
Very energy efficient due to higher chilled water temperatures. Achieving the mandatory T-24 energy performance is readily accomplished and further LEED® credits could be achieved.	
Can work in tandem with natural ventilation as the outdoor air is induced through the active beam, tempering the outside air	

System Narratives

MEP (CONTINUED)

In each option air handling system(s) will be draw-thru unit(s) with supply air fan, return / exhaust fan, outside air, return air and exhaust air dampers for 100% outside air economizer cooling cycle operation (option 1 only, option 2 and 3 are 100% outside air units without return fans or economizer), chilled water cooling coils, hot water heating coils, air filters, and acoustic attenuators as required to achieve design space noise levels.

Indirect evaporative cooling units will be considered and evaluated for 100% outdoor air supply.

Separate systems will be provided for areas with distinct functional or occupancy requirements and/or operating schedules, continuous cooling / heating requirements, and/or other unusual requirements.

Equipment will be selected with sufficient capacities to satisfy calculated building heating and cooling loads with allowances for future growth / remodeling of facilities as determined in collaboration with Campus engineering and facilities personnel.

Cooling and heating coils will be selected in accordance with the requirements of the Campus Standards and Design Guidelines as follows:

- Chilled Water Cooling Coils;
- Hot water heating Coils; and,
- 450 fpm maximum coil face velocity.

Minimum air filter efficiencies will be selected to meet LEED® IEQ 5 criteria:

- MERV 13 for air handling systems serving all spaces.

Temperature control zones will be provided as required by the building envelope design, space uses, occupancy, required times of operation, and/ or other special requirements.

Any night time cooling strategies will take into account the occupant load profile and morning temperatures will not prevent uncomfortable conditions.

Supply (or ventilation air) will be distributed throughout the building via insulated sheet metal ductwork and industry standard air diffusion devices. Displacement diffusers will be used in option 2.

There will be no exposed fiberglass duct liner installed in supply ducts downstream of the air filters. Noise control will be achieved by the use of attenuators.

Return air will be ducted where required, or transferred back to the air handling unit(s) via the ceiling plenums where the building design permits.

Toilet rooms, janitor's rooms, food service and other areas where heat and/or odors are generated will be ventilated with mechanical exhaust systems. Food service areas will be served with dedicated exhaust and make-up air per the recommendations of the kitchen consultant.

Exhaust fans will discharge minimum 10 feet above grade level and minimum 10 feet away from air intakes or other openings into the building.

Mechanical rooms will be designed to accommodate equipment with adequate access and clearances for maintenance and replacement of components during the life of the equipment. Roof top air handling units are envisioned for the project.

Cooling System - Chilled Water Supply & Return

Site Utilities: Chilled water will be supplied to the building from existing campus Central Plant utility sources. Connection locations: Vault-15.

It is anticipated that existing site utility systems have sufficient capacities to support the estimated additional loads to be imposed by the new and/ or renovated structures. Actual loads will be verified during Schematic Design. It should be noted that Options 2 and 3 above require higher chilled water temperature than the 45F available. It is possible that return chilled water can be used to feed the chilled beams or chilled ceilings, raising the general Campus chilled water return temperature and not imposing a load on the chilled water supply.

A hydraulic decoupler will separate the Campus and building chilled water supplies. Two (2) chilled water pumps, each sized for 60% of design flow, will be located in a mechanical room in the Barn. The arrangement and control of the pumps for alternating lead-lag operation will be in accordance with the Campus Standards and Design Guidelines. Variable frequency drives (VFDs) will be used if it is shown to be cost effective to do so. VFDs will be located in cooled spaces or where they can be effectively cooled by general building exhaust air.

Cooling coils will be controlled by modulating control valves with DDC (Direct Digital Control) actuators.

Chilled water supply and return piping will be insulated Schedule 40 black steel, or Type L copper.

System Narratives

MEP (CONTINUED)

Heating System

Heating hot water for the complex will be supplied via the Campus steam loop. Heat transfer will via a tube and shell heat exchanger will occur in the mechanical room, located in the Barn.

Two heating water pumps, each sized for 60% of total design flow, will distribute hot water to heating coils in air handling units and chilled beams/radiant floors (and if provided at VAV boxes).

The arrangement and control of the pumps for alternating lead-lag operation will be in accordance with the Campus Standards and Design Guidelines. Variable frequency drives will be used if it is shown to be cost effective to do so. VFDs will be located in cooled spaces or where they can be effectively cooled by general building exhaust air.

Heating coils will be controlled by modulating control valves with DDC actuators.

Heating piping will be Schedule 40 steel, or Type L copper piping, and will be fully insulated.

Central Plant Option

An alternative approach to using the campus utilities as described in the sections on 'Cooling Systems' and 'Heating Systems' is to build a dedicated central plant for the facility. The central plant would consist of a cooling tower, water-cooled chiller and condensing boiler. Primary pumps for condenser water, chilled water and heating hot water will be provided. Associated secondary pumps for chilled water and heating hot water will be as described in sections 5.3.5 and 5.3.6.

Issues to consider with the central plant option include: requirement for outdoor space for the central plant facility (with covered structures for the chiller, boiler and pumps), acoustical impact of central plant on surrounding outdoor patios and programmed spaces, and additional maintenance requirements for the facility.

HVAC Controls

A direct digital control (DDC) system will be provided for all HVAC equipment and systems. The system will include field panels wired to a PC control front end and will be capable of stand-alone operation. DDC controls shall be BACnet per the Campus Standards and Design Guidelines.

The PC front end will have full color graphics, simulation of all systems, capable of monitoring, remote set point adjustment of all devices, trending, lighting control and other functions as required. The system will be linked to the Campus energy management and control system.

All control valves and motorized dampers will have DDC operators to be controlled and monitored by the DDC control system.

Testing, Adjusting and Balancing and Commissioning

All testing and balancing of HVAC systems will be by an independent test and balance company hired by the General Contractor or directly by the University, as agreed during the design phases of the project.

Air systems will have manual dampers where required for balancing.

Hydronic systems will have manual balancing valves where required for balancing, together with Pete's plugs or similar devices for measurement of temperatures and pressures at coils, pumps, control valves and other strategic locations.

All systems shall be commissioned to the Campus protocol. Additional commissioning to qualify for the LEED® EA3 credit should be priced as a separate line item.

PLUMBING AND FIRE PROTECTION SYSTEMS

Codes and Standards UC Riverside Campus Standards and Design Guide

- California Building Code, 2007
- California Plumbing Code, 2007
- California Fire Code, 2007
- NFPA Codes, current editions, as applicable

General

Site Utilities: Construction and renovation of the buildings will require existing site plumbing utilities to be relocated or removed. Phasing of this work and provision of stub-outs for lateral connections to the new buildings will be coordinated with the Campus facilities and engineering personnel and the project civil engineering consultant. Disruption of existing Campus utilities for the new connections will be coordinated with Campus facilities personnel.

System Narratives

MEP (CONTINUED)

It is anticipated that existing site utility systems have sufficient capacities to support the estimated additional loads to be imposed by the new building as indicated on the Preliminary Utility Demand Form, but this will be verified during Schematic Design. Given the LEED® aspirations for the building it is envisioned that the use of low flow fixtures will reduce the water demand below the projections of the Utilities Demand Form.

Plumbing systems for the buildings include sanitary sewer and vent, roof drains and rainwater piping, domestic cold water and hot water, and natural gas supply piping inside the buildings.

Plumbing utility piping beyond 5 feet outside the building will be designed by the project civil engineering consultant.

The buildings will be fully protected by an automatic wet-pipe fire sprinkler and alarm system.

Plumbing Fixtures

Fixtures will be provided as required by the Room Data Sheets and will be selected to comply with Campus Standards and Design Guidelines.

Plumbing fixtures will be commercial quality with water conserving technologies to meet the LEED® aspirations of the project.

Water closets shall be dual flush 0.8/1.6 gallon per flush and urinals shall be 1/8 gallon per flush or waterless urinals upon prior approval of UCR facilities staff. Fixtures will be wall hung. Metering faucets with 0.5 gpm flow control aerators and other restroom appliances / dimensions will fully comply with ADA and other relevant regulations. It is estimated that all non irrigation LEED® Water

Efficiency credits could be achieved using these low flow fixtures.

Domestic Cold Water

Domestic cold water will be supplied to the buildings from the campus utility main, with an approved water meter installed inside the mechanical room (in the Barn) and reduced pressure backflow preventer.

Maximum pressure in each building will not exceed 80 psi. A pressure reducing station will be provided if necessary.

Piping will be Type L copper, designed in accordance with Campus Standards and Design Guidelines and industry standard sizing methodology to meet the building demands.

Cold water piping will be insulated in unheated attic spaces and where exposed to potential freezing conditions

Shut-off valves will be provided in accessible locations to allow for isolation of each toilet room or small groups of fixtures to facilitate maintenance and future modification.

Industrial (Non-potable) Water

Industrial water for make-up to HVAC systems, and/or other non-potable uses, will be supplied from the potable domestic cold water supply system with a separate reduced pressure backflow preventer.

Piping will be Type L copper, designed in accordance with the Campus Standards and Design Guidelines and industry standard sizing methodology to meet the calculated demands.

Piping will be insulated in unheated attic spaces and where exposed to freezing conditions.

Shut-off valves will be provided in accessible locations to allow for isolation of each piece of equipment to facilitate maintenance and future modification.

Domestic Hot Water

Base building design for generation of domestic hot water will be to utilize gas fired water heaters. An in-line circulation pump will be included to circulate hot water through the heating systems as necessary to maintain temperature in the distribution piping.

Hot water piping will be Type L copper, designed in accordance with Campus Standards and Design Guidelines and industry standard sizing methodology to meet the building demands.

Hot water supply and circulation / return piping will be insulated.

Sanitary Waste and Vent

Sanitary waste and vent system will be connected to the Campus sanitary sewer as coordinated with the project civil engineer.

Piping will be cast iron, designed in accordance with Campus Standards and Design Guidelines and industry standard sizing methodology to meet the building demands.

System Narratives

MEP (CONTINUED)

Roof Drains

Roof drains, overflow drains, conductors, and/or down spouts will be provided and connected into the Campus storm sewer as coordinated with the project civil engineer. The systems shall be designed so that stormwater is not diverted directly to Campus sidewalks and/or exterior courtyard paved surfaces. Detention of stormwater should occur in bioswales or other planted areas, not into or onto paved surfaces used by pedestrians, bicycles and/or "customers" of The Barn Group.

Overflow provisions will be by roof drains with a separate piping system or scuppers, as determined during Schematic Design phase.

Piping will be cast iron, designed in accordance with Campus Standards and Design Guidelines and industry standard sizing methodology to meet the building requirements.

Fire Protection Systems

Based on the findings of the Historic Resources Assessment, the project will be brought up to current Fire Code per the discussions with the Campus Fire Marshall at Workshop #1 of the DPP on 2/05/2010 and Workshop #1 of the DPP Update on 2/03/2012.

The buildings will be fully protected by an automatic fire sprinkler and alarm systems designed in accordance with NFPA 13, and the Campus Standards. Occupancy Hazard classification(s) will be from NFPA 13, as approved by the Fire Marshal. Special extinguishing systems will be provided if required to protect sensitive electronic equipment.

System control valve and fire department

connection will be located outside the building.

ELECTRICAL

Codes and Regulations

All electrical work shall comply with the following codes and standards:

- National Electrical Code (2008 Edition)
- National Fire Protection Association (NFPA 72)
- California Energy Conservation Code, Title 24 CCR
- Illumination Engineering Society of North America (IES)
- Local Utility Company Rules and Regulations
- Local Fire Authority

Electrical Design Criteria

The buildings have a combined area of approximately 20,000 s.f. Based on a preliminary approximation of 10VA/sf for Cottage, 22VA/sf for the Kitchen Addition & 10VA/sf for the remaining space within The Barn, 12VA/sf for the Barn Stable, 12VA/sf for Faculty/Staff Dining Facility, and 16VA/sf for the Barn Theater, the total VA needed for the entire complex equals approximately 350kVA.

TDE recommends a 500kVA, 12kV-480/277V, pad mounted transformer be provided to supply power to the buildings. The main incoming service will be sized at 600A at 480/277V, 3-phase, 4-wire. The pad mounted transformer should be located near the main electrical room (within the Barn) in order to reduce conduit runs and related costs.

Building Power Distribution Systems

In addition to the main electrical room noted above, each building should also have dedicated electrical closets to house electrical panels and any 480-208/120V, 3-phase, dry-type transformers, as needed.

The 480/277V incoming service shall be used to provide power to motor loads rated 1HP or higher and all lighting loads. In order to supply motor loads rated less than 3/4HP, and other receptacle loads, an indoor rated dry-type transformer will be located in the main electrical room.

The exact number of panels will be determined once the final floor layout is decided.

UCR specific requirements such as flush floor receptacles shall be provided for all potential meeting and conference rooms.

Grounding System

Grounding system will be installed per NEC, section 250. A central grounding system will be provided for the main service. All grounded busses from switchboard, transformers, and panel boards will be connected at a central grounds bus in the electrical room.

Load management

In order to reduce power demand in the building TDE recommends using energy efficient lighting fixtures integrated with occupancy sensors and photocells will help reduce loads in the building even further. TDE also recommends the use of Energy Star rated appliances (where available) for the kitchen.

System Narratives

MEP (CONTINUED)

Emergency Power

Emergency power shall be provided via an emergency generator to support The Barn Group in the case of an emergency. In order to provide lighting for path of egress, all emergency fixtures will be connected to the generator, which will power the fixtures in case of a power outage. The generator will also support critical loads within the Kitchen and Faculty/Staff Dining, as identified by the Campus. These needs will be reviewed during the design phases.

Lighting

Lighting Level

Lighting system level will be designed in accordance with Illuminating Engineering Society (IES) recommendations, California Code of Regulations (CCR), and Title 24. The following chart will be adopted as reference:

LIGHTING LEVEL GUIDELINES

Type of Area	Recommended Footcandle Level at WorkStation*
Support Spaces	5-10
Meeting/Conference rooms.	40
Dining Areas	50-60
Work circulation areas, surrounding work stations, bathrooms, work areas where critical visual tasks are not performed	20-30
Offices	30-50

*where general lighting levels fall below UCR standards supplementary task lighting shall be used.

Lighting Control

All lighting will have means of automatic shut-off to comply with Title 24 except where this may create a hazard in areas such as the Kitchen Addition. This will be achieved through the use of occupancy sensors and lighting control panels. A lighting control panel will be located in the electrical room. Lighting in open areas, corridors, and exterior lighting will be controlled by the lighting control panels. Individual offices, restrooms, electrical and mechanical rooms will be controlled by occupancy sensors. All areas greater than 100 square feet will have bi-level switching to comply with Title 24.

Areas greater than 250 square feet with areas fifteen feet or more away from windows will have daylighting control zones to comply with Title 24. The zones will be controlled by ceiling mounted photosensors and will be capable of dimming the light in the associated zone. The daylighting zones will also have bi-level switching to allow 50% of the lights to be switched off.

Fire Alarm System

An addressable fire alarm system complying with the Campus Standards and Design Guidelines will be provided and consist of the following:

- A. A main fire alarm control panel located in the fire alarm control room, if possible.
- B. Heat detectors will be installed in the main electrical room, elevator machine room and kitchen area. Smoke detectors will be installed in accordance with code.

- C. Audio-visual alarm stations will be provided along all egress routes, toilet areas, lobbies and other areas of assembly.

- D. Pull station will be provided along egress routes.

The fire alarm system will be linked with elevators for return to a predetermined floor and mechanical air supply system for shut-down in the event of fire alarm signal.

The fire alarm system will also be linked to the sprinkler flow switches and valve monitors.

The fire alarm system will be tied to the campus main fire alarm system. All devices shall be addressable.

Telecommunication System

Electrical shall run all necessary conduits for telecommunications installation. The telecom infrastructure for the building shall be designed per the telecommunications consultant.

System Narratives



PREVIEWGROUP
ARCHITECTS PROVIDING REGULATORY SOLUTIONS...

August 8, 2012

CODE

**DETAILED PROJECT PROGRAM UPDATE
CODE ANALYSIS
UC RIVERSIDE BARN PROJECT**

Project Description

The project involves alterations to several existing buildings on the University of California Riverside Campus. The initial phase of work will include major utility connections and minor changes to the Barn Theater ramps and fire egress. Later construction work will occur in one phase, except for that for the Barn Theater and addition, which will be done in a separate future phase. The phasing of the project will need to be confirmed as the project moves forward. This code analysis looks at the entire proposed project, including all future building projects in the Barn area, as a single unified project for code analysis purposes. The overall areas for the final build-out are included in the analysis.

Applicable Codes & Standards and Authorities Having Jurisdiction

The basis for our analysis and the conclusions contained within this report are taken from requirements contained in the following codes and standards that currently apply to this project:

2010 California Building Code (CBC), CCR Title 24, Part 2

2010 California Electrical Code (CEC), CCR Title 24, Part 3 (reviewed for architectural impacts only)

2010 California Mechanical Code (CMC), CCR Title 24, Part 4 (reviewed for architectural impacts only)

2010 California Plumbing Code (CPC), CCR Title 24, Part 5 (reviewed for architectural impacts only)

2010 California Energy Code (CEnc), CCR Title 24, Part 6 (Not reviewed for this report)

2010 California Fire Code (CFC), CCR Title 24, Part 4 (reviewed for architectural impacts only)

2010 Green Construction Code (CGC), CCR Title 24, Part 11 (Applicable only to new buildings, not reviewed for this report)

2012 ADA/ABA (ADA/ABA) Accessibility Guidelines (Became mandatory March 15, 2012, not reviewed at this stage of document completion)

The code analysis will need to be updated at the time of construction of each project to verify project compliance with the new editions of the applicable codes that will be in effect at the time of construction.

The Authorities Having Jurisdiction (AHJ) over this project will be the Campus Fire Marshal and the Campus Building Official. Note that while these buildings are in a portion of the campus with historical import none of these buildings have been identified as historic resources and are therefore not eligible for the use of the California State Historical Building Code (SHBC). Accordingly the applicable building code is the 2010 CBC.

System Narratives

Occupancies

CODE (cont.)

The buildings make up a mixed-use facility with a wide variety of anticipated uses. Occupancy groups are classified according to CBC Chapter 3. The anticipated occupancy groups are noted below with an accompanying CBC Chapter 3 citation. We recommend that the uses be treated as nonseparated occupancies to allow the various uses to flow together without occupancy separations. The consideration of how separations of occupancies are treated is described later in this report.

Area / Use Description	CBC Occupancy Classification / Citation	CBC Use Description
The Barn Dining/Kitchen		
Production Kitchen	F-2, CBC Section 306.3	Manufacturing
Food Service Areas	A-2, CBC Section 303.1	Assembly for Food and Drink
Dining	A-2, CBC Section 303.1	Assembly for Food and Drink
Faculty/Staff Dining		
Food Service Areas	A-2, CBC Section 303.1	Assembly for Food and Drink
Dining	A-2, CBC Section 303.1	Assembly for Food and Drink
Barn Stable		
Meeting/Dining Rooms	A-2, CBC Section 303.1	Assembly for Food and Drink
Cottage		
Food Service Areas	A-2, CBC Section 303.1	Assembly for Food and Drink
Barn Theater		
Rehearsal (incidental uses)	A-3, CBC Section 303.1	Assembly without fixed seating
Restrooms		
Joint Use Toilet Facilities	B, CBC Section 304	Educational occupancies for students above the 12th grade

Fire Protection Requirements

The project will be sprinklered per the requirements of several sections of CBC Chapter 9. The sprinkler system will also be used to increase the allowable area of the building(s). The sprinkler system is to be compliant with the requirements of NFPA 13 per CBC and CFC Section 903.3.1.1.

Allowable Heights and Areas, Construction Type and Occupancy Separations

The proposed total area of the group of buildings is approximately 25,070 square feet. All are proposed to be single story buildings. Because of the proximity of the buildings and their interconnected uses it is desirable to analyze the group of buildings as a single building. CBC Section 503.1.2 addresses buildings located together on the same lot. Two or more buildings on the same lot may be considered as portions of one building if the building height of each building and the aggregate building area of all of the buildings are within the limitations of CBC Table 503 as modified by CBC Sections 504 and 506. Also, because the building has many mixed uses it is desirable that the building be treated as a nonseparated occupancy per the requirements of CBC Section 508.3. This section requires that the allowable building area and height be based on the most restrictive allowances for the occupancy groups under consideration for the type of construction of the building using the height and area values shown in Table 503.1. We have examined the requirements for the various occupancies proposed, based on the most restrictive values for each taken from Table 503 compared to the construction type, which is assumed to be Type VB. The formulas for area increase contained in CBC Section 506 are based on location on property and provision of sprinklers. The equations to be used are 5-1 and 5-2. The values to be evaluated are:

CODE (cont.)

- A_t = Area from CBC Table 503
- I_s = Increase for sprinklers per CBC Section 506.3
- I_f = Increase for frontage per CBC Equation 5-2 where I_f = [F/P - 0.25] W/30
 - F = Frontage on a public way
 - P = building perimeter
 - W = width of public way

If the group of buildings is considered to be a single building then the “building” may be considered to be open on all sides for a distance exceeding 30 feet. The perimeter of the group of building elements facing outward toward other adjacent buildings near the site is 990.7 linear feet. There is a 30.25 linear foot section of wall at the Faculty/Staff Dining area which has a fire separation distance of less than 30 feet, but more than 20 feet. Rather than do a proportional assessment of this short length of perimeter at this early point in project design we have deducted it from the perimeter to calculate the frontage area per Equation 5-2. Thus F = 990.7 – 30.25 = 960.45 linear feet and P equals the entire building perimeter, or 990.7 linear feet.

$$\begin{aligned}
 I_f &= [960.45/990.7 - 0.25] 30/30 \\
 &= [0.9695 - 0.25] /1 \\
 I_f &= 0.7195
 \end{aligned}$$

The total allowable area A_a is to be determined per Equation 5-1 where A_a = { A_t + [A_t x I_f] + [A_t x I_s] }. The area for sprinkler increases is per CBC Section 506.3. The sprinkler increase factor (I_s) for single story buildings is 3. This also applies to buildings under the purview of the State Fire Marshal, as are A-2 and A-3 occupancies. Here, the sprinklers are not used for an increase in building height, or for the number of stories, so the factor of 3 may be applied in this case.

The allowable areas for the proposed occupancies noted above as shown in CBC Table 504 for Type VB buildings are:

- A-2 6,000 square feet
- A-3 6,000 square feet
- B 9,000 square feet
- F-2 13,000 square feet

The most restrictive area allowed for nonseparated uses is either for A-2, or A-3; 6,000 square feet. Using Equation 5-1 the allowable area is:

$$\begin{aligned}
 A_a &= \{ 6,000 + [6,000 x 0.7195] + [6,000 x 3] \} \\
 &= 6,000 + 4,317 + 18,000 \\
 &= 28,317 \text{ sf allowable building area, which is greater than the 27,900 sf proposed.}
 \end{aligned}$$

The aggregate area of the group of buildings is under the allowable area so they may be treated as a single building containing nonseparated occupancies. Per the Exception to CBC Section 705.3 no wall or opening protection is required between multiple buildings on a single site that comply with the limitations of Chapter 5 for area, based on the most restrictive allowable area for the occupancies proposed, as does this group of structures.

CODE (cont.)

Fire Resistance Ratings for Building Elements

Based on the VB construction type assumed above the fire resistance rating requirements for building elements per CBC Tables 601 and 602 are as follows:

Structural Frame:	0 hours
Exterior Bearing Walls:	0 hours
Exterior Nonbearing Walls:	Unrated per Table 602, there are no imaginary lines or actual property lines within 30'
Interior Bearing Walls:	0 hours
Interior Nonbearing Walls:	0 hours
Floor Construction:	0 hours
Roof Construction:	0 hours

Occupant Loads

The occupant load calculations for this report are to determine the required number and widths of exits, including those on the site areas between building elements. This information is gathered from the programming area calculations, but areas have been aggregated among those groups of uses which have the same function and the same occupant load factors. Areas not considered as normally occupied, per the CBC definition of "net" floor area in Section 1002 have been omitted. Thus the square footages shown here do not obviously correspond to those shown in the program documents, as they are intended for different purposes than the program documents. The occupant load factors are taken from CBC Table 1004.1.1. Since the group of buildings will be treated as a single building for egress analysis, usable outdoor areas are assigned occupant loads in order to assess the number and width of required means of egress in the areas between building portions. The occupant loads at typical exterior areas are assigned an Occupant Load Factor of 15 square feet per occupant. This is appropriate for their anticipated use as dining or drinking locations with loose tables and chairs. If areas where seats in rows for viewing programs are desired then the occupant loads for those areas were assigned an Occupant Load Factor of 7 square feet per occupant with a clear circulation area assigned around the seating area.

The Barn: Barn Dining/Kitchen Addition

Use	Area (SF)	Occupant Load Factor	Occupant Load
Production Kitchen	2,145	200	11
Back of House Support	564	200	3
Serving and Queuing	1,290	15	86
Indoor Seating & Stage	2,401	15	160
Indoor Area Total			260
Outdoor dining, gathering East	2,140	15	143
Outdoor dining, West	3,255	15	217 (Two exits required)
Outdoor viewing, West	3,255	7	465 (Two exits required, highest use case, used for egress and plumbing fixture count)
Outdoor Area Total			608 (assumes viewing area occupant load)

CODE (cont.)

Occupant Loads (Continued)

Faculty/Staff Dining

Use	Area (SF)	Occupant Load Factor	Occupant Load
Dining Areas/Lobby	1,592	15	102
Back of House Areas	580	200	3
Support Spaces	910	200	5
Interior Total			110
Outdoor Stage	600	15	40
Outdoor Total			40

Barn Stable

Use	Area (SF)	Occupant Load Factor	Occupant Load
Dining/Meeting	868	15	58
Support	1,002	200	5
Interior Total			63
Barn Stable Patio	875	15	58
Outdoor Total			58

Cottage

Use	Area (SF)	Occupant Load Factor	Occupant Load
Serving/Dining/Lobby	445	15	30
Support	294	200	2
Interior Total			32
Covered Porches	346	15	23
East Courtyard	1,000	15	67
South Patio	1,080	15	72
Outdoor Total			162

Barn Theater

Use	Area (SF)	Occupant Load Factor	Occupant Load
Rehearsal	1,905	15	127
Support	1,108	200	6
Interior Total			133
Exterior Stage	670	15	45
Outdoor Total			45

**UC Riverside Barn Project
DPP Update**

**Plumbing Fixture Count - Whole Site
Assumes Simultaneous Occ. W/ West Court**

Code Analy.

CPC Table 4-1

(Sums may vary from line totals due to rounding)

Aggregate Dining and Service Areas (Barn, Faculty/Staff Dining, Cottage, Barn Stable)												
Area/(Occ. For Plg. Fixt.)	Occ.	Size - SF	Occ Load Factor CPC Tables 4-1, A	Occupant Load	Male "M"	Female "F"	WC Basic	Urinals, Footnote 5	WC w/urinal count adjust.	Lavs	Dkg. Ftn. (1:150) M+F	Notes
Dining	A-2	5,306	30	177	88	-	2	1	1	1		
(Aggregate areas)					-	88	2	-	-	1		
Service Areas	A-2	7,893	200	39	20	-	1	1	1	1		Includes Barn
(Aggregate areas)					-	20	1	-	-	1		Theater support
West Courtyard	A-3	-	Viewing	465	233	-	3	3	2	2		465 set by use
Performance Use					-	233	11	-	-	2		not by occ. Load
Outdoor Dining/Assembly	A-2	6,041	30	201	101	-	2	1	1	1		West Court not
(Aggregate areas)					-	101	2	-	-	1		counted here
Total Fixtures Required Per Male Occupant Load					441	-	-	6	3	5		
Fixtures Provided - Males							-	-	-	-		
Total Fixtures Required Per Female Occupant Load					-	441	16	-	-	5		
Fixtures Provided - Females							-	-	-	-		
Drinking Fountains (High-low DF counted as 2 DF)											0	No DF @ dining

Barn Theater												
Area/(Occ. For Plg. Fixt.)	Occ.	Size - SF	Occ Load Factor CPC Tables 4-1, A	Occupant Load	Male "M"	Female "F"	WC Basic	Urinals, Footnote 5	WC w/urinal count adjust.	Lavs	Dkg. Ftn. (1:150) M+F total	Notes
Rehearsal/Support	A-3	1,905	15	127	64	-	1	1	1	1	1	
(Aggregate areas)						64	4	-	-	1		
Total Fixtures Required Per Male Occupant Load					64		-	1	1	1	-	
Fixtures Provided - Males							-	-	-	-	-	
Total Fixtures Required Per Female Occupant Load						64	4	-	-	1	-	
Fixtures Provided - Females							-	-	-	-	-	
Drinking Fountains (High-low DF counted as 2 DF)											1	= 1 hi-low DF

AGGREGATED REQUIREMENTS FOR WHOLE SITE												
Area/(Occ. For Plg. Fixt.)	Occ.	Size - SF	Occ Load Factor CPC Tables 4-1, A	Occupant Load	Male "M"	Female "F"	WC Basic	Urinals, Footnote 5	WC w/urinal count adjust.	Lavs	Dkg. Ftn. (1:150) M+F total	Notes
Total Fixtures Required Per Male Occupant Load					505	-	-	6	3	6		
Fixtures Provided - Males							-	-	-	-		
Total Fixtures Required Per Female Occupant Load					-	505	20	-	-	6		
Fixtures Provided - Females							-	-	-	-		
Drinking Fountains (High-low DF counted as 2 DF)											1	= 1 hi-low DF

CODE (cont.)

SUPPORT DOCUMENTS: LEED

The LEED Checklist is a planning tool for the project team to track targeted credits, unsure or questionable credits, and those not targeted credits. These are presented in an easy to read format helping to insure that the project is on track to meet the LEED requirements. The LEED certification goal is Gold. An effort will be made to pursue as many potential credits as feasible while insuring that the targeted credits are met.

The LEED Matrix provides more details on credit requirements, responsibilities and action items. Most credits provide multiple options for compliance and these will be evaluated during design. Credit requirements are reviewed and updated by USGBC and are subject to change. The project follows the LEED requirements that have been adopted at the time the project is LEED registered.

LEED Checklist



LEED 2009 for New Construction and Major Renovation

Project Checklist

UCR Barn Expansion Project
2/29/12

	20	2	4	Sustainable Sites	Possible Points: 26
	Y	N	?		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Prereq 1 Construction Activity Pollution Prevention	
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 1 Site Selection	1
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 2 Development Density and Community Connectivity	5
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 3 Brownfield Redevelopment	1
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 4.1 Alternative Transportation—Public Transportation Access	6
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 4.2 Alternative Transportation—Bicycle Storage and Changing Rooms	1
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 4.3 Alternative Transportation—Low-Emitting and Fuel-Efficient Vehicles	3
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 4.4 Alternative Transportation—Parking Capacity	2
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 5.1 Site Development—Protect or Restore Habitat	1
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 5.2 Site Development—Maximize Open Space	1
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 6.1 Stormwater Design—Quantity Control	1
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 6.2 Stormwater Design—Quality Control	1
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 7.1 Heat Island Effect—Non-roof	1
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 7.2 Heat Island Effect—Roof	1
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 8 Light Pollution Reduction	1

	4	0	6	Water Efficiency	Possible Points: 10
	Y	N	?		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Prereq 1 Water Use Reduction—20% Reduction	
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 1 Water Efficient Landscaping	2 to 4
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> Reduce by 50%	2
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> No Potable Water Use or Irrigation	4
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 2 Innovative Wastewater Technologies	2
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 3 Water Use Reduction	2 to 4
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> Reduce by 30%	2
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Reduce by 35%	3
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Reduce by 40%	4

LEED Checklist

12	9	15	Energy and Atmosphere		Possible Points: 35
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Prereq 1	Fundamental Commissioning of Building Energy Systems	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Prereq 2	Minimum Energy Performance	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Prereq 3	Fundamental Refrigerant Management	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 1	Optimize Energy Performance	1 to 19
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 12% for New Buildings or 8% for Existing Building Renovations	1
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 14% for New Buildings or 10% for Existing Building Renovations	2
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 16% for New Buildings or 12% for Existing Building Renovations	3
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 18% for New Buildings or 14% for Existing Building Renovations	4
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 20% for New Buildings or 16% for Existing Building Renovations	5
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 22% for New Buildings or 18% for Existing Building Renovations	6
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 24% for New Buildings or 20% for Existing Building Renovations	7
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 26% for New Buildings or 22% for Existing Building Renovations	8
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 28% for New Buildings or 24% for Existing Building Renovations	9
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Improve by 30% for New Buildings or 26% for Existing Building Renovations	10
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Improve by 32% for New Buildings or 28% for Existing Building Renovations	11
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Improve by 34% for New Buildings or 30% for Existing Building Renovations	12
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Improve by 36% for New Buildings or 32% for Existing Building Renovations	13
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Improve by 38% for New Buildings or 34% for Existing Building Renovations	14
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Improve by 40% for New Buildings or 36% for Existing Building Renovations	15
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Improve by 42% for New Buildings or 38% for Existing Building Renovations	16
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Improve by 44% for New Buildings or 40% for Existing Building Renovations	17
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Improve by 46% for New Buildings or 42% for Existing Building Renovations	18
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Improve by 48%+ for New Buildings or 44%+ for Existing Building Renovations	19
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 2	On-Site Renewable Energy	1 to 7
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		1% Renewable Energy	1
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		3% Renewable Energy	2
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		5% Renewable Energy	3
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		7% Renewable Energy	4
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		9% Renewable Energy	5
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		11% Renewable Energy	6
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		13% Renewable Energy	7
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 3	Enhanced Commissioning	2
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 4	Enhanced Refrigerant Management	2
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 5	Measurement and Verification	3
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Credit 6	Green Power	2

SUPPORT DOCUMENTS

LEED Checklist

3	0	3	Innovation and Design Process	Possible Points: 6
1			Credit 1.1 Innovation in Design: Green cleaning	1
		1	Credit 1.2 Innovation in Design: IPM	1
		1	Credit 1.3 Innovation in Design: Double Green power	1
1			Credit 1.4 Innovation in Design: Green Building as an Educational Tool	1
1			Credit 1.5 Innovation in Design: Sustainability in the Curriculum, Eco-Literacy	1
1			Credit 2 LEED Accredited Professional	1
3	0	1	Regional Priority Credits	Possible Points: 4
1			Credit 1.1 Regional Priority: SS 4.1 Public Transit Access	1
1			Credit 1.2 Regional Priority: SS 7.1 Heat Island, Non-Roof	1
		1	Credit 1.3 Regional Priority: WE 3 Water Use Reduction	1
1			Credit 1.4 Regional Priority: EQ 8.1 Daylight	1
60	14	37	Total	Possible Points: 110

Certified 40 to 49 points Silver 50 to 59 points Gold 60 to 79 points Platinum 80 to 110

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus			Original Document Prepared by Simon & Associates, Inc. 4/9/2010					
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)			Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below					
			Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below					
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
Sustainable Sites								
SS Prereq. 1	Construction Activity Pollution Prevention	Create and implement an Erosion and Sedimentation Control (ESC) Plan for all construction activities associated with the project. The ESC Plan shall conform to the erosion and sedimentation requirements of the 2003 EPA Construction General Permit OR local erosion and sedimentation control standards and codes, whichever is more stringent. The Plan shall describe the measures implemented to accomplish the following objectives: <ul style="list-style-type: none"> Prevent loss of soil during construction by stormwater runoff and/or wind erosion, including protecting topsoil by stockpiling for reuse. Prevent sedimentation of storm sewer or receiving streams. Prevent polluting the air with dust and particulate matter. 	X			C	Civil Engineer	
SS 1.0	Site Selection	Do not develop buildings, hardscape, roads or parking areas on portions of sites that meet any one of the following criteria: <ul style="list-style-type: none"> Prime farmland as defined by the United States Department of Agriculture in the United States Code of Federal Regulations, Title 7, Volume 6, Parts 400 to 699, Section 657.5 (citation 7CFR657.5) Previously undeveloped land whose elevation is lower than 5 feet above the elevation of the 100-year flood as defined by FEMA (Federal Emergency Management Agency) Land that is specifically identified as habitat for any species on Federal or State threatened or endangered lists Within 100 feet of any wetlands as defined by United States Code of Federal Regulations 40 CFR, Parts 230-233 and Part 22, and isolated wetlands or areas of special concern identified by state or local rule, OR within setback distances from wetlands prescribed in state or local regulations, as defined by local or state rule or law, whichever is more stringent. Previously undeveloped land that is within 50 feet of a water body, defined as seas, lakes, rivers, streams and tributaries which support or could support fish, recreation or industrial use, consistent with the terminology of the Clean Water Act Land which prior to acquisition for the project was public parkland, unless land of equal or greater value as parkland is accepted in trade by the public landowner (Park Authority projects are exempt). 	I			D	Architect	<p>CPP point.</p> <p><i>Per Workshop #1 (2/03/12): LEED has new guidelines, so LEED boundaries for the Barn Project may need to be re-drawn. The Barn Theater will be excluded.</i></p> <p><i>Since the Barn is comprised of multiple buildings, certification will follow the LEED Application Guide for Multiple Building and On-Campus Building Projects (AGMBC) (see link below) Part 2 with reference to Group Project Certification. This will streamline the certification process.</i></p> <p><i>The Cottage is under the minimum 1,000sf LEED requirement (MPR #4) and therefore will only be required to comply with targeted group credits. It should be treated as an extension of the certifying buildings</i></p> <p>Application Guide for Multiple Building and On-Campus Building Projects (AGMBC)</p>

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT <i>(blue shading indicates a campus baseline credit)</i>		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
SS 2	Development Density and Community Connectivity	<p>OPTION 1 - DEVELOPMENT DENSITY: Construct or renovate building on a previously developed site AND in a community with a minimum density of 60,000 square feet per acre net (Note: density calculation must include the area of the project being built and is based on a typical two-story downtown development). OR</p> <p>OPTION 2 - COMMUNITY CONNECTIVITY: Construct or renovate building on a previously developed site AND within 1/2 mile of a residential zone or neighborhood with an average density of 10 units per acre net AND within 1/2 mile of at least 10 Basic Services AND with pedestrian access between the building and the services. Basic Services include, but are not limited to: 1) Bank; 2) Place of Worship; 3) Convenience Grocery; 4) Day Care; 5) Cleaners; 6) Fire Station; 7) Hair Care; 8) Hardware; 9) Laundry; 10) Library; 11) Medical/Dental; 12) Senior Care Facility; 13) Park; 14) Pharmacy; 15) Post Office; 16) Restaurant; 17) School; 18) Supermarket; 19) Commercial Office; 20) Community Center; 21) Fitness Center; 22) Museum. Proximity is determined by drawing a 1/2 mile radius around the main building entrance on a site map and counting the services within that radius.</p>	5			D	Architect	

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus			Original Document Prepared by Simon & Associates, Inc. 4/9/2010					
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)			Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below					
			Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below					
CREDIT			YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
		DESIGN/CONSTRUCTION REQUIREMENTS						
SS 3.0	Brownfield Redevelopment	OPTION 1 - Develop on a site documented as contaminated (by means of an ASTM E1903-97 Phase II Environmental Site Assessment or a local Voluntary Cleanup Program) OR OPTION 2 - Develop on a site defined as a brownfield by a local, state or federal government agency.				I	D	Owner <i>Do not anticipate that abatement is necessary.</i>
SS 4.1	Alternative Transportation	Public Transportation Access OPTION 1: Rail Station Proximity - Locate project within 1/2 mile walking distance of an existing—or planned and funded—commuter rail, light rail or subway station (measured from the building entrance). OR OPTION 2: Bus Stop Proximity - Locate project within 1/4 mile walking distance of one or more stops for two or more public, campus, or private bus lines usable by building occupants (measured from the building entrance).	6				D	Architect CPP point. <i>OK per Workshop #1 (2/03/12); While losing shuttle, 2 RTA bus lines are still applicable.</i>
SS 4.2		Bicycle Storage & Changing Rooms: CASE 1 For commercial or institutional buildings provide secure bicycle racks and/or storage (within 200 yards of a building entrance) for 5% or more of all building users (calculated on average for the year), AND, provide shower and changing facilities in the building, or within 200 yards of a building entrance, for 0.5% of Full-Time Equivalent (FTE) occupants. CASE 2 For residential buildings, provide covered storage facilities for securing bicycles for 15% or more of building occupants in lieu of changing/shower facilities.	1				D	Architect CPP point. <i>Employee shower is located in the Barn Stable (this was previously assumed in the 2010 DPP) and will be used to achieve SS 4.2.</i>
SS 4.3		Low Emitting & Fuel Efficient Vehicles: OPTION 1 Provide preferred parking for low-emitting and fuel-efficient vehicles for 5% of the total vehicle parking capacity of the site. Providing a discounted parking rate is an acceptable substitute for preferred parking for low-emitting/fuel-efficient vehicles. To establish a meaningful incentive in all potential markets, the parking rate must be discounted at least 20%. The discounted rate must be equal to 5% of the vehicle parking capacity, publicly posted at the entrance of the parking area and available for a minimum of 2 years. OR OPTION 2 Install alternative-fuel refueling stations for 3% of the total vehicle parking capacity of the site (liquid or gaseous fueling facilities must be separately ventilated or located outdoors). OR OPTION 3: Provide low-emitting and fuel-efficient vehicles for 3% of full-time equivalent (FTE) occupants. Provide preferred parking for these vehicles. OR OPTION 4: Provide building occupants access to a low-emitting or fuel efficient vehicle-sharing program.	3				D	Architect Option 1. <i>Lot 4 will be considered off-site. Identify if on-site space nearest to Faculty/Staff Dining can be used. Per Workshop #1 (2/03/12) and continued discussion at Workshop #2 (4/13/12), a preferred parking space for low-emitting and fuel-efficient vehicles will be designated to achieve SS 4.3 Option 1.</i>

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
SS 4.4		<p>Parking Capacity:</p> <p>OPTION 1 — NON-RESIDENTIAL</p> <ul style="list-style-type: none"> Size parking capacity to meet but not exceed minimum local zoning requirements AND provide preferred parking for carpools or vanpools for 5% of the total parking spaces. <p>OR OPTION 2 — NON-RESIDENTIAL</p> <p>For projects that provide parking for less than 3% of FTE building occupants:</p> <ul style="list-style-type: none"> Provide preferred parking for carpools or vanpools, marked as such, for 3% of total provided parking spaces. Providing a discounted parking rate (20% for 2 years) is also acceptable. <p>OR OPTION 3 - RESIDENTIAL</p> <ul style="list-style-type: none"> Size parking capacity to not exceed minimum local zoning requirements, AND, provide infrastructure and support programs to facilitate shared vehicle usage such as carpool drop-off areas, designated parking for vanpools, or car-share services, ride boards, and shuttle services to mass transit. <p>OR OPTION 4 — ALL</p> <p>Provide no new parking.</p> <p>OR OPTION 5- MIXED USE (Residential with Commercial)</p> <ul style="list-style-type: none"> For mixed-use buildings with less than 10% commercial area, the entire building should be considered residential and adhere to the residential requirements in Option 3. For mixed use buildings with greater than 10% commercial area, the commercial space is to adhere to Non-Residential requirements, while the residential component is to adhere to residential requirements. Note - This option is for a mixed use building that is residential + commercial (or retail) as opposed to office + retail (non-residential building) 	2			D	Architect	<i>YES per Workshop #1 (2/03/12), since no new spaces are being added to the site and existing service spaces are remaining.</i>
SS 5.1	Site Development	<p>Protect or Restore Habitat:</p> <p>OPTION 1: On greenfield sites, limit all site disturbance to 40 feet beyond the building perimeter, 10 feet beyond surface walkways, patios, surface parking and utilities less than 12 inches in diameter; 15 feet beyond primary roadway curbs and main utility branch trenches, and 25 feet beyond constructed areas with permeable surfaces (such as pervious paving areas, stormwater detention facilities and playing fields) that require additional staging areas in order to limit compaction in the constructed area;</p> <p>OR OPTION 2: On previously developed or graded sites, restore or protect a minimum of 50% of the site area (excluding the building footprint) or 20% of the total site area (including the building footprint), whichever is greater, with native or adapted vegetation. (Native/adapted plants are plants indigenous to a locality or cultivars of native plants that are adapted to the local climate and are not considered invasive species or noxious weeds.) Projects earning SS credit 2 and using vegetated roof surfaces may apply the vegetated roof surface to this calculation if the plants meet the definition of native/adapted.</p>				I C	Contractor or Landscape Architect	

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
SS 5.2		<p>Maximize Open Space:</p> <p>OPTION 1 - Sites with Local Zoning Open Space Requirements Reduce the development footprint (defined as the total area of the building footprint, hardscape, access roads and parking) and/or provide vegetated open space within the project boundary to exceed the local zoning's open space requirement for the site by 25%.</p> <p>OR</p> <p>OPTION 2 - Sites with No Local Zoning Requirements (e.g., some university campuses, military bases) Provide vegetated open space area adjacent to the building that is equal to the building footprint.</p> <p>OR</p> <p>OPTION 3 - Sites with Zoning Ordinances but No Open Space Requirements Provide vegetated open space equal to 20% of the project's site area.</p> <p>ALL OPTIONS: • For projects located in urban areas that earn SS credit 2, vegetated roof areas can contribute to credit compliance. • For projects located in urban areas that earn SS Credit 2, pedestrian oriented hardscape areas can contribute to credit compliance. For such projects, a minimum of 25% of the open space counted must be vegetated. • Wetlands or naturally designed ponds may count as open space if the side slope gradients average 1:4 (vertical:horizontal) or less and are vegetated.</p>		I		D	Architect	<p>CPP point. Calculations need to be studied.</p> <p><i>Barn Project will be linked to campus-wide credits, per Workshop #1 (2/03/12)</i></p>
SS 6.1	Stormwater Design	<p>Quantity Control:</p> <p>CASE 1: IF EXISTING IMPERVIOUSNESS IS LESS THAN OR EQUAL TO 50%</p> <p>Option 1 - Implement a stormwater management plan that prevents the post-development peak discharge rate and quantity from exceeding the pre-development peak discharge rate and quantity for the one- and two-year 24-hour design storms.</p> <p>OR</p> <p>Option 2 - Implement a stormwater management plan that protects receiving stream channels from excessive erosion. The stormwater management plan must include a stream channel protection strategy and quantity control strategies.</p> <p>CASE 2: IF THE EXISTING IMPERVIOUSNESS IS GREATER THAN 50%</p> <p>Implement a stormwater management plan that results in a 25% decrease in the volume of stormwater runoff from the two-year 24-hour design storm.</p>		I		D	Civil Engineer	<p>Permeable paving (interlocking pavers for onsite filtration), bioswales, rain gardens. Rainwater collection will be considered.</p> <p><i>Change to MAYBE because of amount of green space being removed, per Workshop #1 (2/03/12)</i></p>
SS 6.2		<p>Quality Control: Implement a stormwater management plan that reduces impervious cover, promotes infiltration, and captures and treats the stormwater runoff from 90% of the average annual rainfall using acceptable best management practices (BMPs). BMPs used to treat runoff must be capable of removing 80% of the average annual post development total suspended solids (TSS) load based on existing monitoring reports. BMPs are considered to meet these criteria if (1) they are designed in accordance with standards and specifications from a state or local program that has adopted these performance standards, OR (2) there exists in-field performance monitoring data demonstrating compliance with the criteria. Data must conform to accepted protocol (e.g., Technology Acceptance Reciprocity Partnership [TARP], Washington State Department of Ecology) for BMP monitoring.</p>		I		D	Civil Engineer	<p>Bioswales.</p> <p><i>Change to MAYBE because of amount of green space being removed; per Workshop #1 (2/03/12)</i></p>

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010																		
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below																		
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below																		
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS												
SS 7.1	Heat Island Effect	<p>Non-Roof: OPTION 1: Use any combination of the following strategies for 50% of the site hardscape (including roads, sidewalks, courtyards and parking lots):</p> <ul style="list-style-type: none"> • Provide shade from existing tree canopy or within five years of landscape installation; landscaping (trees) must be in place at the time of certification application. • Provide shade from structures fully covered by solar photovoltaic panels. • Provide shade from architectural devices or structures that have a solar reflectance index (SRI2) of at least 29. • Have paving materials with an SRI of at least 29. • Have an open-grid pavement system (at least 50% pervious). <p>OR OPTION 2 Place a minimum of 50% of parking spaces under cover (defined as under ground, under deck, under roof, or under a building). Any roof used to shade or cover parking must have an SRI of at least 29, be a vegetated green roof or be covered by solar panels that produce energy used to offset some nonrenewable resource use.</p>	I			C	Architect or Landscape Architect	Hardscape will be durable and light-colored. Permeable paving. <i>Definitely YES because of amount of concrete; need SRI >29 which is achievable, per Workshop #1 (2/03/12).</i>												
SS 7.2		<p>Roof:</p> <p>OPTION 1: Use roofing materials having a Solar Reflectance Index (SRI) equal to or greater than the values in the table below for a minimum of 75% of the roof surface. If more than 75% of the roof area is covered with the SRI material, the SRI value may be lower than the required value if the resulting area-weighted equivalent SRI performance is at least as high as having the required value on 75% of the area.</p> <p>OR OPTION 2: Install a "green" (vegetated) roof for at least 50% of the roof area,</p> <p>OR OPTION 3: Install high albedo and vegetated roof surfaces that, in combination, meet the following criteria: (Area of SRI Roof/0.75) + (Area of vegetated roof /0.5) <= Total Roof Area</p> <p>Table:</p> <table border="1"> <thead> <tr> <th>Roof</th> <th>Type</th> <th>Slope</th> <th></th> </tr> </thead> <tbody> <tr> <td>Low-Sloped Roof</td> <td>≤ 2:12</td> <td></td> <td>= SRI 78</td> </tr> <tr> <td>Steep-Sloped Roof</td> <td>> 2:12</td> <td></td> <td>= SRI 29</td> </tr> </tbody> </table>	Roof	Type	Slope		Low-Sloped Roof	≤ 2:12		= SRI 78	Steep-Sloped Roof	> 2:12		= SRI 29	I			D	Architect, Landscape Architect, Green Roof Consultant	Adoption of cool roof standards is a goal of the UCR Sustainability Plan.
Roof	Type	Slope																		
Low-Sloped Roof	≤ 2:12		= SRI 78																	
Steep-Sloped Roof	> 2:12		= SRI 29																	
SS 8.0	Light Pollution Reduction	<p>FOR INTERIOR LIGHTING: Project teams must comply with 1 of the 2 options for interior lighting AND the requirement for exterior lighting.</p> <p>OPTION 1: Reduce the input power (by automatic device of) all non-emergency interior luminaires with the direct line of sight to any opening in the envelope (translucent or transparent) by at least 50% between 11 PM and 5 AM. After hours override may be provided by a manual or occupant sensing device provided that the override last no more than 30 minutes.</p> <p>OR OPTION 2: All openings in the envelope (translucent or transparent), with a direct line of sight to any non-emergency lighting must have shielding (controlled/closed by automatic device for a resultant transmittance of less than 10% between 11 PM and 5 AM).</p> <p>AND FOR EXTERIOR LIGHTING: Light areas only as required for safety and comfort. Lighting power densities must not exceed ANSI/ASHRAE/IESNA Standard 90.1-2007 (with errata but without addenda) for the classified zone.</p>		I		D	Electrical Engineer	Night sky protection policy is an intermediate goal of the UCR Sustainability Plan. Outdoor stage will need lighting weekly.												

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT <i>(blue shading indicates a campus baseline credit)</i>		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
		Classify the project under 1 of the following zones, as defined in IESNA RP-33, and follow all the requirements for that zone: LZ1 - Dark (Developed areas within national parks, state parks forest land and rural areas) LZ2 - Low (Areas predominantly consisting of; Residential zoning, Neighborhood business districts, Light industrial with limited nighttime use, Residential mixed use areas) LZ3 - Medium (All other areas not included in LZ1, LZ2 or LZ4 such as Commercial/Industrial, High-Density Residential) LZ4 - High (High activity commercial districts in major metropolitan areas. To be LZ4 the area must be so designated by the local jurisdiction) Please refer to the Rating System or Reference Guide for explanations of the zones.						
Water Efficiency								
WE prereq. 1	Water Use Reduction: 20% Reduction	Employ strategies that in aggregate use 20% less water than the water use baseline calculated for the building (not including irrigation). Calculate the baseline according to the commercial and/r residential baselines outlined in the reference guide. Calculations are based on estimated occupant usage and must include only the following fixtures and fixture fittings (as applicable to the project scope): water closets, urinals, lavatory faucets, showers, kitchen sink faucets and pre-rinse spray valves. The following fixtures, fittings and appliances are outside the scope of the water use reduction calculation: • Commercial Steam Cookers • Commercial Dishwashers • Commercial (family-sized) Clothes Washers • Residential Clothes Washers • Standard and Compact Residential Dishwashers	X			D	Plumbing Engineer	

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
WE I	Water Efficient Landscaping	<p>Option 1: Reduce by 50% (2 points) - Reduce potable water consumption for irrigation by 50% from a calculated mid-summer baseline case. Reductions shall be attributed to any combination of the following items:</p> <ul style="list-style-type: none"> • Plant species factor • Irrigation efficiency • Use of captured rainwater • Use of recycled wastewater • Use of water treated and conveyed by a public agency specifically for non-potable uses. <p>Groundwater seepage that is pumped away from the immediate vicinity of building slabs and foundations may be used for landscape irrigation to meet the intent of this credit. However, the project team must demonstrate that doing so does not affect site stormwater management systems.</p> <p>Option 2: No Potable Use or No Irrigation (4 points) - Achieve Option 1 AND:</p> <p>Use only captured rainwater, recycled wastewater, recycled greywater, or water treated and conveyed by a public agency specifically for non-potable uses for irrigation. OR Install landscaping that does not require permanent irrigation systems. Temporary irrigation systems used for plant establishment are allowed only if removed within one year of installation.</p>	2			D	Landscape Architect	<p>UCR Sustainability Plan intermediate goal calls for 20% reduction in potable water used for irrigation. Weather-based controls, hydrozoning and xeriscape and turf area reduction are components of the UCR Sustainability Plan.</p> <p>Planting: drought-tolerant perennials and shrubs, sycamores, oaks, citrus and possibly other fruit or nut trees (avocado, walnut); drought-tolerant native or Mediterranean perennials and shrubs; vines (grape or kiwi as potential edible vines). Also, species related to historical landscape will be included with reliance on climate adaptive species.</p>

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus			Original Document Prepared by Simon & Associates, Inc. 4/9/2010					
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)			Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below					
			Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below					
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
WE 2	Innovative Wastewater Technologies	<p>OPTION 1: Reduce potable water use for building sewage conveyance by 50% through the use of water conserving fixtures (water closets, urinals) or non-potable water (captured rainwater, recycled greywater, and on-site or municipally treated wastewater).</p> <p>OR</p> <p>OPTION 2: Treat 50% of wastewater on-site to tertiary standards. Treated water must be infiltrated or used on-site.</p>		2		D	Plumbing Engineer	Rainwater collection will be considered for both irrigation and toilet flushing. Greywater from kitchen addition is under consideration and is listed as an intermediate goal of the UCR Sustainability Plan.
WE 3	Water Use Reduction	<p>Employ strategies that in aggregate use less water than the water use baseline calculated for the building (not including irrigation). The minimum water savings percentage for each point threshold is as follows:</p> <p>30% Reduction = 2 points 35% Reduction = 3 points 40% Reduction = 4 points</p> <p>Calculate the baseline according to the commercial and/or residential baselines outlined in the reference guide. Calculations are based on estimated occupant usage and must include only the following fixtures and fixtures fittings (as applicable to the project scope): water closets, urinals, lavatory faucets, showers, kitchen sink faucets and pre-rinse spray valves.</p> <p>The following fixtures, fittings and appliances are outside the scope of the water use reduction calculation:</p> <ul style="list-style-type: none"> • Commercial Steam Cookers • Commercial Dishwashers • Commercial (family-sized) Clothes Washers • Residential Clothes Washers • Standard and Compact Residential Dishwashers 	2	2		D	Plumbing Engineer	<p>PP/ODC point. Mechanical Engineer narrative indicates 30%. Kitchen water use will have impact on savings.</p> <p>Specs: dual flush WCs 0.8/1.6 gpf, urinals shall be 1/8 gpf or waterless urinals, metering faucets with 0.5 gpm flow control aerators.</p> <p><i>Change to YES for 2 points, per Workshop #1 (2/03/12). Assumptions include low flow fixtures, dual flush toilets, and pint urinals; low flow fixtures and Energy Star rated appliances will be used in Kitchen and Dining Support.</i></p> <p><i>Need to verify this in the cost estimate.</i></p>

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT <i>(blue shading indicates a campus baseline credit)</i>		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
Energy and Atmosphere								
EA Prereq. 1	Fundamental Commissioning of the Building Energy Systems	<p>The following commissioning process activities shall be completed by the commissioning team:</p> <p>1) Designate an individual as the Commissioning Authority (CxA) to lead, review, and oversee the completion of the commissioning process activities.</p> <p>a) The CxA must have documented commissioning authority experience in at least two building projects.</p> <p>b) The individual serving as the CxA shall be independent of the project's design and construction teams, though they may be employees of the firms providing those services. The CxA may be a qualified employee or consultant of the Owner.</p> <p>c) The CxA must report results, findings and recommendations directly to the Owner.</p> <p>d) For projects smaller than 50,000 gross square feet, the CxA may include qualified persons on the design or construction teams who have the required experience.</p> <p>2) The Owner shall document the Owner's Project Requirements (OPR). The design team shall develop the Basis of Design (BOD). The CxA must review these documents for clarity and completeness. The Owner and design team shall be responsible for updates to their respective documents.</p> <p>3) Develop and incorporate commissioning requirements into the construction documents.</p> <p>4) Develop and implement a commissioning plan.</p> <p>5) Verify the installation and performance of the systems to be commissioned.</p> <p>6) Complete a summary commissioning report.</p> <p>COMMISSIONED SYSTEMS:</p> <p>Commissioning process activities shall be completed for the following energy related systems, at a minimum:</p> <ul style="list-style-type: none"> • Heating, ventilating, air conditioning, and refrigeration (HVAC&R) systems (mechanical and passive) and associated controls • Lighting and daylighting controls • Domestic hot water systems • Renewable energy systems (PV, wind, solar etc.) 	X			C	Commissioning Agent	Campus has Cx protocol.

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT <i>(blue shading indicates a campus baseline credit)</i>		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
EA Prereq. 2	Minimum Energy Performance	<p>OPTION 1: Whole Building Energy Simulation - Demonstrate a 10% improvement in the proposed building performance rating for new buildings, or a 5% improvement in the proposed building performance rating for major renovations to existing building, compared with the baseline building performance rating. Calculate the baseline building performance rating according to the building performance rating method in Appendix G of ANSI/ASHRAE/IESNA/ Standard 90.1-2007 (with errata but without addenda) using a computer simulation model for the whole building project.</p> <p>OR OPTION 2: Prescriptive Compliance Path:ASHRAE Advanced Energy Design Guide – Comply with the prescriptive measures of the ASHRAE Advanced Energy Design Guide appropriate to the project scope, outlined below. Project teams must comply with all applicable criteria as established in the Advanced Energy Design Guide for the climate zone in which the building is located. Path 1:ASHRAE Advanced Energy Design Guide for Small Office buildings 2004 –The building must be 1) less than 20,000 SF,AND 2) office Occupancy. Path 2:ASHRAE Advanced Energy Design Guide for Small Retail Buildings 2006 –The building must be 1) less than 20,000 SF,AND 2) retail occupancy. Path 3:ASHRAE Advanced Energy Design Guide for Small Warehouses and Self Storage Buildings 2008 –The building must be 1) less than 50,000 SF,AND 2) warehouse or self-storage occupancy.</p> <p>OR OPTION 3: Prescriptive Compliance Path: Advanced Core Performance Guide – Comply with the prescriptive measures identified in the Advanced Building Core Performance Guide developed by the New Buildings institute.The building must 1) be less than 100,000 SF, 2) comply with Section 1: Design Process Strategies, and Section 2: Core Performance Requirements, 3) office, school, public assembly, and retail projects less than 100,000 SF must comply with Section 1 and Section 2 of the Core Performance Guide, OR 4) other project types less than 100,000 SF implement the basic requirements of the Core Performance Guide,AND 5) health care, warehouse and laboratory projects are ineligible for this path.</p>	X			D	Mechanical Engineer	UC Mandate is 20%. Options for HVAC systems: Option 1, is a base case design of a single duct over head variable air volume (VAV) systems, with hot water reheat. Option 2 is a Dedicated Outside Air System with radiant floors. Option 3 is a Dedicated Outside Air System with active chilled beams.
EA Prereq. 3	Fundamental Refrigerant Management	Zero use of CFC-based refrigerants in new building HVAC&R systems.When reusing existing base building HVAC equipment, complete a comprehensive CFC phase-out conversion prior to project completion. Phase-out plans extending beyond the project completion date will be considered on their merits.	X					

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010																																																																					
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below																																																																					
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below																																																																					
CREDIT		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS																																																															
EA 1	Optimize Energy Performance	<p>Select 1 of the 3 compliance path options described below. Project teams documenting achievement using any of the 3 options are assumed to be in compliance with EA Prerequisite 2: Minimum Energy Performance.</p> <p>OPTION 1 — WHOLE BUILDING ENERGY SIMULATION (1-19 Points)</p> <p>Demonstrate a percentage improvement in the proposed building performance rating compared with the baseline building performance rating per ASHRAE/IESNA Standard 90.1-2007 (with errata but without addenda) using a computer simulation model for the whole building project. The minimum energy cost savings percentage for each point threshold is as follows:</p> <table border="1"> <thead> <tr> <th colspan="3">% Energy Cost Savings (minimum)</th> </tr> <tr> <th>New Buildings</th> <th>Existing Building Renovations</th> <th>Points</th> </tr> </thead> <tbody> <tr><td>12%</td><td>8%</td><td>1</td></tr> <tr><td>14%</td><td>10%</td><td>2</td></tr> <tr><td>16%</td><td>12%</td><td>3</td></tr> <tr><td>18%</td><td>14%</td><td>4</td></tr> <tr><td>20%</td><td>16%</td><td>5</td></tr> <tr><td>22%</td><td>18%</td><td>6</td></tr> <tr><td>24%</td><td>20%</td><td>7</td></tr> <tr><td>26%</td><td>22%</td><td>8</td></tr> <tr><td>28%</td><td>24%</td><td>9</td></tr> <tr><td>30%</td><td>26%</td><td>10</td></tr> <tr><td>32%</td><td>28%</td><td>11</td></tr> <tr><td>34%</td><td>30%</td><td>12</td></tr> <tr><td>36%</td><td>32%</td><td>13</td></tr> <tr><td>38%</td><td>34%</td><td>14</td></tr> <tr><td>40%</td><td>36%</td><td>15</td></tr> <tr><td>42%</td><td>38%</td><td>16</td></tr> <tr><td>44%</td><td>40%</td><td>17</td></tr> <tr><td>46%</td><td>42%</td><td>18</td></tr> <tr><td>48%</td><td>44%</td><td>19</td></tr> </tbody> </table> <p>OR OPTION 2: Prescriptive Compliance Path: ASHRAE Advanced Energy Design Guide – Refer to EA p2 above.</p> <p>OR OPTION 3: PRESCRIPTIVE COMPLIANCE PATH: Advanced Buildings™ Core Performance™ Guide (1-3 Points)</p> <p>Comply with the prescriptive measures identified in the Advanced Buildings™ Core Performance™ Guide developed by the New Buildings Institute. Refer to EA p2 above.</p>	% Energy Cost Savings (minimum)			New Buildings	Existing Building Renovations	Points	12%	8%	1	14%	10%	2	16%	12%	3	18%	14%	4	20%	16%	5	22%	18%	6	24%	20%	7	26%	22%	8	28%	24%	9	30%	26%	10	32%	28%	11	34%	30%	12	36%	32%	13	38%	34%	14	40%	36%	15	42%	38%	16	44%	40%	17	46%	42%	18	48%	44%	19	10		9	D	Mechanical and Electrical Engineer	<p>For Projects in California, the USGBC may allow an equivalency of using T-24-2008 instead of ASHRAE-2007 with the same thresholds as identified on the Table under Option 1.</p> <p>UC Mandate is 20% which would earn 5 points. There are central campus chilled water and steam utilities. A goal of the Sustainability plan is to strive for 30% efficiency, or 10 points.</p> <p>10 points earned assuming an efficient building envelope with good glazing and insulation, efficient lighting with dimming and occupancy/daylight sensors, and radiant floor systems, we would expect at least 30% below T-24.</p> <p>Refer to Mechanical Narrative for potential strategies.</p>
% Energy Cost Savings (minimum)																																																																							
New Buildings	Existing Building Renovations	Points																																																																					
12%	8%	1																																																																					
14%	10%	2																																																																					
16%	12%	3																																																																					
18%	14%	4																																																																					
20%	16%	5																																																																					
22%	18%	6																																																																					
24%	20%	7																																																																					
26%	22%	8																																																																					
28%	24%	9																																																																					
30%	26%	10																																																																					
32%	28%	11																																																																					
34%	30%	12																																																																					
36%	32%	13																																																																					
38%	34%	14																																																																					
40%	36%	15																																																																					
42%	38%	16																																																																					
44%	40%	17																																																																					
46%	42%	18																																																																					
48%	44%	19																																																																					

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010																						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below																						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below																						
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS																
EA 2	Renewable Energy	<p>Use on-site renewable energy systems to offset building energy cost. Calculate project performance by expressing the energy produced by the renewable systems as a percentage of the building annual energy cost and use the table below to determine the number of points achieved. • Use the building annual energy cost calculated in EA Credit 1 or use the Department of Energy (DOE) Commercial Buildings Energy Consumption Survey (CBECS) database to determine the estimated electricity use. The minimum renewable energy percentage for each point threshold is as follows:</p> <table border="1"> <thead> <tr> <th>Percentage Renewable Energy</th> <th>Points</th> </tr> </thead> <tbody> <tr><td>1%</td><td>1</td></tr> <tr><td>3%</td><td>2</td></tr> <tr><td>5%</td><td>3</td></tr> <tr><td>7%</td><td>4</td></tr> <tr><td>9%</td><td>5</td></tr> <tr><td>11%</td><td>6</td></tr> <tr><td>13%</td><td>7</td></tr> </tbody> </table>	Percentage Renewable Energy	Points	1%	1	3%	2	5%	3	7%	4	9%	5	11%	6	13%	7		8		D	Electrical Engineer	<p>PV installation for UCR Campus is currently being evaluated.</p> <p>From the Sustainability Action Plan: UC Policy is to obtain 20% of electricity from renewable sources by 2010. 10 Mw system-wide installation of local renewable power by 2014 is referred to in the UCR Sustainability Plan.</p> <p><i>If 1% renewable energy is achieved, one additional point for regional priority.</i></p>
Percentage Renewable Energy	Points																							
1%	1																							
3%	2																							
5%	3																							
7%	4																							
9%	5																							
11%	6																							
13%	7																							
EA 3	Enhanced Commissioning	<p>Implement, or have a contract in place to implement, the following additional commissioning process activities in addition to the requirements of EA prerequisite 1 and in accordance with the LEED Reference Guide for Green Building Design and Construction, 2009 Edition:</p> <ol style="list-style-type: none"> 1. Prior to the start of the construction documents phase, designate an independent Commissioning Authority (CxA) to lead, review, and oversee the completion of all commissioning process activities. 2. The CA shall conduct, at a minimum, one commissioning design review of the Owner's Project Requirements (OPR), Basis of Design (BOD), and design documents prior to mid-construction documents phase and back-check the review comments following design submission. 3. The CA shall review contractor submittals applicable to systems being commissioned for compliance with the OPR and BOD. This review must be concurrent with A/E reviews and submitted to the design team and the Owner. 4. Develop a systems manual that provides future operating staff the information needed to understand and optimally operate the commissioned systems. 5. Verify that the requirements for training operating personnel and building occupants are completed. 6. The CxA must be involved in reviewing the operation of the building with operations and maintenance staff and occupants within 10 months after substantial completion. A plan for resolving outstanding commissioning-related issues must be included. 		2		C	Commis. Agent	<p>A goal of the UCR Sustainability Plan.</p>																

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
EA 4	Enhanced Refrigerant Management	<p>OPTION 1: Do not use refrigerants.</p> <p>OR OPTION 2: Select refrigerants and HVAC&R that minimize or eliminate the emission of compounds that contribute to ozone depletion and global warming. The base building HVAC&R equipment shall comply with the following formula, which set a maximum threshold for the combined contributions to ozone depletion and global warming potential:</p> $LCGWP + LCODP \times 10^5 \leq 100$ <p>Where: LCODP = $[ODPr \times (Lr \times Life + Mr) \times Rc] / Life$ LCGWP = $[GWPr \times (Lr \times Life + Mr) \times Rc] / Life$ LCODP: Lifecycle Ozone Depletion Potential (lb CFC 11/Ton-Year) LCGWP: Lifecycle Direct Global Warming Potential (lb CO₂/Ton-Year) GWPr: Global Warming Potential of Refrigerant (0 to 12,000 lbCO₂/lbr) ODPr: Ozone Depletion Potential of Refrigerant (0 to 0.2 lb CFC 11/lbr) Lr: Refrigerant Leakage Rate (0.5% to 2.0%; default of 2% unless otherwise demonstrated) Mr: End-of-life Refrigerant Loss (2% to 10%; default of 10% unless otherwise demonstrated) Rc: Refrigerant Charge (0.5 to 5.0 lbs of refrigerant per ton of gross ARI rated cooling capacity) Life: Equipment Life (10 years; default based on equipment type, unless otherwise demonstrated)</p> <p>For multiple types of equipment, a weighted average of all base building level HVAC&R equipment shall be applied using the following formula: $[\text{sum} (LCGWP + LCODP \times 10^5) \times Q_{unit}] / Q_{total} \leq 100$ Where: Qunit = Gross ARI rated cooling capacity of an individual HVAC or refrigeration unit (Tons) Qtotal = Total gross ARI rated cooling capacity of all HVAC or refrigeration.</p> <p>ALL OPTIONS: Small HVAC units (containing less than 0.5 lbs of refrigerant) and other equipment, such as standard refrigerators, small water coolers and any other cooling equipment that contains less than 0.5 pounds of refrigerant, are not considered part of the base building system and are not subject to the requirements of this credit.</p> <p>AND</p> <p>Do not install fire suppression systems that contain ozone-depleting substances (CFCs, HCFCs or Halons).</p>	2			D	Mechanical Engineer	PP point.

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT <i>(blue shading indicates a campus baseline credit)</i>		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
EA 5	Measurement & Verification	<p>OPTION 1: Develop and implement a measurement and verification (M&V) plan consistent with Option D: Calibrated Simulation (Savings Estimation Method 2) as specified in the International Performance Measurement & Verification Protocol (IPMVP) Volume III: Concepts and Options for Determining Energy Savings in New Construction, April, 2003. The M&V period must cover at least 1 year of post-construction occupancy. Provide a process for corrective action if the results of the M&V plan indicate that energy savings are not being achieved.</p> <p>OR OPTION 2: Develop and implement a measurement and verification (M&V) plan consistent with Option B: Energy Conservation Measure Isolation, as specified in the International Performance Measurement & Verification Protocol (IPMVP) Volume III: Concepts and Options for Determining Energy Savings in New Construction, April, 2003. The M&V period must cover at least 1 year of post-construction occupancy. Provide a process for corrective action if the results of the M&V plan indicate that energy savings are not being achieved.</p>		3		D	Commissioning Agent or Mechanical Engineer	DDC (controls and monitoring) for HVAC system will be provided.

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus			Original Document Prepared by Simon & Associates, Inc. 4/9/2010													
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)			Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below													
			Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below													
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS								
EA 6.0	Green Power	Engage in at least a 2-year renewable energy contract to provide at least 35% of the building's electricity from renewable sources, as defined by the Center for Resource Solutions' Green-e Energy product certification requirements. OPTION 1: DETERMINE THE BASELINE ELECTRICITY USE Use the annual electricity consumption from the results of EA Credit 1. OR OPTION 2: ESTIMATE BASELINE ELECTRICITY USE Use the Department of Energy (DOE) Commercial Buildings Energy Consumption Survey (CBECS) database to determine the estimated electricity use. Note - All purchases of green power shall be based on the quantity of energy consumed, not the cost.		2		C	Owner									
Materials and Resources																
MR Prereq.	Storage & Collection of Recyclables	Provide an easily-accessible dedicated area or for the collection of storage materials for recycling for the entire building. Materials must include at minimum paper, corrugated cardboard, glass, plastics and metals.	X			D	Architect	UCR has a recycling and waste management policy, which includes food waste composting and targets a 50% landfill diversion rate of 50% by 2008-9. Zero waste by 2020 is a long term goal.								
MR 1.1	Building Reuse - Maintain Existing Walls, Floors, and Roof	Maintain at least 55% (based on surface area) of existing building structure (including structural floor and roof decking) and envelope (exterior skin and framing, excluding window assemblies and non-structural roofing material). Hazardous materials that are remediated as a part of the project scope shall be excluded from the calculation of the percent maintained. If the project includes an addition to an existing building, this credit is not applicable if the square footage of the addition is more than 2 times the square footage of the existing building. The minimum percentage building reuse for each point threshold is as follows: <table border="1"> <thead> <tr> <th>Building Reuse</th> <th>Points</th> </tr> </thead> <tbody> <tr> <td>55%</td> <td>1</td> </tr> <tr> <td>75%</td> <td>2</td> </tr> <tr> <td>95%</td> <td>3</td> </tr> </tbody> </table>	Building Reuse	Points	55%	1	75%	2	95%	3	1	2		C	Architect	Attempting more than 75%. Walls and floors will be retained.
Building Reuse	Points															
55%	1															
75%	2															
95%	3															
MR 1.2	Building Reuse - Maintain Interior Nonstructural Elements	Using existing interior nonstructural elements (e.g., interior walls, doors, floor coverings and ceiling systems) in at least 50% (by area) of the completed building, including additions. If the project includes an addition with square footage more than 2 times the square footage of the existing building, this credit is not applicable.		1		C	Architect	To be determined.								
MR 2	Construction Waste Management	Recycle and/or salvage at least 50% of non-hazardous construction and demolition debris. Develop and implement a construction waste management plan that, at a minimum, identifies the materials to be diverted from disposal and whether the materials will be sorted on-site or comingled. Excavated soil and land-clearing debris do not contribute to this credit. Calculations can be done by weight or volume, but must be consistent throughout. The minimum percentage debris to be recycled or salvaged for each point threshold is as follows: <table border="1"> <thead> <tr> <th>Recycled or Salvaged</th> <th>Points</th> </tr> </thead> <tbody> <tr> <td>50%</td> <td>1</td> </tr> <tr> <td>75%</td> <td>2</td> </tr> </tbody> </table>	Recycled or Salvaged	Points	50%	1	75%	2	2			C	Contractor	ODC point. Baseline is only 50% (1 point). Recommend the project attempt 75% minimum. <i>75% is in the recommended level noted in the UCR Sustainability Plan.</i> <i>Campus policy is 95% recycled or salvaged construction waste, per Workshop #1 (2/03/12).</i>		
Recycled or Salvaged	Points															
50%	1															
75%	2															

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010												
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below												
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below												
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS						
MR 3	Materials Reuse: 5%	<p>Use of salvaged, refurbished or reused materials, the sum of which constitutes at least 5% or 10%, based on cost, of the total value of materials on the project.</p> <p>Mechanical, electrical and plumbing components and specialty items such as elevators and equipment shall not be included in this calculation. Only include materials permanently installed in the project. Furniture may be included, providing it is included consistently in MR Credits 3-7.</p> <p>The minimum percentage materials reused for each point threshold is as follows:</p> <table border="1"> <thead> <tr> <th>Reused Materials</th> <th>Points</th> </tr> </thead> <tbody> <tr> <td>5%</td> <td>1</td> </tr> <tr> <td>10%</td> <td>2</td> </tr> </tbody> </table>	Reused Materials	Points	5%	1	10%	2			2	C	Architect, Contractor	<i>Identify if any on/off-site material other than what is covered by MR 1.1 + 1.2 can be used for this credit--this is a "big ticket" item</i>
Reused Materials	Points													
5%	1													
10%	2													
MR 4	Recycled Content	<p>Use materials with recycled content such that the sum of post-consumer recycled content plus one-half of the pre-consumer content constitutes at least 10% or 20%, based on cost, of the total value of the materials in the project.</p> <p>The recycled content value of a material assembly shall be determined by weight. The recycled fraction of the assembly is then multiplied by the cost of assembly to determine the recycled content value.</p> <p>Mechanical, electrical and plumbing components and specialty items such as elevators shall not be included in this calculation. Only include materials permanently installed in the project. Furniture may be included, providing it is included consistently in MR Credits 3-7.</p> <p>Recycled content shall be defined in accordance with the International Organization of Standards document, ISO 14021—Environmental labels and declarations—Self-declared environmental claims (Type II environmental labeling).</p> <p>The minimum percentage materials recycled for each point threshold is as follows:</p> <table border="1"> <thead> <tr> <th>Recycled Content</th> <th>Points</th> </tr> </thead> <tbody> <tr> <td>10%</td> <td>1</td> </tr> <tr> <td>20%</td> <td>2</td> </tr> </tbody> </table>	Recycled Content	Points	10%	1	20%	2	I	I		C	Architect, Contractor	Per baseline study, 2 points are listed as maybes, however, the design team considers 1 point achievable. <i>Need to identify early on.</i>
Recycled Content	Points													
10%	1													
20%	2													
MR 5	Regional Materials	<p>Use building materials or products that have been extracted, harvested or recovered, as well as manufactured, within 500 miles of the project site for a minimum of 10% or 20% (based on cost) of the total materials value. If only a fraction of a product or material is extracted/harvested/recovered and manufactured locally, then only that percentage (by weight) shall contribute to the regional value.</p> <p>Mechanical, electrical and plumbing components and specialty items such as elevators and equipment shall not be included in this calculation. Only include materials permanently installed in the project. Furniture may be included, providing it is included consistently in MR Credits 3-6.</p> <p>The minimum percentage regional materials for each point threshold is as follows:</p> <table border="1"> <thead> <tr> <th>Regional Materials</th> <th>Points</th> </tr> </thead> <tbody> <tr> <td>10%</td> <td>1</td> </tr> <tr> <td>20%</td> <td>2</td> </tr> </tbody> </table>	Regional Materials	Points	10%	1	20%	2	I	I		C	Architect, Contractor	ODC point. <i>Need to identify early on.</i>
Regional Materials	Points													
10%	1													
20%	2													
MR 6	Rapidly Renewable Materials	<p>Use rapidly renewable building materials and products for 2.5% of the total value of all building materials and products used in the project, based on cost. Rapidly renewable building materials and products are made from plants that are typically harvested within a 10-year or shorter cycle.</p>		I		C	Architect, Contractor	This credit is difficult to achieve, but it would depend on interior finish selection.						

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus			Original Document Prepared by Simon & Associates, Inc. 4/9/2010					
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)			Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below					
			Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below					
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
MR 7	Certified Wood	Use a minimum of 50% (by cost) of wood-based materials and products, certified in accordance with the Forest Stewardship Council's (FSC) Principles and Criteria, for wood building components. The components include, but not limited to, structural framing and general dimensional framing, flooring, sub-flooring, wood doors and finishes. Only include materials permanently installed in the project. Wood products purchased for temporary use on the project (e.g., formwork, bracing, scaffolding, sidewalk protection, and guard rails) may be included in the calculation at the project team's discretion. If any such materials are included, all such materials must be included in the calculation. If such materials are purchased for use on multiple projects, the applicant may include these materials for only one project, at its discretion. Furniture may be included, providing it is included consistently in MR Credits 3-7.	I			C	Architect, Contractor	Credit is easily achievable, considering the amount of wood in the project.
Indoor Environmental Quality								
EQ Prereq. 1	Minimum IAQ Performance	<p>Mechanically Ventilated Spaces Meet the minimum requirements of Sections 4 through 7 of ASHRAE 62.1-2007, Ventilation for Acceptable Indoor Air Quality (with errata but without addenda). Mechanical ventilation systems must be designed using the Ventilation Rate Procedure or the applicable local code, whichever is more stringent.</p> <p>Naturally Ventilated Spaces Naturally ventilated buildings must comply with ASHRAE 62.1-2007, paragraph 5.1 (with errata but without addenda).</p>	X			D	Mechanical Engineer	<i>Not group—must be achieved per building.</i>
EQ Prereq. 2	Environmental Tobacco Smoke (ETS) Control	<p>OPTION 1</p> <ul style="list-style-type: none"> Prohibit smoking in the building. Prohibit on-property smoking within 25 feet of entries, outdoor air intakes and operable windows. Provide signage to allow smoking in designated areas, prohibit smoking in designated areas or prohibit smoking on the entire property. <p>OR OPTION 2</p> <ul style="list-style-type: none"> Prohibit smoking in the public areas of the building except in designated smoking areas. Public areas include all common areas that are part of the core and shell that are not tenant spaces. Smoking must be prohibited within 25 feet away from entries, outdoor air intakes and operable windows. Provide signage to allow smoking in designated areas, prohibit smoking in designated areas or prohibit smoking on the entire property. <p>OR OPTION 3 (For residential buildings and hotels only).</p> <ul style="list-style-type: none"> Prohibit smoking in all common areas of the building Locate any exterior designated smoking areas, including balconies where smoking is permitted, at least 25 feet away from entries, outdoor air intakes and operable windows opening to common areas. Provide signage to allow smoking in designated areas, prohibit smoking in designated areas or prohibit smoking on the entire property. 	X			D	Owner	<i>Smoking must comply with campus policies. Anticipate UCOP to ban smoking on campus by 2014.</i>

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
EQ 1	Outdoor Air Delivery Monitoring	<p>Install permanent monitoring systems that provide feedback on ventilation system performance to ensure that ventilation systems maintain design minimum ventilation requirements. Configure all monitoring equipment to generate an alarm when the airflow values or carbon dioxide (CO2) levels vary by 10% or more from the design values via either a building automation system alarm to the building operator or a visual or audible alert to the building occupants.</p> <p>AND FOR MECHANICALLY VENTILATED SPACES</p> <ul style="list-style-type: none"> Monitor carbon dioxide concentrations within all densely occupied spaces (those with a design occupant density greater than or equal to 25 people per 1000 sq.ft.). CO2 monitoring locations shall be between 3 feet and 6 feet above the floor. For each mechanical ventilation system, provide a direct outdoor airflow measurement device capable of measuring the minimum outdoor airflow rate with an accuracy of plus or minus 15% of the design minimum outdoor air rate, as defined by ASHRAE 62.1-2007 (with errata but without addenda) for mechanical ventilation systems where 20% or more of the design supply airflow serves non-densely occupied spaces. <p>FOR NATURALLY VENTILATED SPACES</p> <p>Monitor CO2 concentrations within all naturally ventilated spaces. CO2 monitoring shall be located within the room between 3 feet and 6 feet above the floor. One CO2 sensor may be used to represent multiple spaces if the natural ventilation design uses passive stack(s) or other means to induce airflow through those spaces equally and simultaneously without intervention by building occupants.</p> <p>Note - The credit is specifically intended to address issues with ventilation in environments where a fixed amount of minimum outside air is provided through a specific incoming path. CO2 monitoring is required in densely occupied spaces, in addition to outdoor air intake flow measurement.</p>		I		D	Mechanical	<i>CO2 sensors required. Not group. Mechanical to determine how many.</i>
EQ 2	Increased Ventilation	<p>FOR MECHANICALLY VENTILATED SPACES:</p> <ul style="list-style-type: none"> Increase breathing zone outdoor air ventilation rates to all occupied spaces by at least 30% above the minimum rates required by ASHRAE Standard 62.1-2007 (with errata but without addenda) as determined by EQ Prerequisite 1. <p>FOR NATURALLY VENTILATED SPACES:</p> <ul style="list-style-type: none"> Design natural ventilation systems for occupied spaces to meet the recommendations set forth in the Carbon Trust "Good Practice Guide 237" [1998]. Determine that natural ventilation is an effective strategy for the project by following the flow diagram process shown in Figure 1.18 of the Chartered Institution of Building Services Engineers (CIBSE) "Applications Manual 10:2005, Natural ventilation in non-domestic buildings." <p>AND Option 1: Use diagrams and calculations to show that the design of the natural ventilation systems meets the recommendations set forth in the CIBSE Applications Manual 10:2005, Natural ventilation in non-domestic buildings.</p>	I			D	Mechanical	Minimum ventilation rate is 15 cfm / occupant, but Mechanical Engineer narrative indicates LEED EQ rates will be used, therefore point is earned.

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT <i>(blue shading indicates a campus baseline credit)</i>			YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
		DESIGN/CONSTRUCTION REQUIREMENTS						
		OR Option 2: Use a macroscopic, multi-zone, analytic model to predict that room-by-room airflows will effectively naturally ventilate, defined as providing the minimum ventilation rates required by ASHRAE 62.1-2007 Chapter 6, for at least 90% of occupied spaces.						

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
EQ 3.1	Construction IAQ Management Plan	<p>During Construction: Develop and implement an Indoor Air Quality (IAQ) Management Plan for the construction and pre-occupancy phases of the building as follows:</p> <ul style="list-style-type: none"> • During construction meet or exceed the recommended Control Measures of the Sheet Metal and Air Conditioning National Contractors Association (SMACNA) IAQ Guidelines for Occupied Buildings under Construction, 2nd Edition 2007, ANSI/SMACNA 008-2008 (Chapter 3). • Protect stored on-site or installed absorptive materials from moisture damage. • If permanently installed air handlers are used during construction, filtration media with a Minimum Efficiency Reporting Value (MERV) of 8 must be used at each return air grille, as determined by ASHRAE 52.2-1999 (with errata but without addenda). Replace all filtration media immediately prior to occupancy. 	I			C	Contractor	ODC point.
EQ 3.2	Construction IAQ Management Plan - Before Occupancy	<p>Develop and (IAQ) management plan and implement it after all finishes have been installed and the building has been completely cleaned before occupancy.</p> <p>OPTION 1: Flush Out After construction ends, prior to occupancy and with all interior finishes installed, install new filtration media and perform a building flush-out by supplying a total air volume of 14,000 cubic feet of outdoor air per square foot of floor area while maintaining an internal temperature of at least 60F and relative humidity no higher than 60%.</p> <p>OR If occupancy is desired prior to completion of the flush-out, the space may be occupied following delivery of minimum of 3,500 cubic feet of outdoor air per square foot of floor area. Once the space is occupied, it must be ventilated at a minimum rate of 0.30 cubic feet per minute (cfm) per square foot of outside air or the design minimum outside air rate determined in EQ prereq 1, whichever is greater. During each day of the flush-out period, ventilation must begin a minimum of 3 hours prior to occupancy and continue during occupancy. These conditions must be maintained until a total of 14,000 cubic feet per square foot of outside air has been delivered to the space.</p> <p>OR Option 2: Air Testing Conduct baseline IAQ testing, after construction ends and prior to occupancy, using testing protocols consistent with the EPA Compendium of Methods for the Determination of Air Pollutants in Indoor Air and as additionally detailed in the LEED Reference Guide for Green Building Design and Construction, 2009 Edition.</p>	I				Contractor	ODC point. <i>Before Occupancy: Get flush-out requirements from the mechanical early on so the flush-out can be scheduled.</i>
EQ 4.1	Low-Emitting Materials	<p>Adhesives and Sealants: (Refer to Reference Guide for VOC limits) All adhesives and sealants used on the interior of the building (defined as inside of the weatherproofing system and applied on-site) shall comply with the requirements applicable to the project scope:</p> <ul style="list-style-type: none"> • Adhesives, Sealants and Sealant Primers must comply with South Coast Air Quality Management District (SCAQMD) Rule #1168. VOC limits are listed in reference guide and correspond to an effective date of July 1, 2005 and rule amendment date of January 7, 2005. • Aerosol Adhesives must comply with Green Seal Standard for Commercial Adhesives GS-36 requirements in effect on October 19, 2000. <p>Note - Use of VOC budgets is an alternative compliance path that allows for specialty applications for which there is no low VOC product option.</p>	I			C	Architect, Contractor	ODC point. <i>Mechanical to determine flush-out requirements early on.</i>

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus			Original Document Prepared by Simon & Associates, Inc. 4/9/2010					
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)			Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below					
			Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below					
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
EQ 5	Indoor Chemical and Pollutant Source Control	<p>Design to minimize and control pollutant entry into buildings and later cross-contamination of regularly occupied areas:</p> <ul style="list-style-type: none"> • Employ permanent entryway systems at least 10 feet long in the primary direction of travel to capture dirt and particulates from entering the building at all entryways that are directly connected to the outdoors. Acceptable entryway systems include permanently installed grates, grilles, or slotted systems that allow for cleaning underneath. Roll-out mats are only acceptable when maintained on a weekly basis by a contracted service organization. Qualifying entryways are those that serve as regular entry points into the core and shell of the building by building users. • Where hazardous gases or chemicals may be present or used (including garages, housekeeping/laundry areas and copying/printing rooms), exhaust each space sufficiently to create negative pressure with respect to adjacent spaces with the doors to the room closed. • In mechanically ventilated buildings, provide regularly occupied areas of the building with air filtration media prior to occupancy that provides a Minimum Efficiency Reporting Value (MERV) of 13 or better. Filtration should be applied to process both return and outside air that is to be delivered as supply air. • Provide containment drains plumbed for appropriate disposal of hazardous liquid wastes in places where water and chemical concentrate mixing occurs (e.g. housekeeping, janitorial and science laboratories). 	I			D	Architect, Mechanical, Plumbing, Contractor	ODC point.
EQ 6.1	Controllability of Systems	<p>Lighting: Provide individual lighting controls for 90% (minimum) of building occupants to enable adjustments to suit individual task needs and preferences. Provide lighting system controls for all shared multi-occupant spaces to enable adjustments that meet group needs and preferences.</p>			I	D	Architect, Electrical	
EQ 6.2	Controllability of Systems	<p>Thermal Comfort: Provide individual comfort controls for 50% (minimum) of the building occupants to enable adjustments to suit individual task needs and preferences. Operable windows can be used in lieu of comfort controls for occupants of areas that are 20 feet inside of and 10 feet to either side of the operable part of the window. The areas of operable window must meet the requirements of ASHRAE 62.1-2007 paragraph 5.1 Natural Ventilation. AND Provide comfort system controls for all shared multi-occupant spaces to enable adjustments to suit group needs and preferences. Conditions for thermal comfort are described in ASHRAE Standard 55-2004 to include the primary factors: of air temperature, radiant temperature, air speed, and humidity. Comfort system control for the purposes of this credit is defined as the provision of control over at least one of these primary factors in the occupant's local environment.</p>		I		D	Architect, Electrical	This credit needs to be studied in consideration of the health code as it pertains to food service areas.
EQ 7.1	Thermal Comfort	<p>Design: Design HVAC systems and the building envelope to meet the requirements of ASHRAE Standard 55-2004, Thermal Comfort Conditions for Human Occupancy. Demonstrate design compliance in accordance with the Section 6.1.1 Documentation.</p>	I			D	Architect	ODC point.

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus		Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)		Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
		Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT <i>(blue shading indicates a campus baseline credit)</i>		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
EQ 7.2	Thermal Comfort	<p>Verification</p> <p>Achieve EQ 7.1 AND agree to conduct a thermal comfort survey of building occupants (adults and students of grades 6 and above) within 6 to 18 months after occupancy. This survey should collect anonymous responses about thermal comfort in the building, including an assessment of overall satisfaction with thermal performance and identification of thermal comfort problems. Agree to develop a plan for corrective action if the survey results indicate that more than 20% of occupants are dissatisfied with thermal comfort of the building. This plan should include measurement of relevant environmental variables in problem areas in accordance with ASHRAE Standard 55-2004 (with errata but with addenda).</p> <p>AND Provide a permanent monitoring system to ensure that building performance meets the desired comfort criteria as determined by EQ 7.1. Residential Projects are not eligible for this credit.</p>	I			D	Architect	Provides an opportunity for educational benefit for the project.
EQ 8.1	Daylight and Views	<p>Daylight 75% of Spaces</p> <p>OPTION 1 - SIMULATION</p> <p>Demonstrate through computer simulation that 75% or more of regularly occupied spaces achieve daylight illuminance levels of a minimum of 25 footcandles (fc) and a maximum of 500 fc in a clear sky condition on September 21 at 9 am and 3 pm: areas with illuminance levels below or above the range do not comply. However, designs that incorporate view-preserving automated shades for glare control may demonstrate compliance for only the minimum 25 fc illuminance level.</p> <p>OR OPTION 2 - PRESCRIPTIVE</p> <p>Sidelighting Daylight Zone Top-lighting Daylight Zone</p> <p>OR OPTION 3 - MEASUREMENT</p> <p>OR OPTION 4 - COMBINATION</p>	I			D	Architect	
EQ 8.2		<p>Views for 90% of Spaces:</p> <p>Achieve direct line of sight to the outdoor environment via vision glazing between 30" and 90" above finish floor for building occupants in 90% of all regularly occupied areas. Determine the area with direct line of sight by totaling the regularly occupied square footage that meets the following criteria:</p> <ul style="list-style-type: none"> In plan view, the area is within sight lines drawn from the area to perimeter vision glazing. In section view, a direct sight line can be drawn from the area to perimeter vision glazing. Line of sight may be drawn through interior glazing. For private offices, the entire square footage of the office can be counted if 75% or more of the area has direct line of sight to perimeter vision glazing. For multi-occupant spaces, the actual square footage with direct line of sight to perimeter vision glazing is counted. 	I			D	Architect	

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus			Original Document Prepared by Simon & Associates, Inc. 4/9/2010					
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)			Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below					
			Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below					
CREDIT (blue shading indicates a campus baseline credit)		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS
Innovation & Design Process								
ID 1.1-1.5	Innovation in Design	Purpose: To provide design teams and projects the opportunity to be awarded points for exceptional performance above requirements set by the LEED Rating System and/or innovative performance in Green Building categories not specifically addressed by the LEED Rating System. Requirements: In writing, identify the Intent of the proposed innovation credit, the proposed requirement for compliance, the proposed submittals to demonstrate compliance, and the design approach (strategies) that might be used to meet the requirements. Substantially exceed a LEED performance credit such as energy performance or water efficiency. Apply strategies or measures that demonstrate a comprehensive approach and quantifiable environment and/or health benefits.						
ID 1.1	TBD	e.g. Green cleaning		I		D	TBD	Green Seal cleaners are among the UCR Sustainability Plan goals.
ID 1.2	TBD	e.g. Integrated pest management		I		D	TBD	IPM is among the UCR Sustainability Plan goals.
ID 1.3	TBD	e.g. Double green power		I		D	TBD	
ID 1.4	TBD	e.g. Green Building as Educational Tool	I			D	TBD	Case Studies will be an intermediate goal outlined in the UCR Sustainability Plan.
ID 1.5	TBD	e.g. Sustainability in the Curriculum, Eco-Literacy	I			D	TBD	Currently a goal of the UCR Sustainability plan.
ID 1.6	TBD	Construction Waste Management--zen waste and 95% construction diversion.		I		C	TBD	<i>Doing on other projects on campus.</i>
ID 2	LEED Accredited Professional	Intent: To support and encourage the design integration required by a LEED-NC green building project and to streamline the application and certification process. Requirements: At least one principal participant of the project team shall be a LEED Accredited Professional(AP).	I			D	Simon & Assoc.	ODC point.

SUPPORT DOCUMENTS

LEED Matrix

UCR Barn Project, East Campus			Original Document Prepared by Simon & Associates, Inc. 4/9/2010						
LEED 2009 Green Building Design & Construction Priorities Matrix (NC)			Revisions & Comments from Workshop #1 of 2/03/2012 in <i>red italic</i> below						
			Revisions per Comments issued 3/27/2012 in <i>blue italic</i> below						
CREDIT <i>(blue shading indicates a campus baseline credit)</i>		DESIGN/CONSTRUCTION REQUIREMENTS	YES	MAYBE	NO	(D) DESIGN OR (C) CONSTRUCTION PHASE	PARTIES RESPONSIBLE FOR DOCUMENTATION	COMMENTS/ACTION ITEMS	
Regional Bonus Credits									
RB 1.1-1.4	Regional Bonus Credit	To provide design teams and projects the opportunity to be awarded points for achievement of existing LEED credits that deliver regionally important benefit which has been deemed, by the regional authority, to have benefit above the point value set by the LEED Green Building Rating System. Requirements: Achieve one of the six (6) credits, to a maximum of four (4), that have been identified as regionally important by the regional authority where the LEED project is located.							
RB 1.1	SS 4.1	Alternative Transportation: Public Transportation Access	I			D	TBD		
RB 1.2	SS 7.1	Heat Island Effect: Non-Roof	I			D	TBD		
RB 1.3	WE 2	Innovative Wastewater Technology				D	TBD		
RB 1.4	WE 3 (40%)	Water Use Reduction		I		D	TBD		
	EA 2 (1%)	On-site Renewable Energy							
	EQ 8.1	Daylight and Views: Daylight	I						
TOTAL POINTS			60	38	14				
LEED Certified = 40-49, Silver = 50-59, Gold = 60-79, Platinum = 80-110			110 Possible Points						
RESPONSIBLE PARTY KEY: Owner Architect Civil Landscape MEP Cx Agent LEED/Sustainability Simon & Associates Contractor Construction Manager Other Environmental							Project Schedule: SD DD CD Bid CA CO		
LEED-Online Access: http://leedonline.com									

V. COST PLAN

A Preliminary Budget Estimate has been prepared and reflects the program and systems presented in the DPP Update. For costing purposes, the project has been broken into phases and the building and landscape elements are costed separately. The start date of construction is December 2014 for Phase 1A, June 2015 for Phase 1B, and June 2017 for Phase 2.

Preliminary Budget Estimate

Oppenheim | Lewis

University of California, Riverside
The Barn Project
Preliminary Design Estimate

26 June 2012

Prepared for Fernau & Hartman Architects

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Construction Cost Summary	Area	Cost/SF	Total
Phase 1A			
Sitework Phase 1A			\$503,826
Phase 1B			
Cottage	1,185 SF	\$644.52	\$763,760
Barn Dining	4,425 SF	433.26	1,917,163
Kitchen Addition	4,435 SF	812.39	3,602,950
Faculty Staff Dining & Performance Stage	5,610 SF	692.55	3,885,185
Barn Stable	1,675 SF	659.85	1,105,255
Barn Stable Addition	1,090 SF	702.84	766,091
East Courtyard Restrooms	995 SF	726.25	722,615
Barn Theater Entry Modifications	1,651 SF	62.66	103,455
Sitework Phase 1B			3,724,302
Phase 2			
Barn Theater & Associated Sitework		Excluded from Scope	
Total Estimated Const Cost in May 2012 Dollars	21,066 SF	\$811.48	\$17,094,602
Escalation to Midpoint of Construction			2,403,583
Total Estimated Construction Cost	21,066 SF	\$925.58	\$19,498,185
Alternates			
1) Provide Alterations to Sproul Hall Loading Dock		Add	\$493,214
2) Provide Onsite Chiller & Boiler in lieu of Conn to Campus HW/CHW		Add	(73,834)
3) Provide Audio Visual Equipment		Add	487,308
4) Provide Emerg Power for Kitchen Addition & Fac/Staff Dining		Add	460,727
5) Provide Enhanced Comm/3rd Party Commissioning Services		Add	82,500
6) Allow for Patching & Painting Barn Theater		Add	16,500
7) Provide Security Devices		Add	156,529
8) Theater Lighting Package		Add	160,000
Allowances Included in the Estimate			
Shade Structure over Viewing Area at West Courtyard			\$360,000

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

1 Basis of Estimate

This statement is based on program plans by Fernau & Hartman Architects, along with verbal direction from the architectural team and Owner.

2 Conditions of Construction

The pricing is based on the following general conditions of construction:

Start date of construction December 2014 for Phase 1A, June 2015 for Phase 1B, and June 2017 for Phase 2.

A construction period of 6 months for Phases 1A and 12 months for Phase 1B; and a construction period of 6 months for Phase 2.

Construction contract procurement method is design bid build with a prequalified short list.

Contractor's performance bond is to be included by the general contractor.

Contractor's Risk Insurance is deemed to be included by the general contractor, Owner's Risk Insurance is by the Owner and excluded from the estimate.

Phasing assumptions are noted above, and shown on the summary sheet.

The general contractor will have full access to the site during normal business hours.

Contractor's General Conditions and Site Management are included in the estimate, but only for the duration of construction. They are excluded for the duration between phases.

Alternate costs include contractor markups and escalation based on the phase of work in which the scope occurs. Where the scope covers more than one phase, the higher escalation rate is used.

LEED Commissioning and Certification fees are included on LEED Silver rating.

However per Owner direction, certain terms required to reach LEED Silver are costed below the line.

3 Items Not Included Within Estimate

The following cost items are excluded from this estimate:

Theater Renovation and Expansion

Professional fees, inspections and testing

Construction Management Pre-construction Fees

Cost escalation beyond the midpoint of construction

Plan check fees and building permit fees

Movable Furnishings, fixtures and equipment (FF&E)

Costs of offsite construction except potential new utility connections at east of site

Construction contingency costs

4 Notes

We recommend that the client review this statement, and that any interpretations contrary to those intended by the design documents be fully addressed. The statement is based upon measurements where possible and from information provided by the Architect and Owner.

Reasonable allowances have been made for items not clearly defined in the documents.

The facts presented, and the recommendations made, are believed to be reliable. The cost estimate is distributed upon the condition that the Owner and the Architect shall review the estimate documents for scope of work and content.

Preliminary Budget Estimate

6/26/2012

Basis of Estimate

Basis of Estimate (Continued)

The statement reflects probable construction costs obtainable in a competitive and stable bidding market. This estimate presumes a minimum of four (4) competitive bids from prequalified general contractors, with bids from a minimum of three (3) subcontractors per trade. This statement is a determination of fair market value for the construction of the project and is not intended to be a prediction of low bid. Experience indicates that a fewer number of bidders may result in a higher bid amount, and more bidders may result in a lower bid amount.

1 bid add 25% to 40%
 2 to 3 bids add 8% to 12%
 4 to 5 bids -4% to +4%
 7 to 8 bids deduct 5% to 7%

5 Escalation

For the purpose of this report cost escalation has been assumed at the following levels:

2012 3%
 2013 4%
 2014 4%
 2015 4%
 2016 4%

COST PLAN

Preliminary Budget Estimate

6/26/2012

UC Cost Summary

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

UC Cost Summary	Phase 1A	Phase 1B								Phase 1B Subtotal	TOTAL	
	Sitework	Cottage	Barn Dining	Kitchen Addition	Faculty Dining & Performance Stage	Barn Stable	Barn Stable Addition	East Courtyard Restrooms	Barn Theater			Sitework
1.0 Foundations	\$0	\$119,981	\$81,218	\$95,246	\$81,218	\$156,869	\$26,802	\$9,598	\$0	\$0	\$570,933	\$570,933
2.0 Vertical Structure	0	33,632	190,641	\$219,584	274,812	44,485	56,114	64,029	0	0	883,297	883,297
3.0 Floor & Roof Structures	0	66,584	238,279	\$367,843	556,786	93,142	82,872	94,744	0	0	1,500,250	1,500,250
4.0 Exterior Cladding	0	92,500	340,672	\$643,098	783,089	196,917	206,884	163,425	118,135	0	2,544,720	2,544,720
5.0 Roofing, Waterproofing & Skylights	0	56,424	145,011	\$148,112	196,237	65,329	56,262	26,876	0	0	694,251	694,251
Total Shell (1.0 - 5.0)	\$0	\$369,121	\$995,821	\$1,473,884	\$1,892,142	\$556,742	\$428,934	\$358,673	\$118,135	\$0	\$6,193,451	\$6,193,451
6.0 Interior Partitions, Doors & Glazing	\$0	\$25,606	\$41,495	\$133,936	\$339,284	\$32,221	\$64,118	\$8,122	\$0	\$0	\$644,782	\$644,782
7.0 Floor, Wall & Ceiling Finishes	0	\$36,090	173,659	\$223,940	390,710	84,703	53,574	75,511	0	0	1,038,187	1,038,187
Total Interiors (6.0 - 7.0)	\$0	\$61,696	\$215,154	\$357,876	\$729,994	\$116,924	\$117,692	\$83,632	\$0	\$0	\$1,682,969	\$1,682,969
8.0 Function Equipment & Specialties	\$0	\$189,688	\$250,650	\$1,104,276	\$465,061	\$186,543	\$60,057	\$51,287	\$0	\$0	\$2,307,562	\$2,307,562
9.0 Stairs & Vertical Transportation	0	\$8,860	0	\$0	0	0	0	0	0	0	8,860	8,860
Total Equip and Vert Transportation (8.0-9.0)	\$0	\$198,548	\$250,650	\$1,104,276	\$465,061	\$186,543	\$60,057	\$51,287	\$0	\$0	\$2,316,422	\$2,316,422
10.0 Plumbing Systems	\$0	\$39,664	\$64,531	\$297,368	\$228,167	\$38,047	\$60,950	\$134,024	\$0	\$0	\$862,752	\$862,752
11.0 Heating, Ventilating & Air Conditioning	0	\$28,234	189,865	\$251,259	276,244	88,830	48,937	37,626	0	0	920,997	920,997
12.0 Electric Lighting, Power & Communications	0	\$89,905	297,756	\$327,707	524,963	124,736	80,834	56,956	0	0	1,502,857	1,502,857
13.0 Fire Protection Systems	0	\$14,088	42,529	\$43,415	61,224	17,366	10,942	14,353	0	0	203,916	203,916
Total Mechanical and Electrical (10.0 - 13.0)	\$0	\$171,890	\$594,681	\$919,749	\$1,090,598	\$268,979	\$201,664	\$242,960	\$0	\$0	\$3,490,522	\$3,490,522
Subtotal Building Construction (1.0 - 13.0)	\$0	\$801,256	\$2,056,305	\$3,855,785	\$4,177,795	\$1,129,188	\$808,347	\$736,553	\$118,135	\$0	\$13,683,364	\$13,683,364
14.0 Site Preparation & Demolition	0	\$26,580	\$29,534	\$25,842	\$44,301	\$14,767	\$22,150	\$0	\$0	\$290,391	\$453,565	\$453,565
15.0 Site Paving, Structures & Landscaping	30,670	0	0	99,677	66,724	0	0	0	0	3,094,979	3,261,380	3,292,050
16.0 Site Utilities	522,521	44,301	103,368	132,902	147,669	118,135	44,301	88,601	0	867,408	1,546,685	2,069,206
Subtotal Site Construction (14.0 - 16.0)	\$553,191	\$70,881	\$132,902	\$258,421	\$258,694	\$132,902	\$66,451	\$88,601	\$0	\$4,252,778	\$5,261,630	\$5,814,821
TOTAL BUILDING & SITE COST (1.0-16.0)	\$553,191	\$872,137	\$2,189,207	\$4,114,205	\$4,436,489	\$1,262,090	\$874,798	\$825,154	\$118,135	\$4,252,778	\$18,944,994	\$19,498,185

COST PLAN

Preliminary Budget Estimate

6/26/2012

UC Cost Summary

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

UC Cost Summary	Phase 1A	Phase 1B								Phase 1B Subtotal	TOTAL		
	Sitework	Cottage	Barn Dining	Kitchen Addition	Faculty Dining & Performance Stage	Barn Stable	Barn Stable Addition	East Courtyard Restrooms	Barn Theater			Sitework	
1.0 Foundations	\$0	\$81,250	\$55,000	\$64,500	\$55,000	\$106,230	\$18,150	\$6,500	\$0	\$0	\$386,630	\$386,630	
2.0 Vertical Structure	0	22,775	129,100	148,700	186,100	30,125	38,000	43,360	0	0	598,160	598,160	
3.0 Floor & Roof Structures	0	45,090	161,360	249,100	377,050	63,075	56,120	64,160	0	0	1,015,955	1,015,955	
4.0 Exterior Cladding	0	62,640	230,700	435,500	530,300	133,350	140,100	110,670	80,000	0	1,723,260	1,723,260	
5.0 Roofing, Waterproofing & Skylights	0	38,210	98,200	100,300	132,890	44,240	38,100	18,200	0	0	470,140	470,140	
Total Shell (1.0 - 5.0)	\$0	\$249,965	\$674,360	\$998,100	\$1,281,340	\$377,020	\$290,470	\$242,890	\$80,000	\$0	\$4,194,145	\$4,194,145	
6.0 Interior Partitions, Doors & Glazing	\$0	\$17,340	\$28,100	\$90,700	\$229,760	\$21,820	\$43,420	\$5,500	\$0	\$0	\$436,640	\$436,640	
7.0 Floor, Wall & Ceiling Finishes	0	24,440	117,600	151,650	264,585	57,360	36,280	51,135	0	0	703,050	703,050	
Total Interiors (6.0 - 7.0)	\$0	\$41,780	\$145,700	\$242,350	\$494,345	\$79,180	\$79,700	\$56,635	\$0	\$0	\$1,139,690	\$1,139,690	
8.0 Function Equipment & Specialties	\$0	\$128,455	\$169,738	\$747,805	\$314,935	\$126,325	\$40,670	\$34,731	\$0	\$0	\$1,562,659	\$1,562,659	
9.0 Stairs & Vertical Transportation	0	6,000	0	0	0	0	0	0	0	0	6,000	6,000	
Total Equip and Vert Transportation (8.0-9.0)	\$0	\$134,455	\$169,738	\$747,805	\$314,935	\$126,325	\$40,670	\$34,731	\$0	\$0	\$1,568,659	\$1,568,659	
10.0 Plumbing Systems	\$0	\$26,860	\$43,700	\$201,375	\$154,513	\$25,765	\$41,275	\$90,760	\$0	\$0	\$584,248	\$584,248	
11.0 Heating, Ventilation & Air Conditioning	0	19,120	128,575	170,150	187,070	60,155	33,140	25,480	0	0	623,690	623,690	
12.0 Electric Lighting, Power & Communications	0	60,883	201,638	221,920	355,500	84,470	54,740	38,570	0	0	1,017,720	1,017,720	
13.0 Fire Protection Systems	0	9,540	28,800	29,400	41,460	11,760	7,410	9,720	0	0	138,090	138,090	
Total Mechanical and Electrical (10.0 - 13.0)	\$0	\$116,403	\$402,713	\$622,845	\$738,543	\$182,150	\$136,565	\$164,530	\$0	\$0	\$2,363,748	\$2,363,748	
Subtotal Building Construction (1.0 - 13.0)	\$0	\$542,603	\$1,392,510	\$2,611,100	\$2,829,163	\$764,675	\$547,405	\$498,786	\$80,000	\$0	\$9,266,241	\$9,266,241	
14.0 Site Preparation & Demolition	\$0	\$18,000	\$20,000	\$17,500	\$30,000	\$10,000	\$15,000	0	0	\$196,650	\$307,150	\$307,150	
15.0 Site Paving, Structures & Landscaping	21,600	0	0	67,500	45,185	0	0	0	0	2,095,890	2,208,575	2,230,175	
16.0 Site Utilities	368,000	30,000	70,000	90,000	100,000	80,000	30,000	60,000	0	587,400	1,047,400	1,415,400	
Subtotal Site Construction (14.0 - 16.0)	\$389,600	\$48,000	\$90,000	\$175,000	\$175,185	\$90,000	\$45,000	\$60,000	\$0	\$2,879,940	\$3,563,125	\$3,952,725	
SUBTOTAL BUILDING AND SITE COST	\$389,600	\$590,603	\$1,482,510	\$2,786,100	\$3,004,348	\$854,675	\$592,405	\$558,786	\$80,000	\$2,879,940	\$12,829,366	\$13,218,966	
General Conditions	12.5%	48,700	73,825	185,314	348,263	375,543	106,834	74,051	69,848	10,000	359,993	\$1,603,671	\$1,652,371
Contractor's Fee	4.5%	19,724	29,899	75,052	141,046	152,095	43,268	29,991	28,289	4,050	145,797	649,487	669,210
Design Contingency	10.0%	45,802	69,433	174,288	327,541	353,199	100,478	69,645	65,692	9,405	338,573	1,508,252	1,554,055
Escalation		49,365	108,377	272,044	511,256	551,305	156,835	108,708	102,539	14,680	528,476	2,354,218	2,403,583
TOTAL BUILDING & SITE COST (1.0-16.0)	\$553,191	\$872,137	\$2,189,207	\$4,114,205	\$4,436,489	\$1,262,090	\$874,798	\$825,154	\$118,135	\$4,252,778	\$18,944,994	\$19,498,185	

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Schedule of Areas	Gross Area
Cottage Relocation & Renovation	
Enclosed Area	880 SF
Covered Area 1/2	305 SF
Gross Area	1,185 SF

Control Quantities	Ratio to Gross Area	
Cottage Relocation & Renovation		
Number of Stories	1 Ea	
Total Area	1,185 SF	1.0
Enclosed Area	880 SF	0.7
Covered Area	610 SF	0.5
Footprint Area	1,490 SF	1.3
Volume (Gross)	8,500 CF	7.2
Gross Wall Area	1,774 SF	1.5
Retaining Wall Area	0 SF	0.0
Finished Wall Area	1,664 SF	1.4
Windows or Glazing Area	110 SF	0.09
Roof Area - Pitched	1,590 SF	1.3
Finished Area	880 SF	0.7
Interior Partitions	44 LF	0.0
Shelled Area	0 SF	
Elevators	0 Ea	
Plumbing Fixtures	3 Ea	0.003

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Schedule of Areas	Gross Area
Barn Dining Renovation	
Enclosed Area	4,150 SF
Covered Area 1/2	275 SF
Gross Area	<u>4,425 SF</u>

Control Quantities		Ratio to Gross Area
Barn Dining Renovation		
Number of Stories	1 Ea	
Total Area	4,425 SF	1.0
Enclosed Area	4,150 SF	0.9
Covered Area	550 SF	0.1
Footprint Area	4,700 SF	1.1
Volume (Gross)	56,450 CF	12.8
Gross Wall Area	4,560 SF	1.0
Retaining Wall Area	0 SF	0.0
Finished Wall Area	3,760 SF	0.8
Windows or Glazing Area	800 SF	0.18
Roof Area - Pitched	4,800 SF	1.1
Finished Area	4,150 SF	0.9
Interior Partitions	100 LF	0.0
Shelled Area	0 SF	
Elevators	0 Ea	
Plumbing Fixtures	4 Ea	0.001

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Schedule of Areas	Gross Area
Kitchen Addition	
Enclosed Area	4,050 SF
Covered Area 1/2	385 SF
Gross Area	4,435 SF

Control Quantities		Ratio to Gross Area
Kitchen Addition		
Number of Stories	1 Ea	
Total Area	4,435 SF	1.0
Enclosed Area	4,050 SF	0.9
Covered Area	770 SF	0.2
Footprint Area	4,820 SF	1.1
Volume (Gross)	48,500 CF	10.9
Gross Wall Area	6,700 SF	1.5
Retaining Wall Area	1,000 SF	0.2
Finished Wall Area	4,700 SF	1.1
Windows or Glazing Area	1,000 SF	0.23
Roof Area - Pitched	4,680 SF	1.1
Finished Area	4,050 SF	0.9
Interior Partitions	400 LF	0.1
Shelled Area	0 SF	
Elevators	0 Ea	
Plumbing Fixtures	20 Ea	0.005

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Schedule of Areas	Gross Area
Faculty Staff Dining & Performance Stage	
Enclosed Area	4,710 SF
Covered Area 1/2	900 SF
Gross Area	<u>5,610 SF</u>

Control Quantities		Ratio to Gross Area
Faculty Staff Dining & Performance Stage		
Number of Stories	1 Ea	
Total Area	5,610 SF	1.0
Enclosed Area	4,710 SF	0.8
Covered Area	1,800 SF	0.3
Footprint Area	6,510 SF	1.2
Volume (Gross)	76,000 CF	13.5
Gross Wall Area	7,485 SF	1.3
Retaining Wall Area	700 SF	0.1
Finished Wall Area	5,585 SF	1.0
Windows or Glazing Area	1,200 SF	0.21
Roof Area - Pitched	6,910 SF	1.2
Finished Area	4,710 SF	0.8
Interior Partitions	700 LF	0.1
Shelled Area	0 SF	
Elevators	0 Ea	
Plumbing Fixtures	20 Ea	0.004

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
 The Barn Project
 Preliminary Budget Estimate

Schedule of Areas	Gross Area
Barn Stable	
Enclosed Area	1,490 SF
Covered Area 1/2	185 SF
Gross Area	1,675 SF

Control Quantities	Ratio to Gross Area	
Barn Stable		
Number of Stories	1 Ea	
Total Area	1,675 SF	1.0
Enclosed Area	1,490 SF	0.9
Covered Area	370 SF	0.2
Footprint Area	1,860 SF	1.1
Volume (Gross)	19,970 CF	11.9
Gross Wall Area	3,280 SF	2.0
Retaining Wall Area	0 SF	0.0
Finished Wall Area	2,880 SF	1.7
Windows or Glazing Area	400 SF	0.24
Roof Area - Pitched	1,960 SF	1.2
Finished Area	1,490 SF	0.9
Interior Partitions	90 LF	0.1
Shelled Area	0 SF	
Elevators	0 Ea	
Plumbing Fixtures	4 Ea	0.002

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
 The Barn Project
 Preliminary Budget Estimate

Schedule of Areas	Gross Area
Barn Stable Addition	
Enclosed Area	1,040 SF
Covered Area 1/2	50 SF
Gross Area	1,090 SF

Control Quantities	Ratio to Gross Area	
Barn Stable Addition		
Number of Stories	1 Ea	
Total Area	1,090 SF	1.0
Enclosed Area	1,040 SF	1.0
Covered Area	100 SF	0.1
Footprint Area	1,140 SF	1.0
Volume (Gross)	10,400 CF	9.5
Gross Wall Area	2,000 SF	1.8
Retaining Wall Area	0 SF	0.0
Finished Wall Area	1,600 SF	1.5
Windows or Glazing Area	400 SF	0.37
Roof Area - Pitched	1,200 SF	1.1
Finished Area	1,040 SF	1.0
Interior Partitions	130 LF	0.1
Shelled Area	0 SF	
Elevators	0 Ea	
Plumbing Fixtures	6 Ea	0.006

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Schedule of Areas	Gross Area
East Courtyard Restrooms	
Enclosed Area	910 SF
Covered Area 1/2	85 SF
Gross Area	995 SF

Control Quantities	Ratio to Gross Area	
East Courtyard Restrooms		
Number of Stories	1 Ea	
Total Area	995 SF	1.0
Enclosed Area	910 SF	0.9
Covered Area	170 SF	0.2
Footprint Area	1,080 SF	1.1
Volume (Gross)	8,200 CF	8.2
Gross Wall Area	1,880 SF	1.9
Retaining Wall Area	0 SF	0.0
Finished Wall Area	1,880 SF	1.9
Windows or Glazing Area	0 SF	0.00
Roof Area - Pitched	1,515 SF	1.5
Finished Area	910 SF	0.9
Interior Partitions	25 LF	0.0
Shelled Area	0 SF	
Elevators	0 Ea	
Plumbing Fixtures	26 Ea	0.026

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Phase 1A Sitework Summary		Cost
14.0 Site Preparation & Building Demolition		\$0
15.0 Site Paving, Structures & Landscaping		21,600
16.0 Utilities on Site		<u>368,000</u>
SUBTOTAL SITE CONSTRUCTION (14.0 - 16.0)		\$389,600
General Conditions	12.5%	48,700
Contractor's Fee	4.5%	19,724
Design Contingency	10.0%	<u>45,802</u>
Subtotal in May 2012 Dollars		\$503,826
Escalation For Construction Start December 2014	9.8%	<u>49,365</u>
Total Construction Cost		\$553,191

Note: Estimate excludes construction contingency and soft costs.

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Phase 1A Sitework

14.0 Site Preparation & Building Demolition		None		
15.0 Site Paving, Structures & Landscaping				
Landscape & Paving Repairs @ Offsite Utilities	720	LF	30.00	<u>\$21,600</u>
Total 15.0 Site Paving, Structures & Landscaping				<u>\$21,600</u>
16.0 Utilities on Site				
Mechanical				
Piping				
Steam	800	LF	112.00	\$89,600
CW	800	LF	62.00	49,600
CHW	800	LF	82.00	65,600
Manholes	4	Ea	2,500	10,000
Connection to Existing	1	LS		15,000
Relocations & Capping	1	LS		5,000
Trenching	400	LF	65.00	26,000
Electrical				
Power				
Primary	320	LF	165.00	52,800
Transformer	1	Ea	20,000	20,000
Trenching	320	LF	45.00	14,400
Manholes	2	Ea	2,500	5,000
Connect to Existing	1	LS		15,000
Telecom			None	
Total 16.0 Utilities on Site				<u>\$368,000</u>

6/26/2012

Cottage Relocation Renovation Summary Page 1 of 4

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Cottage Relocation & Renovation Summary	Cost	Cost/SF	
1.0 Foundations	\$81,250	\$68.57	
2.0 Vertical Structure	22,775	19.22	
3.0 Floor & Roof Structure	45,090	38.05	
4.0 Exterior Cladding	62,640	52.86	
5.0 Roofing & Waterproofing	38,210	32.24	
Total Shell (1.0 - 5.0)	\$249,965	\$210.94	
6.0 Interior Partitions, Doors & Glazing	\$17,340	\$14.63	
7.0 Floor, Wall & Ceiling Finish	24,440	20.62	
Total Interiors (6.0 - 7.0)	\$41,780	\$35.26	
8.0 Function Equipment & Specialties	\$128,455	\$108.40	
9.0 Stairs and Vertical Transportation	6,000	5.06	
Total Equipment and Vertical Transportation (8.0 - 9.0)	\$134,455	\$113.46	
10.0 Plumbing Systems	\$26,860	\$22.67	
11.0 Heating, Ventilation & Air Conditioning	19,120	16.14	
12.0 Electrical Lighting, Power & Communication	60,883	51.38	
13.0 Fire Protection Systems	9,540	8.05	
Total Mechanical and Electrical (10.0 - 13.0)	\$116,403	\$98.23	
Subtotal Building Construction (1.0 - 13.0)	\$542,603	\$457.89	
14.0 Site Preparation & Building Demolition	\$18,000	\$15.19	
15.0 Site Paving, Structures & Landscaping	0	0.00	
16.0 Utilities on Site	30,000	25.32	
Total Site Construction (14.0 - 16.0)	\$48,000	\$40.51	
SUBTOTAL BUILDING & SITE CONSTRUCTION (1.0 - 16.0)	\$590,603	\$498.40	
General Conditions	12.5%	73,825	62.30
Contractor's Fee	4.5%	29,899	25.23
Design Contingency	10.0%	69,433	58.59
Subtotal		\$763,760	\$644.52
Escalation For Construction Start June 2015	14.2%	108,377	91.46
Total Construction Cost		\$872,137	\$735.98

Note: Estimate excludes construction contingency and soft costs.

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Cottage Relocation & Renovation Estimate

1.0 Foundations			
Earthwork			
Cut & Fill Onsite	50 CY	35.00	\$1,750
Excavate & Haul	None		
Imported Fill	None		
Hazmat Mitigation	1 LS		30,000
Allow for Dryrot Repairs	1 LS		10,000
Allow for Obstacles & Misc Conditions	1 LS		6,000
Foundations/Tie Beams	30 CY	450.00	13,500
Relocate Building	Allow		<u>20,000</u>
Total 1.0 Foundations			\$81,250
2.0 Vertical Structure			
Upgrade to Existing Structure	1185 SF	15.00	\$17,775
Misc. Rough Carpentry	1 LS		5,000
Retaining Walls	None		
Total 2.0 Vertical Structures			\$22,775
3.0 Floor and Roof Structure			
Slab on Grade with Curbs @ Ramps	300 SF	24.00	\$7,200
Pads & Curbs	175 LF	20.00	3,500
Roof Structure Upgrade	1590 SF	15.00	23,850
Porch Repairs	670 SF	12.00	8,040
Miscellaneous	1 LS		<u>2,500</u>
Total 3.0 Floor and Roof Structure			\$45,090
4.0 Exterior Cladding			
Repair Existing Wall Cladding & Repaint	1764 SF	10.00	\$17,640
Replace Windows	110 SF	100.00	11,000
Louvers	1 LS		1,000
Mechanical Equipment Screen	None		
Doors - Double	1 Pr	3,700	3,700
- Single	2 Ea	1,500	3,000
Roof Hatch	None		
Card Readers	None		
Railings	90 LF	125.00	11,250
Soffits	670 SF	15.00	10,050
Sunshades	None		
Miscellaneous Metal & Hardware	1 LS		<u>5,000</u>
Total 4.0 Exterior Cladding			\$62,640

6/26/2012

COST PLAN

Preliminary Budget Estimate

5.0 Roofing & Waterproofing			
Waterproofing	None		
Roofing & Insulation - Corrug Metal	1590 SF	19.00	\$30,210
Skylights	None		
Sheet Metal	Included Above		
Caulking & Sealants	1 LS		6,000
Roof Accessories & Miscellaneous	1 LS		2,000
			<u>8,000</u>
Total 5.0 Roofing & Waterproofing			\$38,210
6.0 Interior Partitions, Doors & Glazing			
Partitions			
Stud & GWB, Painted	440 SF	11.00	\$4,840
GWB @ New Shear Walls	1000 SF	4.00	4,000
Miscellaneous Cut & Patch for MEP	1 LS		4,000
Interior Glazing	None		
Doors			
Single	3 Ea	1,500	4,500
Double	None		
Roll Down	None		
Card Readers	None		
			<u>4,500</u>
Total 6.0 Interior Partitions, Doors & Glazing			\$17,340
7.0 Floor, Wall & Ceiling Finishes			
Floor Finishes	880 SF	14.00	\$12,320
Wall Finishes	300 SF	14.00	4,200
Ceiling Finishes	880 SF	9.00	7,920
			<u>24,440</u>
Total 7.0 Floor, Wall & Ceiling Finishes			\$24,440
8.0 Function Equipment & Specialties			
Specialties			
Toilet Rooms	None		
Other Fixture Accessories	2 Ea	400.00	800
Other Div 10 Specialties	1185 SF	3.00	3,555
Refurbish Fireplace	Allow		12,000
Millwork	106 LF	350.00	37,100
Kitchen Equipment	1 LS		70,000
Miscellaneous	1 LS		5,000
			<u>124,100</u>
Total 8.0 Function Equipment & Specialties			\$128,455
9.0 Stairs and Vertical Transportation	2 Sets	3,000	\$6,000
10.0 Plumbing Systems			
Toilet Rooms	None		
Kitchen	1 LS		12,000
Grease Trap	1 LS		8,500
Roof Drainage	1590 SF	4.00	6,360
			<u>26,860</u>
Total 10.0 Plumbing			\$26,860

6/26/2012

COST PLAN

Preliminary Budget Estimate

11.0 Heating, Ventilation & Air Conditioning			
Heat Pump	1 Ea	7,000	\$7,000
Ductwork & Accessories	880 SF	6.00	5,280
Pipework & Accessories	880 SF	5.50	4,840
Controls	1 LS		<u>2,000</u>
Total 11.0 Heating, Ventilation & Air Conditioning			\$19,120
12.0 Electrical Lighting, Power & Communication			
Primary Power	1185 SF	5.50	\$6,518
TVSS	None		
Emergency Power	None		
Feeders	None		
Equipment Power	4 Ea	750.00	3,000
User Convenience Power	12 Ea	375.00	4,500
Lighting	1590 SF	11.00	17,490
Low Voltage Systems			
Telephone/Data System	8 Ea	1,000	8,000
Master Clock System	None		
Public Address System	1185 SF	2.00	2,370
Security System - Rough In Only	1185 SF	5.00	5,925
Audio Visual Systems - Rough In Only	1185 SF	5.00	5,925
Fire Alarm System	1590 SF	4.50	<u>7,155</u>
Total 12.0 Electrical Lighting, Power & Communication			\$60,883
13.0 Fire Protection Systems			
	1590 SF	6.00	\$9,540
14.0 Site Preparation & Building Demolition			
Miscellaneous Demolition @ New Site	1 LS		\$12,000
Miscellaneous Demolition @ Existing Site	1 LS		<u>6,000</u>
Total 14.0 Site Preparation & Building Demolition			\$18,000
15.0 Site Paving, Structures & Landscaping			
			Included in Phase 1B Sitework
16.0 Utilities on Site			
Mechanical Utilities	Allow		\$15,000
Electrical Utilities	Allow		<u>15,000</u>
Total 16.0 Utilities on Site			\$30,000

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Barn Dining Renovation Summary	Cost	Cost/SF	
1.0 Foundations	\$55,000	\$12.43	
2.0 Vertical Structure	129,100	29.18	
3.0 Floor & Roof Structure	161,360	36.47	
4.0 Exterior Cladding	230,700	52.14	
5.0 Roofing & Waterproofing	98,200	22.19	
Total Shell (1.0 - 5.0)	\$674,360	\$152.40	
6.0 Interior Partitions, Doors & Glazing	\$28,100	\$6.35	
7.0 Floor, Wall & Ceiling Finish	117,600	26.58	
Total Interiors (6.0 - 7.0)	\$145,700	\$32.93	
8.0 Function Equipment & Specialties	\$169,738	\$38.36	
9.0 Stairs and Vertical Transportation	0	0.00	
Total Equipment and Vertical Transportation (8.0 - 9.0)	\$169,738	\$38.36	
10.0 Plumbing Systems	\$43,700	\$9.88	
11.0 Heating, Ventilation & Air Conditioning	128,575	29.06	
12.0 Electrical Lighting, Power & Communication	201,638	45.57	
13.0 Fire Protection Systems	28,800	6.51	
Total Mechanical and Electrical (10.0 - 13.0)	\$402,713	\$91.01	
Subtotal Building Construction (1.0 - 13.0)	\$1,392,510	\$314.69	
14.0 Site Preparation & Building Demolition	\$20,000	\$4.52	
15.0 Site Paving, Structures & Landscaping	0	0.00	
16.0 Utilities on Site	70,000	15.82	
Total Site Construction (14.0 - 16.0)	\$90,000	\$20.34	
SUBTOTAL BUILDING & SITE CONSTRUCTION (1.0 - 16.0)	\$1,482,510	\$335.03	
General Conditions	12.5%	185,314	41.88
Contractor's Fee	4.5%	75,052	16.96
Design Contingency	10.0%	174,288	39.39
Subtotal		\$1,917,163	\$433.26
Escalation For Construction Start June 2015	14.2%	272,044	61.48
Total Construction Cost		\$2,189,207	\$494.74

Note: Estimate excludes construction contingency and soft costs.

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Barn Dining Renovation Estimate

1.0 Foundations			
Earthwork			
Cut & Fill Onsite		None	
Excavate & Haul		None	
Hazmat Mitigation	1 LS		\$30,000
Allow for Dryrot Repairs	1 LS		10,000
Allow for Obstacles & Misc Conditions	1 LS		6,000
Foundations/Tie Beams for New Structure	20 CY	450.00	9,000
			<hr/>
Total 1.0 Foundations			\$55,000
2.0 Vertical Structure			
Upgrade to Existing Structure			
	4425 SF	20.00	\$88,500
New Shear Walls			
	1680 SF	20.00	33,600
Misc. Rough Carpentry			
	1 LS		7,000
Retaining Walls			
		None	
			<hr/>
Total 2.0 Vertical Structures			\$129,100
3.0 Floor and Roof Structure			
Slab on Grade			
	480 SF	18.00	\$8,640
Pads & Curbs			
	200 LF	20.00	4,000
Roof Structure Upgrade			
	4800 SF	20.00	96,000
New Eave Framing			
	320 LF	75.00	24,000
New Roof Structure			
	520 SF	36.00	18,720
Miscellaneous			
	1 LS		10,000
			<hr/>
Total 3.0 Floor and Roof Structure			\$161,360
4.0 Exterior Cladding			
Repair Existing Wall Cladding & Repaint			
	2880 SF	10.00	\$28,800
Replace Windows			
	800 SF	100.00	80,000
New Exterior Walls			
	880 SF	55.00	48,400
Louvers			
	1 LS		3,000
New Windows			
	80 SF	100.00	8,000
Doors - Double - Repair & Reset Existing			
	7 Pr	4,500	31,500
- Single			
	5 Ea	2,000	10,000
Roof Hatch			
		None	
Card Readers			
		None	
Soffits - Painted			
	550 SF	20.00	11,000
Sunshades			
		None	
Miscellaneous Metal & Hardware			
	1 LS		10,000
			<hr/>
Total 4.0 Exterior Cladding			\$230,700

COST PLAN

Preliminary Budget Estimate

6/26/2012

5.0 Roofing & Waterproofing			
Roofing & Insulation - Corrug Metal	4800 SF	19.00	\$91,200
Skylights	None		
Sheet Metal	Included Above		
Caulking & Sealants	1 LS		5,000
Roof Accessories & Miscellaneous	1 LS		2,000
			<u>7,000</u>
Total 5.0 Roofing & Waterproofing			\$98,200
6.0 Interior Partitions, Doors & Glazing			
Partitions			
Stud & GWB, Painted	1200 SF	11.00	\$13,200
GWB on Shear Walls	2600 SF	4.00	10,400
Interior Glazing	None		
Doors			
Single	3 Ea	1,500	4,500
Double	None		
Card Readers	None		
			<u>4,500</u>
Total 6.0 Interior Partitions, Doors & Glazing			\$28,100
7.0 Floor, Wall & Ceiling Finishes			
Floor Finishes	4150 SF	14.00	\$58,100
Wall Finishes	1000 SF	18.00	18,000
Ceiling Finishes	4150 SF	10.00	41,500
			<u>107,600</u>
Total 7.0 Floor, Wall & Ceiling Finishes			\$117,600
8.0 Function Equipment & Specialties			
Specialties			
Toilet Rooms	None		
Other Fixture Accessories	None		
Other Div 10 Specialties	4425 SF	3.50	15,488
Millwork	175 LF	350.00	61,250
Stage Construction & Finish	400 SF	45.00	18,000
Column Wraps	1 LS		20,000
Acoustical Treatment	1 LS		25,000
Kitchen Equipment	1 LS		25,000
Miscellaneous	1 LS		5,000
			<u>169,738</u>
Total 8.0 Function Equipment & Specialties			\$169,738
9.0 Stairs and Vertical Transportation			
	None		
10.0 Plumbing Systems			
Toilet Rooms	None		
Kitchen	2 Fixt	4,000	\$8,000
Grease Trap	None		
Roof Drainage	4800 SF	3.75	18,000
Gas & Miscellaneous	4425 SF	4.00	17,700
			<u>25,700</u>
Total 10.0 Plumbing			\$43,700

Preliminary Budget Estimate

6/26/2012

11.0 Heating, Ventilation & Air Conditioning			
Wet Equipment			
Connection to CHW/HW	1 LS		\$20,000
Dry Equipment			
AHU	1 Ea	37,000	37,000
Exhaust Fans	2 Ea	4,000	8,000
Ductwork & Accessories	4150 SF	6.50	26,975
Pipework & Accessories	4150 SF	4.00	16,600
Controls	1 LS		20,000
			<u>20,000</u>
Total 11.0 Heating, Ventilation & Air Conditioning			\$128,575
12.0 Electrical Lighting, Power & Communication			
Primary Power			
TVSS	4425 SF	5.50	\$24,338
Emergency Power		None	
Feeders		Included in Primary Power Above	
Equipment Power	12 Ea	750.00	9,000
User Convenience Power	30 Ea	400.00	12,000
Lighting	4800 SF	12.00	57,600
Low Voltage Systems			
Telephone/Data System	24 Ea	1,000	24,000
Master Clock System		None	
Public Address System	4425 SF	2.00	8,850
Security System - Rough In Only	4425 SF	5.00	22,125
Audio Visual Systems - Rough In Only	4425 SF	5.00	22,125
Fire Alarm System	4800 SF	4.50	21,600
			<u>21,600</u>
Total 12.0 Electrical Lighting, Power & Communication			\$201,638
13.0 Fire Protection Systems	4800 SF	6.00	\$28,800
14.0 Site Preparation & Building Demolition			
Exterior Demolition	1 LS		\$10,000
Interior Demolition	1 LS		10,000
			<u>10,000</u>
Total 14.0 Site Preparation & Building Demolition			\$20,000
15.0 Site Paving, Structures & Landscaping			Included in Phase 1B Sitework
16.0 Utilities on Site			
Mechanical Utilities	Allow		\$40,000
Electrical Utilities	Allow		30,000
			<u>30,000</u>
Total 16.0 Utilities on Site			\$70,000

Preliminary Budget Estimate

6/26/2012

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Kitchen Addition	Cost	Cost/SF	
1.0 Foundations	\$64,500	\$14.54	
2.0 Vertical Structure	148,700	33.53	
3.0 Floor & Roof Structure	249,100	56.17	
4.0 Exterior Cladding	435,500	98.20	
5.0 Roofing & Waterproofing	100,300	22.62	
Total Shell (1.0 - 5.0)	\$998,100	\$225.05	
6.0 Interior Partitions, Doors & Glazing	\$90,700	\$20.45	
7.0 Floor, Wall & Ceiling Finish	151,650	34.19	
Total Interiors (6.0 - 7.0)	\$242,350	\$54.64	
8.0 Function Equipment & Specialties	\$747,805	\$168.61	
9.0 Stairs and Vertical Transportation	0	0.00	
Total Equipment and Vertical Transportation (8.0 - 9.0)	\$747,805	\$168.61	
10.0 Plumbing Systems	\$201,375	\$45.41	
11.0 Heating, Ventilation & Air Conditioning	170,150	38.37	
12.0 Electrical Lighting, Power & Communication	221,920	50.04	
13.0 Fire Protection Systems	29,400	6.63	
Total Mechanical and Electrical (10.0 - 13.0)	\$622,845	\$140.44	
Subtotal Building Construction (1.0 - 13.0)	\$2,611,100	\$588.75	
14.0 Site Preparation & Building Demolition	\$17,500	\$3.95	
15.0 Site Paving, Structures & Landscaping	67,500	15.22	
16.0 Utilities on Site	90,000	20.29	
Total Site Construction (14.0 - 16.0)	\$175,000	\$39.46	
SUBTOTAL BUILDING & SITE CONSTRUCTION (1.0 - 16.0)	\$2,786,100	\$628.21	
General Conditions	12.5%	348,263	78.53
Contractor's Fee	4.5%	141,046	31.80
Design Contingency	10.0%	327,541	73.85
Subtotal		\$3,602,950	\$812.39
Escalation For Construction Start June 2015	14.2%	511,256	115.28
Total Construction Cost		\$4,114,205	\$927.67

Note: Estimate excludes construction contingency and soft costs.

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Kitchen Addition Estimate

1.0 Foundations			
Earthwork			
Cut & Fill Onsite	100 CY	45.00	\$4,500
Excavate & Haul	None		
Imported Fill	None		
Hazmat Mitigation			
Allow for Obstacles & Misc Conditions	1 LS		6,000
Foundations/Tie Beams	120 CY	450.00	<u>54,000</u>
Total 1.0 Foundations			\$64,500
2.0 Vertical Structure			
Shear Walls - CMU	4600 SF	22.00	\$101,200
Misc. Rough Carpentry & Metals	1 LS		7,500
Retaining Walls	1000 SF	40.00	<u>40,000</u>
Total 2.0 Vertical Structures			\$148,700
3.0 Floor and Roof Structure			
Slab on Grade	4500 SF	10.00	\$45,000
Pads & Curbs & Trench Drain	1 LS		17,500
Loading Dock Slabs on Grade	1000 SF	10.00	10,000
Roof Structure	4900 SF	34.00	166,600
Miscellaneous	1 LS		<u>10,000</u>
Total 3.0 Floor and Roof Structure			\$249,100
4.0 Exterior Cladding			
Exterior Wall Assembly - Metal Siding	4600 SF	44.00	\$202,400
Windows	1000 SF	100.00	100,000
Louvers	1 LS		7,000
Fencing	920 SF	20.00	18,400
Mechanical Equipment Screen	None		
Doors - Double	7 Pr	3,700	25,900
- Single	7 Ea	1,700	11,900
- Sliding Gates	2 Ea	5,000	10,000
- Swinging Gates	1 Pr	5,000	5,000
Roof Hatch	None		
Card Readers	None		
Soffits	770 SF	20.00	15,400
Sunshades	400 SF	80.00	32,000
Miscellaneous Metal & Hardware	1 LS		<u>7,500</u>
Total 4.0 Exterior Cladding			\$435,500

6/26/2012

Preliminary Budget Estimate

5.0 Roofing & Waterproofing			
Waterproofing	1000 SF	9.00	\$9,000
Roofing & Insulation - Comp Shingle	4900 SF	17.00	83,300
Skylights	None		
Sheet Metal	Included Above		
Caulking & Sealants	1 LS		6,000
Roof Accessories & Miscellaneous	1 LS		2,000
			<u>100,300</u>
Total 5.0 Roofing & Waterproofing			\$100,300
6.0 Interior Partitions, Doors & Glazing			
Partitions			
Stud & GWB, Painted	4400 SF	11.00	\$48,400
CMU	800 SF	22.00	17,600
Interior Glazing	None		
Doors			
Single	8 Ea	1,700	13,600
Double	3 Pr	3,700	11,100
Roll Down	None		
Card Readers	None		
			<u>\$90,700</u>
Total 6.0 Interior Partitions, Doors & Glazing			\$90,700
7.0 Floor, Wall & Ceiling Finishes			
Floor Finishes	4050 SF	15.00	\$60,750
Wall Finishes	4200 SF	12.00	50,400
Ceiling Finishes	4050 SF	10.00	40,500
			<u>\$151,650</u>
Total 7.0 Floor, Wall & Ceiling Finishes			\$151,650
8.0 Function Equipment & Specialties			
Specialties			
Toilet Rooms	2 Rms	6,500	\$13,000
Other Fixture Accessories	10 Ea	400.00	4,000
Other Div 10 Specialties	4435 SF	3.00	13,305
Millwork	150 LF	350.00	52,500
Kitchen Equipment	Allowance		600,000
Exterior BBQ Unit	1 LS		40,000
Miscellaneous	1 LS		25,000
			<u>\$747,805</u>
Total 8.0 Function Equipment & Specialties			\$747,805
9.0 Stairs and Vertical Transportation		None	
10.0 Plumbing Systems			
Toilet Rooms Fixtures	12 Fixt	3,000	\$36,000
Kitchen Fixtures	8 Fixt	3,500	28,000
Grease Trap	1 Ea	15,000	15,000
Drinking Fountain	2 Ea	8,500	17,000

6/26/2012

Preliminary Budget Estimate

10.0 Plumbing Systems (Continued)			
Kitchen Equipment Rough In	1 LS		17,000
Roof Drainage	4900 SF	3.75	18,375
Greywater System	1 LS		35,000
Gas & Miscellaneous	1 LS		<u>35,000</u>
Total 10.0 Plumbing			<u>\$201,375</u>
11.0 Heating, Ventilation & Air Conditioning			
Wet Equipment			
Connection to CHW/HW	1 LS		\$20,000
Dry Equipment			
AHU	2 Ea	30,000	60,000
Exhaust Fans	3 Ea	3,500	10,500
Miscellaneous Equipment	1 LS		15,000
Ductwork & Accessories	4050 SF	8.50	34,425
Pipework & Accessories	4050 SF	4.50	18,225
Controls	1 LS		<u>12,000</u>
Total 11.0 Heating, Ventilation & Air Conditioning			<u>\$170,150</u>
12.0 Electrical Lighting, Power & Communication			
Primary Power	4435 SF	10.00	\$44,350
TVSS		None	
Emergency Power		None	
Feeders	20 LF	90.00	1,800
Equipment Power	20 Ea	800.00	16,000
User Convenience Power	30 Ea	375.00	11,250
Lighting	4900 SF	12.00	58,800
Low Voltage Systems			
Telephone/Data System	12 Ea	1,000	12,000
Master Clock System		None	
Public Address System	4435 SF	2.00	8,870
Security System - Rough In Only	4435 SF	5.00	22,175
Audio Visual Systems - Rough In Only	4435 SF	5.00	22,175
Fire Alarm System	4900 SF	5.00	<u>24,500</u>
Total 12.0 Electrical Lighting, Power & Communication			<u>\$221,920</u>
13.0 Fire Protection Systems	4900 SF	6.00	\$29,400
14.0 Site Preparation & Building Demolition			
Demolition @ Existing Building	1 LS		\$10,000
Site Reconfiguration	1 LS		<u>7,500</u>
Total 14.0 Site Preparation & Building Demolition			<u>\$17,500</u>

Preliminary Budget Estimate

6/26/2012

15.0 Site Paving, Structures & Landscaping			
Fine Grading			Included in Phase 1B Sitework
Paving			Included in Phase 1B Sitework
Landscape & Irrigation			Included in Phase 1B Sitework
Site Structures			
Trash Enclosure	1 LS	\$20,000	
Utility Enclosure	1 LS	25,000	
Site Lighting			
Miscellaneous	1 LS	15,000	
Railings	1 LS	7,500	
			None
			<hr/>
Total 15.0 Site Paving, Structures & Landscaping		\$67,500	
16.0 Utilities on Site			
Mechanical Utilities	Allow	\$50,000	
Electrical Utilities	Allow	40,000	
			<hr/>
Total 16.0 Utilities on Site		\$90,000	

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Faculty & Staff Dining Summary	Cost	Cost/SF	
1.0 Foundations	\$55,000	\$9.80	
2.0 Vertical Structure	186,100	33.17	
3.0 Floor & Roof Structure	377,050	67.21	
4.0 Exterior Cladding	530,300	94.53	
5.0 Roofing & Waterproofing	132,890	23.69	
Total Shell (1.0 - 5.0)	\$1,281,340	\$228.40	
6.0 Interior Partitions, Doors & Glazing	\$229,760	\$40.96	
7.0 Floor, Wall & Ceiling Finish	264,585	47.16	
Total Interiors (6.0 - 7.0)	\$494,345	\$88.12	
8.0 Function Equipment & Specialties	\$314,935	\$56.14	
9.0 Stairs and Vertical Transportation	0	0.00	
Total Equipment and Vertical Transportation (8.0 - 9.0)	\$314,935	\$56.14	
10.0 Plumbing Systems	\$154,513	\$27.54	
11.0 Heating, Ventilation & Air Conditioning	187,070	33.35	
12.0 Electrical Lighting, Power & Communication	355,500	63.37	
13.0 Fire Protection Systems	41,460	7.39	
Total Mechanical and Electrical (10.0 - 13.0)	\$738,543	\$131.65	
Subtotal Building Construction (1.0 - 13.0)	\$2,829,163	\$576.20	
14.0 Site Preparation & Building Demolition	\$30,000	\$5.35	
15.0 Site Paving, Structures & Landscaping	45,185	8.05	
16.0 Utilities on Site	100,000	17.83	
Total Site Construction (14.0 - 16.0)	\$175,185	\$31.23	
SUBTOTAL BUILDING & SITE CONSTRUCTION (1.0 - 16.0)	\$3,004,348	\$535.53	
General Conditions	12.5%	375,543	66.94
Contractor's Fee	4.5%	152,095	27.11
Design Contingency	10.0%	353,199	62.96
Subtotal		\$3,885,185	\$692.55
Escalation For Construction Start June 2015	14.2%	551,305	98.27
Total Construction Cost		\$4,436,489	\$790.82

Note: Estimate excludes construction contingency and soft costs.

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Faculty & Staff Dining Estimate

1.0 Foundations			
Earthwork			
Cut & Fill Onsite	100 CY	50.00	\$5,000
Excavate & Haul	None		
Imported Fill	None		
Hazmat Mitigation			
Allow for Obstacles & Misc Conditions	1 LS		5,000
Foundations/Tie Beams	100 CY	450.00	<u>45,000</u>
Total 1.0 Foundations			\$55,000
2.0 Vertical Structure			
Shear Walls - Wood Framed	7530 SF	20.00	\$150,600
Misc. Rough Carpentry & Metals	1 LS		7,500
Retaining Walls	700 SF	40.00	<u>28,000</u>
Total 2.0 Vertical Structures			\$186,100
3.0 Floor and Roof Structure			
Slab on Grade	7170 SF	10.00	\$71,700
Pads & Curbs	400 LF	20.00	8,000
Roof Structure	6910 SF	35.00	241,850
Stage Covering	600 SF	80.00	48,000
Miscellaneous	1 LS		<u>7,500</u>
Total 3.0 Floor and Roof Structure			\$377,050
4.0 Exterior Cladding			
Exterior Wall Assembly			
Metal Siding	3325 SF	44.00	\$146,300
Wood Siding	2000 SF	41.00	82,000
Stage Wall	260 SF	50.00	13,000
Windows	1400 SF	100.00	140,000
Louvers	1 LS		2,500
Mechanical Equipment Screen	None		
Doors - Double	2 Pr	4,000	8,000
- Single	5 Ea	2,000	10,000
- Sliding	1 Ea	8,500	8,500
Roof Hatch	None		
Card Readers	None		
Soffits	1300 SF	25.00	32,500
Stage Covering & Soffit	600 SF	80.00	48,000
Sunshades	400 SF	80.00	32,000
Miscellaneous Metal & Hardware	1 LS		<u>7,500</u>
Total 4.0 Exterior Cladding			\$530,300

6/26/2012

Preliminary Budget Estimate

5.0 Roofing & Waterproofing			
Waterproofing	None		
Roofing & Insulation - Corrug Metal Membrane	5110 SF	19.00	\$97,090
Skylights	1800 SF	16.00	28,800
Sheet Metal	None		
Caulking & Sealants	Included Above		
Roof Accessories & Miscellaneous	1 LS		5,000
	1 LS		2,000
			<u>7,000</u>
Total 5.0 Roofing & Waterproofing			\$132,890
6.0 Interior Partitions, Doors & Glazing			
Partitions			
Stud & GWB, Painted	8530 SF	12.00	\$102,360
GWB on Shear Walls	17000 SF	4.00	68,000
CMU	1000 SF	22.00	22,000
Interior Glazing	100 SF	90.00	9,000
Doors			
Single	14 Ea	1,500	21,000
Double	2 Pr	3,700	7,400
Card Readers	None		
			<u>28,400</u>
Total 6.0 Interior Partitions, Doors & Glazing			\$229,760
7.0 Floor, Wall & Ceiling Finishes			
Floor Finishes	4710 SF	14.00	\$65,940
Wall Finishes	4000 SF	18.00	72,000
Ceiling Finishes	4710 SF	12.00	56,520
Acoustical Treatment	5610 SF	12.50	70,125
			<u>264,585</u>
Total 7.0 Floor, Wall & Ceiling Finishes			\$264,585
8.0 Function Equipment & Specialties			
Specialties			
Toilet Rooms	4 Rms	2,000	\$8,000
Other Fixture Accessories	12 Ea	400.00	4,800
Other Div 10 Specialties	5610 SF	3.50	19,635
Millwork	200 LF	350.00	70,000
Storage Shelving	Allow		30,000
Acoustical Treatment	1 LS		25,000
Kitchen Equipment	Allow		150,000
Miscellaneous	1 LS		7,500
			<u>314,935</u>
Total 8.0 Function Equipment & Specialties			\$314,935
9.0 Stairs and Vertical Transportation			
	None		

Preliminary Budget Estimate

10.0 Plumbing Systems			
Toilet Rooms Fixtures	8 Fixt	3,700	\$29,600
Kitchen Fixtures	10 Fixt	3,700	37,000
Grease Trap	1 Ea	15,000	15,000
Drinking Fountain	2 Ea	8,500	17,000
Roof Drainage	6910 SF	3.75	25,913
Gas & Miscellaneous	1 LS		<u>30,000</u>
Total 10.0 Plumbing			\$154,513
11.0 Heating, Ventilation & Air Conditioning			
Wet Equipment			
Connection to CHW/HW	1 LS		\$20,000
Dry Equipment			
AHU	2 Ea	20,000	40,000
Exhaust Fans	2 Ea	3,500	7,000
Kitchen Rough In & Misc Equip	1 LS		20,000
Ductwork & Accessories	4710 SF	5.00	23,550
Pipework & Accessories - Incl. Radiant	4710 SF	12.00	56,520
Controls	1 LS		<u>20,000</u>
Total 11.0 Heating, Ventilation & Air Conditioning			\$187,070
12.0 Electrical Lighting, Power & Communication			
Primary Power	5610 SF	9.00	\$50,490
TVSS	None		
Emergency Power	None		
Feeders	20 LF	90.00	1,800
Equipment Power	12 Ea	800.00	9,600
User Convenience Power	100 Ea	400.00	40,000
Lighting	6910 SF	14.00	96,740
Low Voltage Systems			
Telephone/Data System	55 Ea	1,000	55,000
Master Clock System	None		
Public Address System	5610 SF	2.00	11,220
Security System - Rough In Only	5610 SF	5.00	28,050
Audio Visual Systems - Rough In Only	5610 SF	5.00	28,050
Fire Alarm System	6910 SF	5.00	<u>34,550</u>
Total 12.0 Electrical Lighting, Power & Communication			\$355,500
13.0 Fire Protection Systems	6910 SF	6.00	\$41,460
14.0 Site Preparation & Building Demolition			
Demolition @ Existing	1 LS		\$15,000
Site Reconfiguration	1 LS		<u>15,000</u>
Total 14.0 Site Preparation & Building Demolition			\$30,000

Preliminary Budget Estimate

15.0 Site Paving, Structures & Landscaping			
Fine Grading			Included in Phase 1B Sitework
Paving			Included in Phase 1B Sitework
Landscape & Irrigation			Included in Phase 1B Sitework
Site Structures			
Ramps to Entries	541 SF	35.00	\$18,935
Railings @ Ramps	210 LF	125.00	26,250
Site Lighting			Included in Phase 1B Sitework
Miscellaneous Site Accessories			Included in Phase 1B Sitework
Total 15.0 Site Paving, Structures & Landscaping			<u>\$45,185</u>
16.0 Utilities on Site			
Mechanical Utilities	Allow		\$50,000
Electrical Utilities	Allow		<u>50,000</u>
Total 16.0 Utilities on Site			<u>\$100,000</u>

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Barn Stable Summary	Cost	Cost/SF	
1.0 Foundations	\$106,230	\$63.42	
2.0 Vertical Structure	30,125	17.99	
3.0 Floor & Roof Structure	63,075	37.66	
4.0 Exterior Cladding	133,350	79.61	
5.0 Roofing & Waterproofing	44,240	26.41	
Total Shell (1.0 - 5.0)	\$377,020	\$225.09	
6.0 Interior Partitions, Doors & Glazing	\$21,820	\$13.03	
7.0 Floor, Wall & Ceiling Finish	57,360	34.24	
Total Interiors (6.0 - 7.0)	\$79,180	\$47.27	
8.0 Function Equipment & Specialties	\$126,325	\$75.42	
9.0 Stairs and Vertical Transportation	0	0.00	
Total Equipment and Vertical Transportation (8.0 - 9.0)	\$126,325	\$75.42	
10.0 Plumbing Systems	\$25,765	\$15.38	
11.0 Heating, Ventilation & Air Conditioning	60,155	35.91	
12.0 Electrical Lighting, Power & Communication	84,470	50.43	
13.0 Fire Protection Systems	11,760	7.02	
Total Mechanical and Electrical (10.0 - 13.0)	\$182,150	\$108.75	
Subtotal Building Construction (1.0 - 13.0)	\$764,675	\$456.52	
14.0 Site Preparation & Building Demolition	\$10,000	\$5.97	
15.0 Site Paving, Structures & Landscaping	0	0.00	
16.0 Utilities on Site	80,000	47.76	
Total Site Construction (14.0 - 16.0)	\$90,000	\$53.73	
SUBTOTAL BUILDING & SITE CONSTRUCTION (1.0 - 16.0)	\$854,675	\$510.25	
General Conditions	12.5%	106,834	63.78
Contractor's Fee	4.5%	43,268	25.83
Design Contingency	10.0%	100,478	59.99
Subtotal		\$1,105,255	\$659.85
Escalation For Construction Start June 2015	14.2%	156,835	93.63
Total Construction Cost		\$1,262,090	\$753.49

Note: Estimate excludes construction contingency and soft costs.

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Barn Stable Estimate

1.0 Foundations			
Earthwork			
Cut & Fill Onsite	78 CY	35.00	\$2,730
Excavate & Haul	None		
Imported Fill	None		
Hazmat Mitigation	1 LS		30,000
Allow for Dryrot Repairs	1 LS		10,000
Allow for Obstacles & Misc Conditions	1 LS		6,000
Foundations/Tie Beams	50 CY	450.00	22,500
Relocate Building	Allow		<u>35,000</u>
Total 1.0 Foundations			\$106,230
2.0 Vertical Structure			
Upgrade to Existing Structure	1675 SF	15.00	\$25,125
Misc. Rough Carpentry	1 LS		5,000
Retaining Walls	None		
Total 2.0 Vertical Structures			<u>\$30,125</u>
3.0 Floor and Roof Structure			
Slab on Grade @ Ramps	None		
Pads & Curbs	200 LF	20.00	\$4,000
Roof Structure Upgrade	1960 SF	20.00	39,200
New Eave Framing	165 LF	75.00	12,375
Porch Repairs	None		
Miscellaneous	1 LS		<u>7,500</u>
Total 3.0 Floor and Roof Structure			\$63,075
4.0 Exterior Cladding			
Repair Existing Wall Cladding & Repaint	2880 SF	10.00	\$28,800
Replace & Enlarge Windows	600 SF	100.00	60,000
Louvers	1 LS		5,000
Doors - Double	3 Pr	3,700	11,100
- Single	2 Ea	1,500	3,000
Roof Hatch	None		
Card Readers	None		
Soffits	390 SF	15.00	5,850
Sunshades	120 SF	80.00	9,600
Miscellaneous Metal & Hardware	1 LS		<u>10,000</u>
Total 4.0 Exterior Cladding			\$133,350

COST PLAN

Preliminary Budget Estimate

6/26/2012

5.0 Roofing & Waterproofing			
Waterproofing	None		
Roofing & Insulation - Corrug Metal	1960 SF	19.00	\$37,240
Skylights	None		
Sheet Metal	Included Above		
Caulking & Sealants	1 LS		5,000
Roof Accessories & Miscellaneous	1 LS		2,000
			<u>7,000</u>
Total 5.0 Roofing & Waterproofing			\$44,240
6.0 Interior Partitions, Doors & Glazing			
Partitions			
Stud & GWB, Painted	1120 SF	11.00	\$12,320
Interior Glazing			
Doors			
Single	4 Ea	1,500	6,000
Double	1 Pr	3,500	3,500
Roll Down	None		
Card Readers	None		
			<u>9,500</u>
Total 6.0 Interior Partitions, Doors & Glazing			\$21,820
7.0 Floor, Wall & Ceiling Finishes			
Floor Finishes	1490 SF	14.00	\$20,860
Wall Finishes	1200 SF	18.00	21,600
Ceiling Finishes	1490 SF	10.00	14,900
			<u>57,360</u>
Total 7.0 Floor, Wall & Ceiling Finishes			\$57,360
8.0 Function Equipment & Specialties			
Specialties			
Toilet Rooms	None		
Other Fixture Accessories	2 Ea	400.00	\$800
Other Div 10 Specialties	1675 SF	3.00	5,025
Millwork			
Bar Enclosure	80 LF	350.00	28,000
Kitchen Equipment	125 SF	100.00	12,500
Miscellaneous	1 LS		75,000
	1 LS		5,000
			<u>110,500</u>
Total 8.0 Function Equipment & Specialties			\$126,325
9.0 Stairs and Vertical Transportation			
	None		
10.0 Plumbing Systems			
Toilet Rooms			
Kitchen	1 LS		\$12,000
Grease Trap			
Roof Drainage	1960 SF	2.75	5,390
Gas & Miscellaneous	1675 SF	5.00	8,375
			<u>13,765</u>
Total 10.0 Plumbing			\$25,765

Preliminary Budget Estimate

11.0 HVAC			
Wet Equipment			
Connection to CHW/HW	1 LS		\$15,000
Dry Equipment			
AHU	1 Ea	20,000	20,000
Exhaust Fans	2 Ea	3,000	6,000
Ductwork & Accessories	1490 SF	6.00	8,940
Pipework & Accessories	1490 SF	3.50	5,215
Controls	1 LS		5,000
Total 11.0 HVAC			\$60,155
12.0 Electrical Lighting, Power & Communication			
Primary Power	1675 SF	6.00	\$10,050
TVSS	None		
Emergency Power	None		
Feeder	Included in Primary Power Above		
Equipment Power	4 Ea	750.00	3,000
User Convenience Power	16 Ea	375.00	6,000
Lighting	1960 SF	12.00	23,520
Low Voltage Systems			
Telephone/Data System	12 Ea	1,000	12,000
Master Clock System	None		
Public Address System	1675 SF	2.00	3,350
Security System - Rough In Only	1675 SF	5.00	8,375
Audio Visual Systems - Rough In Only	1675 SF	5.00	8,375
Fire Alarm System	1960 SF	5.00	9,800
Total 12.0 Electrical Lighting, Power & Communication			\$84,470
13.0 Fire Protection Systems	1960 SF	6.00	\$11,760
14.0 Site Preparation & Building Demolition			
Demolition			
New Site	1 LS		\$5,000
Existing Site	1 LS		5,000
Total 14.0 Site Preparation & Building Demolition			\$10,000
15.0 Site Paving, Structures & Landscaping		Included in Phase 1B Sitework	
16.0 Utilities on Site			
Mechanical Utilities	Allow		\$40,000
Electrical Utilities	Allow		40,000
Total 16.0 Utilities on Site			\$80,000

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Barn Stable Addition Summary	Cost	Cost/SF	
1.0 Foundations	\$18,150	\$16.65	
2.0 Vertical Structure	38,000	34.86	
3.0 Floor & Roof Structure	56,120	51.49	
4.0 Exterior Cladding	140,100	128.53	
5.0 Roofing & Waterproofing	38,100	34.95	
Total Shell (1.0 - 5.0)	\$290,470	\$266.49	
6.0 Interior Partitions, Doors & Glazing	\$43,420	\$39.83	
7.0 Floor, Wall & Ceiling Finish	36,280	33.28	
Total Interiors (6.0 - 7.0)	\$79,700	\$73.12	
8.0 Function Equipment & Specialties	\$40,670	\$37.31	
9.0 Stairs and Vertical Transportation	0	0.00	
Total Equipment and Vertical Transportation (8.0 - 9.0)	\$40,670	\$37.31	
10.0 Plumbing Systems	\$41,275	\$37.87	
11.0 Heating, Ventilation & Air Conditioning	33,140	30.40	
12.0 Electrical Lighting, Power & Communication	54,740	50.22	
13.0 Fire Protection Systems	7,410	6.80	
Total Mechanical and Electrical (10.0 - 13.0)	\$136,565	\$125.29	
Subtotal Building Construction (1.0 - 13.0)	\$547,405	\$502.21	
14.0 Site Preparation & Building Demolition	\$15,000	\$13.76	
15.0 Site Paving, Structures & Landscaping	0	0.00	
16.0 Utilities on Site	30,000	27.52	
Total Site Construction (14.0 - 16.0)	\$45,000	\$41.28	
SUBTOTAL BUILDING & SITE CONSTRUCTION (1.0 - 16.0)	\$592,405	\$543.49	
General Conditions	12.5%	74,051	67.94
Contractor's Fee	4.5%	29,991	27.51
Design Contingency	10.0%	69,645	63.89
Subtotal		\$766,091	\$702.84
Escalation For Construction Start June 2015	14.2%	108,708	99.73
Total Construction Cost		\$874,798	\$802.57

Note: Estimate excludes construction contingency and soft costs.

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Barn Stable Addition Estimate

1.0 Foundations			
Earthwork			
Cut & Fill Onsite	20 CY	45.00	\$900
Excavate & Haul	None		
Imported Fill	None		
Hazmat Mitigation			
Allow for Obstacles & Misc Conditions	1 LS		6,000
Foundations/Tie Beams	25 CY	450.00	<u>11,250</u>
Total 1.0 Foundations			\$18,150
2.0 Vertical Structure			
Shear Walls - Wood	1800 SF	20.00	\$36,000
Misc. Rough Carpentry & Metals	1 LS		2,000
Retaining Walls	None		
Total 2.0 Vertical Structures			<u>\$38,000</u>
3.0 Floor and Roof Structure			
Slab on Grade	1090 SF	10.00	\$10,900
Pads & Curbs	130 LF	20.00	2,600
Roof Structure	1140 SF	33.00	37,620
Miscellaneous	1 LS		<u>5,000</u>
Total 3.0 Floor and Roof Structure			\$56,120
4.0 Exterior Cladding			
Exterior Wall Assembly - Metal Siding	1600 SF	44.00	\$70,400
Windows	400 SF	100.00	40,000
Louvers	1 LS		2,500
Mechanical Equipment Screen	None		
Doors - Double	3 Pr	4,500	13,500
- Single	2 Ea	1,500	3,000
Roof Hatch	None		
Card Readers	None		
Soffits	100 SF	32.00	3,200
Sunshades	None		
Miscellaneous Metal & Hardware	1 LS		<u>7,500</u>
Total 4.0 Exterior Cladding			<u>\$140,100</u>

6/26/2012

COST PLAN

Preliminary Budget Estimate

5.0 Roofing & Waterproofing			
Waterproofing	None		
Roofing & Insulation - Single Ply	1140 SF	15.00	\$17,100
Skylights	100 SF	140.00	14,000
Sheet Metal	Included Above		
Caulking & Sealants	1 LS		5,000
Roof Accessories & Miscellaneous	1 LS		2,000
			<hr/>
Total 5.0 Roofing & Waterproofing			\$38,100
6.0 Interior Partitions, Doors & Glazing			
Partitions			
Stud & GWB, Painted	1320 SF	11.00	\$14,520
GWB on Shear Walls	3600 SF	4.00	14,400
CMU	None		
Interior Glazing	None		
Doors			
Single	5 Ea	1,500	7,500
Double	2 Pr	3,500	7,000
Card Readers	None		
			<hr/>
Total 6.0 Interior Partitions, Doors & Glazing			\$43,420
7.0 Floor, Wall & Ceiling Finishes			
Floor Finishes	1040 SF	11.00	\$11,440
Wall Finishes	1040 SF	12.00	12,480
Ceiling Finishes	1030 SF	12.00	12,360
			<hr/>
Total 7.0 Floor, Wall & Ceiling Finishes			\$36,280
8.0 Function Equipment & Specialties			
Specialties			
Toilet Rooms	2 Rms	2,000	\$4,000
Other Fixture Accessories	1 Ea	400.00	400
Other Div 10 Specialties	1090 SF	3.00	3,270
Millwork	80 LF	350.00	28,000
Kitchen Equipment	None		
Miscellaneous	1 LS		5,000
			<hr/>
Total 8.0 Function Equipment & Specialties			\$40,670
9.0 Stairs and Vertical Transportation	None		
10.0 Plumbing Systems			
Toilet Rooms Fixtures	5 Fixt	3,700	\$18,500
Kitchen Fixtures	None		
Drinking Fountain	1 Ea	8,500	8,500
Roof Drainage	1140 SF	3.75	4,275
Gas & Miscellaneous	1 LS		10,000
			<hr/>
Total 10.0 Plumbing			\$41,275

Preliminary Budget Estimate

6/26/2012

11.0 Heating, Ventilation & Air Conditioning			
Wet Equipment		Included in Barn Stable	
Dry Equipment			
Heat Pump	1 Ea	8,000	\$8,000
Exhaust Fan	1 Ea	3,500	3,500
Ductwork & Accessories	1040 SF	4.00	4,160
Pipework & Accessories - Incl Radiant	1040 SF	12.00	12,480
Controls	1 LS		<u>5,000</u>
Total 11.0 Heating, Ventilation & Air Conditioning			\$33,140
12.0 Electrical Lighting, Power & Communication			
Primary Power	1090 SF	8.00	\$8,720
TVSS		None	
Emergency Power		None	
Feeders		Included in Primary Power Above	
Equipment Power	4 Ea	750.00	3,000
User Convenience Power	16 Ea	400.00	6,400
Lighting	1140 SF	12.00	13,680
Low Voltage Systems			
Telephone/Data System	8 Ea	1,000	8,000
Master Clock System		None	
Public Address System	1090 SF	2.00	2,180
Security System - Rough In Only	1090 SF	4.00	4,360
Audio Visual Systems - Rough In Only	1090 SF	3.00	3,270
Fire Alarm System	1140 SF	4.50	<u>5,130</u>
Total 12.0 Electrical Lighting, Power & Communication			\$54,740
13.0 Fire Protection Systems	1140 SF	6.50	\$7,410
14.0 Site Preparation & Building Demolition			
Miscellaneous Demolition @ New Addition	1 LS		\$7,500
Miscellaneous Demolition @ Existing Building	1 LS		<u>7,500</u>
Total 14.0 Site Preparation & Building Demolition			\$15,000
15.0 Site Paving, Structures & Landscaping		Included in Phase 1B Sitework	
16.0 Utilities on Site			
Mechanical Utilities	Allow		\$15,000
Electrical Utilities	Allow		<u>15,000</u>
Total 16.0 Utilities on Site			\$30,000

6/26/2012

East Courtyard Restrooms Summary Page 1 of 4

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

East Courtyard Restrooms Summary	Cost	Cost/SF	
1.0 Foundations	\$6,500	\$6.53	
2.0 Vertical Structure	43,360	43.58	
3.0 Floor & Roof Structure	64,160	64.48	
4.0 Exterior Cladding	110,670	111.23	
5.0 Roofing & Waterproofing	18,200	18.29	
Total Shell (1.0 - 5.0)	\$242,890	\$244.11	
6.0 Interior Partitions, Doors & Glazing	\$5,500	\$12.06	
7.0 Floor, Wall & Ceiling Finish	51,135	51.39	
Total Interiors (6.0 - 7.0)	\$56,635	\$56.92	
8.0 Function Equipment & Specialties	\$34,731	\$76.17	
9.0 Stairs and Vertical Transportation	0	0.00	
Total Equipment and Vertical Transportation (8.0 - 9.0)	\$34,731	\$34.91	
10.0 Plumbing Systems	\$90,760	\$199.04	
11.0 Heating, Ventilation & Air Conditioning	25,480	25.61	
12.0 Electrical Lighting, Power & Communication	38,570	38.76	
13.0 Fire Protection Systems	9,720	9.77	
Total Mechanical and Electrical (10.0 - 13.0)	\$164,530	\$165.36	
Subtotal Building Construction (1.0 - 13.0)	\$498,786	\$501.29	
14.0 Site Preparation & Building Demolition	\$0	\$0.00	
15.0 Site Paving, Structures & Landscaping	0	0.00	
16.0 Utilities on Site	60,000	60.30	
Total Site Construction (14.0 - 16.0)	\$60,000	\$60.30	
SUBTOTAL BUILDING & SITE CONSTRUCTION (1.0 - 16.0)	\$558,786	\$561.59	
General Conditions	12.5%	69,848	70.20
Contractor's Fee	4.5%	28,289	28.43
Design Contingency	10.0%	65,692	66.02
Subtotal		\$722,615	\$726.25
Escalation For Construction Start June 2015	14.2%	102,539	103.05
Total Construction Cost		\$825,154	\$829.30

Note: Estimate excludes construction contingency and soft costs.

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

East Courtyard Restrooms Estimate

1.0 Foundations			
Earthwork			
Cut & Fill Onsite	20 CY	50.00	\$1,000
Excavate & Haul	None		
Imported Fill	None		
Hazmat Mitigation			
Allow for Obstacles & Misc Conditions	1 LS		1,000
Foundations/Tie Beams	10 CY	450.00	<u>4,500</u>
Total 1.0 Foundations			\$6,500
2.0 Vertical Structure			
Shear Walls			
Misc. Rough Carpentry & Metals	1880 SF	22.00	\$41,360
Retaining Walls	1 LS		2,000
	None		
Total 2.0 Vertical Structures			<u>\$43,360</u>
3.0 Floor and Roof Structure			
Slab on Grade			
Pads & Curbs	1080 SF	20.00	\$21,600
	192 LF	20.00	3,840
Roof Structure			
Miscellaneous	1080 SF	34.00	36,720
	1 LS		<u>2,000</u>
Total 3.0 Floor and Roof Structure			\$64,160
4.0 Exterior Cladding			
Exterior Walls - Metal Siding			
Louvers	1730 SF	44.00	\$76,120
Windows	1 LS		2,500
	150 SF	100.00	15,000
Doors - Double			
- Single	None		
- Gate @ East Entry	3 Ea	1,500	4,500
Roof Hatch	1 Pr	8,000	8,000
Card Readers	None		
	None		
Soffits			
Miscellaneous Metal & Hardware	170 SF	15.00	2,550
	1 LS		<u>2,000</u>
Total 4.0 Exterior Cladding			\$110,670

Preliminary Budget Estimate

6/26/2012

5.0 Roofing & Waterproofing			
Waterproofing	None		
Roofing & Insulation - Single Ply	1080 SF	15.00	\$16,200
Skylights	None		
Sheet Metal	Included Above		
Caulking & Sealants	1 LS		1,000
Roof Accessories & Miscellaneous	1 LS		1,000
			<u>1,000</u>
Total 5.0 Roofing & Waterproofing			\$18,200
6.0 Interior Partitions, Doors & Glazing			
Partitions			
Stud & GWB, Painted	None		
CMU, Painted	250 SF	22.00	\$5,500
Interior Glazing	None		
Doors	None		
			<u>5,500</u>
Total 6.0 Interior Partitions, Doors & Glazing			\$5,500
7.0 Floor, Wall & Ceiling Finishes			
Floor Finishes	910 SF	13.50	\$12,285
Wall Finishes	2380 SF	12.50	29,750
Ceiling Finishes	910 SF	10.00	9,100
			<u>9,100</u>
Total 7.0 Floor, Wall & Ceiling Finishes			\$51,135
8.0 Function Equipment & Specialties			
Specialties			
Toilet Rooms	2 Rms	15,000	\$30,000
Other Div 10 Specialties	995 SF	3.75	3,731
Millwork	None		
Miscellaneous	1 LS		1,000
			<u>1,000</u>
Total 8.0 Function Equipment & Specialties			\$34,731
9.0 Stairs and Vertical Transportation			
	None		
10.0 Plumbing Systems			
Toilet Rooms	26 Fixt	3,200	\$83,200
Roof Drainage	1080 SF	7.00	7,560
			<u>7,560</u>
Total 10.0 Plumbing			\$90,760
11.0 Heating, Ventilation & Air Conditioning			
	910 SF	28.00	\$25,480

6/26/2012

COST PLAN

Preliminary Budget Estimate

12.0 Electrical Lighting, Power & Communication			
Primary Power	995 SF	7.00	\$6,965
TVSS	None		
Emergency Power	None		
Feeders	None		
Equipment Power	6 Ea	750.00	4,500
User Convenience Power	6 Ea	400.00	2,400
Lighting	1080 SF	11.00	11,880
Low Voltage Systems			
Telephone/Data System	1 Ea	1,000	1,000
Master Clock System	None		
Public Address System	995 SF	2.00	1,990
Security System - Rough In Only	995 SF	3.00	2,985
Audio Visual Systems - Rough In Only	995 SF	2.00	1,990
Fire Alarm System	1080 SF	4.50	<u>4,860</u>
Total 12.0 Electrical Lighting, Power & Communication			\$38,570
13.0 Fire Protection Systems	1080 SF	9.00	\$9,720
14.0 Site Preparation & Building Demolition	None		
15.0 Site Paving, Structures & Landscaping			
Fine Grading			Included in Phase 1B Sitework
Paving			Included in Phase 1B Sitework
Landscape & Irrigation			Included in Phase 1B Sitework
Site Structures			
Trellis			Included in Barn Dining Estimate
Railings			None
Site Lighting			Included in Phase 1B Sitework
Miscellaneous Site Accessories			Included in Phase 1B Sitework
Total 15.0 Site Paving, Structures & Landscaping			<u>\$0</u>
16.0 Utilities on Site			
Mechanical Utilities	Allow		\$40,000
Electrical Utilities	Allow		<u>20,000</u>
Total 16.0 Utilities on Site			\$60,000

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Phase 1B Sitework Summary		Cost
14.0 Site Preparation & Building Demolition		\$196,650
15.0 Site Paving, Structures & Landscaping		2,095,890
16.0 Utilities on Site		<u>587,400</u>
SUBTOTAL SITE CONSTRUCTION (14.0 - 16.0)		\$2,879,940
General Conditions	12.5%	359,993
Contractor's Fee	4.5%	145,797
Design Contingency	10.0%	<u>338,573</u>
Subtotal		\$3,724,302
Escalation For Construction Start June 2015	14.2%	<u>528,476</u>
Total Construction Cost		\$4,252,778

Note: Estimate excludes construction contingency and soft costs.

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Phase 1B Sitework

14.0 Site Preparation & Building Demolition

Demolition				
Remove Existing Paving & Landscaping	60500	SF	1.15	\$69,575
Demo Existing Structures & Miscellaneous	60500	SF	1.15	69,575
Protection of Existing to Remain	1	LS		15,000
Allow for Temporary Egress & Access Staging	1	LS		20,000
Barricades & Access	1500	LF	15.00	<u>22,500</u>
Total 14.0 Site Preparation & Building Demolition				\$196,650

15.0 Site Paving, Structures & Landscaping

Barn Walk				
Fine Grading	7370	SF	1.00	\$7,370
Paving				
Concrete	7370	SF	12.00	88,440
AC Paving		None		
Landscape & Irrigation				
Fine Grading	4800	SF	1.00	4,800
Trees	20	Ea	1,000	20,000
Planted Areas Including Irrigation & Soil Prep	4800	SF	9.00	43,200
Site Structures		None		
Railings		None		
Site Lighting	12	Ea	1,800	21,600
Perimeter Fencing		None		
Campus Walk				
Fine Grading	5725	SF	1.00	5,725
Paving				
Concrete	5725	SF	12.00	68,700
AC Paving		None		
Landscape & Irrigation				
Fine Grading	400	SF	1.00	400
Trees	3	Ea	1,000	3,000
Planted Areas Including Irrigation & Soil Prep	400	SF	9.00	3,600
Site Structures		Allow		20,000
Railings		None		
Site Lighting	10	Ea	1,800	18,000
Perimeter Fencing	40	LF	225.00	9,000
Gates	2	Pr	8,000	16,000
Gates - Sliding	1	Ea	20,000	20,000
Bench at West	80	LF	400.00	32,000
Miscellaneous Site Accessories	1	LS		20,000

6/26/2012

Preliminary Budget Estimate

15.0 Site Paving, Structures & Landscaping (Continued)

East Courtyard				
Fine Grading	3240	SF	1.00	3,240
Paving				
Precast Pavers	3240	SF	18.00	58,320
Landscape & Irrigation				
Fine Grading	400	SF	1.00	400
Trees	4	Ea	1,500	6,000
Planted Areas Including Irrigation & Soil Prep	400	SF	9.00	3,600
Site Structures				
			Allow	12,000
Trellis @ Cottage	360	SF	70.00	25,200
New Enclosure @ Cottage	70	LF	225.00	15,750
Gates	4	Pr	4,000	16,000
Trellis @ North Edge	600	SF	80.00	48,000
Gates	4	Pr	6,000	24,000
Railings			None	
Site Lighting	10	Ea	1,800	18,000
Perimeter Fencing	110	LF	225.00	24,750
Miscellaneous Site Accessories	1	LS		25,000
Patio at Barn Stable Addition				
Fine Grading	920	SF	1.00	920
Paving				
Precast Pavers	920	SF	18.00	16,560
Landscape & Irrigation	1	LS		7,000
Site Structures				
Trellis	500	SF	75.00	37,500
Fencing	110	LF	190.00	20,900
Gates	2	Ea	6,500	13,000
Railings			None	
Site Lighting	10	Ea	1,800	18,000
Miscellaneous Site Accessories	1	LS		40,000
West Courtyard				
Fine Grading	5955	SF	1.00	5,955
Paving				
Precast Pavers	5955	SF	18.00	107,190
Landscape & Irrigation			None	
Site Structures				
Stage Covering			Included in Faculty Dining Estimate	
Canopy Over Performance Seating Area	3000	SF	120.00	360,000
Acoustical Treatment	1	LS		35,000
Railings			None	
Bench at North Edge	60	LF	400.00	24,000
Site Lighting	15	Ea	1,800	27,000
Perimeter Fencing	40	LF	225.00	9,000
Gates	3	Pr	4,000	12,000
Miscellaneous Site Accessories	1	LS		40,000

6/26/2012

Preliminary Budget Estimate

Remaining Areas			
Fine Grading	22290 SF	1.00	22,290
Concrete Paving	14290 SF	12.00	171,480
AC Paving	7600 SF	5.00	38,000
Turf Block	400 SF	20.00	8,000
Landscape & Irrigation			
Fine Grading	10900 SF	1.00	10,900
Trees	20 Ea	1,500	30,000
Planted Areas Including Irrigation & Soil Prep	10900 SF	9.00	98,100
Repairs to Existing Cottage Site	4000 SF	7.50	30,000
Site Structures			
Railings		Allow None	20,000
Site Lighting	25 Ea	1,800	45,000
Perimeter Fencing			
Gates	100 LF	1,000	100,000
Gates	2 Ea	4,000	8,000
Gates	3 Pr	6,000	18,000
Miscellaneous Site Accessories	1 LS		40,000
Total 15.0 Site Paving, Structures & Landscaping			<u>\$2,095,890</u>
16.0 Utilities on Site			
Mechanical			
Pumps	2 Ea	12,000	\$24,000
Heat Exchangers	2 Ea	21,000	42,000
Valves & Accessories	1 LS		35,000
Storm Drainage System	60500 SF	2.00	121,000
FDC, PRV & Misc. Connections	1 LS		40,000
Manholes & Structures	4 Ea	2,500	10,000
Meters			
Connection to Existing	10 Ea	2,500	25,000
Relocations & Capping	1 LS		25,000
Relocations & Capping	1 LS		20,200
Pads, Curbs & Misc. Support	1 LS		20,000
Electrical			
Power			
Secondary	600 LF	110.00	66,000
Meters	5 Ea	2,500	12,500
Telecom			
Conduit & Cable	600 LF	110.00	66,000
Fire Alarm Conn to Sproul	370 LF	110.00	40,700
Utility Tunnel to Sproul		Exsiting to Remain	
Miscellaneous Site Power			
Manholes & Structures	1 LS		15,000
Manholes & Structures	4 Ea	2,500	10,000
Connection to Existing	1 LS		15,000
Total 16.0 Utilities on Site			<u>\$587,400</u>

6/26/2012

COST PLAN

Preliminary Budget Estimate

University of California, Riverside
The Barn Project
Preliminary Budget Estimate

Alternates

1.0 Provide Alterations to Sproul Hall Loading Dock			
Demolition of Existing Structure	1 LS		\$25,000
Demolition of Existing Paving & Surf Treatment	9800 SF	3.00	29,400
Miscellaneous Cut & Fill	40 CY	50.00	2,000
Hazmat Mitigation	By Owner		
Allow for Obstacles & Misc Conditions	1 LS		15,000
New Dock Structure Alterations	1500 SF	50.00	75,000
New Concrete Paving	2080 SF	10.00	20,800
New AC Paving	3520 SF	5.00	17,600
Alterations to Existing Roadway	3200 SF	6.00	19,200
New Landscaping & Irrigation	1000 SF	8.00	8,000
New Trees	12 Ea	1,000	12,000
Utility Relocations & Connections	1 LS		50,000
Site Lighting	1 LS		25,000
Work Inside Existing Building	None		
Temporary Access & Egress	1 LS		20,000
Miscellaneous Other Work	Allow		15,000
Subtotal 1.0 Alterations to Sproul Hall			\$334,000
Contractor Overheads			159,214
Total 1.0			\$493,214
2.0 Provide Onsite Chiller and Boiler in lieu of Campus Connection			
Delete Steam	(800) LF	100.00	(\$80,000)
Delete CW	(800) LF	50.00	(40,000)
Delete CHW	(800) LF	75.00	(60,000)
Delete Misc Trenching Premiums	1 LS		(20,000)
Delete Manholes	(4) Ea	2,500	(10,000)
Delete Valves & Connections	1 LS		(30,000)
Delete Heat Exchangers	(2) Ea	20,500	(41,000)
Delete Landscape Repairs	(400) LF	25.00	(10,000)
Chillers	2 Ea	50,000	100,000
Boilers	2 Ea	16,500	33,000
Valves & Piping	1 LS		25,000
Building/Pad Area to Support Equipment	800 SF	85.00	68,000
Miscellaneous Other Work	Allow		15,000
Subtotal 2.0 Onsite Chiller & Boiler in lieu of Campus Connection			(\$50,000)
Contractor Overheads			(23,834)
Total 2.0			(\$73,834)

COST PLAN

Preliminary Budget Estimate

6/26/2012

Allowances


3.0 Provide Audio Visual Equipment as Described in DPP Report			
Interior Stage @ Barn Dining	1 LS		\$275,000
Outdoor Stage @ KUCR	1 LS		30,000
Event Space @ Barn Stable	1 LS		25,000
			<u>330,000</u>
Subtotal 3.0 Provide Audio Visual Equipment			\$330,000
Contractor Overheads			<u>157,308</u>
Total 3.0			\$487,308
4.0 Provide Emergency Power for Kitchen Addition & Fac/Staff Dining			
Diesel Generator & Day Tank	1 Ea	150,000	\$150,000
Three Day Storage Tank	1 LS		60,000
Emergency Barrels	2 Ea	3,500	7,000
Feeders	250 LF	100.00	25,000
Auto Transfer Switches	2 Ea	12,500	25,000
Acoustic Enclosure	300 SF	150.00	45,000
			<u>312,000</u>
Subtotal 4.0 Provide Emergency Power for Kitchen & Fac/Staff Dining			\$312,000
Contractor Overheads			<u>148,727</u>
Total 4.0			\$460,727
5.0 Provide Enhanced Commissioning/3rd Party Commissioning Allow			\$82,500
6.0 Allow for Painting & Patching Barn Theater Allow			\$16,500
7.0 Allow for Security Devices			
Cameras	12 Ea	5,000	\$60,000
Intrusion Detection	20 Ea	500.00	10,000
Card Keys	12 Ea	3,000	36,000
			<u>106,000</u>
Subtotal 7.0 Allow for Security Devices			\$106,000
Contractor Overheads			<u>50,529</u>
Total 7.0			\$156,529
8.0 Provide Theater Lighting Package Allow			\$160,000

VI. IMPLEMENTATION

The initial project schedule and implementation diagrams were developed in close coordination with the Project Management Team and the Steering Team. The Cost Plan assumed that construction for Phase 1B will begin in June of 2015.

IMPLEMENTATION

Project Schedule



NOTE: The Project Schedule is shown monthly and is based on a yet-to-be-determined start date. Durations of tasks are shown in weeks.

IMPLEMENTATION

Phasing & Implementation Diagrams


PHASING & IMPLEMENTATION STRATEGY: PHASE 1A & PHASE 1B

PHASE 1A

Initial work in Phase 1A will include: bringing all campus utilities to the site.

PHASE 1B

Phase 1B will include: the relocation of the Barn Stable and the Cottage, and their renovations and additions. This phase will include the Barn renovation and addition, as well as the Kitchen Addition. This phase will also include the Faculty / Staff Dining Facility, Outdoor Stage and East Courtyard Restrooms, along with the East Courtyard and West Courtyard with shade structure, the Barn Stable Patio, Campus Walk, Loading Dock and Drive Aisle along West Campus drive. Minor changes to the Barn Theater will be made, including relocation of ramps on the West side and moving of the South exit to the North side.



PHASING & IMPLEMENTATION STRATEGY: PHASE 1A + PHASE 1B




IMPLEMENTATION

Phasing & Implementation Diagrams

PHASING & IMPLEMENTATION STRATEGY: PHASE 2

PHASE 2

Phase 2 will include: the Barn Theater's renovation and addition.



PHASING & IMPLEMENTATION STRATEGY: PHASE 2



VII. APPENDIX

A record of the decision making process is provided that includes visual materials, the meeting notes, key correspondence, and other materials.

APPENDICES INDEX

Campus Supporting Documents

2012 - Meeting Notes, Action Items presented at:

Workshop #1	February 3, 2012
Workshop #2	April 13, 2012
Cost Conference Call	May 9, 2012

2012 - Correspondence

2010 - Participants

2010 - Meeting Notes, Action Items, and/or Site Plan Alternatives presented at:

Workshop #1	February 5, 2010
Workshop #2	February 26, 2010
KUCR Conference Call	March 11, 2010
Workshop #3	March 19, 2010
Performances Issues Conference Call	April 5, 2010
DRB Presentation	April 6, 2010
Workshop #4	April 16, 2010

2010 - Correspondence

APPENDIX

Campus Supporting Documents

The following documents, provided by UCR, were used or referred to in preparation of the 2010 Barn Project Phases 1 & 2 DPP and the 2012 Barn Expansion Project DPP Update.

August 1991	EIR Humanities & Social Sciences	August 3, 2009	ADA Site Assessment Report: UCR P5251 Theater Workshop
June 16, 1993	Historic Resource Inventory, The Barn Theater and The Barn Group	August 3, 2009	ADA Site Assessment Report: UCR P5251 Theater Workshop Cost Report
November 2000	Tenant Improvement for the Barn	August 9, 2009	ADA Site Assessment Report: UCR Lot 16
June 2002	East Campus Infrastructure DPP	August 9, 2009	ADA Site Assessment Report: UCR Lot 16 Cost Report
March 15, 2003	Asbestos and Lead Information for the Barn Complex	October 2009	Barn Area Study
October 3, 2005	Campus Green Building Baseline Substantiation	October 5, 2009	Existing Building Information Summaries
November 2005	Long Range Development Plan	October 5, 2009	Existing Space Inventory, Barn Group
May 2006	East / Southeast Campus Area Study	October 5, 2009	UCR Vision and Goals
May 24, 2006	Communications Infrastructure Planning Guidelines	November 7, 2009	ADA Site Assessment Report: UCR Lot P4
2007	Campus Design Guidelines	November 7, 2009	ADA Site Assessment Report: UCR Lot P4 Cost Report
2008	Campus Aggregate Master Planning Study	November 16, 2009	Dining Master Planning Study
July 2007	Room Numbering Standards	February 19, 2010	Asbestos and Lead Based Paint Survey: Barn Complex
July 2007	Facilities Management System CAD Standards	March 2, 2010	GeoVision: Site Map with Geophysical Interpretation
January 4, 2008	Campus Sign Program	April 2010	Historic Resources Assessment (title page and Executive Summary, page i., of which are included on the following page of this DPP)
April 1, 2008	UCR West Campus Graduate & Professional Center DRB Presentation		Soils Report, Humanities & Social Sciences
August 2008	Room Use Codes		Humanities & Social Science Drawings
Fall 2008	Room Use Codes and Definitions		AutoCAD Data Delivery for UCR Planning & Design Projects
February 2, 2009	UCR Student Recreation Center Expansion DRB Presentation	January 20, 2012	Building Area Overview
April 2009	Sustainability Action Plan – DRAFT	April 8, 2012	Barn Master Plan Aerial Topography 2011
August 1, 2009	ADA Site Assessment Report: UCR P5338 The Barn	April 12, 2012	LEED Application Guide for Multiple Buildings and On-Campus Building Projects
August 1, 2009	ADA Site Evaluation Cost Report	April 12, 2012	Applicability for Credits and Prerequisites in LEED 2009

Campus Supporting Documents

HISTORIC RESOURCES ASSESSMENT

THE BARN GROUP AND UNIVERSITY COTTAGE
UNIVERSITY OF CALIFORNIA, RIVERSIDE

CITY OF RIVERSIDE

RIVERSIDE COUNTY, CALIFORNIA

Prepared for:

The University of California, Riverside
Office of Design and Construction
Tricia D. Thrasher, ASLA, LEED AP
Principal Environmental Project Manager
3615-A Canyon Crest Drive
Riverside, California 92521-0322

Prepared by:

Casey Tibbet, M.A., and Elisa Bechtel
LSA Associates, Inc.
1500 Iowa Avenue, Suite 200
Riverside, California 92507

LSA Project No. UCR1001

LSA

April 2010

EXECUTIVE SUMMARY

LSA Associates, Inc. (LSA) conducted a historic resources assessment for the Barn Group and University Cottage located on the University of California, Riverside (UCR) campus in the City of Riverside, Riverside County, California. The assessment included a review of previous reports, archival research, a field survey, and this report. The project area is currently developed with the Barn Group (the Barn, the Barn Theater, and the Barn Stable; 33-7877), the University Cottage (33-7878), and two sheds. UCR, as Lead Agency for the project, required this study in support of both the project planning and design process and the environmental review process to comply with the California Environmental Quality Act (CEQA).

The purpose of the study is to provide UCR with the necessary information and analysis to determine whether the proposed project would cause substantial adverse changes to any historical resources that may exist in or around the project area, as mandated by CEQA. In addition, UCR will utilize the historic resources assessment to inform the planning and design of the Barn Project. In order to identify and evaluate such resources, LSA conducted historical background research and carried out an intensive-level field survey.

Through the various avenues of research, this study did not encounter any "historical resources," as defined by CEQA, within the project area. Therefore, LSA recommends to UCR a finding of *No Impact* regarding cultural resources. No further cultural resources investigation and no mitigation measures are recommended for the project unless development plans undergo such changes as to include areas not covered by this study. However, because the buildings are associated with the earliest history of campus, specifically the Citrus Experiment Station, and over time have become an integral part of campus life, it is recommended that they be given special consideration in project planning and design. This could include keeping the buildings together as a group and preserving the rustic feel of the buildings by retaining features that contribute to their historic character. Some of these features include the exterior board-and-batten style siding (Barn Group), barn-style doors, the decorative details on the north and south ends of the Barn, historic-period windows, the horizontal wood siding (University Cottage), and the cottage's arched entry area.

If buried cultural materials are encountered during earthmoving operations associated with the project, all work in that area should be halted or diverted until a qualified archaeologist can evaluate the nature and significance of the finds.

In the event human remains are encountered, State Health and Safety Code Section 7050.5 states that no further disturbance shall occur until the County Coroner has made a determination of origin and disposition pursuant to Public Resources Code Section 5097.98. The County Coroner must be notified of the find immediately. If the remains are determined to be Native American, the County Coroner will notify the Native American Heritage Commission (NAHC), which will determine and notify a Most Likely Descendant (MLD). With the permission of the landowner or his/her authorized representative, the MLD may inspect the site of the discovery. The MLD shall complete the inspection within 48 hours of notification by the NAHC. The MLD will have the opportunity to offer recommendations for the disposition of the remains.

2012 DPP UPDATE

2012 - Meeting Notes, Action Items presented at:

Workshop #1	February 3, 2012
Workshop #2	April 13, 2012
Cost Conference Call	May 9, 2012

2012 - Correspondence

Workshop #1: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

ISSUED: February 23, 2012

MEETING NOTES

Project Management Team Meeting #1

PROJECT: DPP Update– UCR Barn Project
TIME/DATE: 9:30 AM – 10:00 AM, 3:15 PM – 3:30 PM, February 3, 2012
LOCATION: University Village, Capital Programs 210-16

ATTENDEES:

Project Management Team

Jon Harvey (JH)	Principal Education Facilities Planner, Capital Resource Management
Jacqueline Norman (JN)	Senior Project Manager, Architects & Engineers
Kieron Brunelle (KB)	Executive Director, Capital Resource Management
Andy Plumley (AP)	Assistant Vice Chancellor, Housing, Dining & Residential Services
Susan Marshburn (SM)	Executive Director of Housing Services
Cheryl Garner (CG)	Executive Director of Dining, Conference and Catering Services
Yun Baird (YB)	Director of Capital Projects

Consultant Team

Laura Hartman (F&H)	Principal, Fernau & Hartman Architects
Laura Boutelle (F&H)	Project Manager, Fernau & Hartman Architects
Anastasia Yee (F&H)	Junior Designer, Fernau & Hartman Architects
Larry Lanier (LL)	Food Service Consultant, Laschober + Sovich

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

	<p>1. DPP Update Goals: Dining goals are to streamline the food program for profitability, and avoid a space that is overly focused or tailored to faculty and staff with flexibility for later change. Focus of the DPP Update will be spaces West of the Barn.</p>
	<p>2. General Progress Status:</p> <p>a. F&H has met with consultant team (Larry Lanier (LL), Food Service Consultant; Charles Salter (CS), Acoustical Consultant; Adam Shalleck (AS), Theater Consultant; and Mike Brewer (MB), Beverage Consultant). Questions and diagrams were sent to Fire Marshall Scott Corrin (SC) with no response yet.</p> <p>b. The Faculty/Staff Dining building has increased by about 1,500 SF from KUCR in Basic Gross Total (does not include Outdoor Space). There are some concerns/confusions from Beverage and Food Service about the compound perimeter and possible overlap in the program.</p>
	<p>3. Workshop #1 Goals:</p> <p>a. establish feel and character of West Courtyard, Faculty/Staff Dining, and Beer Garden</p> <p>b. resolve sizing issues, and as they relate to cost</p> <p>c. discuss various implications of West Courtyard having a solid roof (additional cost, sprinklers, additional square footage in code analysis)</p>

Workshop #1: Meeting Notes

ACTION BY:	ITEM:
	d. establish priorities
	4. Physical Plant: Utility connection points and capacities are defined in the DPP. If the buildings are larger, capacity will need to be verified at a later date. No Civil, MEP, Structural, or Telecommunications consulting will occur in this round, so the DPP Utility Diagram will remain unchanged.
F&H	5. Action Items:
F&H	<ul style="list-style-type: none"> a. F&H needs to get final sign-off from Mike Brewer on Beverage Conference Call Notes, and may want Mike Brewer to provide quantitative risk diagnostics. Once approved, final notes will be distributed to the committee. b. F&H will discuss kitchen adjustments with LL.
	6. Schedule:
	<ul style="list-style-type: none"> a. DRB and CPAC are pending. b. Date of cost review with Cost Consultant Scott Lewis (SL) is pending. c. Review by UCR of F&H updated key materials will be in early March, turn-around times are reviewed. d. DPP Update Schedule (01/27/12) is accepted.

Workshop #1: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

ISSUED: February 23, 2012

MEETING NOTES

Workshop #1: Program Review and Refinement, Site Requirements

PROJECT: DPP Update – UCR Barn Project
TIME/DATE: 10:00 AM – 3:30 PM, February 3, 2012
LOCATION: University Village, Capital Programs 210-16

ATTENDEES:

Project Management Team

Jon Harvey (JH)	Principal Education Facilities Planner, Capital Resource Management
Jacqueline Norman (JN)	Senior Project Manager, Architects & Engineers
Kieron Brunelle (KB)	Executive Director, Capital Resource Management
Andy Plumley (AP)	Assistant Vice Chancellor, Housing, Dining & Residential Services
Susan Marshburn (SM)	Executive Director of Housing Services
Cheryl Garner (CG)	Executive Director of Dining, Conference and Catering Services
Yun Baird (YB)	Director of Capital Programs

Steering Committee

Andy Plumley (AP)	Assistant Vice Chancellor, Housing, Dining & Residential Services
Susan Marshburn (SM)	Executive Director of Housing Services
Cheryl Garner (CG)	Director of Dining, Catering and Catering Services
Yun Baird (YB)	Director of Capital Projects
David Henry (DH)	Director of Residential Dining
Albert Esqueda (AE)	General Manager for Retail Dining
Nita Bullock (NB)	Director of Physical Planning, Campus Landscape Architect

Campus Representatives

Scott Corrin (SC)	Fire Marshall
Weston Lewis (WL)	Office of Sustainability

Consultant Team

Laura Hartman (F&H)	Principal, Fernau & Hartman Architects
Laura Boutelle (F&H)	Project Manager, Fernau & Hartman Architects
Anastasia Yee (F&H)	Junior Designer, Fernau & Hartman Architects
Larry Lanier (LL)	Food Service Consultant, Laschober + Sovich
Adam Shalleck (AS)	Theater Consultant, The Shalleck Collaborative (via conference call)

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

- | | |
|--|---|
| | <p>1. Drawings Presented: Twelve 24” x 36” prints were displayed, and copies provided to the committee in a handout. Materials were also reviewed as a digital presentation—Area on Site for Faculty/Staff Dining, 2 Courtyard Fire Exit schemes and Existing Overhangs, Fire Egress Site Plan with Distances, updated Barn Kitchen and Site Adjacency Diagrams and new Faculty/Staff Dining Adjacency Diagram. From 2010 DPP—Security Diagram, Seating Diagram, Phasing Diagrams 1-3,</p> |
|--|---|

Workshop #1: Meeting Notes

ACTION BY:	ITEM:
	Composite Site Organization Plan.
	2. Description of Goals: Complete program refinements and site requirements for DPP Update. Note, all DPP Project Goals are still being met without KUCR. Faculty/Staff Dining should not be framed as an additional goal.
CG	<p>3. Faculty/Staff Dining:</p> <ul style="list-style-type: none"> a. Character: The setting is casual and club-like, primarily for beverages but comfortable enough for eating, and should be flexible for future changes. A capacity for 50 seats is desired, which includes a mix of dining and soft seating. F&H to confirm size; now assumed to be about 1400 SF to include entry/transition space. b. Food Service: A very abbreviated meal period only; lunch only with a rotating menu and possibly a streamlined buffet. SF for buffet is needed (not assumed to be 192 SF), but need not be a separate space from Dining. c. Seating: A mix of seating is desired; suggestions include cocktail tables, bar seating, booths, soft seating at tables and comfortable low seating. CG showed images of the UCSD faculty dining as a good precedent. Action: CG will send photos she presented (showing UCSD and other bar/dining character) to JH to distribute to everyone. d. Main Entry: The Main Entry should not be from the West Courtyard. All agree that an entry from the North side is the most promising. e. Lobby: The lobby is a transition and not a formal lobby space. A separate 400 SF Lobby is no longer part of the program. The Faculty/Staff Dining Room should be increased by about 100 SF for transition. f. Relationship to West Courtyard: The Bar should serve both the Faculty/Staff Dining and the West Courtyard. Doors from Faculty/Staff Dining to West Courtyard are acceptable, but not prominent. Instead, Dining should be thought of as a “back wall”, avoiding a feeling of prominence or exclusivity. The stage may help with this connection, but performance is the priority for the stage and should not be compromised for Dining. Students should not have a sense that they can see the space but cannot enter. g. Dining Support: The 800 SF Pantry is redundant and is no longer in the program. According to LL, Food Staging and Set-up can be in the same room, and can be 200 SF total instead of 300 SF total. Dish-washing in Faculty/Staff Dining Support is desired, but may be less than 150 SF. Dining Support will receive deliveries of food only from the Barn Kitchen. h. Beer Garden: The Beer Garden is no longer in the program. (The Beer Garden was originally conceived of as an operational necessity, but is no longer needed as a separate entity.) SF for the Beer Garden will be given back to the West Courtyard. i. Private Dining Room: The Private Dining Room is no longer in the program.
CG	<p>4. Beverage Points of Sale and Consumption: The general goal is to allow for two operational situations: 1) maximize control and visibility of students on a day-to-day basis, but 2) allow for catered events elsewhere in the compound (e.g. in the Barn Stable).</p> <ul style="list-style-type: none"> a. Perimeter: The entire compound is to be licensed for alcohol consumption. This perimeter barrier is an ABC barrier and needs merely to be definition; for example, barrels, ramps, bollards, or low wall, which is acceptable since openness is desired for day-to-day use. (Decisions regarding the perimeter barrier found in Site discussion below.) Action: CG will confirm with Mike Brewer that club membership is only needed

Workshop #1: Meeting Notes

ACTION BY:	ITEM:
	<p>for the purchase of alcohol, and that the same club membership or a second type of membership is not required to enter the perimeter of the area licensed for alcohol consumption.</p> <ul style="list-style-type: none"> b. Point of Sale: On a day-to-day basis, sale of alcohol only occurs at the Bar. c. Consumption: On a day-to-day basis, consumption of alcohol is allowed in the Barn, Faculty/Staff Dining, and West Courtyard only. Consumption of alcohol is not allowed in the East Courtyard. There will be signage at the east exits of the Barn, and Barn Dining staff will enforce this barrier. d. Club Membership: Only Club Members can purchase alcohol. Club membership sales and support space will occur off site or at the Ticket Booth, during non-event periods. This is an operational issue and does not affect design.
	<p>5. Bar:</p> <ul style="list-style-type: none"> a. Configuration and Seating: The Bar is conceived of as an “L”-shaped bar, with the short leg opening to the Faculty/Staff Dining (interior) and the long leg opening to the West Courtyard (exterior). Both legs of the bar will have casual, moveable seating. During a busy concert, outside seating can be removed to make room for the increase in people ordering at the bar. According to Larry Lanier, since food is served in Faculty/Staff Dining, there must be an airtight barrier between the two legs of the bar. b. Size: Desired dimensions of the bar are 15’ x 10’ for the West Courtyard leg and 12’ x 10’ for the Faculty/Staff Dining leg, which is total of 270 SF Bar with a width of 10 ft (to be reviewed). c. Operations: Both legs of the bar will have taps, with more on the West Courtyard leg (10 to 15). Hard liquor will be available behind counter on the Faculty/Staff Dining leg. During slow hours, one bartender should be able to serve both Faculty/Staff Dining and Courtyard from the Bar. d. Bar Support: Since the Bar is managed by a third party, all support must be together. Sizes of support spaces are assumed to be: 100 SF Office and Packaging, 80 SF Dry Storage, and 150 SF Walk-in Refrigerator/Wine Cooler. No Bar Support should be in the Faculty/Staff Dining Support, although the Bar will need access to the Janitor’s Closet.
	<p>6. Theater and A/V: The stage will host bands (typically rock bands), comedy and stand-up; 2 to 3 larger performances will occur per week in addition to smaller campus events. Large events will generally occur in the evening, and more than one ticketed show will not occur simultaneously. The desire is to maximize audience size. Assume previous DPP goal of not having to move tables and chairs in the West Courtyard is maintained.</p> <ul style="list-style-type: none"> a. Outdoor Stage Configuration: According to AS, a 20’ x 30’ stage for a total of 600 SF stage is sufficient for a band and on-stage monitor mix. The stage should be elevated between 2 ft. and 3 ft. above audience ground level (3 ft. is ideal), with a mosh area that is at audience ground level but never has seating. Ramps up to stage directly from audience are needed; all agree landscape/hardscape features are an opportunity to use ramps as alternative seating and offer flexibility. b. Stage Canopy: The canopy needs to protect on-stage equipment from rain and provide armature and rain protection for lighting. c. Shade Structure: A lightweight and open shade structure over the audience is desired to provide shade, an armature for lights, and permanent heating elements. A solid, opaque or fully weatherproof structure is not needed; it would be significantly more costly and would require sprinkler system. A structure that

Workshop #1: Meeting Notes

ACTION BY:	ITEM:
F&H	<p>feels heavy or overbearing should be avoided.</p> <p>Action: F&H will confirm that a shade structure needs to have sprinklers if it is made from opaque fabric, even if it is retractable.</p> <p>d. AV: All agree that a good solution for elevating the audio mixes for the Outdoor Stage is a temporary platform that folds in half and is stored in the Green Room when not in use (a permanent platform would require a ramp). Students will not be technical operators for performances. All venues will have background music on separate channels. A/V equipment is needed in the Barn Stable, but not in Faculty/Staff Dining; there will be TVs in Faculty/Staff dining, as in a lounge atmosphere.</p> <p>e. Acoustics: Sound needs to be contained to prevent bleed into the academic area, including during lunch time events when classes are in session in the South wing of CHASS. According to Adam Shalleck, this is an issue for the acoustic consultant and will be addressed in discussion of the sound system. Acoustic separation between the different venues is not needed.</p> <p>f. Stage Support: Outdoor stage will share Bathrooms with Faculty/Staff Dining but does not share any other support space. Within the Backstage area, a secured storage closet should be provided. Size and function will be determined by the Theater Consultant.</p>
AS	<p>Action: AS will further define the function of backstage spaces.</p>
	<p>7. Barn Kitchen Addition:</p> <p>a. Configuration: The Barn Kitchen will be reconfigured to facilitate the new service connection between Barn Kitchen and Faculty/Staff Dining.</p> <p>b. System Narratives: DPP Update Foodservice System Narratives are now only applicable to Faculty/Staff Dining and should no longer include any information pertaining to the University Club. Catering truck is no longer supported by the Barn Kitchen. Remove Bar and bar storage from Barn Kitchen program. Kitchen's overall size remains as previously programmed.</p>
	<p>8. Fire Marshall—Summary of Scott Corrin's Comments</p> <p>a. Site: SC agrees the compound should be considered as one large building.</p> <p>b. Egress:</p> <p>i. Exit Scheme: In order to maximize audience size, three exits from the West Courtyard are needed. Therefore, an exit pathway through the Southwest corner between Faculty/Staff and Barn Kitchen is needed (shown in Scheme A). An open passage or a breezeway are preferred by SC. An exit through two layers of doors through an indoor corridor might be acceptable. The concern is that exits doors/pathway could become storage areas thus blocking the exit. (F&H code consultant does not think an indoor corridor would be acceptable.)</p> <p>ii. Exit Pathways: Exits must be dedicated exit paths, to be kept clear at all times. Perimeter barriers must be permanent pieces with emergency exit doors, or have an exit component that is permanent.</p> <p>iii. Shade Structure: The shade structure does not affect egress if it is non-combustible and permeable to smoke.</p> <p>c. Occupancy: Need to determine the maximum population that could be supported for shows in the West Courtyard. Event planning assumed a 500 or more people would be attending shows. Direction provided was that planning will assume 3, 7, and 15 ASF per person for standing, seating, and table seating (F&H will verify with Code Consultant). This will be used to determine occupancy and plumbing fixture counts. East Courtyard occupancy is as defined in DPP.</p>

Workshop #1: Meeting Notes

ACTION BY:	ITEM:
F&H	<p>Action: F&H will verify square footage assumptions for the West Courtyard to be used to determine occupancy and plumbing fixture counts.</p> <ul style="list-style-type: none"> d. Fire Truck Aisle: The northwest corner of the site between CHASS and Faculty/Staff Dining is a designated Fire Truck access point. It must maintain a 20' wide unobstructed aisle; it may be landscaped as long as it supports 40,000 lb. axel load. e. Systems: <ul style="list-style-type: none"> i. Significant emergency lights will be needed at the West Courtyard, and will have different cost and maintenance implications including the possible need for a generator. A decision should be made early on for AQMD Permitting requirements. ii. A voice evacuation system will likely be required. iii. Existing fire hydrants are sufficient. iv. One sprinkler system will be used for all buildings, with subsystems for each building. It is advised to examine the existing sprinkler and fire alarm/smoke detector systems early on for possible re-use.
F&H	<p>Action: F&H will review costing of systems and possible savings with Oppenheim Lewis Inc. For new systems, use SC's estimate of \$5 - \$6 per SF for now.</p>
F&H, SC	<p>9. Phasing and Implementation: Proposed Barn Expansion project will now be completed in a single phase. Original DPP identified three phases. DPP Phase 3, Barn Theater, is now Phase 2. According to SC, it is greatly preferable to interrupt emergency systems only once for an uninterrupted work period. If the interruption is greater, temporary lines must be installed. It is advised to examine existing sprinkler lines and cost a temporary line early on.</p> <p>Action: F&H to review with SC temporary fire protection for Barn Theater, once plan and schedule are developed.</p>
	<p>10. Site:</p> <ul style="list-style-type: none"> a. Parking: Parking provided for KUCR in the DPP are still part of the program for the Barn Project. b. Physical Plant: Utility services will be the same as presented in DPP. c. Service Access: Assumptions from DPP On-site Service Circulation remain unchanged. The Loading Dock serves both Faculty/Staff and the Barn. Bar Support will receive deliveries directly from the Loading Dock, and Dining Support will receive deliveries primarily from the Barn Kitchen. Visiting bands will likely enter Stage Support at the North entry. A "back of house" entry on the South end of Faculty/Staff Dining is needed. d. Perimeter Barriers: Two Options for pay zone and alcohol zone configuration were discussed, and will be considered operationally: <ul style="list-style-type: none"> i. Option 1: Ticketing is moved outward to Northeast corner of East Courtyard. The East Courtyard is included in the pay zone and requires secure, 6 ft. high fencing on its South and East perimeters. Secure fencing is needed on East of complex at the edge of the Barn Walk and on North between Barn Theater and Stable. Secure fencing needs to keep people out of the pay zone, but visual permeability is desired. ii. Option 2: Ticketing occurs as is, at Northeast corner of the Barn. Secure, 6 ft. high fencing is needed at the edge of the West Courtyard, between the Barn and Barn Theater. ABC soft barriers are needed other points on the complex perimeter. The East Courtyard is not in the payzone and does not require secure fencing. A wristband is required to go to the Bathrooms in the East

Workshop #1: Meeting Notes

ACTION BY:	ITEM:
CG, DH	<p>Courtyard. The Cottage remains open to the public during an event.</p> <p>Action: Dining Services will review operational issues and provide direction on ticket booth location. (The Question was whether the East Courtyard and Coffee outlet would be open or closed to those not attending shows.) Will be reviewed within two weeks (by February 17, 2012).</p>

Workshop #1: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480

fax 510.848-4532

ISSUED: February 23, 2012

MEETING NOTES

Sustainability Meeting #1

PROJECT: DPP Update– UCR Barn Project
TIME/DATE: 3:30 PM – 4:00 PM, February 3, 2012
LOCATION: University Village, Capital Programs 210-16

ATTENDEES:

Project Management Team

Jon Harvey (JH) Principal Education Facilities Planner, Capital Resource Management

Campus Representatives

Weston Lewis (WL) Office of Sustainability

Consultant Team

Laura Hartman (F&H) Principal, Fernau & Hartman Architects
 Laura Boutelle (F&H) Project Manager, Fernau & Hartman Architects
 Anastasia Yee (F&H) Junior Designer, Fernau & Hartman Architects
 Larry Lanier (LL) Food Service Consultant, Laschober + Sovich

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

The following are items that Weston Lewis pointed out as issues needing further study or on which he had questions or comments.

	<p>1. LEED Boundaries: LEED has new guidelines, so LEED boundaries for the Barn Project may need to be re-drawn. The Barn Theater will be excluded. It is unclear for now if the compound, since it is a mix of buildings, can be considered LEED New Construction (NC) or Renovation. Clarification from GBCI is needed. Note, in DPP the compound was considered as one project for LEED.</p>
	<p>2. SS 4.2 Bicycle Storage & Changing Rooms: Discuss feasibility and location for an employee shower. Shower was assumed in the DPP LEED Matrix (SS 4.2) but was not shown in drawings in Room Data Sheets.</p>
	<p>3. SS 5.2 Maximize Open Space: Barn Project will be linked to campus-wide credits. Keep “maybe” for now, but probably “yes”.</p>
	<p>4. SS 6.1 & SS 6.2 Stormwater Design: Possibly “no” because of amount of green space being removed. The use of bioswale and permeable paving will help to balance out the amount of hardscape, but may have maintenance implications. Civil is not a part of DPP Update, so assumptions will need to be made.</p>
	<p>5. SS 7.1 Heat Island Effect—Non-Roof: Definitely “yes” because of amount of concrete (more concrete than asphalt is needed). Need SRI > 29 which is achievable.</p>
	<p>6. SS 7.2 Heat Island Effect—Roof: Pitched vs. flat roofs will affect the required SRI value.</p>

Workshop #1: Meeting Notes

ACTION BY:	ITEM:
	7. WE 3 Water Use Reduction: Likely “yes” for a target of 2 points. Assumptions include low flow fixtures, dual flush toilets, and pint urinals; low flow fixtures and Energy Star rated appliances will be used in Kitchen and Dining Support.
	8. Energy Performance: No CFCs will be used. Water cooled ice and other appliances could use chilled water from the campus-wide system. Need to check if this is the assumption in the DPP and consider for the Design Phases. (Unsure if the loads were considered in the DPP. If not, this will increase the overall chilled water requirement.) Need to verify.
	9. Title 24: The Barn Project will be linked to the campus-wide target, which is to outperform Title 24 by at least 20%. When possible, the project should strive to outperform the energy efficiency standard by 30%. WL advises that we use an energy model that works for both LEED and Title 24.
	10. MR 4 & MR 5 Recycled Content and Regional Materials: The Barn Project goal is 10% recycled content and regional materials. Certified wood is a possibility. Steel has the potential for up to 75% recycled content, and it is advised to identify the recycled potential for materials early on.
	11. MR 2 Construction Waste Management: The campus-wide policy is 95% recycled or salvaged construction waste, which targets 3 points.
	12. Environmental Quality: It is advised to build Construction Indoor Air Quality (IAQ) Management Plan (Before Occupancy) into the schedule early on.
	13. SS 4.1 Alternative Transportation Access: Still “yes” for 7 points. While losing the shuttle, two RTA bus lines are applicable.
	14. SS 4.4 Parking: “Yes” for 2 points, since no new spaces are being added to the site and existing service spaces are remaining.
	15. SS 4.3 Low-Emitting and Fuel-Efficient Vehicles: “Yes” for 3 points, by providing one dedicated space for fuel-efficient vehicles. Providing service spaces for Faculty/Staff Dining electric vehicles is a possibility.
WL	Action: WL will provide UCR Campus Baseline (still in development) to JH.
F&H	Action: F&H will provide an updated LEED checklist to WL for comments.

Workshop #1: Action Items

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

ISSUED: February 23, 2012

ACTION ITEM STATUS TABLE

PROJECT: DPP Update– UCR Barn Project

Jon Harvey (JH)	Principal Education Facilities Planner, Capital Resource Management
Cheryl Garner (CG)	Executive Director of Dining, Conference and Catering Services
David Henry (DH)	Director of Residential Dining
Scott Corrin (SC)	Fire Marshall
Weston Lewis (WL)	Office of Sustainability
Larry Lanier (LL)	Food Service Consultant, Laschober + Sovich
Adam Shalleck (AS)	Theater Consultant, The Shalleck Collaborative
Mike Brewer (MB)	Beverage Consultant, ABC Consulting Service
(F&H)	Fernau & Hartman Architects

The Action Item Status Table is meant to summarize the action items raised at the meeting(s) listed above and responsible party for each action item. If they differ from your recollection, please contact Fernau & Hartman immediately. Completed items are taken off the list after review by the PMT.

No.	WS Date	Action By	Issue, Notes & Comments	Status
1.01	02/03/12	CG	CG will send photos she presented (showing UCSD and other bar/dining character) to JH to distribute to everyone.	Completed 02/13/12
1.02	02/03/12	CG	CG will confirm with MB that club membership is only needed for the purchase of alcohol, and that the same club membership or a second type of membership is not required to enter the perimeter of the area licensed for alcohol consumption.	
1.03	02/03/12	F&H	F&H will confirm that a shade structure for the West Courtyard needs to have sprinklers if it is made from opaque fabric, even if it is retractable.	
1.04	02/03/12	AS	AS will further define the function of backstage spaces.	

Workshop #1: Action Items

Action Item Status Table

No.	WS Date	Action By	Issue, Notes & Comments	Status
1.05	02/03/12	F&H	F&H will verify square footage assumptions for the West Courtyard to be used to determine occupancy and plumbing fixture counts. (Direction provided was that planning will assume 3, 7, and 15 ASF per person for standing, seating, and table seating.)	
1.06	02/03/12	F&H	F&H will review costing of emergency fire systems and possible savings with Oppenheim Lewis Inc.	
1.07	02/03/12	F&H, SC	F&H to review with SC temporary fire protection for Barn Theater (in relation to discussion about phasing), once plan and schedule are developed.	
1.08	02/03/12	CG, DH	Dining Services will review operational issues and provide direction on ticket booth location. (The question was whether the East Courtyard and Coffee outlet would be open or closed to those not attending shows.) Will be reviewed within two weeks (by February 17, 2012).	
1.09	02/03/12	WL	WL will provide UCR LEED Campus Baseline (still in development) to JH.	Completed 2/06/12
1.10	02/03/12	F&H	F&H will provide an updated LEED checklist to WL for comments.	
1.11	02/03/12	F&H	F&H needs to get final sign-off from MB on Beverage Conference Call Notes of 01/17/12, and may want MB to provide quantitative risk diagnostics.	
1.12	02/03/12	F&H	F&H will discuss adjustments to Barn Kitchen with LL.	

Workshop #2: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480

fax 510.848-4532

Issued May 2, 2012

MEETING NOTES

Project Management Team Meeting #2

PROJECT: DPP Update– UCR Barn Project
TIME/DATE: 8:30 AM – 9:00 AM April 13, 2012
LOCATION: University Village, Capital Programs 210-16

ATTENDEES:

Project Management Team

Jon Harvey (JH)	Principal Education Facilities Planner, Capital Resource Management
Jacqueline Norman (JN)	Senior Project Manager, Architects & Engineers
Andy Plumley (AP)	Assistant Vice Chancellor, Housing, Dining & Residential Services
Susan Marshburn (SM)	Executive Director of Housing Services
Cheryl Garner (CG)	Executive Director of Dining, Conference and Catering Services
Yun Baird (YB)	Director of Capital Projects

Consultant Team

Laura Hartman (F&H)	Principal, Fernau & Hartman Architects
Richard Fernau (F&H)	Principal, Fernau & Hartman Architects
Laura Boutelle (F&H)	Project Manager, Fernau & Hartman Architects
Anastasia Yee (F&H)	Junior Designer, Fernau & Hartman Architects
Larry Lanier (LL)	Food Service Consultant, Laschober + Sovich

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

	1. Workshop #2 Goals: All information needed for the Cost Estimate will be finalized by the end of Workshop #2.
	2. General Progress Status: F&H has received clear direction from Scott Corrin (SC), Fire Marshall and Mike Brewer (MB), Alcoholic Beverage Consulting Service regarding fire exit and alcoholic beverage containment requirements. Housing and Dining has provided their decision of 460 people for the West Courtyard maximum capacity. Code analysis from Steve Winkel (SW), The Preview Group, has resulted in 11 additional fixtures for women’s WCs and 3 fire exits required for the maximum capacity of 460 people.
	3. Barn Theater: Impact of changes to the Barn Theater should be well noted in the DPP Update, including cost implications of relocating the ramp on the West side, gating at the Northwest corner, and other changes to the West and South entrances. Relationship of the Barn Theater to the adjacent academic programs will be studied operationally (AP).
	4. LEED: The following items were confirmed per LEED Checklist Review conference call with LH, JH, and Weston Lewis (WL) of 4/04/2012, and were noted as changes to the LEED Checklist to be made prior to the DPP Update Administrative Draft. <ul style="list-style-type: none"> a. A dedicated parking space for fuel-efficient vehicles will be used.

DPP Update—UCR Barn Expansion Project– Meeting Notes from Workshop #2, 4/13/2012

Final Notes – Issued May 2, 2012

Page 1 of 2

Workshop #2: Meeting Notes

ACTION BY:	ITEM:
	<ul style="list-style-type: none"> b. On-site renewable energy will include domestic hot water as an alternate. c. Enhanced commissioning will be included as an alternate. d. Misterters will not be used.
	<p>5. Cost Estimate: The goal of the Cost Estimate conference call will be to review with Scott Lewis (SL) all changes from the 2010 DPP based on the parameters finalized at Workshop #2. Date of the conference call is pending.</p>
	<p>6. DRB & CPAC: It is assumed that a CPAC meeting will be needed due to the addition of Faculty/Staff Dining. The need for a DRB meeting will be discussed. Dates for DRB and CPAC are pending.</p>

Workshop #2: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

Issued May 2, 2012

MEETING NOTES

Workshop #2: Charrette to finalize Site Plan & Comprehensive Space Plans and Prepare for Cost Estimate

PROJECT: DPP Update – UCR Barn Project
TIME/DATE: 9:00 AM – 4:15 PM, April 13, 2012
LOCATION: University Village, Capital Programs 210-16

ATTENDEES:

Project Management Team

Jon Harvey (JH)	Principal Education Facilities Planner, Capital Resource Management
Jacqueline Norman (JN)	Senior Project Manager, Architects & Engineers
Andy Plumley (AP)	Assistant Vice Chancellor, Housing, Dining & Residential Services
Susan Marshburn (SM)	Executive Director of Housing Services
Cheryl Garner (CG)	Executive Director of Dining, Conference and Catering Services
Yun Baird (YB)	Director of Capital Programs

Steering Committee

Andy Plumley (AP)	Assistant Vice Chancellor, Housing, Dining & Residential Services
Susan Marshburn (SM)	Executive Director of Housing Services
Cheryl Garner (CG)	Director of Dining, Catering and Catering Services
Yun Baird (YB)	Director of Capital Projects
David Henry (DH)	Director of Residential Dining
Albert Esqueda (AE)	General Manager for Retail Dining
Catalina Zavala (CZ)	Graduate Student Association
John Ganim (JG)	Physical Resources Committee

Campus Representatives

Scott Corrin (SC)	Fire Marshall
Weston Lewis (WL)	Office of Sustainability
Uma Ramasubramanian (UR)	Senior Facilities Planner

Consultant Team

Laura Hartman (F&H)	Principal, Fernau & Hartman Architects
Richard Fernau (F&H)	Principal, Fernau & Hartman Architects
Laura Boutelle (F&H)	Project Manager, Fernau & Hartman Architects
Anastasia Yee (F&H)	Junior Designer, Fernau & Hartman Architects
Larry Lanier (LL)	Food Service Consultant, Laschober + Sovich
Scott Lewis (SL)	Cost Estimator, Oppenheim Lewis (via conference call)

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

1. Drawings Presented:

Eight 24" x 36" prints were displayed, and shown as a digital presentation:

- Comprehensive Site Plan of 4/12/2012
- Comprehensive Space Plans for Barn Kitchen and Faculty/Staff Dining of 4/12/12
- Site, Barn Kitchen, and Faculty/Staff Dining Adjacency Diagrams of 4/12/2012

Workshop #2: Meeting Notes

ACTION BY:	ITEM:
	<ul style="list-style-type: none"> • Phasing & Implementation Diagrams of 4/05/2012 • West Courtyard Area & Seating Study (Diagrams 1 & 2) of 4/12/2012 • Updated Room Data Sheets from Barn Kitchen and Faculty/Staff Dining of 4/12/2012 were reviewed digitally. • Updated Project Area Summary of 4/12/2012 was reviewed as a handout to the committee. • Updated LEED Matrix of 4/11/2012 and System Narratives of 4/12/2012 were available digitally. • From 2010 DPP: Truck Turning Diagram, Utility Points of Connection. • 24" x 36" Site Plan sketch was drawn and presented during the Charrette.
	<p>2. Description of Goals: Complete the site plan and the comprehensive space plan, and necessary final input for cost estimating and production of the DPP Update.</p>
<p>F&H, SC</p>	<p>3. West Courtyard</p> <p>a. Event Capacity: AP confirmed that a maximum capacity of 460 people standing will be used for all code calculations. A factor of 7 SF/person for standing room is used. SC confirmed that he is comfortable with this direction, but wants to verify the calculations. Although the event capacity is 460, SC wants to planning to assume that the courtyard occupancy is 500. This will require three West Courtyard exits. Action: F&H will send SC the documents and calculations used to reach 460 people as maximum capacity. SC will confirm.</p> <p>b. Alcoholic Beverage Containment: The reconfigured West Courtyard seating diagram has been reviewed with Mike Brewer (MB). Per conference call with MB on 3/08/12 and follow-up call with LH and MB of 4/11/12: a permanent barrier such as a bench or planter is required for alcoholic beverage containment; a permeable barrier such as bollards or barrels is insufficient; a clearly defined entrance is needed, and the entrance can be a maximum of 10' - 0" wide. A narrower entrance may be desired operationally. F&H proposed a double-sided bench with approx. 3'-0" high back at the north edge of the shade structure; all agreed that this solution is desirable, as it allows attendees to look over the barrier to view the show and creates a secondary open space for the Barn Theater.</p> <p>c. Ticketed Event Containment: Event capacity of 460 people includes both areas licensed for alcohol and non-alcoholic areas. A 10' -0" wide path for egress will be maintained at all required exit aisles, and operations will maintain this clearance where there is no physical barrier (specifically at the Campus Walk North of the bench and throughout West Courtyard Circulation.)</p> <p>d. Seating Configurations & Storage: The goal is to maintain maximum available seating in the West Courtyard for day-to-day dining purposes, but to make the West Courtyard available for events either by storing all or some seats or by increasing the density of seats in the East Courtyard and/or Barn Stable Patio. The amount of required storage to remain as shown pending a decision on what type of furniture will be desired by Dining Services. It will be noted in the DPP Update that storage for West Courtyard tables and chairs was considered and will be further studied during Design. The total number of seats in the East Courtyard and West Courtyard have changed since the DPP, and the difference will be noted in the DPP Update.</p> <p>e. Fire Exiting: SC confirmed that three exits are required as previously noted above. These exits are needed to accommodate fluctuating densities of people, and SC is comfortable with these exits as shown (exits at Northwest, Southwest, and Northeast corners).</p>

Workshop #2: Meeting Notes

ACTION BY:	ITEM:
	<p>f. Southwest Corner Fire Exit: According to SC, an enclosed corridor with fire exit doors in the southwest corner of the West Courtyard is an unsafe and unacceptable exit, due to the danger of obstruction by carts. F&H agreed that an enclosed exit would be counterintuitive and confusing to event attendees during an emergency. Even with an enclosed corridor, in order to move from the Kitchen to Faculty/Staff Dining food carts would need to pass through the Loading Dock and would be exposed. According to LL, food can be wrapped and enclosed in carts safely for transport through a covered breezeway. All agree that the covered breezeway design will be used in the DPP Update, and that other options can be revisited during Design if needed.</p> <p>g. Emergency Systems: According to SC, CHASS has a generator that could possibly bear the additional load of the Barn Expansion Project, and this option should be considered instead of an inverter system. It will be noted in the DPP Update that the need for a generator for emergency systems will be investigated during Design.</p>
JH	<p>4. Overall Site and Other Deliverables</p> <p>a. Fire Exiting: As defined in the DPP, the East Courtyard has three exits and the Barn Stable has two exits. These remain sufficient. In the context of the overall campus, the Barn Expansion Project has five exits: directly East, North past CHASS, South out of the East Courtyard, Southwest out of the West Courtyard, and the 20'-0" wide turf block aisle for fire trucks to the Northwest. SC confirmed that he is comfortable with this direction.</p> <p>b. Plumbing Fixture Count: The maximum capacity of 460 people in the West Courtyard has increased the need for plumbing fixtures on site by eleven WCs for women. This will be accommodated in the East Courtyard women's restrooms. The women's restrooms will be divided from the East Courtyard men's restrooms to the South by a covered walkway that opens to the Barn Walk, aligning with the East-West campus axis; all agree that this configuration is desired and is promising in terms of landscaping and the feel of the entry. Investigation is needed to determine whether the existing sewer lines can support this plumbing fixture count. It will be noted in the DPP Update that sewer lines will be further studied in Design.</p> <p>Action: JH will contact Physical Plant to see if there is sufficient capacity in the sewer line to support the additional loads.</p> <p>c. Truck Turning: Truck Turning diagram as shown in the DPP remains sufficient.</p> <p>d. Utility Points of Connection: Utility Points of Connection diagram as shown in the DPP remains as previously identified. It will be noted in the DPP Update that a review of sewer capacity by physical plant will be needed prior to the start of design.</p> <p>e. Adjacency Diagrams for Site, Faculty/Staff Dining & Barn Dining/Kitchen: Adjacency Diagrams have been revised to include the Campus Walk, and will be updated to include the expanded restrooms.</p> <p>f. Systems Narratives: Systems Narratives were not reviewed. Updated Systems Narratives will be provided as part of the Preliminary Draft Report. The Architectural System Narrative will be expanded to include specific items to be addressed during Design.</p> <p>g. Project Area Summary: Basic Gross and Covered Outdoor will be rounded up to the next 10 SF.</p>
	<p>5. Loading Dock The site topography information received from UCR on 4/08/2012 will be used for the DPP Update; further study will happen during Design when a site</p>

Workshop #2: Meeting Notes

ACTION BY:	ITEM:
CG	<p>survey is available. The covered portion of the Loading Dock can be accessed by a short ramp for deliveries; the Loading Dock is covered with the exception of the covered compactor due to requirements for height clearance. Storage space is needed for a bin lifter, and can be accommodated in the Loading Dock, per LL. Action: CG will send F&H a cutsheet for UCR's bin lifter, so that its dimensions can be accommodated by a designated storage space on the Loading Dock.</p>
	<p>6. Faculty/Staff Dining a. Entry & Ramps: The Faculty/Staff Dining Facility will have an entry porch approached from the North accessible by a ramp. This entrance area is also the beginning of the ramp that provides access to the outdoor stage. It wraps around the Northeast corner of the Faculty/Staff Dining Facility behind a low wall. b. Dining Room: The Dining Room will have a 30" to 36" by 8'-0" buffet table, and the sketch produced during Workshop #2 provides more soft seating (replacing booths). A privacy wall, that might be casework up to about 8' – 0", will be incorporated into the Lobby. All agree that this configuration is desirable.</p>
CG	<p>7. Barn Dining/Kitchen Addition a. Janitor's Closets: A dedicated Janitor's closet is needed for each WC and must be sized to store the owner's cleaning unit. One janitor's closet has been included in the East Courtyard women's WC and one will be added near the Loading Dock to serve the West Courtyard WCs. Action: CG will send F&H a cutsheet for UCR's restroom cleaning unit, so that its dimensions can be accommodated in all janitor's closets.</p>
CG	<p>8. Room Data Sheets The following items were discussed with relation to the Room Data Sheets for Barn Dining/Kitchen Addition and Faculty/Staff Dining. Updated Room Data Sheets will be provided as part of the Preliminary Draft Report. a. Barn Kitchen Back of House Support: For Changing Room, Office, and all Kitchen Support related rooms, floors will be an anti-slip epoxy or Silikal instead of quarry tile or resin. Walls will have washable paint. Action: UCR will send its requirements for size and number of lockers for the Barn Dining Changing Rooms. b. Production & Manager's Office: Three workstations are needed. c. Changing Room: A mirror is needed. d. Indoor Stage: Reverse the orientation of the ramp to allow for exiting of the Green Room to lead directly to steps up to the stage. e. Barn Green Room: Lockers with locks will be used and a lockable safe is no longer needed. It was confirmed that the exterior door is desired. A door directly onto the stage is not needed. Hangers or a cloths hanging area is needed. f. BBQ: The POS will have a lockable cover. The hood and flue may not be needed and will be studied further during Design. g. Bussing: A bussing station is needed in the West Courtyard. h. Bar: The interior bar counter will extend to the room divider. If more taps are desired on the exterior bar, the two beer towers will remain with more taps per tower. i. Dry Storage: Four half-size lockers are needed for third party bar operator staff. j. Faculty/Staff Dining Back of House Support: A door in the corridor that divides Dishwashing from Bar Support spaces is no longer needed. A double door is needed at the entry on the Southeast corner to accommodate food carts. k. Outdoor Stage: It was confirmed that the stage will be concrete and when needed, a rental wood floor will be used for dance.</p> <p>9. Costing The following items were discussed with relation to upcoming costing as</p>

Workshop #2: Meeting Notes

ACTION BY:	ITEM:
	<p>specific points of note per SL.</p> <ul style="list-style-type: none"> a. Sitework: Sitework will include the East Courtyard, West Courtyard, and Campus Walk as separate elements. Trellises will be associated with sitework in order to avoid increasing the cost per SF of each building. F&H will send SL a graphic that diagrams sitework pieces. b. LEED: LEED Silver Certification is a minimum requirement. Enhanced commissioning and solar hot water should be alternates. c. Phasing: All work for the Barn Expansion Project will be done in Phase 1A (bringing utilities to site) & Phase 1B (relocation of Barn Stable, and renovation and addition for all buildings except for the Barn Theater). The Phase 1A & 1B boundary will include area North of the Barn Theater to facilitate the relocation of sprinkler risers. The Barn Theater Expansion will be done in Phase 2. d. Theater Scope: The Barn Theater relocation of the ramp on the West, relocation of sprinkler risers on the South, and exit from the North side will be included as additional line items. These will be further studied during Design. e. A/V & Security: The sound system at the West Courtyard will be part of the A/V package. Security alarming will be costed as a line item. Outdoor Stage Control will be costed with in-slab wiring. SL will get input from AS, Theater Consultant, regarding Outdoor Stage lighting allowance and in-slab conduit. f. Faculty/Staff Dining Facility Entry: Costing will reflect changes to the Northeast exterior of Faculty/Staff Dining that effect an increase of overhang, ramp (Outdoor Stage), and bench.
	<p>10. Schedule & Construction</p> <ul style="list-style-type: none"> a. Design is expected to start Summer of 2013. Closure for construction is expected January of 2015, opening in Fall of 2016 with construction completion date in 2016. b. Process will be Design-Bid-Build with a minimum of three to four prequalified contractors.

Workshop #2: Action Items

FERNAU & HARTMAN ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480

fax 510.848-4532

Issued May 2, 2012

ACTION ITEM STATUS TABLE

PROJECT: DPP Update– UCR Barn Project

Jon Harvey (JH)	Principal Education Facilities Planner, Capital Resource Management
Cheryl Garner (CG)	Executive Director of Dining, Conference and Catering Services
David Henry (DH)	Director of Residential Dining
Scott Corrin (SC)	Fire Marshall
Weston Lewis (WL)	Office of Sustainability
Larry Lanier (LL)	Food Service Consultant, Laschober + Sovich
Adam Shalleck (AS)	Theater Consultant, The Shalleck Collaborative
Mike Brewer (MB)	Beverage Consultant, ABC Consulting Service
(F&H)	Fernau & Hartman Architects

The Action Item Status Table is meant to summarize the action items raised at the meeting(s) listed above and responsible party for each action item. If they differ from your recollection, please contact Fernau & Hartman immediately. Completed items are taken off the list after review by the PMT.

No.	WS Date	Action By	Issue, Notes & Comments	Status
2.01	4/13/12	F&H, SC	F&H will send SC the documents and calculations used to reach 460 people as maximum capacity. SC will confirm.	Documents pending JH & KB Review
2.02	4/13/12	JH	JH will contact Physical Plant to see if there is sufficient capacity in the sewer line to support the additional loads of plumbing fixtures as confirmed at Workshop #2.	
2.03	4/13/12	CG	CG will send F&H a cutsheet for UCR's bin lifter, so that its dimensions can be accommodated by a designated storage space on the Loading Dock.	Completed
2.04	4/13/12	CG	CG will send F&H a cutsheet for UCR's restroom cleaning unit, so that its dimensions can be accommodated in all janitor's closets.	Completed
2.05	4/13/12	CG	UCR will send its requirements for size and number of lockers for the Barn Dining Changing Rooms.	Completed

Cost Conference Call: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

Issued: May 11, 2012

DPP Update – UCR Barn Expansion Project
Fernau & Hartman Architects, Inc.
2:00 PM – 4:00 PM, May 9, 2012
Cost Conference Call

Participants:

Jon Harvey	Principal Education Facilities Planner, Capital Resource Management
Andy Plumley	Assistant Vice Chancellor, Housing, Dining & Residential Services
Jacqueline Norman	Senior Project Manager, Architects & Engineers
Susan Marshburn	Executive Director of Housing Services
Yun Baird	Director of Capital Programs
Cheryl Garner	Executive Director of Dining, Conference and Catering Services
Laura Hartman	Principal, Fernau & Hartman Architects
Anastasia Yee	Junior Designer, Fernau & Hartman Architects
Scott Lewis	Cost Consultant, Oppenheim Lewis, Inc. (OLI)

Documents Reviewed: Preliminary Budget Estimate for the Barn Project, Revised May 5, 2012

Notes:

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

1) Summary

- a. All sections of the cost estimate have been updated from the point of view of scope, schedule, and pricing. The total increase is approximately \$4.3M, due to escalation, the replacement of KUCR with Faculty/Staff Dining, the increase in the East Courtyard Restrooms, and other various small changes.

2) Escalation

- a. Escalation accounts for half of the total cost increase.
- b. Raw cost escalation from 2010 to 2012 is updated, at approximately 6%. In addition, the estimate now includes the three year escalation rate from 2012 to 2015. The total escalation, which recognizes compounding, is about 16% or \$2.3M.
- c. Escalation occurs up to the midpoint of construction, or December of 2015.

Cost Conference Call: Meeting Notes

3) Program and Areas

- a. The Faculty/Staff Dining Facility is a larger building than the original KUCR building, resulting in a \$1.4M increase.
- b. The size increase of the East Courtyard Restrooms building results in a \$500,000 increase.
- c. There are no programmatic changes to any buildings other than the Faculty/Staff Dining and the Barn Kitchen. Some shifting of areas has occurred due to study and clarifications of the way areas are divided.
 - i. The Cottage has a slight increase in order to account for overhangs that were not previously included.
 - ii. The Barn Stable has a slight increase in restrooms as a result of code analysis performed in 2012.
 - iii. The East Courtyard Restrooms are now divided as a separate building instead of being part of the Barn.
- d. About \$500,000 - \$600,000 increase is due to the combined results of miscellaneous small changes, such as in sitework, utility routing, and the Barn Kitchen.

4) Sitework

- a. Sitework has a total increase of about 29%, or \$0.7M. All sitework occurs during Phase 1B.
- b. Some increase is due to changes to the gates and perimeter fencing.
- c. Trellisses are now included in sitework instead of as part of buildings. This results in shifting some cost to sitework and away from buildings, reducing the apparent cost per SF of some buildings.
- d. Some increase is due to the introduction of permeable pavers, which was noted in the Landscape Narrative in the DPP of 2010 but not previously accounted for. This paving system also benefits LEED targeting.
- e. Some sitework occurs at the Barn Theater due to ramps, entry, and fire exit issues.

5) Kitchen Equipment

- a. Bar equipment is provided as a build-out.
- b. All Kitchen Equipment cost quantities have been reviewed and approved by the food consultant.

6) LEED

- a. LEED Silver is accounted for.

Cost Conference Call: Meeting Notes

7) Phasing and Construction

- a. Phase 1A is utilities only; it includes picking up chilled water to the East of the site and transformer to the West of the site.
- b. The emergency generator, which covers the Faculty/Staff Dining Facility and the Barn Kitchen, is included in the alternates.

8) Next Steps

- a. Jon Harvey will review the Project Area Summary with F&H. F&H will then coordinate with OLI to ensure direct correlation between the Project Area Summary and the cost estimate.
- b. OLI will provide the assumptions for alternates.
- c. DPP Update Administrative Draft will be delivered the week of May 14, 2012.

Correspondence

INDEX OF CORRESPONDENCE - 2012

January 17, 2012	Beverage Conference Call (notes)	April 8, 2012	West Courtyard Event Seating, Occupancy and Barrier Questions (email and diagrams)
January 17, 2012	Faculty / Staff Dining Facility Pantry (email)	April 9, 2012	West Courtyard Occupancy Confirmation (email)
February 9, 2012	Indoor Dining Seating (email and images)	April 9, 2012	New Topography (email)
February 29, 2012	West Courtyard Seating Options (email and diagrams)	April 11, 2012	West Courtyard Areas for Beverage Consultant (email and diagram)
March 2, 2012	Ticket Booth (email)	April 13, 2012	Bathroom Cleaning Cart (email and cutsheet)
March 9, 2012	Beverage Campus Meeting - Revised (notes)	April 19, 2012	Courtyard Area study and Site Plan for Fire Marshal (email)
April 3, 2012	West Courtyard Occupancy and Tables (email, diagrams and chart)	April 15, 2012	Waste Caddy (email and cutsheet)
April 5, 2012	Courtyards Area Naming and Adjacencies (email)	April 30, 2012	Project Area Summary "Rounding" (email)
April 5, 2012	LEED Application Guide (email)	May 4, 2012	Changing Room Lockers (email and cutsheet)
		May 7, 2012	Barn Theater Entry Modifications for Cost (email)

Correspondence

FERNAU & HARTMAN • ARCHITECTS .INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

Notes from Conference Call Tuesday, January 17, 2012 from 1-2P

Purpose of Discussion: Obtain an understanding of the requirements and regulations associated with the proposed beverage service.

Participants:

Jon Harvey-Requestor
Kieron Brunelle
Andy Plumley
Susan Marshburn
Cheryl Garner
Yun Baird
Laura Hartman
Laura Boutelle
Mike Brewer-- Beverage Sub-Consultant

Summary Notes:

These are summary notes. If they differ from your recollection, please let us know immediately.

1. Alcoholic beverages will be sold by a third party. (CG)
2. UCR plans to get a full club license, with various tiers for membership. (e.g. Tier 1-- Faculty and Staff, Tier 2--Students, plus other tiers such as Tier 3--alumni, Tier 4-- General public, if follow rules for membership)
3. Alcoholic beverages will be served in the Bar. Bar is to open to the Beer Garden and to Faculty / Staff Dining (CG)
4. It may be a full bar. The bar will not serve food.
5. The plan is to license the entire complex. Alcoholic beverages can then be purchased in the Bar and consumed anywhere on the premises. Operationally, the areas for consumption may want to be controlled and may vary. (MB)
6. Flexibility is important. (AP)
7. Most of the alcoholic consumption will be in the West Court Yard, the Beer Garden, the Barn, and Faculty / Staff Dining. For special events there may be consumption in the Barn Stable.

CC W/ Beverage Consultant
January 17, 2012

page 1

8. If you have a club license you do not have to serve food. (MB)
9. It is ok to have under age students in a club area. (MB)
10. It is possible to get a catering permit, if there is a big event open to the public. (MB)
11. With a club license, the catering permit can only be used for events on the premises. (MB)
12. A member of the club can bring a guest.
13. Membership cannot be sold at the door. Needs to be a genuine membership, possibly could be purchased in advance on-line.
14. When selling alcohol, the big issues to be addressed will be: are you a member, are you 21, and are you not intoxicated.
15. The current relationship with the University Club is not a factor in the planning for this project, unless at some future date they decide to fund the Barn Stable. (AP)
16. You cannot have two club licenses in one area. (MB)
17. The ABC's requirements for containment include: a minimum barrier 3' high (the higher the better); as self contained as possible; and they will want a place where records are stored. Their primary fear is people leaving the premises with alcoholic beverages. The more contained the space, the more comfortable they will be.
18. The ABC's requirements do not address: storage or security.
19. The third party operator will have requirements / desires for how the alcohol is stored and how the Bar is locked up. Spaces needed for the third party operator include: the Bar, an office, storage, and possibly other spaces that will be discussed further. Will likely have different operating hours.
20. MB has not seen this done with students in a broad class of members.

CC W/ Beverage Consultant

page 2

Correspondence

From: Laura Hartman <lh@fernauhartman.com>
Date: January 17, 2012 4:48:03 PM PST
To: Larry Lanier <llanier@laschobersovich.com>
Cc: "ucr@fernauhartman.com" <ucr@fernauhartman.com>
Subject: Fwd: Barn Expansion - Pantry

Sent from my iPhone

Begin forwarded message:

From: Jon Harvey <jon.harvey@ucr.edu>
Date: January 17, 2012 4:23:10 PM PST
To: Laura Hartman <lh@fernauhartman.com>
Cc: Kieron Brunelle <kieron.brunelle@ucr.edu>
Subject: Barn Expansion - Pantry

Laura,

The proposed Faculty / Staff Dining Room facility will require a Pantry space per conversation. This is a new space that will serve multiple functions such as point-of-sales, bussing area, non-alcohol beverage services, dishes, setups, etc. Initial space requirement is 800 to 1,000 asf. Actual space needs will need to be determined as part of the overall process.

We were also informed that the service in the Faculty/Staff Dining room will use china, not disposables plates as currently planned for the Barn. This will require a dish room, which may or may not be included in the above space figure. Assume that Larry will be attending the workshop to provide direction as needed in these and other areas.

Thanks

Jon

Jon Harvey, AICP
 Principal Educational Facilities Planner

 Capital Resource Management
 951.827.6952 | jon.harvey@ucr.edu

APPENDIX

Correspondence

Begin forwarded message:

From: Cheryl Garner <cheryl.garner@ucr.edu>

Date: February 9, 2012 8:27:36 AM PST

To: "Laura Hartman (lh@fernauhartman.com)" <lh@fernauhartman.com>, Jon Harvey <jon.harvey@ucr.edu>

Cc: Yunsook Lee Baird <yun.baird@ucr.edu>

Subject: FW:

I am going to forward the pictures that I had at the meeting last week for your records.

Cheryl Garner
 Executive Director of Dining Services
 University of California, Riverside
 Office: (951) 827-5857
 Cell: (951) 333-4700

If you don't like change, you're going to like irrelevance a lot less.

Tom Feltenstein

-----Original Message-----

From: Cheryl Garner


Sent: Friday, February 03, 2012 6:45 AM

To: Cheryl Garner

Subject:



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_01_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_02_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_03_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_04_CG.jpeg

APPENDIX

Correspondence



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_05_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_06_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_09_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_10_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_07_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_08_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_11_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_12_CG.jpeg

APPENDIX

Correspondence



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_13_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_14_CG.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_15_CG.jpeg

APPENDIX

Correspondence

From: Jon Harvey <jon.harvey@ucr.edu>
Date: February 9, 2012 2:06:00 PM PST
To: Laura Boutelle <lb@fernauhartman.com>, Laura Hartman <lh@fernauhartman.com>
Subject: FW: USD Pictures - Faculty / Student Dining Area - Part 1

Laura, Laura,

FYI. Additional photos.

Jon



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_16_JH.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_17_JH.jpeg

From: David E Henry
Sent: Thursday, February 09, 2012 1:10 PM
To: Jon Harvey
Cc: Cheryl Garner; David E Henry
Subject: USD Pictures - Faculty / Student Dining Area - Part 1

Jon,

Here are the pictures of USD's combined faculty and student dining room that we referenced the other day during the Barn meeting.

Let me know if you any additional information.

Thanks

David Henry
 Director of Dining Services
 University of California, Riverside
 3637 Canyon Crest Drive | Suite F-101
 Riverside, CA 92507
 Office 1(951)827-1202
 Cell 1(951) 237-9997
David.Henry@UCR.edu



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_18_JH.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_19_JH.jpeg

APPENDIX

Correspondence



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_20_JH.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_21_JH.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_24_JH.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_25_JH.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_22_JH.jpeg



UCR DPP U_2012_0209_PRECEDENT_FacStaffDining UCSD_23_JH.jpeg

Correspondence

From: Laura Hartman <lh@fernauhartman.com>
 Subject: **UCR Barns**
 Date: February 29, 2012 5:48:36 PM PST
 To: Jonathan Harvey <jon.harvey@ucr.edu>
 Cc: ucr@fernauhartman.com, David Mar <david.mar@tippingmar.com>, Larry Lanier <llanier@laschobersovich.com>, Steve Winkel <swinkel@preview-group.com>, Adam Shalleck <adam@shalleck.com>, Tom Schindler <thomas.schindler@cmsalter.com>, Scott Lewis <scott@oppenheimlewis.com>, Mike Brewer <mike@calabc.com>
 2 Attachments, 8.4 MB

Jon,

Please find attached the draft materials due today for the DPP Update--see (1) below.

Also included in (2) is an overall site plan that can be used in upcoming meetings with Mike Brewer and the ABC, plus 4 alternative West Courtyard layouts for discussions with Housing and Dining. The restrooms numbers will vary a great deal depending on the option you select. We would like to get direction from you on the preferred option(s) before working further on the restrooms. We ask you to consider the following:

--the cost benefit of the number of people accommodated in the West Courtyard in relation to the cost of rest rooms.
 --the frequency of large events--if rare say 3x per year--then renting portable toilets may be less expensive
 --if large events happen more frequently --say 1x per month it may be worth the additional cost for more restrooms
 --note we have added 2 restrooms to the Faculty / Dining Facility, in anticipation of the certain need for some more restrooms that shown in the DPP
 --many more restrooms will need to be added to accommodate the higher occupancy numbers for the west Courtyard
 --we should keep the occupancy below 500 per our code consultant

Note--we are still waiting to hear back from UCR on the location of the ticketing booth and the gates on the east side of the compound. For now we have left this area as shown in the DPP.

Please review our materials carefully and call me if you have questions. Note that I will be away on Friday and Monday, so best to contact me tomorrow if you have questions on these documents prior to distributing them.

All the best, Laura

Attachments:

1. Draft Materials Issued 2/29/2012 in .zip
 - a. Updated Project Area Summary of 2/29/2012
 - b. LEED Matrix and Checklist of 2/29/2012 (updated with comments per Workshop #1)
 - c. Updated Room Data Sheets of 2/29/2012 for Faculty/Staff Dining and relevant Barn Dining
 - d. Updated Systems Narratives of 2/29/2012
2. West Courtyard Options Diagrams in .zip
 - a. Updated Site Plan of 2/29/2012 at 1/16" scale
 - b. 4 Seating Options for West Courtyard of 2/29/2012 as pdf (4 pages)



[2012_0229_....zip \(4.6 MB\)](#)




[2012_0229_....zip \(3.8 MB\)](#)

 Laura Hartman
 Fernau & Hartman Architects, Inc.
 ph. (510) 848-4480
 fx. (510) 848-4532
<http://www.fernauhartman.com>


APPENDIX

Correspondence



APPENDIX

Correspondence



Correspondence

On Mar 2, 2012, at 2:59 PM, Jon Harvey <jon.harvey@ucr.edu> wrote:

Laura,

As requested.

Jon

From: Cheryl Garner

Sent: Friday, March 02, 2012 10:16 AM

To: Jon Harvey; Yunsook Lee Baird

Cc: Susan Marshburn; Andy Plumley; David E Henry; Albert Esqueda;
David E Sakover

Subject: the Barn ticket booth

I met with my operators yesterday to discuss the ticket booth and operation of the new Barn during concerts. We would like to keep the ticket booth in the current location and feel that when there is a concert, the Barn should be closed to the general public. We will allow ticketed (paying) customers to enter the Barn to dine, but not those who have not been ticketed. We think this makes sense because what would keep a non-ticketed customer from going into the Barn and listening to the entertainment, plus the cost of security and the complexity of determining who was who. We have monitors inside the Barn so that ticketed customers can watch inside if they want to sit out a set or have a quiet spot to dine. I also think it will allow us to sell more tickets as it will increase the space for customers to watch. We are planning to leave the coffee house open to the general public, but that is something we can play by ear. If keeping the entire server open for concerts is cost prohibitive, we can open with a limited menu or even create a limited menu from the BBQ area outside. It is going to be a fun place!

I hope this helps.

Correspondence

Barn Expansion
 March 9, 2012
 Revised: April 11, 2012

Campus Meeting Notes

Meeting was called by Mike Brewer, consultant to Fernau & Hartman, to review Barn Expansion plans with Department of Alcoholic Beverage Control (ABC).

Participants: Cheryl Garner, Susan Marshburn, Andy Plumley, Yun Baird, Jon Harvey, Michael J. Brewer (Alcoholic Beverage Consulting Service), Kathleen Barnes (ABC), and Nick ?? (ABC)

1. Representatives from the Department of ABC were open to the idea of creating a club/entertainment venue at the Barn.
2. Key planning considerations are to identify areas that HDRS would like to be responsible for via the license, and limiting the license to only those areas.
3. Barriers are required to clearly identify areas where beer and wine can be consumed. They must provide some level of barrier to prevent people from just walking through them, and be approximately 3 feet tall. Opening through the barrier should be approximately 4-6 feet wide to keep the ABC comfortable.
4. One consideration is that the license would be for the Faculty/Staff Dining Room, West Courtyard, The Barn, East Courtyard, Cottage, and the Barn Stable. The campus walkway would not be included as part of the license. Another option would be to include the walkway in license. The latter would require entrance barriers on all campus entrances. Since the campus circulation through the space is not clearly defined, a request was made to review Campus circulation options.
5. The Campus walkway would be closed for West Courtyard concerts as previously discussed, but the area would be off-limits for alcohol consumption.
6. The Club license provides the ability to obtain a permit for non-campus events, and there is a limit to the number of permits one can get in a year. Although a specific number was not mentioned during the meeting (say 20), it appeared that these would be limited to a few per year. There would be no limit to the number of events held at the site for club members (students, faculty and staff) and their guests.

APPENDIX

Correspondence

From: Jon Harvey <jon.harvey@ucr.edu>
Date: April 9, 2012 12:03:02 PM PDT
To: Laura Hartman <lh@fernauhartman.com>
Subject: FW: Barn Expansion - West Courtyard Occupancy

Laura,

The West Courtyard occupancy limit is 460 as noted below.

The West Courtyard will be flexible, and setup options include standing only, and a combination of standing and seating. Thus the concept show a standing and sitting area would remain.

Please give me a call if you have any questions.

Thanks

Jon

From: Susan Marshburn
Sent: Monday, April 09, 2012 11:39 AM
To: Jon Harvey
Subject: Re: Barn Expansion - West Courtyard Occupancy

Great...thanks Jon.

Susan Marshburn
 Executive Director Housing Services
 Sent from my iPhone

On Apr 9, 2012, at 11:28 AM, "Jon Harvey" <jon.harvey@ucr.edu> wrote:

Susan,

Thanks for providing the occupancy counts for the West Courtyard. Per conversation, West Courtyard maximum occupancy will be 460 people.

High: standing 180, seated at tables 80 = 260

Occupancy counts were computed using the space factors provided by F&H shown on the diagram (code and recommended).

Direction on the West Courtyard occupancy figures is needed quickly (basically today) so the consultant team can prepare and provide advance materials to the committee prior to the workshop. Figures are also needed to determine restroom fixture counts.

I would be happy to review the above with you at your convenience.

Thanks

Jon


Jon Harvey, AICP
 Principal Educational Facilities Planner

Capital Resource Management
 951.827.6952 | jon.harvey@ucr.edu



APPENDIX

Correspondence



West Courtyard: 2,917 SF

If standing only: 5 SF per person = 583 people (limited to 499 people with 2 exits as shown here)

If seating only: 7 SF per person = 416 people

If table seating: 15 SF per person = 194 people (operationally recommend 20 SF per person = 145 people)

Stage Control: 81 SF (not included above)

West Courtyard Circulation: 2,444 SF unoccupied circulation and egress space.

TOTAL West Courtyard + Stage Control + Circulation: 5,442 SF

GROUND FLOOR PLAN - COURTYARD AREA DIAGRAM - 03/27/12
1/16" = 1' - 0"

APPENDIX

Correspondence

Barn Expansion

April 4, 2012

West Courtyard Seating Estimates

	Length	Width	Total	5 asf/ person	7 asf/ seat	15 asf/ station	20 asf/ station
West Courtyard Area Under Shade Structure	68	49	2,917	583	416	194	146
South Edge	68	12	816			54	41
South Edge with Circulation	60	12	720			48	36
East Edge	37	12	444			30	22
Total Edge Area and Seating			1,164			78	58
Side Areas that are not considered good seating			300				
Remaining Area and Seating			1,453	291	208		


Summary	Count
Standing	291
Seating	208
Stations (Tables & Chairs)	
Low	58
High	78

Total Occupancy Range	
Low	260
High	360

APPENDIX

Correspondence

Barn West Courtyard Seating Planning Assumptions



Correspondence

Begin forwarded message:

From: Weston Lewis <weston.lewis@ucr.edu>
Date: April 5, 2012 2:21:32 PM PDT
To: "lh@fernauhartman.com" <lh@fernauhartman.com>
Cc: John J Cook <john.cook@ucr.edu>, Jon Harvey <jon.harvey@ucr.edu>
Subject: UCR Barn LEED Follow-up

Hi Laura,

Since the Barn is comprised of multiple buildings, certification will follow the LEED [Application Guide for Multiple Building and On-Campus Building Projects](#) (AGMBC) Part 2 with reference to Group Project Certification. This will streamline the certification process. You can find an overview of this process in the attached file "LEED AGMBC Part 2". In the attached file "LEED AGMBC for NC" shows a breakdown of which credits are group credits and gives a description of the necessary documentation.

As you see in these documents, they mention campus credits as well. LEED allows you to take the group credit streamline approach and achieve credits campus wide. We should not concern ourselves with the campus credits for now. I'm working on a handful of campus credits that we could potentially use for this project if they are accepted by the LEED reviewers when we submit this summer, and should consider them a bonus not relying on them at this point.

Below I've identified credits out of the "LEED AGMBC for NC" document credits that are not eligible for streamlined group documentation and need to be documented at the building level. For the most part it is intuitive why documentation needs to be done for each building and not aggregated for these credits. The only one that I can see that would be redundant having documentation for each building is SSc4.1. For larger projects, buildings can be space out over great distances so some bldgs. might not have access to public transportation but for this project it shouldn't be a problem.

SSc4.1†	Alternative Transportation- Public Transportation Access
WEp1	Water Use Reduction
EAp3†	Fundamental Refrigerant Management
EAc3	Enhanced Commissioning
IEQp1	Minimum Indoor Air Quality Performance
IEQc1	Outdoor Air Delivery Monitoring
IEQc2	Increased Ventilation
IEQc3.2	Construction Indoor Air Quality Management Plan- Before Occupancy
IEQc6.2	Controllability of Systems- Thermal Comfort
EQc7.2	Thermal Comfort- Verification
IEQc8.1	Daylight and Views- Daylight
IEQc8.2	Daylight and Views- Views

With regards to MRC2 Construction Waste Management, it is a UCR priority to divert at least 95% or more of construction waste from the landfill (weight basis). This would also allow the project to get an innovation point. There are some strategies I would be happy to run through with you when the time comes.

Please let me know if you have any more questions or need any more info.

Thanks,
Weston

Weston Lewis, LEED AP O+M
LEED Analyst

Office of Sustainability
Direct: 708.202.8734 | Office: 951.827.6951
wlewis@ucr.edu | <http://sustainability.ucr.edu>

APPENDIX

Correspondence

From: Anastasia Yee <ay@fernauhartman.com>
Date: April 5, 2012 12:23:35 PM PDT
To: Jon Harvey <jon.harvey@ucr.edu>
Cc: ucr@fernauhartman.com
Subject: Re: UCR DPP U--West Courtyard Naming

Hi Jon,

Thanks for you questions. These multiple subdivisions are leftover from the 2010 DPP. They correspond to the numbers in the current Project Area Summary. We agree that they need to be simplified, and just wanted to get your input first before making these changes. See responses to your comments below in red.

I will make the proposed changes below and send along updated Adjacency Diagrams today.

Thanks,

Anastasia

 Anastasia Yee
 Fernau & Hartman Architects, Inc.
 (t) 510.848.4480
 (f) 510.848.4532
<http://www.fernauhartman.com>

On Apr 5, 2012, at 8:42 AM, Jon Harvey wrote:
 Anastasia,

I am confused with the materials provided. The Adjacency diagram identifies multiple areas in the west courtyard which do not appear on the site plan. Note that the total space seems greater than the available area. These area #s appear in the current Project Area Summary. Propose changing and simplifying these (in both the Adjacency diagram and the Project Area Summary) to correspond to the available area shown in the West Courtyard Area diagram.

Is the idea to sub-divide the west courtyard into a number of activity or functional areas? Let's simplify, as below.

Suggest keeping the area designations simple as in the East Courtyard. For example, Outdoor circulation, outdoor seating, etc. Propose the following simplification: OUTDOOR CIRCULATION = 2,444 SF. OUTDOOR DINING SEATING/GATHERING AREA = 2,917 SF.

Will the stage be part of the Faculty / Staff Dining or the West Courtyard? The Outdoor Stage will be part of Faculty / Staff Dining. Outdoor Stage also includes the Stage Control movable platform.

Assume the Dining/Stage bubble is actually the Barn or Indoor Dining / Stage. Yes, the Dining/Stage bubble represents the Indoor Dining/Stage. Propose change "DINING/STAGE" to "INDOOR DINING/STAGE" and small bubble "PERFORMANCE STAGE" to "INDOOR STAGE".

Will there be a single diagram that illustrates the big picture site relationship (i.e., Faculty / Staff Dining, West Courtyard, The Barn, Barn Kitchen, East Courtyard, Cottage, Barn Stable)? Yes, this is the Site Adjacency Diagram. Will send you the current version today.

Thanks

Jon

From: Anastasia Yee [<mailto:ay@fernauhartman.com>]
Sent: Wednesday, April 04, 2012 6:57 PM
To: Jon Harvey
Cc: Laura Hartman
Subject: UCR DPP U--West Courtyard Naming

Hi Jon,

Attached is the current Adjacency Diagram for Barn Dining/Kitchen Addition and again the Site Plan with West Courtyard seating areas diagrammed. Per your comments of 03/27 (Comments #40 + #41) there is confusion about how the West Courtyard areas are categorized. We need to look at how these areas should be named.

Please comment on the West Courtyard naming in the Site Adjacency Diagram, which I've circled in red on the PDF. We'll be sending the updated set of Adjacency Diagrams tomorrow based on your comments.

Thanks,

Anastasia

APPENDIX

Correspondence

From: Laura Hartman <lh@fernauhartman.com>
Date: April 8, 2012 9:33:51 PM PDT
To: Jonathan Harvey <jon.harvey@ucr.edu>
Cc: ucr@fernauhartman.com
Subject: UCR Barns: feedback on direction given on 4.6.12

Dear Jon,

Please find attached the "quick feedback" you requested from us on Friday--4.6.12.

We have attached two site plan / diagrams that show our investigations of the direction you have sent us. For comparison, Diagram #1 uses the layout and sf / person assumed prior to 4.6.12, with your proposed seating layout. Diagram #2 shows a revised layout that investigates the direction given on 4.6.12.

A summary of our response to the direction given and our current assumptions the main points follows--*in italics*. Note, however, that none of this has as yet been reviewed by our code consultant, who is not available until Tuesday to review these investigations.

1. Fire Marshall is considering / reviewing the need for a third exit. *We have shown that a third exit could be achieved in the NW corner with a revised ramp configuration.*
2. Fire Marshall would like to use the following space factors for computing occupancy counts: 7 SF standing; and 15 SF seated (*we assume this is row seating--please confirm*). *We have used these numbers, in Diagram #2, which differ from the UCB's Table 1004.1.1 for Assembly spaces, and they result in fewer occupants being possible.*
3. CRM to provide Fire Marshall with a diagram that shows Barn Theater exits and ramps. *We have shown the ramps and exits as contained in existing conditions drawing you sent to us on 1.17.10*
4. Goal is to have a space where 500 people can attend a show. *We are not able to achieve these numbers, based on the area available and the Fire Marshall's requirements.*
5. Proposed area for the audience would be the West Courtyard and Campus Walk. *We have included as much of the Campus Walk as possible, given that it also must be used for exiting.*
6. Retain 75 to 80 seats (tables and chairs) along perimeter of West Courtyard audience area as illustrated in the attached diagram. *Assuming that the Stage Control must be in place for shows, we are able to get 72 seats at the south and west perimeter. This is based on the "Seating Planning Assumptions" you provided on 4.3.12. (We want to confirm these are acceptable with our code consultant.)*

7. Remaining space in front of the stage would be a standing area. *Yes.*

8. Excess tables and chairs from West Courtyard could be moved to the Campus Walk for use during shows. Please note that this may not be feasible since the Campus Walk is an exit. The Fire Marshal will need to review this concept as well. *A portion of the Campus Walk could absorb excess tables and chairs, but to get closer to the desired number for shows, people will need will to be standing in that area.*

9. Some table and chair storage may be necessary (location and space requirement to be identified). *We have been able to get a storage space on the south side of the West Courtyard--see diagrams.*

10. Barrier for ABC does not need to be permanent. Separating the spaces where people can and cannot consume alcohol is an operational issue. Campus walk will not be part of the liquor license. *We are reviewing this with Mike Brewer, the Beverage Consultant, but do not yet have his feedback yet.*

11. Fire Marshall needs to verify Barn Theater exits and ramps when considering West Courtyard occupancy. *We anticipate some re-grading in the NW corner of the Campus Walk, that may result in being able to shorten the ramp on the west elevation of the Barn Theater in Phase 1.*

Now to address you three key questions from the Friday email:

1. Do you have any issues with the direction?

We have shown you in the attached diagrams that there are conflicts between the size of the West Courtyard and Campus Walk, the number of people desired to attend a show, and the space factors the Fire Marshall would like us to use.

2. Number of people that the West Courtyard can accommodate for an event.

Based on the direction given on 4.6.12: See Diagram #2 --72 at tables plus 313 standing in the West Courtyard and a portion of the Campus Walk = total of 385

3. Will F&H be ready for the workshop next Friday?

This will need further discussion with you. The Workshop could be a useful forum for a group discussion of the programmatic and physical consequences of the direction given, in order to reach resolution. It seems clear now, though, that the desired numbers for shows are not possible. If the discussion of that issue is an internal UCR issue--then it may be best to postpone the Workshop until resolution is reached by UCR.

APPENDIX

Correspondence

From: Jon Harvey <jon.harvey@ucr.edu>
Date: April 9, 2012 12:03:02 PM PDT
To: Laura Hartman <lh@fernauhartman.com>
Subject: FW: Barn Expansion - West Courtyard Occupancy

Laura,

The West Courtyard occupancy limit is 460 as noted below.

The West Courtyard will be flexible, and setup options include standing only, and a combination of standing and seating. Thus the concept show a standing and sitting area would remain.

Please give me a call if you have any questions.

Thanks

Jon

From: Susan Marshburn
Sent: Monday, April 09, 2012 11:39 AM
To: Jon Harvey
Subject: Re: Barn Expansion - West Courtyard Occupancy

Great...thanks Jon.

Susan Marshburn
 Executive Director Housing Services
 Sent from my iPhone

On Apr 9, 2012, at 11:28 AM, "Jon Harvey" <jon.harvey@ucr.edu> wrote:

Susan,

Thanks for providing the occupancy counts for the West Courtyard. Per conversation, West Courtyard maximum occupancy will be 460 people.

This assumes that no seating is provided, and the entire audience is standing. Space factor used is 7sf / person.

The information will be sent to FAHD to prepare for the last workshop which is scheduled for Friday. The goal of the workshop is to provide all information the consultant team requires to complete the DPP update.

Please let me know if you have any questions or concerns with the above.

Thanks

Jon

Jon Harvey, AICP
 Principal Educational Facilities Planner
 <image001.png>

Capital Resource Management
 951.827.6952 | jon.harvey@ucr.edu

Correspondence

From: Laura Hartman <lh@fernauhartman.com>
Date: April 11, 2012 11:34:17 AM PDT
To: Jonathan Harvey <jon.harvey@ucr.edu>
Cc: ucr@fernauhartman.com, Mike Brewer <mike@calabc.com>
Subject: UCR Barns: Comments fro Mike Brewer

Jon,

I just spoke with Mike Brewer, using the 2 attached diagrams for discussion.

Diagram #1 is much like the drawing shown to ABC at the site meeting. The barrier to Campus walk would need to be lengthened a bi to the east.

Diagram #2 is significantly different.

--ABC normally wants permanent partitions at the edge of licensed premises. Mike thinks the ABC will want a permanent barrier between Campus Walk and the West Courtyard. They will want the licensed premises clearly defined. Mike does not think movable partitions will work.

If flexibility is needed for operational purposes it could happen within the licensed premises.

--A permanent barrier such as fence or planter 3' high is acceptable. The access points should be narrowed to less than 10'. 4'-6' each would be fine, some negotiation might be needed to get to 10'. Widths need to be reviewed with the Fire marshal and code consultant as well.

--We can still have exits on the NE and NW corners of the West Courtyard on to Campus Walk.

--Mike says this could be explored further with the ABC, by showing them very specific proposals with substantial detail. But he notes that containment of alcohol on a college campus is always a very sensitive issue.


Please let me know if you have any questions. (Mike, please let me know if I have represented your views correctly.)

Best, Laura

Attached: 2012_0408 West Courtyard Seating Diagrams 1 & 2


APPENDIX

Correspondence



APPENDIX

Correspondence



Correspondence

From: Jon Harvey <jon.harvey@ucr.edu>
Date: April 13, 2012 12:37:14 PM PDT
To: Anastasia Yee <ay@fernauhartman.com>, Laura Hartman <lh@fernauhartman.com>
Subject: FW: Cutsheet for bathroom cleaning carts

Per meeting

From: Cheryl Garner
Sent: Friday, April 13, 2012 12:03 PM
To: Jon Harvey
Subject: Fwd: Cutsheet for bathroom cleaning carts

Sent from my iPhone

Begin forwarded message:

From: "Gustavo Plascencia" <gustavo.plascencia@ucr.edu>
To: "Cheryl Garner" <cheryl.garner@ucr.edu>
Subject: RE: Cutsheet for bathroom cleaning carts

Here's what I have. I think the \$999 special price was for a limited time only.

Thanks,

Gustavo

-----Original Message-----

From: Cheryl Garner
Sent: Friday, April 13, 2012 11:56 AM
To: Gustavo Plascencia
Subject: Cutsheet for bathroom cleaning carts

Can you send a cut sheet to me?

Sent from my iPhone

Ecolab Cleaning Caddy
 Touch-Free Restroom Cleaning

Smart Design

- Lock-and-key product dispensing
- Spray wand (90 PSI spray pressure) evenly distributes product
- Rechargeable battery lasts 4 hours on a single charge
- On-board tool storage
- Wet vacuum removes dirty solution for a complete clean

Easy to Use

- Easy-access tank holds up to 13.5 gallons of water
- Compact and easy to maneuver, similar footprint to mop and bucket
- Easy to use control panel simplifies operation

www.ecolab.com 1.800.35.CLEAN

Caddy + Wet Vacuum
 # 9205-1020

Caddy + Shelf
 # 9205-1021

Includes:

- On-board Wet Vacuum
- Professional Window Squeegee
- Hand Caddy
- Doorhairs (2)
- Dual Surface Deck Brush
- Charger
- Welcome Packet & Training Material

Includes:

- Storage Shelf
- Professional Window Squeegee
- Hand Caddy
- Doorhairs (2)
- Dual Surface Deck Brush
- Charger
- Welcome Packet & Training Material

Cleaning Caddy Accessories

ITEM NAME	DESCRIPTION	PICK CODE
Wet Vacuum		
WET VACUUM	10 gallon wet vacuum kit	9205-2106
WET VACUUM HEAD	Wet vacuum replacement head	9205-2107
WET VACUUM SQUEEGEE BLADE	Wet vacuum squeegee blade replacement kit	9205-2102
FIL-FILTRANT KIT	Wet vacuum filter replacements (qty. 3)	9205-2107
Cleaning Tools		
BROOM HANDLE-BLUE	Combo scrub brush & squeegee handle	60302-01-001*
COMBINATION SCRUB BRUSH/SQUEEGEE HEAD	Combo scrub brush & squeegee head	60334-01-001*
STEEL-SURFACE DECK BRUSH-BLUE	Replacement deck brush head	61803-01-001*
FIBERGLASS INTERLOCKING HANDLE-BLUE	Dual surface deck brush handle	61807-01-001*
ERGO TOILET BRUSH WITH HOLDER	Ergonomic toilet brush tool and holder	60779-01-001*
PROFESSIONAL WINDOW SQUEEGEE	14" window squeegee	60332-01-001*
WINDOW SQUEEGEE REPLACEMENT BLADE	Window squeegee replacement blade (qty. 3)	60332-10-001*
WORN SURFACE SQUEEGEE-BLUE	6.5" handle, 9" blade	30403-01-001*
Miscellaneous		
"DISINFECTED DAILY" STICKER-WHITE	White "Restroom Disinfected Daily" sticker (1 sheet of 6)	9205-2129
"DISINFECTED DAILY" STICKER-CLEAR	Clear "Restroom Disinfected Daily" sticker (1 sheet of 6)	9205-2130
DOORSTOP	Doorstop (qty. 1)	9205-2127
HAND CADDY	Hand caddy holds tools and up to 3 spray bottles	60205-12-001*
MOP SINK HOSE	6" hose	9480-2188

* Fleet Safety Specifications Products

APPENDIX

Correspondence

WasteCaddy Dumpster Mover

Prevents the physical strain and pain associated with pushing or pulling heavy dumpsters and trash containers to curb side for pickup by waste haulers.



Insert tube on the front of the WasteCaddy attaches to the bottom of the dumpster.




Custom receivers provided for quick and easy connection to containers.



WasteCaddy Dumpster Mover can easily pull heavy trash containers up inclines through snow and ice.

DJ PRODUCTS, INC.
1009 4th St. NW, Little Falls, MN 56345 • PH: 800-686-2651 • FAX: 320-632-3553 • www.djproducts.com

WasteCaddy Dumpster Mover



WasteCaddy Standard Features

- Tubular Steel Frame
- 1500 lb. Differential/Transaxle
- High Tech Speed Controller
- Neutral Throttle Braking
- Adjustable Acceleration/Braking
- 36v(3) 115 Amp Batteries
- Variable Speed Twist Grip
- 0-3 mph Forward/Reverse
- Non-Marking Tires
- Battery Discharge Indicator
- Automatic Charger

WasteCaddy Pricing & Options

WasteCaddy Dumpster Mover	
350 lbs Weight: For increased traction on inclines	
High Output Motor and Controller Package	
5th Wheel Arm	
Powder Coated Steel Insert Tube	
Safety Stop Switch and Guard Kit	
Foam Filled Tires (Set)	
	\$ 5,295
Available Options	
Safety Horn	\$ 95
Flashing Light and Pole	\$ 150
Maintenance-free Batteries (set of 3)	\$ 225
Onboard Charger	\$ 150
Dumpster Receiver (bolted or welded to dumpster)	\$ 40
Heavy Duty Package (includes larger motor/controller and more weight)	\$ 1000

These options are only recommendations. Please consult a Sales Engineer at DJ Products, Inc. for your specific application. Other options are available.

DJ PRODUCTS, INC.
1009 4th St. NW, Little Falls, MN 56345 • PH: 800-686-2651 • FAX: 320-632-3553 • www.djproducts.com

Correspondence

From: Anastasia Yee <ay@fernauhartman.com>
Subject: DPP U_Courtyard Area Study + Site Plan DWG - to Scott Corrin
Date: April 19, 2012 2:01:30 PM PDT
To: Jonathan Harvey <jon.harvey@ucr.edu>, kieron.brunelle@ucr.edu
Cc: ucr@fernauhartman.com
▶ 1 Attachment, 3.6 MB

Jon + Kieron,

Attached are 2 PDFs that can be printed to scale: West Courtyard Area Study of 04/18/12 at 11"x17" and Site Plan of 04/18/12 at 24"x36" showing the Courtyard Area Study in context, and DWG of the file per Scott Corrin's request.

Note that while some interior changes are still missing, the site has been updated per the end of Workshop #2 to suit Scott's purposes, with the area calculations for 7 SF/person standing room for the areas noted per the end of Workshop #2.




[2012_0418_...l.zip \(3.6 MB\)](#)

Anastasia Yee
Fernau & Hartman Architects, Inc.
(t) 510.848.4480
(f) 510.848.4532
<http://www.fernauhartman.com>

APPENDIX

Correspondence



Correspondence

From: Jon Harvey <jon.harvey@ucr.edu>
 Subject: **FW: Barn DPP Lockers**
 Date: May 4, 2012 11:49:16 AM PDT
 To: Anastasia Yee <ay@fernauhartman.com>
 Cc: Laura Hartman <lh@fernauhartman.com>

Anastasia,

As requested, locker sizes are noted below.

Thanks

Jon

From: Yunsook Lee Baird
Sent: Friday, May 04, 2012 11:27 AM
To: Jon Harvey; Yunsook Lee Baird
Cc: Cheryl Garner
Subject: Barn DPP Lockers

http://www.hallowell-list.com/lockers_prod_hdc.php

Jon,

Full time staff: 36" height lockers (full height of 72" with 2 lockers)
 Students: 18" height lockers (full height of 72" with 4 lockers)
 Please see the link above for specs.
 Thanks.

yun baird

Director Capital Projects
 UCR | HDRS | 3595 Canyon Crest Drive
 Phone: 951.827.7446 | ybaird@ucr.edu

5/5/12

Corridor Lockers by Hallowell - HDC Heavy-Duty Corridor Production Lockers

Hallowell | About | Contact | Tradeshows | QuickShip | Support Center | Installation Gallery

Main / Production Lockers / HD Corridor KD

Products

- Shelving
 - Hi-Tech
 - Standard Shelving
 - Antimicrobial
 - Bin Shelving
 - H-Post High Capacity
- Rivetwell
 - Standard
 - Black
 - DuraTech
- Safety Equipment
 - Portable Gates
 - Guardrail
 - Post Protectors
- Utility Carts
 - U-Boat
- Locking Cabinets
 - 800 Series
 - DuraTough
 - High Visibility
- Workbenches
 - Fort Knox
 - Hallowell Workbench
- Lockers
 - QuickShip Lockers
 - Production Lockers**
 - TA-50
 - Bulk Storage
 - Cubbies
 - Aquamax Plastic
 - Accessories
- Price Book

Heavy-Duty Corridor KD - Production Lockers

PRODUCTION ITEM Heavy-Duty Corridor KD Lockers (HDC)

Heavy-Duty Corridor lockers, commonly known as HDC lockers, are designed to include all the great features of our Standard KD wardrobe lockers with the doors upgraded to 14 gauge.

Features:

- **Body Construction:** Knock down with 24 gauge solid body components
- **Doors:** 14 gauge louvered doors are standard. Plain, Secure-Air-Flow, Safety-View and diamond perforated door styles are available
- **Frame:** 16 gauge frame with 16 gauge horizontal cross member between doors on double and triple tier wardrobe lockers
- **Handle:** Deep-drawn seamless stainless steel recessed handle
- **Door Strike:** Continuous vertical door strike at both hinge and latch side
- **Latching:** 12 gauge latch hooks MIG welded to frame. Gravitly lift-type multi-point spring loaded latching:
 - 3-point latching for openings 48" high and higher
 - 2-point latching for openings 20" high thru 36" high
- **Hinges:** 16 gauge continuous piano hinge
- **Hooks:** 2-single hooks and 1-double hook is standard. 1- double hook only for triple tier and 1-double and 1- single hook for 9" wide openings 30" and higher
- **Shelves:** Hat shelf for single tier openings 60" and 72" high
- **Notes:** All production KD lockers are supplied without legs unless otherwise specified
- **Warranty:** 2 Years

HDC KD Locker		Opening			
	Sizes	Width	Depth	Height	Frame Height
Wardrobe	Single Tier	9" 12" 15" 18" 24"	12" 15" 18" 21" 24"	36" 48" 60" 72"	36" 48" 60" 72"
	Double Tier	9" 12" 15" 18"	12" 15" 18" 21"	30" 36"	60" 72"
	Triple Tier	9" 12" 15" 18"	12" 15" 18" 21"	20" 24"	60" 72"
	Four Tier	12", 15"	12" 15" 18"	15", 18"	60" 72"
Box	Five Tier	12", 15"	12" 15" 18"	12", 14.4"	60" 72"
	Six Tier	12", 15"	12" 15" 18"	12"	72"
	Two Person	15", 18"	12" 15" 18"	N/A	60" 72"
Specialty	Duplex	15"	12" 15" 18"	60", 72"	60" 72"
	Sixteen Person	72"	18"	12"	78" (includes 6" legs)
	4 Wide wall mount	48"	18"	12"	14-3/4"

Copyright © 2012 Hallowell - All Rights Reserved | [employee login](#) | [distributor login](#) | [e-quote](#) | [site map](#)

Correspondence

From: Jon Harvey <jon.harvey@ucr.edu>
 Subject: **RE: Barn Theater - Existing Space**
 Date: May 7, 2012 4:31:22 PM PDT
 To: Anastasia Yee <ay@fernauhartman.com>
 Cc: Scott Lewis <scott@oppenheimlewis.com>, Laura Hartman <lh@fernauhartman.com>

Anastasia,

There needs a clear link between the Cost Estimate and the Project Area Summary per conversation. The Barn Theater program also remains constant since neither the original DPP nor the Update considers the Barn Theater.

The Proposed plan to address the above appears reasonable.

Thanks

Jon

From: Anastasia Yee [<mailto:ay@fernauhartman.com>]
Sent: Monday, May 07, 2012 4:25 PM
To: Jon Harvey
Cc: ucr@fernauhartman.com; Scott Lewis
Subject: Re: Barn Theater - Existing Space

Thanks Jon.

I assume you mean that the 1,651 GSF should be used in Scott's estimate for "Barn Theater Entry Modifications", and not as the GSF in the Project Area Summary.

I've attached the Barn Theater program that was shown in the DPP 2010. The GSF is 3,465 SF (i.e. 3,470 SF "rounded"). I assume you mean that we should still use this number for the Project Area Summary, omitting building overhang from the OGSF50 and OGSF100 calculations.

The current Theater size of 1,651 GSF would be noted as a footnote in the Project Area Summary.

Is this correct?

Thanks,

Anastasia

 Anastasia Yee
 Fernau & Hartman Architects, Inc.

2010 DPP

2010 - Participants

2010 - Meeting Notes, Action Items, and/or Site Plan Alternatives presented at:

Workshop #1	February 5, 2010
Workshop #2	February 26, 2010
KUCR Conference Call	March 10, 2010
Workshop #3	March 19, 2010
Performances Issues Conference Call	April 5, 2010
DRB Presentation	April 6, 2010
Workshop #4	April 16, 2010

2010 - Correspondence

Participants - 2010 DPP

UNIVERSITY OF CALIFORNIA, RIVERSIDE

PROJECT MANAGEMENT TEAM

Tim Ralston	Associate Vice Chancellor, Capital and Physical Planning
Kieron Brunelle	Director, Capital and Physical Planning
Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Don Caskey	Associate Vice Chancellor, Campus Architect
Richard Racicot	Assistant Vice Chancellor, Design and Construction
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Andy Plumley	Assistant Vice Chancellor, Housing, Dining and Residential Services
Susan L. Marshburn	Executive Director, Housing Services

STEERING COMMITTEE

Andy Plumley	Assistant Vice Chancellor, Housing, Dining and Residential Services
Susan L. Marshburn	Executive Director, Housing Services
Cheryl Garner	Executive Director, Dining Services
Nita Bullock	Director of Physical Planning, Campus Landscape Architect
Professor John Ganim	Academic Senate Physical Resources Planning Committee Representative
Nathan Ziadie	Associated Students of UCR (ASUCR) Representative

CAMPUS REPRESENTATIVES

Trish D. Thrasher	Office of Design and Construction
Kenyon Potter	Office of Design and Construction
Louis Vandenberg	KUCR General Manager
Robert Heath	University Club
Connie Young	University Club
Nathaniel Jones	Assistant Dean, CHASS
Paul Richardson	Arts Facilities Manager, CHASS
Tim Gable	Communications
Scott Corrin	Fire Marshal
Pat Simone	Assistant Director, Physical Plant
Pat Nugent	Physical Plant
Mike Terry	Physical Plant
Eric Shuler	Supervisor, Electrical Shop
Mike Delo	Transportation and Parking Services
Andy Stewart	Transportation and Parking Services
John Freese	UCR Police
Hassan Ghamlouch	Director of Housing Operations
Berent Pippert	Campus Space Manager, Capital and Physical Planning
Israel Fletes	Multimedia Technologies

Workshop #1: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

ISSUED: February 23, 2010

MEETING NOTES

Project Management Team Meeting #1

PROJECT: DPP – UCR Barn Project Phases 1 & 2
TIME/DATE: 8:30 AM – 9:00 AM, February 5, 2010
LOCATION: Capital and Physical Planning Offices

ATTENDEES:

Project Management Team

Don Caskey	Associate Vice Chancellor, Campus Architect
Kieron Brunelle	Director, Capital and Physical Planning
Richard Racicot	Assistant Vice Chancellor, Design and Construction
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Andy Plumley	Assistant Vice Chancellor, Housing, Dining and Residential Services
Susan Marshburn	Associate Director of Housing Services

Consultant Team

Richard Fernau	Design Principal, Fernau & Hartman Architects
Laura Hartman	Principal in Charge, Fernau & Hartman Architects
Jason Wilkinson	Project Manager, Fernau & Hartman Architects
Ron Lutsko	Landscape Architect, Lutsko Associates
Larry Lanier	Food Service Consultant, Laschober + Sovich

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

ACTION BY:	ITEM:
SM	<p>1. Differences between the Questionnaire Responses:</p> <p>a. The majority of the responses to the F&H questionnaire have indicated a request for additional square footage as compared to the 2009 Barn Area Study (BAS). The consultant team's role for the Workshop #1 Interviews is primarily to listen to input from building users, not to question square footage changes. That will be addressed by the PMT.</p> <p>b. Dining has identified new needs and is currently engaged in a Dining Study Report which is not yet complete, but will be sent to the Consultant Team when available.</p> <p>Action: Susan Marshburn will ask Dining Services to provide the draft Dining Study for the Barn, and once available the completed Dining Study report.</p>
	<p>2. "Barn Annex": There was a reminder that the building known as the "Barn Annex" should not be referred to as the University Club.</p>

Workshop #1: Meeting Notes

ACTION BY: ITEM:

JN	<p>3. Planning Studies:</p> <p>a. Historical Resources Inventory: There is an RFP out for an updated Historical Resources Inventory for the Barn Group. For now the Consultant Team will use the 1993 Historical Inventory Report that was prepared for construction of the Humanities Building. The target date for this study to be complete is February 26th to coincide with Workshop #2.</p> <p>Action: Jacqueline Norman will provide status on the report at the next meeting.</p>
JN	<p>b. Utility Survey: An underground scan of the site utilities will be done shortly. The original target date for this information is February 26th to coincide with Workshop #2. Confirmation of the schedule for completing this study is needed. In the meantime, any information regarding existing utilities will be sent to the Consultant Team. Mike Terry is the representative for the Physical Plant.</p> <p>Action: Jacqueline Norman will provide status of the utility surveys at the next meeting.</p>
	<p>4. Sproul Loading Dock: It was noted that the Consultant Team is reviewing the Sproul Loading Dock as part of their DPP contract, but it is not currently included in Phase 1 or 2.</p>

Workshop #1: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480

fax 510.848-4532

ISSUED: February 23, 2010

MEETING NOTES

Workshop #1: Program Review and Refinement; Site Plan Analysis; Establish Project Goals

PROJECT: DPP – UCR Barn Project Phases 1 & 2

TIME/DATE: 9:10 AM – 4:30 PM, February 5, 2010

LOCATION: Capital and Physical Planning Offices, Bannockburn, J-102

ATTENDEES:

Project Management Team

Don Caskey	Associate Vice Chancellor, Campus Architect
Kieron Brunelle	Director, Capital and Physical Planning
Richard Racicot	Assistant Vice Chancellor, Design and Construction
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Andy Plumley	Assistant Vice Chancellor, Housing, Dining and Residential Services
Susan Marshburn	Associate Director of Housing Services

Steering Committee

Andy Plumley	Assistant Vice Chancellor, Auxiliary Services
Susan Marshburn	Associate Director of Housing Services
Cheryl Garner	Director of Dining Services
Nita Bullock	Directory Physical Planning, Campus Landscape Architect
Professor John Ganmin	Faculty Representative, Academic Senate

Campus Representatives

Tim Gable	Communications
Scott Corrin	Campus Fire Marshal
Mike Terry	Physical Plant
Mike Delo	Transportation and Parking Services
Andy Steward	Transportation and Parking Services
John Freese	UCR Police
Suzanne Trotta	Services for Students with Disabilities
Louis Vandenberg	KUCR General Manager
Trish D. Thrasher	Office of Design and Construction
Connie Young	University Club
Paul Richardson	Arts Facilities Manager CHASS
Nathaniel Jones	Assistant Dean, CHASS
Berent Pippert	Campus Space Manager, Capital and Physical Planning
Israel Fletes	Multimedia Technologies

Consultant Team

Richard Fernau	Design Principal, Fernau & Hartman Architects
Laura Hartman	Principal in Charge, Fernau & Hartman Architects
Jason Wilkinson	Project Manager, Fernau & Hartman Architects
Ron Lutsko	Landscape Architect, Lutsko Associates
Larry Lanier	Food Service Consultant, Laschober + Sovich

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

Workshop #1: Meeting Notes

ACTION BY: ITEM:

	<p>1. Drawings Presented - Nine 24x36 boards: BAS Program Area Matrix Sheets for each building, BAS Site Analysis, Site Organization Options A, B and C.</p>
	<p>2. 2009 Barn Area Study: Nita Bullock made a presentation summarizing the 2009 Barn Area Study and provided suggestions for how the Consultant Team could use it as the foundation for the DPP. The study included discussions with multiple stakeholders and developed a master plan that will serve as a strong baseline for moving forward. Following the presentation it was noted that the proposed phasing of the project has changed since the 2009 BAS was completed. For the DPP, phasing is now proposed as follows: Phase 1 includes the Barn Annex, and KUCR; Phase 2 includes the Barn Dining, the Cottage, and the Barn Kitchen.</p>
	<p>3. Goal For Project: As defined by the BAS the goal for the Barn Project is to become a "Unique Dining and Entertainment Center."</p>
	<p>4. Additional Goals: To expand food service by about 3 times the current level and to expand entertainment to have a full schedule throughout the week.</p>
JN	<p>5. Historical Status: Per the 1993 Historical Resources Inventory, the buildings are not currently designated as having historic status, however the group of buildings as a whole has the potential at a local or regional level to have historical status as a campus cultural resource. There is currently an RFP to prepare an updated Historical Resources Inventory for the Barn Group. This study is needed as soon as possible to support the DPP process. In general the PMT and SC want to maintain the character of the existing buildings without the formality of a historical designation. Action: Jacqueline Norman will provide the Historical Resources Inventory report to F&H as soon as it is available.</p>
	<p>6. Landscape:</p> <ul style="list-style-type: none"> a. Clearance for Service and Fire Vehicles: 20'-0" wide by 13'-6" high b. Suggested Plant Types: Do not use Eucalyptus. Drought tolerant species are preferred. The Barn Project is part of a special agricultural planting area. Suggested plantings include: Citrus, Avocado, and herb gardens. Large canopy trees and arbors for shade are encouraged.
RR	<p>7. Fire Protection Issues: Interview with Campus Fire Marshal, Scott Corrin</p> <ul style="list-style-type: none"> a. Historical Status: If the buildings are not given historical status, there will be different restrictions for fire protection, design, and new construction in general. b. Fire Protection Systems: All buildings will need to have sprinklers and early fire alarm ADA notification systems. c. Bringing Project up to Current Code Requirements: There was some discussion about whether to consider the Barn Group as a single complex or as a collection of individual buildings, separated by "imaginary property lines." Further clarification / direction is needed. The project will use the most recent building codes. Action: Richard Racicot will review fire protection issues with Campus Fire Marshall and will report back to the Committee. d. Drawing Review: If the project is designated with historic status it will be reviewed by both the State Fire Marshall and local fire authorities. If the project is not designated with historic status it will be reviewed by just the State Fire

Workshop #1: Meeting Notes

ACTION BY: ITEM:

	<p>Marshall. If Alternate Means are requested then it will go to the local fire authorities for review, which could cause delays.</p> <p>e. Fire Truck Access: Scott Corrin considers the fire lane access along the Sproul Hall to be “existing non-conforming.” He also determined that a fire truck turnaround is not needed and in the event that a service turnaround is provided the fire truck will use it on an interim basis, until the fire lane through to the Carillion Mall is completed as part of a separate future project.</p>
<p>JH</p>	<p>8. Physical Plant: Interview with Physical Plant representatives, Mike Terry</p> <p>a. Truck Turnaround: A study is being conducted on the refuse trucks, which are the largest used in the Sproul Loading Dock, to determine if the vehicles will require a 48 foot radius (the City of Riverside Standard). Backing up the trucks to West Campus Drive presents safety concerns.</p> <p>Action: Jon Harvey will follow up with Mike Terry to obtain truck turning radius.</p> <p>b. Sproul Loading Dock: One consideration for the Loading Dock as proposed in the BAS is coordination with the existing infrastructure, including stand pipes, in this area. Fumes and noise in the tight space between the two buildings was also brought up as a concern. This could be managed by scheduling refuse pick ups earlier in the morning before classes start.</p> <p>c. Access: Access by unauthorized vehicles will continue to be restricted by the existing gate.</p> <p>d. Separations: For safety reasons the pedestrian area should be separated from the vehicular areas with a physical barrier. A landscape buffer is suggested in the BAS.</p> <p>e. Bicycles: The bicycle lane is currently grouped with the vehicle lane. This is not ideal. The separation of pedestrians from bikes and bikes from other vehicles at UCD was referred to as a possible model.</p>
	<p>9. KUCR: Interview with the General Manger of KUCR, Louis Vandenberg</p> <p>a. Introduction: Louis Vandenberg gave a brief introduction to the history, special issues and needs of KUCR.</p> <p>b. Significance: This will be the first UC that has built a facility especially to house a campus radio station.</p> <p>c. Concerns: Safety is a very important concern, especially with KUCR being moved to a building adjacent to outdoor entertainment venue where alcohol will be served.</p> <p>d. Stage: The stage will provide opportunities to air live interviews, full band performances and other lower scale events.</p> <p>e. Tower: KUCR would like to reuse the existing (original) tower, which has significance for the radio station’s history and is also the correct height for line of sight to the Box Spring Mountains. It is not possible to mount the tower on top of a building.</p> <p>f. Misc: The radio station will need a kitchenette (addition to the BAS).</p> <p>g. Archive: Making the archive visible while maintaining security is appealing. The archive is a “fantastic collection of very rare stuff.”</p> <p>h. New Building vs. Existing: Having KUCR in the Barn Area is the “best idea ever” for relocation. A new building would allow for easier customization to meet the current and future needs. The Barn Stable provides a connection to the “deep, long history of this place.” In either case the production studios should be located in a new building.</p>

Workshop #1: Meeting Notes

ACTION BY: ITEM:

	<p>10. Barn Annex: Interview with Dining and Food Services and University Club representatives: Andy Plumley, Susan Marshburn, Cheryl Garner, and Connie Young</p> <ul style="list-style-type: none"> a. University Club History: Connie Young provided a brief history and special considerations for the University Club. b. Partnership: The University Club will rent space in the Barn Annex from Dining and Food Services, and the University Club will continue to provide a liquor license. c. Liquor License: The University Club holds a liquor license which allows the Barn to serve Beer and Wine, and the Club area to have a full bar. d. Kitchen: The Annex will have a finishing kitchen only. e. Outdoor Area: A dedicated outdoor area for the Barn Annex is desirable. f. Interior Room Changes: Instead of a Banquet Room and separate Bar as proposed in the BAS, there will be one large room that should feel comfortable when only a portion is used. The bar will be able to open and close into this room with some type of moveable screen or shutters.
<p>LL</p> <p>JH</p>	<p>11. Barn Dining: Interview with Dining and Food Services representatives</p> <ul style="list-style-type: none"> a. Outdoor Spaces: A variety of spaces and seating is desired. The west courtyard will be the loud entertainment area, and the east will be the more formal dining area. Heaters and misters are also desirable. b. Food Service Concept: The food service concept was discussed at length. Larry Lanier will follow up with Cheryl Garner to better determine needs and possible solutions. Action: Larry Lanier will review and update food service program with Cheryl. c. Character: The Barn should have a different character than the HUB, which is identified as having “a more slick food court feel.” Overall the project should showcase the agricultural heritage of UCR through various means including a farmer’s market, and use of citrus and herb gardens. d. Seating (change from BAS): 188 outdoor seats, and 108 indoor seats are required. A variety of seating options including built-in to reduce the need to move furniture for events. e. Kitchen: The Barn will support catering and satellite operations. f. ADA: A recent draft ADA study for the Barn identified many issues of non-compliance including that the truss buttresses will require cane detectable barriers which will affect the look and seating capacity around the buttresses. ADA compliance will be carefully reviewed during the design phase. A final ADA Transition Plan for the existing Barn complex is being prepared; PMT will send to consultant team when completed. Action: Jon Harvey will send Barn Theater ADA Report to F&H, and once available, will provide final ADA Transition Plan.

Workshop #1: Meeting Notes

ACTION BY:	ITEM:
JH	<p>12. Barn Theater: Interview with CHASS representatives</p> <ul style="list-style-type: none"> a. General: The Barn Theater is not part of Phases 1 or 2 as there is no funding identified for this project. b. Rehearsal Space: CHASS would like to be able to join two rehearsal spaces into one. c. Stage: Sharing a stage is acceptable. d. Box Office: A box office for charging admissions for performances is desirable and could be shared with the Barn. e. Confirm Area Sizes: The PMT will confirm the space requirements of CHASS for the interior rehearsal space and storage. <p>Action: Jon Harvey will follow up with Nate Jones (CHASS), who will provide comments on the Barn Theater program presented in the BAS.</p>
	<p>13. Site Analysis: The Consultant Team gave a brief presentation of the issues and questions raised by the site plan as proposed in the BAS. Following this presentation Mike Delo from TAPs brought up the following issues:</p> <ul style="list-style-type: none"> a. Cross Walk: The cross walk linking Lot 4 to Barn Group is in a poor location, consider relocating as part of project. b. Bus Pull Out: An additional bus pull out is needed on the opposite side of West Campus Drive from the Barn. c. ADA Parking: Disabled parking by the Barn Group is a priority. d. Special Student Services: Need to maintain the existing 2 parking spaces for Special Student Services. e. Bike Parking: Location of the bike parking is another consideration. The LRDP and the Multi-Modal Transportation Management Analysis suggests bike corrals at the periphery of the Carillon Mall. One is proposed at the northwest corner of Sproul on the south side of the Mall walkway.
LH & SL	<p>14. Cost: Based on a very brief initial review of costs in the 2009 BAS, that was done by F&H in preparation for the interview, the budget seems tight. To meet the budget it is important to keep the buildings the same size or smaller than the BAS. The Consultant Team will review the preferred scheme in relation to the current budget.</p> <p>Action: Laura Hartman will review the 2009 BAS estimate with Scott Lewis (Cost Estimator) and provide comments on the current construction budget.</p>

Workshop #1: Action Items

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

ISSUED: February 23, 2010

ACTION ITEM STATUS TABLE

PROJECT: DPP – UCR Barn Project Phases 1 & 2

The Action Item Status Table is meant to summarize the action items raised at the meeting(s) listed above and responsible party for each action item. If they differ from your recollection, please contact Fernau & Hartman immediately.


No.	WS Date	Action By	Issue, Notes & Comments	Status
1.01	02/05/10	SM	PMT: Susan Marshburn will ask Dining Services to provide the draft Dining Study for the Barn, and once available the completed Dining Study report. 02/09/10 – spread sheet of draft Dining Study provided to F&H, completed Dining Study report still pending	
1.02	02/05/10	JN	PMT: Jacqueline Norman will provide the Historical Resources Inventory report to F&H as soon as it is available.	
1.03	02/05/10	JN	PMT: Jacqueline Norman will provide status of the utility surveys at the next meeting.	
1.04	02/05/10	RR	PMT: Richard Racicot will review fire protection issues with Campus Fire Marshall and will report back to the Committee.	
1.05	02/05/10	RR	PMT: Richard Racicot will investigate the cost of a site survey.	
1.06	02/05/10	JH	PMT: Jon Harvey will follow up with Mike Terry to obtain truck turning radius. 02/23/10. Information request sent 02-12-10 via email.	
1.07	02/05/10	LL	F&H: Larry Lanier will review and update food service program with Cheryl.	
1.08	02/05/10	JH	PMT: Jon Harvey will send Barn Theater ADA Report to F&H, and once available, will provide final ADA Transition Plan. 2/10/10 – Barn Theater report sent to F&H, final ADA Transition Plan is pending.	

Workshop #1: Action Items

No.	WS Date	Action By	Issue, Notes & Comments	Status
1.09	02/05/10	JH	PMT: Jon Harvey will follow up with Nate Jones (CHASS), who will provide comments on the Barn Theater program presented in the BAS. 02/17/10. Nate will provide comments no later than March 15.	
1.10	02/05/10	F&H: LH, SL	F&H: Laura Hartman will review the 2009 BAS estimate with Scott Lewis (Cost Estimator) and provide comments on the current construction budget.	
1.11	02/05/10	F&H	F&H will prepare a composite plan that addresses the site organization issues.	
1.12	02/05/10	JW	F&H: Jason Wilkinson will furnish a Project Area Summary with comparison table of preliminary program and the 2009 BAS. 02/18/10 – JW sent program area comparison summary	Complete
1.13	02/05/10	F&H	F&H: Jason Wilkinson will send out draft materials including a list of questions from the sub-consultants regarding building systems and sustainability, and the draft room data sheets. 02/12/10 – JW sent draft materials to JH. Per JH room data sheets will be distributed for comment once project spaces and allowances as shown in Project Area Summary are confirmed.	
1.14	02/05/10	JH	Jon Harvey will return comments and responses to the draft materials sent on 2/11. 02/17/10 – Sustainability and LEED issues will be discussed at WS-2. Balance of questions will be addressed by Subsurface Utility Investigation, and the Utility Services Connection Points review.	
1.15	02/05/10	RF	F&H: Richard Fernau will contact Louis Vandenberg to discuss options for housing KUCR in a new building. 02/16/10 – RF followed up with Louis by phone	Complete
1.16	02/05/10	JW	F&H: Jason Wilkinson will show the existing road as the basis for the site plans in the DPP. The future location of the road, as shown in the 2009 BAS, will be shown “dashed” in the DPP.	

APPENDIX

Workshop #1: Site Plan Alternatives



 **SITE ORGANIZATION - OPTION A**

DPP - UCR BARN PROJECT PHASES 1 & 2
WORKSHOP #1, 02/05/10
FERNAU & HARTMAN ARCHITECTS, INC

APPENDIX

Workshop #1: Site Plan Alternatives




SITE ORGANIZATION - OPTION B

DPP - UCR BARN PROJECT PHASES 1 & 2
WORKSHOP #1, 02/05/10
FERNAU & HARTMAN ARCHITECTS, INC

APPENDIX

Workshop #1: Site Plan Alternatives



SITE ORGANIZATION - OPTION C

DPP - UCR BARN PROJECT PHASES 1 & 2
WORKSHOP #1, 02/05/10
FERNAU & HARTMAN ARCHITECTS, INC

Workshop #2: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

ISSUED: March 15, 2010

MEETING NOTES

Project Management Team Meeting #2

PROJECT: DPP – UCR Barn Project Phases 1 & 2
TIME/DATE: 9:00 AM – 9:30 AM, February 26, 2010
LOCATION: Capital and Physical Planning Offices

ATTENDEES:

Project Management Team

Don Caskey	Associate Vice Chancellor, Campus Architect
Kieron Brunelle	Director, Capital and Physical Planning
Richard Racicot	Assistant Vice Chancellor, Design and Construction
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Andy Plumley	Assistant Vice Chancellor, Auxiliary Services
Susan Marshburn	Associate Director of Housing Services

Consultant Team

Laura Hartman	Principal in Charge, Fernau & Hartman Architects
Jason Wilkinson	Project Manager, Fernau & Hartman Architects
Bry Sarte	Civil Engineer, Sherwood Engineers
John Rozeluk	Mechanical /Electrical / Plumbing Engineers, Timmons Design Engineers
Larry Lanier	Food Service Consultant, Laschober + Sovich

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

ACTION BY:	ITEM:
	<p>1. Meeting Notes / Action Items</p> <ul style="list-style-type: none"> a. PMT to provide review of the meeting notes and action items within four days after receiving the draft from F&H. b. Action Items that are complete will be moved off the list of current Action Items List and kept as part of the record for future reference.
JN	<p>2. Review Studies:</p> <ul style="list-style-type: none"> a. Historical Resources Inventory (1.02): A firm has been selected to perform the Historical Resources Inventory for the Barn Group. A schedule for the completion of this work will be provided by the Jacqueline Norman once the contract is finalized. The scope of the work is limited to the historic review and does not include a review of the building condition as proposed by several RFP respondents.
JN	<ul style="list-style-type: none"> b. Utility Survey (1.03): An underground scan of the site utilities has been completed. The data is being transferred into a CAD format and will be reviewed by the Physical Plant. Jacqueline Norman will provide the completed underground utility survey drawings as soon they are available.

Workshop #2: Meeting Notes

ACTION BY: ITEM:

	<p>c. As-built Drawings: The only CAD format As-built Drawings for the Barn buildings are the existing floor plans prepared by Nakada for the BAS. Elevations, sections and other drawings will be needed as the project moves forward into Schematic Design. F&H to provide a fee for preparing As-built Drawings as part of the design phase. .</p> <p>d. Site Survey (1.05): Richard Racicot will review the cost of a site survey.</p> <p>e. Utility Connection Point Survey: A subsurface survey of the area between the Barn Group and the proposed utility connection point will be completed once it is determined which connection point the project will use.</p>
	<p>3. Project Area Summary:</p> <p>a. Barn Dining: Larry Lanier is concerned that the space allocation for interior seating at the Barn Dining is too tight on a SF per person basis. Susan Marshburn emphasized that the program must meet the seat count for the Barn Dining per the Dining Study. Andy Plumley suggested that the allocation be generous rather than tight. The issue will be discussed during the Workshop.</p>
	<p>4. Cost:</p> <p>a. Cost Estimate: Laura Hartman related that Scott Lewis the Cost Estimator was nervous with the BAS cost estimate and is more nervous after reviewing the Project Area Summary (comparing the Preliminary Program and BAS Program). Increasing the size of the Barn Dining was his main concern. The additional cost of a two-story building for KUCR and moving the Barn Stable is potentially offset by omitting the basement below the Barn Stable and adapting the historic building to the technological challenges of a radio station as proposed in the BAS.</p> <p>b. Cost and Increasing Areas: Increases to the areas from the BAS will most likely result in an increase in the project cost. Susan Marshburn suggested that the Kitchen Addition to the Barn Dining is the heart of the project if the project areas do increase it is where the growth should occur.</p>
	<p>5. LEED / Sustainability: Kenyon with the Office of Design and Construction will be present for the workshop to share his experience with LEED through his involvement in another UCR project that is currently seeking LEED Certification.</p>

Workshop #2: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480

fax 510.848-4532

ISSUED: March 15, 2010

MEETING NOTES

Workshop #2: Site Plan Options; Building Systems; Sustainability

PROJECT: DPP – UCR Barn Project Phases 1 & 2
TIME/DATE: 9:30 AM – 4:30 PM, February 26, 2010
LOCATION: Capital and Physical Planning Offices, Bannockburn, J-102

ATTENDEES:

Project Management Team

Don Caskey	Associate Vice Chancellor, Campus Architect
Kieron Brunelle	Director, Capital and Physical Planning
Richard Racicot	Assistant Vice Chancellor, Design and Construction
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Andy Plumley	Assistant Vice Chancellor, Auxiliary Services
Susan Marshburn	Associate Director of Housing Services

Steering Committee

Andy Plumley	Assistant Vice Chancellor, Auxiliary Services
Susan Marshburn	Associate Director of Housing Services
Cheryl Garner	Director of Dining Services
Nita Bullock	Director of Physical Planning, Campus Landscape Architect

Campus Representatives

Tim Gable	Communications
Pat Simone	Assistant Director, Physical Plant
Pat Nugent	Physical Plant
Mike Terry	Physical Plant
Eric Shuler	Supervisor, Electrical Shop
Hassan Ghamlouch	Director of Housing Operations
Louis Vandenberg	KUCR General Manager
Tricia D. Thrasher	Office of Design and Construction
Kenyon Potter	Office of Design and Construction
Nathan Ziadie	Associated Students of UCR (ASUCR)

Consultant Team

Laura Hartman	Principal in Charge, Fernau & Hartman Architects
Jason Wilkinson	Project Manager, Fernau & Hartman Architects
Ryan Metcalf	Junior Designer, Fernau & Hartman Architects
John Rozeluk	Mechanical Engineer, Timmons Design Engineers
Bry Sarte	Civil Engineer, Sherwood Design Engineers
Larry Lanier	Food Service Consultant, Laschober + Sovich

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

Workshop #2: Meeting Notes

ACTION BY: ITEM:

	<p>1. Drawings Presented: one 24"x36" board (Composite Site Organization Plan), in addition to boards presented previously at Workshop #1.</p>
<p>JH</p>	<p>2. Utilities: Representatives from UCR Physical Plant provided information regarding existing utilities.</p> <p>a. General Utility Issues</p> <ul style="list-style-type: none"> i. Building footprints need to be at least 5 feet away from center of utility lines. ii. Separate meters for buildings are proposed for leasing/billing purposes as well as for attaining LEED credits. iii. Jon Harvey to follow up with Physical Plant to provide draft building standards to Consultant Team. iv. Connections should be shared as much as possible to reduce trenching. <p>b. Electrical</p> <ul style="list-style-type: none"> i. Points of Connection <ul style="list-style-type: none"> • There are multiple options for electrical connections. Vault 3A (near West Campus Drive and Humanities) is proposed for all primary connections although Vault 4A (west of Sproul Hall) would also suffice and is less congested. A benefit of Vault 3A is that it is located in a grass area. • Copper piping is preferred; no aluminum. • AV switching mechanism to be placed outside the vault. • Replace the existing transformer and 800 amp service with a new service to handle full complex. • Abandon the existing conduit and consider reuse for data/telecommunications. ii. Cottage <ul style="list-style-type: none"> • Run from Vault 13 to Vault 14 is currently empty. • Two vaults exist near the proposed Cottage location; one is for telecommunications and the other is empty. The Cottage may have to shift to the north to avoid several utility lines. • The new footing of the relocated Cottage can be directly adjacent to a vault. If a new vault is needed it should be concrete. iii. KUCR <ul style="list-style-type: none"> • There is an existing duct bank at the proposed KUCR location. Recommendation from Physical Plant is that service for KUCR and Barn Theater comes from west of existing Barn Stable. The new building footings can span over the existing electrical line, but plans and construction must protect conduits in place..
<p>F&H</p>	<ul style="list-style-type: none"> c. Water / Sewer: 110 psi soft, hot water service to Kitchen Addition proposed. <ul style="list-style-type: none"> i. Points of Connection: Multiple lateral connections are preferred to a single tap. Manhole proposed at location of incoming supply. ii. Reroute 12" Line at KUCR: The existing 12" water line that runs north/south to the west of the Barn Stable will need to be rerouted further west to accommodate the KUCR addition. The footings of the KUCR addition should not be placed over this water supply. iii. Sproul Loading Dock: The truck turnaround at Sproul loading dock may impact sewer or water lines. F&H will review Sproul loading dock for impact on utilities. d. Steam + Chilled Water <ul style="list-style-type: none"> i. A central plant at UCR provides steam and chilled water throughout

Workshop #2: Meeting Notes

ACTION BY:	ITEM:
JN	<p>Campus. Connecting to this system at vault 15 (south of Sproul Hall) is proposed for the Barn Project.</p> <ul style="list-style-type: none"> ii. No PVC to be used; only steel. iii. 3-way bypass valves (per campus standard) to be used (Physical Plant to provide standards). iv. Minimum of 60°F return water temperature for chilled water. v. BTU meters provided on steam and chilled water. <p>e. Gas: Gas is provided by Southern California Gas.</p> <p>f. Storm Water</p> <ul style="list-style-type: none"> i. Policy: The DPP recommended approach to storm water management will be tailored to fit Campus standards. Jacqueline Norman to follow-up with Tricia Thrasher for information regarding the campus-wide storm water policy. ii. Approach: Careful management of storm water can respond to the agrarian nature of the buildings. Bioswales, rainwater harvesting, and fossil filters are options for retention and treatment of storm water. <ul style="list-style-type: none"> • Points of Connection: Multiple points of connection are available. Currently, a 12" drain runs N-S through the drive to the east of the site while a 24" line runs E-W to the south of the site (just outside Kitchen Addition and Barn Dining). <p>g. Telecommunications: The Barn Area contains 2 conduit runs; the current feed on the south side of Barn Dining and an existing duct bank on the west side, from which the new KUCR building and Barn Annex should be fed. The two manholes near the proposed location for the Cottage will likely serve as the connection point for the project.</p>
JH	<p>3. Additional Items</p> <ul style="list-style-type: none"> a. Building Envelope: Improvements to be made to improve energy performance, including improved daylighting, structure, and insulation. b. Historical Character: Completion of the historical report is important for understanding possibilities for design changes. c. Tree of Concern: Existing legacy tree on site (an English walnut grafted to a black walnut) is relevant to the history of the UCR campus; would be great to preserve the tree. Mike Terry via Jon Harvey will verify the location of tree trunk.
RR	<ul style="list-style-type: none"> d. Paving: Office of Design and Construction is currently in the process of developing standards for the use of interlocking pavers. Richard Racicot to provide a copy of the standards when available.
	<p>4. LEED / Overview of Sustainability Strategies</p> <ul style="list-style-type: none"> a. Project is mandated to achieve LEED Silver Certification minimum. Project will be certified as a single project. b. Desire for simple sustainable systems. Low-tech, passive, cost-effective systems are seen as most beneficial (well-designed daylighting, use of campus chilled water and steam system, etc.) c. There is an opportunity for the project to be a pilot project as presented in the Draft UCR Sustainability Action Plan and serve as an education tool. The project will emphasize cost-effective sustainable strategies while illustrating a campus-wide dedication to sustainable practices. It is important to continue a careful assessment of short- and long-term costs involving both first costs and maintenance costs.

Workshop #2: Meeting Notes

ACTION BY:	ITEM:
	<p>5. HVAC</p> <ul style="list-style-type: none"> a. Systems <ul style="list-style-type: none"> i. Passive systems are preferred (passive solar, campus-wide steam and chilled water, insulation, possible solar water heating, kitchen heat reclaim, etc.). The project should tap into existing campus-wide efforts whenever/wherever possible. ii. Sustainable systems to be weaved into all parts of the project, both existing and new. b. Thermal Comfort <ul style="list-style-type: none"> i. For certain areas of the program, setting a wider range of occupants' thermal comfort will improve efficiency. However in the kitchen and other food preparation areas increased temperature fluctuations are not tolerable. ii. Improved air circulation, large ceiling fans, radiant floor heating/cooling, and zoning are all approaches that will improve the performance of the buildings. iii. Due to the varied use of the spaces (some spaces will host both small groups and large gatherings), the buildings will need to respond quickly and efficiently to abrupt changes in heating/cooling demands.
<p>F&H</p>	<p>6. Structural</p> <ul style="list-style-type: none"> a. Durability and seismic resistance are part of sustainability. b. An assessment of the structural impact and extent of the dry rot at the existing buildings will be completed during Schematic Design. c. KUCR: For new construction, wood frame is most cost effective. Steel studs and block construction are also options. d. Cottage: Moving the Cottage offers the opportunity to address dry rot at the base. By putting the crawl space below grade, it becomes possible to reduce the amount of ramps required for access. e. Cottage + Barn Annex: F&H will investigate the different approaches to moving buildings. f. Barn Dining: There may be missing canted beams. The proposed layout lends itself nicely to introducing shear walls at the north and south ends of the building.
	<p>7. Composite Site Plan</p> <ul style="list-style-type: none"> a. General Issues <ul style="list-style-type: none"> i. Cottage: May need to move to the north to avoid existing utilities. A ramp up to the front entrance/porch rather than around to the rear entrance as shown in BAS may be preferable. ii. Barn Annex: Will act to buffer the associated outdoor terrace from the Sproul loading dock to the east. Also, incorporation of a trellis or low walls around the terrace will help to create an enclosed, yet open space for gathering. The existing Barn Annex sliding doors will provide a strong indoor / outdoor connection as well as ample daylight. ("Think wedding" – CG) iii. Barn Dining: Space is open to both courtyards (east and west). iv. KUCR: Current design has the KUCR building as two-stories, with different options for stacking. Questions on adjacencies still remain. The placement

Workshop #2: Meeting Notes

ACTION BY:	ITEM:
F&H	<p>of KUCR and the orientation of its entrance make it a visible destination from the north. A next step is for KUCR to provide input on program adjacencies.</p>
F&H	<p>v. Performance Courtyard: Need to further address acoustical concerns and stage/equipment layout. F&H to obtain a proposal for a quick review by the team's theater consultant (Landry & Bogan).</p>
F&H	<p>vi. Ticket Office: This newly proposed space should be included in the project program. It could be stand-alone or could potentially function as a permanent space attached to another building (not attached to Barn Theater). F&H to add the Ticket Office to Project Area Summary.</p>
F&H	<p>vii. F&H to produce overlay sketches on site plan: how "stuff" can be moved and site security.</p>
F&H	<p>viii. F&H to roughly determine the latitude and longitude of proposed location of KUCR radio tower using Google Earth for understanding any conflicts with line of sight to the Box Spring Mountains.</p>
	<p>ix. Jon Harvey will examine options to provide approximate tree locations in a timely manner (as part of 3.c. above).</p>
	<p>b. Security</p>
	<p>i. In order to maintain a strong connection to Campus, The Barn Area should feel open to pedestrian circulation. However it needs to be able to be fully enclosed at times due to security concerns and for alcohol containment. Gates between buildings and location of fencing will be studied by F&H (Action Item 7.a.vii).</p>
	<p>ii. The backstage area for the outdoor stage (currently proposed as a part of the KUCR building) needs to function separately from the radio station. Different groups, many of which are not connected to KUCR, will be using this space to prepare for performances and should not have access to the rest of the building. Clarification on this issue from LV and theater consultant is needed.</p>
AP	<p>c. Liquor License: Currently, the University Club holds an ABC license, which it extends to Barn Dining. Physically removing the University Club from Barn Dining complicates this relationship, as alcohol service must be contained within the space occupied by the license-holding body. Andy Plumley to obtain additional information to determine whether the license can be modified, fencing options, or if a new ABC license for Barn Dining is required.</p>
	<p>d. Access / Circulation</p>
F&H	<p>i. KUCR needs space for a loading dock. F&H to study KUCR loading dock south of KUCR near Barn Dining loading dock.</p>
CG	<p>ii. Bussing trash and dishes around the site remains an issue.</p>
	<ul style="list-style-type: none"> • Trash: Need to make sure there is adequate space for trash bins throughout the site. Cheryl Garner will determine if a compactor is needed West of Kitchen Addition.
	<ul style="list-style-type: none"> • A three foot wide sidewalk along the South side of Barn Dining is needed to transport materials from East courtyard and provide a connection between the Cottage and Barn Dining.
CG	<ul style="list-style-type: none"> • Bussing dishes: Cheryl Garner to determine if Dining will use permanent or disposable dishware. If permanent dishware is chosen, it will be difficult to transport dishes to/from the dishwashing station in Kitchen Addition. Dishes will be coming from Barn Dining as well as from Cottage and Barn Annex, making transportation difficult. Also, a bussing station along the path to the East of the site may be needed to

Workshop #2: Meeting Notes

ACTION BY:	ITEM:
F&H, SL	<p>b. Dining Services</p> <p>i. Issues</p> <ul style="list-style-type: none"> • Since the BAS, Dining has brought in a master planning group to look at the feasibility of the project; some concerns remain. • The proposed program has 1,323 GSF more than 2009 BAS. Current drawings are based on footprints from BAS. • In order to determine order of magnitude costs increase it is necessary to determine the cost per square foot. F&H and Cost Estimator, Scott Lewis, to determine the order of magnitude cost increase for the increase to the building program. <p>ii. Kitchen Addition</p> <ul style="list-style-type: none"> • Current Concerns: <ul style="list-style-type: none"> ○ At least two offices will be needed ○ Restrooms inside Kitchen Addition can be eliminated, but a changing room will be needed in their place. An additional office may also occupy some of the space formerly assigned to the restrooms. <ul style="list-style-type: none"> ▪ Proposed restrooms at Northwest corner of Kitchen Addition will suffice for employees. A “dog trot” configuration, or two rooms on either side of a open hall, will be studied ○ Dry storage has been reduced; space will be tight. ○ More space is needed for hot food preparation / grill. ○ Cheryl Garner proposed that the bar pop out into the West Courtyard in an effort to provide more square footage for food preparation. If sufficient space cannot be gained from this move, Kitchen Addition may need to be widened. <ul style="list-style-type: none"> ▪ The form of these possible additions/shifts needs to be studied. ▪ Bar still needs to serve both inside and outside and should be able to be staffed by one person. ○ One concern is that there is currently no area for catering equipment storage. This are will be for storing chafing dishes and mobile carts
F&H	<p>iii. Barn Dining</p> <ul style="list-style-type: none"> • Current Concerns: <ul style="list-style-type: none"> ○ Lack of seated dining space within Barn Dining. <ul style="list-style-type: none"> ▪ May need to decrease the size of the interior stage or make part of it removable to accommodate additional seating. ▪ Servery queuing could possibly begin outside Barn Dining rather than upon entering Servery. ▪ Kitchen Addition could possibly extend to the west. F&H to review truck turning at Barn Dining Loading Dock. ▪ Additional outdoor seating may be added to west and east of Barn Dining (Laura Hartman’s proposed porch-like seating scheme). <p>iv. Barn Annex: Bar can be reduced to 100 sf. It will require counter space for a bartender and storage for all bar needs. Currently, there is no storage space for tables and chairs. This space will need to be 250 sf.</p>
	<p>9. Next Steps</p> <p>a. Utilities – There are several options for utility connections that need to be studied. The final underground utility survey will aid in understanding the utility options.</p> <p>b. Historical Survey – The Historical Resources Survey that is being prepared will help determine design flexibility for the existing structures.</p>

Workshop #2: Meeting Notes

ACTION BY:

ITEM:

- c. **LEED / Sustainability** – There is a need for further review of the sustainability goals as they relate to the budget, the requirement for LEED Silver Certification and Campus-wide sustainability efforts.
- d. **HVAC and Thermal Comfort** – In general the project should use passive systems for heating and cooling. However there is a need for certain spaces, such as the Kitchen, to maintain a tight range of thermal comfort, in which case more intensive mechanical systems may be necessary.
- e. **Structural** – There is a need for a better understanding of the options for seismic resistance and how the Barn Annex and Cottage could be moved.
- f. **Site Plan** –
 - i. **The Cottage may need to shift from its proposed location to avoid utilities.**
 - ii. **Security** – Security will need to be studied in relation to the desire to maintain a connection to open feeling campus.
 - iii. How “stuff” is moved around the site needs to be studied.
 - iv. Input from the Theater consultant is needed to address various programmatic questions about the indoor and outdoor stage.
- g. **Cost** – The Cost Consultant will provide information about the order of magnitude cost increase related to increasing the program areas.
- h. **KUCR** – Many questions remain about the needs of KUCR. A discussion with the Acoustical Consultant is needed to help understand the KUCR program.
- i. **Barn Dining** –Barn Dining will be studied by Cheryl Garner and Larry Lanier to address concerns about Kitchen space allocation and layout, and sufficient space for interior seating.
- j. **Implementation and Phasing** will be discussed in detail at Workshop #3.
- k. **See also attached Action Items List**

Workshop #2: Action Items

FERNAU & HARTMAN • ARCHITECTS, INC.
 2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
 fax 510.848-4532

ISSUED: March 16, 2010

ACTION ITEM STATUS TABLE

PROJECT: DPP – UCR Barn Project Phases 1 & 2

The Action Item Status Table is meant to summarize the action items raised at the meeting(s) listed above and responsible party for each action item. If they differ from your recollection, please contact Fernau & Hartman immediately. Completed items are taken off the list after review by the PMT.

No.	WS Date	Action By	Issue, Notes & Comments	Status
1.01	02/05/10	SM	PMT: Susan Marshburn will ask Dining Services to provide the draft Dining Study for the Barn, and once available the completed Dining Study report. 2/09/10 – spread sheet of draft Dining Study provided to F&H, completed Dining Study report still pending	
1.02	02/05/10	JN	PMT: Jacqueline Norman will provide the Historical Resources Inventory report to F&H as soon as it is available. 2/26/10 – A firm has been selected to conduct the study. Schedule for completion is TBD. Note: For now proceeding with direction set by 1993 Report.	
1.03	02/05/10	JN	PMT: Jacqueline Norman will provide status of the utility surveys at the next meeting. 2/26/10 – Underground survey is complete. 3/3/10 – Initial CAD file sent to F&H. Review and confirmation by the Physical Plant is pending. 3/12/10 – Review by Plumbing and Telecom sent to F&H by JH. Comments on other trades pending.	
1.04	02/05/10	RR	PMT: Richard Racicot will review fire protection issues with Campus Fire Marshall and will report back to the Committee.	
1.05	02/05/10	RR	PMT: Richard Racicot will investigate the cost of a site survey. 2/26/10 – Cost for a site survey should be available second week of March.	

APPENDIX

Workshop #2: Action Items

No.	WS Date	Action By	Issue, Notes & Comments	Status
1.07	02/05/10	LL	F&H: Larry Lanier will review and update food service program with Cheryl. 3/4/10 – LL reviewed areas and layout with Cheryl Garner and Food Managers. Revised sketch to inform Project Area Summary is pending.	Complete
1.08	02/05/10	JH	PMT: Jon Harvey will send Barn Theater ADA Report to F&H, and once available, will provide final ADA Transition Plan. 2/10/10 – Barn Theater report sent to F&H, final ADA Transition Plan is pending.	
1.09	02/05/10	JH	PMT: Jon Harvey will follow up with Nate Jones (CHASS), who will provide comments on the Barn Theater program presented in the BAS. 2/17/10. Nate will provide comments no later than March 15.	
2.03	02/26/10	F&H	F&H to provide a fee for preparing As-built Drawings.	
2.04	02/26/10	JH	Jon Harvey to follow up with Physical Plant to provide draft building standards to Consultant Team. 03/08/10 – Housing is reviewing the Physical Plant standards and will provide direction.	
2.05	02/26/10	F&H	F&H will review truck turning at the Sproul loading dock for impact on utilities. 3/10/10 – F&H and Civil reviewed truck turning to be presented at WS #3.	Complete
2.06	02/26/10	JN	Jacqueline Norman to follow-up with Tricia Thrasher for information regarding the campus-wide storm water policy.	
2.07	02/26/10	JH	Jon Harvey to verify location of tree trunk of the Walnut tree near proposed location for KUCR. 3/3/10 – Locations of trees trunks have been identified. Drawing to F&H still pending. 03/12/10 – Provided map showing tree locations around the Barn and information that identified Walnut Tree location.	Complete
2.08	02/26/10	RR	Richard Racicot to provide a copy of the interlocking paving standards when available.	
2.09	02/26/10	F&H	F&H will investigate the different approaches to moving buildings	

Workshop #2: Action Items

No.	WS Date	Action By	Issue, Notes & Comments	Status
2.10	02/26/10	F&H	F&H will obtain a proposal for quick review by theater consultant (Landry & Bogan). 3/12/10 – F&H sent Additional Service Proposal with two separate items to JH: Theater Consultant review and Acoustical Consultant review of KUCR.	Complete
2.11	02/26/10	F&H	F&H will add Ticket Office to Project Area Summary. 3/9/10 – Ticket Office added to Project Area Summary.	Complete
2.12	02/26/10	F&H	F&H to produce overlay sketches on site plan: how “stuff” can be moved and site security. 3/15/10 – F&H drafts overlay sketches on site to be presented at WS #3.	Complete
2.13	02/26/10	F&H	F&H to roughly determine the latitude and longitude of proposed location of KUCR radio tower using Google Earth for understanding any conflicts with line of sight to the Box Spring Mountains. 03/01/10 – F&H identified tower location. 03/12/10 – KUCR review shows location is less than ideal.	Complete
2.14	02/26/10	AP	Andy Plumley to obtain additional information to determine whether the liquor license can be modified, fencing options, or if a new ABC license for Barn Dining is required.	
2.15	02/26/10	F&H	F&H to study KUCR loading dock south of KUCR near Barn Dining loading dock. 3/12/10 – F&H current site plan addresses loading at KUCR (to be presented at WS #3).	Complete
2.16	02/26/10	CG	Cheryl Garner will determine if a compactor is needed west of Kitchen Addition. 03/10/10 – Compactor is needed	Complete
2.17	02/26/10	CG	Cheryl Garner to determine if Dining will use permanent or disposable dishware. 3/4/10 – Meeting with LL and CG: Dining will use disposable dishware (basket with disposable paper liner).	Complete
2.18	02/26/10	F&H, AP	F&H and the Theater Consultant to work with AP to determine required size and needs for the Backstage Space.	
2.19	02/26/10	JH	LV volunteered to measure the linear length of the KUCR library materials. Jon Harvey to track. 3/3/10 - F&H sent email to JH requesting information. 03/11/10 – Information provided	Complete

Workshop #2: Action Items


No.	WS Date	Action By	Issue, Notes & Comments	Status
2.20	2/26/10	F&H, SL	In order to determine order of magnitude costs increase it is necessary to determine the cost per square foot. F&H and Cost Estimator, Scott Lewis, to determine the order of magnitude cost increase for the increase to the building program. 3/13/10 – F&H and Scott Lewis discuss order of magnitude cost increase to be presented at WS #3.	Complete
2.21	02/26/10	F&H	Kitchen Addition could possibly extend to the west. F&H to review truck turning at Barn Dining Loading Dock. 3/10/10 – F&H and Civil reviewed truck turning to be presented at WS #3.	Complete

APPENDIX

Workshop #2: Site Plan Alternatives



COMPOSITE SITE ORGANIZATION PLAN



DPP - UCR BARN PROJECT PHASES 1 & 2
 WORKSHOP #2, 02/26/10
 FERNAU & HARTMAN ARCHITECTS, INC

APPENDIX

KUCR Conference Call: Meeting Notes

Jon Harvey

From: Jon Harvey [jon.harvey@ucr.edu]
Sent: Wednesday, March 10, 2010 5:01 PM
To: Louis Vandenberg; Andy Plumley; Susan Marshburn
Cc: Kieron Brunelle
Subject: KUCR Program Adjustments
Attachments: KUCR_Prgm_Review_03-10-10.pdf

Susan, Andy, Louis,

Adjustments to the KUCR Project Summary dated 03/05/10 from this afternoon's conference call is attached for your information. Changes to the program are:

One open office work station (64 asf) was added to the Other Spaces.

Revised the KUCR production area follows: Master Control room space increase to 190 asf, Studio Production Room A increased to 130 asf, and Studio Production Room B was removed.

As noted on the program sheet, KUCR Library space requires further review. Media collection information will be refined by KUCR to show LF by type (LP, CD, etc). Requested updated collection information by the end of this week.

Please let me know if you have any questions or comments.

Thanks

Jon

Jon Harvey
 Capital & Physical Planning
 951-827-6952

PROJECT AREA SUMMARY
 UCR Barn Project Phases 1 & 2
 3/05/10

PRELIMINARY DRAFT
 FOR INTERNAL USE ONLY

AREA DESCRIPTION	2009 BAS*	PRELIMINARY PROGRAM	WORKSHOP #2	DIFFERENCE
KUCR				
ASF: PRODUCTION				
KUCR Production	500	500		
Studio: Master Control**			190	
Studio: Production Room A**			130	
Studio: Production Room B**				
Studio: Interview/Program Host**				
Conference Room (Interview / Program Host)			240	
Edit Post/Production Room #1****			48	
Edit Post/Production Room #2****			48	
SUBTOTAL	500	500	656	156
ASF: OTHER SPACES				
Lobby 01	68			
Backstage/Flex Space	565	450		
KUCR Library ¹	125	900		
Office Service / Kitchenette		40		
Remote Live Equipment			100	
Office	983			
Private Offices (4)		400		
Private Office (Director)**	2		110	
Private Office (Asst. Dir./Program Dir.)***	2		110	
Private Office (Music Dept.)***	2		110	
Private Office (Engineering)***	2		110	
Private Office (Administrative Assistant)***	2		110	
Open Offices ¹		400		
Open Office (shared workspace)***			64	
Open Office News/Public Affairs**	2		128	
Server/Transmission Equipment Room**		100		
Lobby 02	345	275		
"ASSIGNABLE TOTAL"	3,586	3,055	2,784	-802
NON-ASSIGNABLE (NON-ASF) SPACES				
Circulation	548	600	600	
Elevator/Stair(s)	280	600	600	
Mechanical		150	150	
Telecom Closet			100	
Public Restrooms	118	115	115	
NON-ASSIGNABLE TOTAL	944	1,465	1,565	621
NET TOTAL ASF & NON-ASF	4,530	4,530	4,349	
Building Net to Gross Factor 15%	680	690	652	
GROSS TOTAL	5,210	5,210	5,001	-208
PROGRAMMABLE COVERED OUTDOOR SPACE				
Backstage Space (secure)***			100	
Stage	500	875	875	
SUBTOTAL	500	875	875	375
TOTAL	5,710	6,085	5,876	167

190
 130
 Review

Review
 visible + secure

TOTAL 128 ASF

* The 2009 BAS areas for each space were originally calculated as gross including walls and circulation. F&H has adjusted the numbers to find the net square footage in order to have a direct comparison for the
 ** Names of spaces from KUCR response to DPP Questionnaire dated 1/27/10 areas were not assigned Spaces and allowances to be confirmed
 *** Changes made to program at Workshop #2
 **** More information needed
¹ Linear length of collection materials by type is needed in order to determine size requirements for KUCR Library KUCR Library size is reduced from BAS by sharing circulation space with other secure

Handwritten initials/signature

Workshop #3: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480

fax 510.848-4532

ISSUED: April 8, 2010

MEETING NOTES

Project Management Team Meeting #3

PROJECT: DPP – UCR Barn Project Phases 1 & 2
TIME/DATE: 9:00 AM – 9:30 AM, March 19, 2010
LOCATION: Capital and Physical Planning Offices

ATTENDEES:

Project Management Team

Don Caskey	Associate Vice Chancellor, Campus Architect
Kieron Brunelle	Director, Capital and Physical Planning
Richard Racicot	Assistant Vice Chancellor, Design and Construction
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Andy Plumley	Assistant Vice Chancellor, Housing, Dining & Residential Services
Susan Marshburn	Executive Director of Housing Services

Consultant Team

Jason Wilkinson	Project Manager, Fernau & Hartman Architects
Laura Boutelle	Project Designer, Fernau & Hartman Architects
Scott Lewis	Cost Estimator, Oppenheim Lewis
Larry Lanier	Food Service Consultant, Laschober + Sovich

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

ACTION BY:	ITEM:
	<p>1. KUCR:</p> <ul style="list-style-type: none"> a. Concerns were raised about the cost of KUCR being two stories as well as the size of program and the inefficient net-to-gross ratio. b. KUCR currently has approximately 2,000 ASF in their existing space. The current program adds 800 ASF, however the total building is 5000 GSF. Options to consider include: a single story KUCR; a careful review of non-assignable spaces; a review of what can be stored off-site and which items currently being stored can be disposed of. c. Housing and Dining Services would like to understand phasing in order to develop a business plan and cash flow model, which is needed for approval of the project.
F&H	<p>2. Performances:</p> <ul style="list-style-type: none"> a. Theater Consultant: F&H to provide a revised proposal from Theater Consultant to ensure that crowd control, lighting, sound cueing, and stage support spaces are included. The cover letter will be revised to include the appropriate participants for the conference call.

Workshop #3: Meeting Notes

ACTION BY: ITEM:

	<p>b. Seating capacity will drive the types of performances that will take place.</p> <p>c. A goal is to provide the ability to use each facility independently and a concern with sound transmission from one location to another was identified. The project will need to address acoustic issues so sound from the west courtyard stage not disrupts food sales in the Barn. The project will also address sound transmission from one location to another within reason. Complete acoustic separation is not a condition.</p>
	<p>3. Meeting Goals: The following goals are critical issues to address in Workshop #3:</p> <p>a. Finalize project program areas and allocation.</p> <p>b. Finalize Site Organization Plan.</p>
SM	<p>4. Action Items:</p> <p>a. Dining Study (1.01): SM reported that the final Dining Study is not yet completed.</p> <p>b. Historical Resources Inventory (1.02): The EDPA is in process for the firm selected to perform the Historical Resources Inventory. F&H will move forward with the 1993 study and state clearly that the DPP is based on this version.</p> <p>c. Utility Survey (1.03): RR reported that the Geovision survey missed some water lines because it did not pick up non-metallic lines. Additional work to survey the possible steam and chilled water lines alignment is on hold for now. The information is not needed to complete the DPP. Item is completed.</p> <p>d. Ground Survey (1.05): The ground survey will be delayed until design phase (after the DPP). For the purposes of the DPP, the item is completed.</p> <p>e. Barn Theater ADA Report (1.08): JH is still waiting on the final ADA Transition Plan.</p> <p>f. Barn Theater Program (1.09): JH is still waiting for comments on the Barn Theater program in the 2009 BAS from Nathaniel Jones (NJ). <i>Note: NJ hand-delivered these comments to JH and JW at WS#3.</i></p> <p>g. As-Built Drawings (2.03): F&H has been reviewing the many considerations in documenting these historic structures and will be gathering more information and taking photos.</p> <p>h. Building Standards (2.04): SM reported that Housing and Dining have received Physical Plant standards and will send them to F&H in about one and one half weeks, once they have had a chance to clarify and summarize the findings in a more presentable form. JH to forward to F&H.</p> <p>i. Storm Water Policy (2.06): JN reported that the UCR storm water policy will not contain anything unusual. This item is complete.</p> <p>j. Interlocking Paving (2.08): RR reported that the interlocking paving standards are being developed.</p> <p>k. Liquor License (2.14): AP reported that the liquor license is a non-issue and it will change if necessary. This item is complete.</p>
JN	
JN	
RR	
JH	
JH	
F&H	
JH	
JN	
RR	
AP	

Workshop #3: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480

fax 510.848-4532

ISSUED: April 8, 2010

MEETING NOTES

Workshop #3: Finalize Elements of DPP; Prepare for Cost Estimate

PROJECT: DPP – UCR Barn Project Phases 1 & 2
TIME/DATE: 9:30 AM – 4:30 PM, March 19, 2010
LOCATION: Capital and Physical Planning Offices, Bannockburn, J-102

ATTENDEES:

Project Management Team

Don Caskey	Associate Vice Chancellor, Campus Architect
Kieron Brunelle	Director, Capital and Physical Planning
Richard Racicot	Assistant Vice Chancellor, Design and Construction
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Andy Plumley	Assistant Vice Chancellor, Housing, Dining & Residential Services
Susan Marshburn	Executive Director of Housing Services

Steering Committee

Andy Plumley	Assistant Vice Chancellor, Housing, Dining & Residential Services
Susan Marshburn	Associate Director of Housing Services
Cheryl Garner	Executive Director, of Dining Services
Nita Bullock	Director of Physical Planning, Campus Landscape Architect

Campus Representatives

Louis Vandenberg	General Manager, KUCR
Nathaniel Jones	Assistant Dean, CHASS
Paul Richardson	Arts Facilities Manager, CHASS
John Freese	UCR Police
Robert Heath	Board President, University Club
Tim Ralston	Capital and Physical Planning
Nathan Ziadie	Associated Students of UCR (ASUCR)

Consultant Team

Jason Wilkinson	Project Manager, Fernau & Hartman Architects
Laura Boutelle	Project Designer, Fernau & Hartman Architects
Ryan Metcalf	Junior Designer, Fernau & Hartman Architects
Scott Lewis	Cost Estimator, Oppenheim Lewis
Larry Lanier	Food Service Consultant, Laschober + Sovich

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

Workshop #3: Meeting Notes

ACTION BY: ITEM:

	<p>1. Drawings Presented: Twelve 24" x 36" boards [Composite Site Organization Plan, Composite Site Plan—Alternate (Preserves Walnut Tree), Security Diagram, Moving "Stuff" Diagram, Truck Turning Diagram, Phasing + Implementation Strategy #1—Phases 1-3, Phasing + Implementation Strategy #2—Phases 1-3, Utility Points of Connection Diagram] were presented, in addition to boards shown at previous workshops. Also, adjacency diagrams showing programmatic relationships between spaces were presented.</p>
	<p>2. Naming Conventions: Names for the buildings and spaces contained in the project were agreed upon. All names were accepted as presented, with the exception of Barn Annex, which will be referred to as "Barn Stable" and Barn Annex Terrace, which will be referred to as "Barn Stable Patio" from here on out.</p> <p>The project will include the following buildings: Barn Dining, Kitchen Addition, Cottage, Barn Stable, KUCR, Barn Theater, and Restrooms.</p> <p>Outdoor spaces will include West Courtyard, East Courtyard, and Barn Stable Patio.</p>
F&H / LL	<p>3. Barn Dining: F&H reported changes in the design made since WS#2, including the reduced square footage of the Kitchen and the Barn Dining stage.</p> <p>a. Indoor Seating</p> <p>i. Existing canted beams create difficulties for seating layouts and placement of the POS stations. A section sketch of Barn Dining will be developed to study interior layout options.</p> <ul style="list-style-type: none"> F&H presented a layout with the sloping columns incorporated into fixed tables to mitigate ADA issues. Bar tables serving a similar function will be studied as a seating option around the perimeter of the Dining Area to preserve view of stage. F&H and LL to study orienting the seating North-South and in an angled configuration.
CG	<p>ii. Cheryl Garner (CG) was concerned about seat utilization with bench-style seating. CG recommended 2-tops and 4-tops tables. CG to provide party size and current seat utilization statistics to F&H.</p>
CG	<p>iii. Barn Dining may need an A/V mixing booth for existing sound system. CG to provide F&H information regarding current mix setup, which may be applicable to the sound system in the West Courtyard as well.</p>
F&H	<p>b. General Program Discussion</p> <p>i. F&H to study relocating the Kitchen Mechanical room to the southwest corner of Kitchen for easier connection to steam and chilled water to the east at Vault 15.</p>
F&H	<p>ii. F&H to study relocating the Green Room to the northwest of Barn Dining, adjacent to Stage.</p>
F&H	<p>iii. F&H to revise the adjacency diagrams to reflect current program relationships.</p>
F&H	<p>iv. F&H to study adding a structural bay at the north end of the Dining Area and recreating the existing façade.</p> <ul style="list-style-type: none"> Andy Plumley (AP) noted that the original north façade burned in a fire and the current façade dates to 1986.

Workshop #3: Meeting Notes

ACTION BY:	ITEM:
<p>F&H</p> <p>F&H</p> <p>F&H</p> <p>F&H</p> <p>F&H</p> <p>F&H</p>	<p>4. Cottage: F&H reported changes in the design made since WS#2, including moving the Cottage to the north to clear existing utilities and manholes.</p> <p>a. Entry / Access: There were several concerns about access to the Cottage and the perceived “front door” (South Porch) and “back door” (East Courtyard) relationship.</p> <p>i. F&H to study the indoor/outdoor circulation and number and location of doors to make the South Porch entry more prominent. Double doors will be considered.</p> <p>ii. F&H to study widening the ramp at the South Porch to address ADA concerns.</p> <p>iii. F&H to study adding a ramp at the North Porch to address ADA concerns at this exit.</p> <p>b. General Program Discussion</p> <p>i. No seating is to be provided inside the Cottage in order to provide sufficient space for circulation and queuing.</p> <p>ii. Office and Telecommunications/Electrical seem too large for the space. F&H to study a Telecommunications/Electrical cabinet that opens up into Office, rather than a dedicated room.</p> <p>iii. Storage is too small. F&H to study shifting square footage to Storage from Office and Telecommunications/Electrical.</p>
<p>F&H</p> <p>F&H</p> <p>F&H</p> <p>F&H</p> <p>F&H</p>	<p>5. Barn Stable: F&H reported refinements in the design made since WS#2, including the Meeting room seating capacity of 42 persons (using 6-tops tables).</p> <p>The Barn Stable Patio can serve as a spillover seating area if additional seating is needed.</p> <p>a. Meeting / Bar</p> <p>i. The two small storage closets at the south end of the Meeting space are not needed. F&H to study the possibility of additional seating in this area.</p> <p>ii. Bar does not need to wrap-around or provide seating. F&H to study a linear walk-up bar with direct access to the Kitchen, shutters, and storage for liquor and bar supplies.</p> <p>iii. Barn Stable will use china, not disposable dishware.</p> <p>b. Electrical / Storage</p> <p>i. F&H to study location of Electrical room to provide access from the outside.</p> <p>c. Lobby</p> <p>i. Lobby should provide a space for gathering, coat check/closet, space to leave gifts, some kind of furniture (benches), and an entry piece (wedding announcement, etc.)</p> <p>ii. F&H to review Lobby flow and layout.</p> <p>d. General Program Discussion</p> <p>i. F&H to update adjacency diagram to reflect current program relationships, including adding the Barn Stable Patio and showing connection between Restrooms and Lobby.</p>

Workshop #3: Meeting Notes

ACTION BY: ITEM:

F&H	6. KUCR: F&H reported refinements in the design made since WS#2, including the relocation of the radio tower.
JH	<ul style="list-style-type: none"> a. General Program Discussion <ul style="list-style-type: none"> i. F&H to first and foremost pursue a single-story option for a more efficient net-to-gross ratio. If a second story is necessary, F&H to study the possibility of removing the second stair. <ul style="list-style-type: none"> • One benefit of the two-story design is that it would help to block freeway noise. Consideration should be given to sloping the roof up to the west to help mitigate freeway noise. ii. The Conference Room will be removed from the program. KUCR staff meetings can occur elsewhere in the Barn complex or around campus. iii. Jon Harvey (JH) noted that the library is an area that could be reduced. iv. JH to provide F&H with the detailed KUCR archive shelving analysis that he recently prepared.
F&H	<ul style="list-style-type: none"> v. F&H to compare compact shelving to standard shelving and determine square footage savings. vi. F&H to study location of KUCR Remote Live Equipment Room to minimize distance away from loading area. vii. F&H presented an alternate site plan that preserved the walnut tree west of KUCR. The Steering Committee determined that the tree would interfere with access to the service drive and greatly compromise the KUCR floor plan and therefore should not be preserved. Nita Bullock (NB) also noted that the walnut tree located to the west of KUCR is not identified in the UCR LRDP nor listed in any historic registries and should be identified and mitigated through CEQA if determined to be of importance. viii. Louis Vandenberg (LV) is concerned about the security of the archive collection and would like to keep archive materials out of the Production spaces. An alternate suggestion was discussed in which a portion of the archive is displayed in the Production spaces while being properly secured (behind glass, possibly). KB suggested that valuable portions of the KUCR collection might be relocated to special collections in the UCR Library. ix. LV approved the location of the KUCR radio tower at the south end of the building. Master Control should be located as close as possible to the tower to minimize the amount of cable run required (critical adjacency).
F&H	<ul style="list-style-type: none"> b. Master Control / Production <ul style="list-style-type: none"> i. The possibility of placing the tower on the roof of KUCR will be reviewed during Schematic Design. ii. An Interview / Talent room will need to be added into the program. This space will need to be adjacent to Master Control, with clear visual connection and acoustical separation between the two rooms. iii. A separate Studio Production room is needed. F&H to study if two studios adjacent to Master Control can be provided.
JH	<ul style="list-style-type: none"> iv. JH to follow up with LV to provide F&H information about the number of occupants and equipment Master Control needs to accommodate. v. LV mentioned Master Control at KPFK station as a good precedent.
<p>7. Shared Outdoor Spaces</p> <ul style="list-style-type: none"> a. West Courtyard <ul style="list-style-type: none"> i. Program Discussion 	

Workshop #3: Meeting Notes

ACTION BY:	ITEM:
F&H	<ul style="list-style-type: none"> F&H to add BBQ and support in drawings, to be located along the southern end of West Courtyard, in the recess formed by the Kitchen Addition.
AP	<ul style="list-style-type: none"> West Courtyard will host various types of performances. AP to provide F&H with lists of current performance types and frequencies, along with potential new uses and priorities.
F&H	<ul style="list-style-type: none"> LV expressed concerns about the acoustical ability to host loud performances in an outdoor space/venue.
F&H	<ul style="list-style-type: none"> Stage and stepped performance pit are too large and should be downsized. F&H to coordinate with Theater Consultant and revise layout.
F&H	<ul style="list-style-type: none"> F&H to add an A/V mixing booth, centered on the stage and located near seating area. The booth should be permanent to limit the amount of equipment than needs to be moved for a show..
F&H	<ul style="list-style-type: none"> ii. Outdoor Seating <ul style="list-style-type: none"> F&H to revise drawings to show more outdoor seating at the West Courtyard than the East Courtyard (CG noted that this area will become premium seating during performances) with the goal of doubling the amount of West Courtyard seating as compared to the current design. One benefit of an enlarged area will be to allow for additional room for circulation. Upper deck will be fixed seating for dining. Lower levels will have movable furniture (cocktail tables possibly) and provide standing room during performances. Currently, furniture is moved 2-3 times per week in the Barn.
	<p>8. Security: F&H presented a diagram of both proposed and optional security gates and fences.</p> <ul style="list-style-type: none"> a. All proposed security enclosures were approved. These include gates at the north end of the West Courtyard running from KUCR to the Barn Theater, gates at the west end of the West Courtyard running from the Kitchen Addition to KUCR, gates at the east end of the West Courtyard running from Barn Dining to Barn Theater, enclosure at the Barn Stable Patio, and enclosure at the east end of the East Courtyard. b. Additional security will be needed in the form of gates at the trellis along the north end of East Courtyard. c. The enclosure at the Barn Stable Patio will be a low wall with fencing, vines, and access via gates.
	<p>9. Moving "Stuff": F&H presented a diagram illustrating how materials, trash and dishes will be transported around the site.</p> <ul style="list-style-type: none"> a. Outdoor bussing stations in the East Courtyard should move to the east end of the courtyard, near the gates that exit out to the Barn Walk. b. The compactor will be used for compost (food waste, green waste, compostable dishware, etc.); additional bins for recycling and trash will also be provided. c. Carts will be used to move items to and from the Barn Stable.

Workshop #3: Meeting Notes

ACTION BY:	ITEM:
<p>F&H</p> <p>F&H/OLI</p>	<p>10. Truck Turning: F&H presented a diagram illustrating how trucks will access and exit the Loading Dock area at the Kitchen Addition and Sproul Hall.</p> <ul style="list-style-type: none"> a. Richard Racicot (RR) noted that trucks accessing the Kitchen Loading Dock do not need to back up; they can simply pull up into the drive and unload. F&H to study if there is clearance for a car to access KUCR parking when a truck is unloading at the Kitchen Addition loading dock area. b. RR suggested the entire Kitchen trash, recycling, and waste oil area be enclosed, with a rolling door. c. The Sproul Loading Dock was reviewed in relation to the Barn Project. The truck turn around in this area is not a necessary element of the Barn Project. F&H and Oppenheim Lewis (OLI) to include two options in the Draft DPP (site plan and Cost Plan) for further review. <ul style="list-style-type: none"> i. One option with truck turnaround (as shown). ii. One option that merely replaces parking, screens trash pickup, and requires the garbage trucks to back out as they do currently.
<p>F&H/OLI</p> <p>F&H/LL</p>	<p>11. Utility Points of Connection</p> <ul style="list-style-type: none"> a. Steam and Chilled Water <ul style="list-style-type: none"> i. The proposed vault (Vault 15) for connecting to the steam and chilled water lines is 300 feet East of site. <ul style="list-style-type: none"> • It is very expensive to extend the line this distance. • It may be cheaper to place a stand-alone HVAC unit at each building or to provide a single stand-alone chiller and boiler that feeds the entire site. However, more efficient units needed to achieve LEED Silver will add to the cost. • Another benefit of connecting to the steam and chilled water system would be the need for only one mechanical room to support the entire Barn complex. • F&H and OLI to study both options (stand-alone HVAC units or connecting to the steam and chilled water system) as part of Cost Plan. b. Electrical <ul style="list-style-type: none"> i. Vault 3A will feed electricity to a transformer south of the Kitchen, then distribute to rest of site. c. Water <ul style="list-style-type: none"> i. LL noted that grease interceptors will be needed at both the Barn Stable and Kitchen Addition. F&H / LL to study.
<p>F&H</p>	<p>12. Phasing: F&H presented two strategies for implementation and phasing of the project. The first phasing strategy maintained the phasing approach described in the RFP. The second, preferred option involves underground utility work and building the Dining facilities in Phase 1, KUCR in Phase 2, and the Barn Theater in a future Phase 3.</p> <ul style="list-style-type: none"> a. General Comments <ul style="list-style-type: none"> i. F&H to revise diagrams to show what is changing at the current phase (along with existing buildings) with future buildings dashed. ii. Underground utility work will need to occur at the beginning of Phase 1, with consideration of maintaining set utilities serving buildings that continue to be in operation during construction. iii. Occupancy dates remain fixed; Phase 1 work will be completed and

Workshop #3: Meeting Notes

ACTION BY:	ITEM:
	<p>occupied September 1, 2012 and Phase 2 work will be completed and occupied September 1, 2013.</p> <ul style="list-style-type: none"> • To meet these deadlines, construction should finish at the end of July. If construction is to run over the expected dates, it would be preferable for construction to slip into the Spring rather than the Fall quarter. <p>iv. Parking Lot 4 may be used for contractor staging, cargo, trailer, etc, and the use will need to be confirmed with TAPS during design.</p> <p>b. Phasing Concerns</p> <ol style="list-style-type: none"> i. KUCR can move to Phase 2 since the schedule has been delayed for Dundee Residence Hall, which necessitates the demolition of the existing KUCR facility. ii. CG will need three weeks to complete training within the Dining facilities. iii. Beginning construction in June is negotiable; if necessary, pushing into spring is preferred to pushing into fall. iv. The Cottage should be constructed concurrently with Barn Dining over summer so that access to the Barn is not infringed upon during the winter and spring. <ul style="list-style-type: none"> • CG noted that if Barn Dining begins to slip, the Cottage should not slip. If Barn Dining is unable to generate revenue for a period of time, Cottage should be up and running by the end of August. v. AP confirmed that leaving the University Club without a meeting space for a period of time is acceptable (within Phase 1, the construction schedule of the Barn Stable has flexibility). <p>c. Phasing Consensus</p> <ol style="list-style-type: none"> i. Phase 1 <ul style="list-style-type: none"> • 1A: All underground utility work and moving Barn Stable • 1B: Barn Kitchen • 1C: Barn Dining and Cottage ii. Phase 2: KUCR, West Courtyard, and Stage iii. Phase 3: Barn Theater
<p>F&H/TM</p> <p>F&H/TDE</p> <p>F&H/LA</p> <p>OLI</p>	<p>13. Consultant Narratives: F&H presented briefs from narratives compiled by the consultants.</p> <p>a. Feedback</p> <ol style="list-style-type: none"> i. Structural <ul style="list-style-type: none"> • RR suggested concrete masonry units for Restrooms and KUCR (for sound purposes) and steel studs for Kitchen. • RR suggested that rafter tails be kept, pulling the ridge up for airflow. F&H noted that Tipping Mar (TM), Structural Engineer, had advised against this strategy. F&H/TM to study options for adding insulation above the existing roof framing. ii. MEP <ul style="list-style-type: none"> • F&H and Timmons Design Engineers (TDE) to study options for radiant heating and cooling at the Barn. • F&H and Lutsko Associates (LA) to address site lighting in the Draft DPP. • CG would like to have an emergency generator in place for Barn and Kitchen to support the community in case of emergency. Oppenheim Lewis, Inc. (OLI), cost estimator, to cost.

Workshop #3: Meeting Notes

ACTION BY:	ITEM:
	<ul style="list-style-type: none"> • As discussed in WS#2, all buildings will be metered separately. <p>iii. Foodservice</p> <ul style="list-style-type: none"> • RR noted that all Kitchen walls are to have concrete curbs; he also recommended FRP on cementitious board.
JH	<p>14. LEED</p> <p>a. KB noted that Kenyon Potter is updating UCR LEED baseline. JH to provide F&H with this document for preparing the LEED Matrix.</p> <p>b. Don Caskey (DC) suggested organizing a LEED workshop.</p> <p>i. Begin with UCR baseline and add low-hanging fruit.</p> <p>ii. Educational potential of the project is great. Look at all sustainable options as if project were going beyond LEED Silver. Best to shoot for all options and then scale back as needed.</p>
F&H/OLI	<p>iii. F&H and OLI to develop criteria for a project that meets LEED Silver for the DPP and Cost Plan.</p>
AP	<p>15. CHASS: During a break, there was a side meeting with CHASS representatives Nathaniel Jones (NJ) and Paul Richardson (PR). AP, JH, JW, and Laura Boutelle (LB) were also in attendance.</p> <p>a. NJ presented a list of issues that were not addressed in the 2009 BAS which will be added to the Appendix of the DPP.</p> <p>b. AP will present the Draft DPP plan to chairs of the department (3) and Dave Keltstrand (sp?) for input. However, the project schedule cannot be delayed when setting this meeting date. If necessary, input will be added as an attachment to the completed DPP.</p>
JH	<p>c. JH to invite CHASS and representatives to the conference call with the Theater and AV consultants (4/5/10).</p>
AP	<p>d. AP to collect types of performances by CHASS that the Outdoor Spaces and stages will need to support.</p>
F&H/OLI	<p>16. Cost Plan: F&H and OLI to develop the draft Cost Plan using the format of the two sample Cost Plans provided by JH.</p> <p>a. "Below the Line" items:</p> <p>i. Sproul truck turning (this is a campus issue, not specific to this project).</p> <p>ii. Barn Dining/Kitchen emergency generator.</p> <p>b. Escalation will be 2-3% carried to the mid-point of construction.</p> <p>c. A design contingency of 10% or higher will be used in the estimate. CM will be assumed at 5%.</p> <p>d. Each individual building will be broken out, as well as site landscaping per zone.</p> <p>e. The Barn Theater will not be part of the Cost Plan.</p>

Workshop #3: Action Items

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

ISSUED: April 8, 2010

ACTION ITEM STATUS TABLE

PROJECT: DPP – UCR Barn Project Phases 1 & 2

The Action Item Status Table is meant to summarize the action items raised at the meeting(s) listed above and responsible party for each action item. If they differ from your recollection, please contact Fernau & Hartman immediately. Completed items are taken off the list after review by the PMT.

No.	WS Date	Action By	Issue, Notes & Comments	Status
1.01	02/05/10	SM	PMT: Susan Marshburn will ask Dining Services to provide the draft Dining Study for the Barn, and once available the completed Dining Study report. 2/09/10 – spread sheet of draft Dining Study provided to F&H, completed Dining Study report still pending 3/19/10 – Report still pending 04-06-10 – Task is completed for the purposes of the DPP. The final report will be provided once available.	Completed
1.02	02/05/10	JN	PMT: Jacqueline Norman will provide the Historical Resources Inventory report to F&H as soon as it is available. 2/26/10 – A firm has been selected to conduct the study. Schedule for completion is TBD. Note: For now proceeding with direction set by 1993 Report. 3/19/10 – Report still pending. DPP will move forward with the 1993 Study as the basis.	
1.03	02/05/10	JN	PMT: Jacqueline Norman will provide status of the utility surveys at the next meeting. 2/26/10 – Underground survey is complete. 3/3/10 – Initial CAD file sent to F&H. Review and confirmation by the Physical Plant is pending. 3/12/10 – Review by Plumbing and Telecom sent to F&H by JH. Comments on other trades pending. 3/19/10 – Geovision survey missed some non-metallic utility lines. An additional survey of the	Completed

DPP - UCR Barn Project Phases 1 & 2 –Action Item Status Table

4/10

Page 1 of 6

Workshop #3: Action Items

No.	WS Date	Action By	Issue, Notes & Comments	Status
1.07	02/05/10	LL	F&H: Larry Lanier will review and update food service program with Cheryl. 3/4/10 – LL reviewed areas and layout with Cheryl Garner and Food Managers. Revised sketch to inform Project Area Summary is pending.	Complete
1.08	02/05/10	JH	PMT: Jon Harvey will send Barn Theater ADA Report to F&H, and once available, will provide final ADA Transition Plan. 2/10/10 – Barn Theater report sent to F&H, final ADA Transition Plan is pending.	
1.09	02/05/10	JH	PMT: Jon Harvey will follow up with Nate Jones (CHASS), who will provide comments on the Barn Theater program presented in the BAS. 2/17/10. Nate will provide comments no later than March 15.	
2.03	02/26/10	F&H	F&H to provide a fee for preparing As-built Drawings.	
2.04	02/26/10	JH	Jon Harvey to follow up with Physical Plant to provide draft building standards to Consultant Team. 03/08/10 – Housing is reviewing the Physical Plant standards and will provide direction.	
2.05	02/26/10	F&H	F&H will review truck turning at the Sproul loading dock for impact on utilities. 3/10/10 – F&H and Civil reviewed truck turning to be presented at WS #3.	Complete
2.06	02/26/10	JN	Jacqueline Norman to follow-up with Tricia Thrasher for information regarding the campus-wide storm water policy.	
2.07	02/26/10	JH	Jon Harvey to verify location of tree trunk of the Walnut tree near proposed location for KUCR. 3/3/10 – Locations of trees trunks have been identified. Drawing to F&H still pending. 03/12/10 – Provided map showing tree locations around the Barn and information that identified Walnut Tree location.	Complete
2.08	02/26/10	RR	Richard Racicot to provide a copy of the interlocking paving standards when available.	
2.09	02/26/10	F&H	F&H will investigate the different approaches to moving buildings	

APPENDIX

Workshop #3: Action Items

No.	WS Date	Action By	Issue, Notes & Comments	Status
2.08	02/26/10	RR	Richard Racicot to provide a copy of the interlocking paving standards when available. 3/19/10 – Standards still pending.	
2.09	02/26/10	F&H	F&H will investigate the different approaches to moving buildings 3/19/10 – F&H reported at WS 3 on options for moving Cottage and Barn Stable	Completed
2.14	02/26/10	AP	Andy Plumley to obtain additional information to determine whether the liquor license can be modified, fencing options, or if a new ABC license for Barn Dining is required. 3/19/10 – AP reported this is a non-issue. The license will change if necessary.	Completed
2.18	02/26/10	F&H, AP	F&H and the Theater Consultant to work with AP to determine required size and needs for the Backstage Space. 3/23/10 – Additional services approved for Theater Consultant review and conference call set for 4/5/10. 04/05/10 – Conference call with Theater Consultant reviewed size of Backstage Space.	Completed
3.01	03/19/10	F&H, LL	F&H and LL to study orienting the Barn Dining seating in North-South and angled configurations.	
3.02	03/19/10	CG	CG to provide Barn Dining party size and current seat utilization statistics to F&H. 04-05-10 – Information provided to F&H	Completed
3.03	03/19/10	CG	CG to provide F&H information on current sound mixing booth at Barn Dining.	
3.04	03/19/10	F&H	F&H to study relocating the Kitchen Mechanical Room to the southwest corner of Kitchen for easier connection to steam and chilled water from Vault 15. 04/02/10 – F&H developed site plan showing Mechanical Room south of Kitchen Addition	Completed
3.05	03/19/10	F&H	F&H to study relocating the Green Room to the northwest corner of Barn Dining, adjacent to Stage. 04/02/10 – F&H developed site plan showing Green Room relocated as discussed	Completed
3.06	03/19/10	F&H	F&H to revise the adjacency diagrams to reflect current program relationships.	Completed

APPENDIX

Workshop #3: Action Items

No.	WS Date	Action By	Issue, Notes & Comments	Status
3.07	03/19/10	F&H	F&H to study adding a structural bay at the north end of the Dining Area. 04/02/10 – F&H developed site plan showing additional structural bay at north end of Barn as discussed	Completed
3.08	03/19/10	F&H	F&H to study the indoor/outdoor circulation and number and location of doors at the Cottage.	
3.09	03/19/10	F&H	F&H to study widening the ramp at the South Porch of the Cottage. 04/02/10 – F&H developed site plan showing a wider ramp at South Porch of the Cottage	Completed
3.10	03/19/10	F&H	F&H to study adding a ramp at the North Porch of the Cottage to address ADA concerns. 04/02/10 – F&H developed site plan showing ramp at North Porch of Cottage	Completed
3.11	03/19/10	F&H	F&H to study a Telecommunications/Electrical cabinet at the Cottage that opens up into Office, rather than a dedicated room.	
3.12	03/19/10	F&H	F&H to study shifting square footage at the Cottage to Storage from Office and Telecommunications/Electrical.	
3.13	03/19/10	F&H	The two small storage closets at the south end of the Meeting space of the Barn Stable are not needed. F&H to study the possibility of additional seating in this area.	
3.14	03/19/10	F&H	F&H to study a linear walk-up bar at the Barn Stable with direct access to the Kitchen, shutters, and storage for liquor and bar supplies.	
3.15	03/19/10	F&H	F&H to study location of Electrical room at the Barn Stable to provide access from the outside.	
3.16	03/19/10	F&H	F&H to study Barn Stable Lobby flow and layout.	
3.17	03/19/10	F&H	F&H to update Barn Stable adjacency diagram to reflect current program relationships, including adding the Patio and showing connection between Restrooms and Lobby.	
3.18	03/19/10	F&H	F&H to study a single-story option for a more efficient net-to-gross ratio at KUCR. If a second story at KUCR is necessary, F&H to study the possibility of removing the second stair. 04/02/10 – F&H sent site plan with single story KUCR	Completed
3.19	03/19/10	JH	JH to provide F&H with the detailed KUCR archive shelving analysis that he recently prepared. 04/06-10 –Information furnished to F&H.	Completed

APPENDIX

Workshop #3: Action Items


No.	WS Date	Action By	Issue, Notes & Comments	Status
3.20	03/19/10	F&H	F&H to compare compact shelving to standard shelving and determine square footage savings at KUCR.	
3.21	03/19/10	F&H	A separate KUCR Studio Production room is needed. F&H to study if two studios adjacent to Master Control can be provided. 04/02/10 – F&H sent site plan showing two Production Studios as discussed	Completed
3.22	03/19/10	JH	JH to follow up with LV to provide F&H information about the number of occupants and equipment KUCR Master Control needs to accommodate. 04-05-10 – LV will review KUCR program and room data sheets during the Administrative Draft review period. Additional information will be provided with comments.	Completed
3.23	03/19/10	F&H	F&H to add BBQ and support in drawings, to be located along the southern end of West Courtyard, in recess formed by Kitchen Addition.	
3.24	03/19/10	AP	AP to provide F&H with lists of current performance types and frequencies, along with potential new uses and priorities. 04-05-10 – Information provided to F&H	Completed
3.25	03/19/10	F&H	Stage and stepped performance pit at West Courtyard are too large and should be downsized. F&H to coordinate with Theater Consultant and revise layout. 04/02/10 – F&H sent site plan showing revised layout as discussed	Completed
3.26	03/19/10	F&H	F&H to add an A/V mixing booth, centered on the stage and located near seating area in West Courtyard. The booth should be permanent to reduce the need for moving equipment.	
3.27	03/19/10	F&H	F&H to revise drawings to show more outdoor seating at the West Courtyard with the goal of doubling the amount of seating in this location.	
3.28	03/19/10	F&H	F&H to study if there is clearance for a car to access KUCR parking when a truck is unloading at the Kitchen Addition loading dock area.	
3.29	03/19/10	F&H/OLI	F&H and OLI to include two options for the Sproul loading dock: one option with truck turnaround, one option that merely replaces parking, screens trash pickup, and requires the garbage trucks to back out as they do currently.	

Workshop #3: Action Items

No.	WS Date	Action By	Issue, Notes & Comments	Status
3.30	03/19/10	F&H/OLI	F&H and OLI to study two HVAC options as part of Cost Plan: one option involving stand-alone HVAC units at each building, one option involving connection to the steam and chilled water system.	
3.31	03/19/10	F&H/LL	F&H and LL to study adding grease interceptors at both the Stable and Kitchen Addition.	
3.32	03/19/10	F&H	F&H to revise phasing diagrams to show what is changing at the current phase (along with existing buildings) with future buildings dashed.	
3.33	03/19/10	F&H/TM	F&H and TM to study options for adding insulation above the existing roof framing at Barn Dining.	
3.34	03/19/10	F&H/TDE	F&H and TDE to study options for radiant heating and cooling at the Barn.	
3.35	03/19/10	F&H/LA	F&H and LA to address site lighting in the Draft DPP.	
3.36	03/19/10	OLI	Oppenheim Lewis to cost the inclusion of an emergency generator for Barn Dining and Kitchen Addition to support the community in case of emergency.	
3.37	03/19/10	JH	JH to provide F&H with UCR LEED baseline for preparing the LEED Matrix. 04/06/10 – F&H to use information provided to date to develop LEED matrix.	Completed
3.38	03/19/10	F&H	F&H to develop criteria for a project that meets LEED Silver for the DPP and Cost Plan.	
3.39	03/19/10	AP	AP will present the Draft DPP plan to chairs (3) of CHASS and Dave Kellstrand for input.	
3.40	03/19/10	JH	JH to invite CHASS and representatives to participate on the conference call with the Theater and AV consultants (4/5/10).	Complete
3.41	03/19/10	F&H/OLI	F&H and OLI to develop the draft Cost Plan using the format of the two sample Cost Plans provided by JH.	

APPENDIX


Workshop #3: Site Plan Alternatives



DPP - UCR BARN PROJECT PHASES 1 & 2
 WORKSHOP #3, 03/19/10
 FERNAU & HARTMAN ARCHITECTS, INC

APPENDIX

Workshop #3: Site Plan Alternatives



**COMPOSITE SITE PLAN - ALTERNATE
(PRESERVES THE WALNUT TREE)**



DPP - UCR BARN PROJECT PHASES 1 & 2
 WORKSHOP #3, 03/19/10
 FERNAU & HARTMAN ARCHITECTS, INC

Performance Issues Conference Call: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480

fax 510.848-4532

Issued: May 25, 2010

DPP – UCR Barn Project Phases 1 & 2
Fernau & Hartman Architects, Inc.
3:30 – 5:00 pm April 05, 2010
Performance Issues Conference Call

Participants:

Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Richard Racicot	Assistant Vice Chancellor, Office of Design and Construction
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Susan Marshburn	Executive Director of Housing Services
Andy Plumley	Assistant Vice Chancellor, Housing, Dining & Residential Services
Cheryl Garner	Executive Director, of Dining Services
Nate Jones	Assistant Dean, CHASS
Paul Richardson	Arts Facilities Manager, CHASS
Laura Hartman	Principal in Charge, Fernau & Hartman Architects
Jason Wilkinson	Project Manager, Fernau & Hartman Architects
Rose Steel	Principal Consultant, Landry & Bogan, Inc. (Theater Consultant)
Tom Schindler	Vice President, Charles M. Salter Associates, Inc. (AV Consultant)

Notes

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

1) Occupancy

- a. Fire Marshal will determine maximum number of occupants and exiting requirements for performances or any other use beyond normal dining operations.

2) Back of House Support Spaces

- a. Smaller support spaces are OK. If necessary the Barn Stable can be used.

3) Outdoor Stage

- a. Mosh Pit: Angle steps to allow for better views and dancing area
- b. Sound / lighting control outdoor stage - two connection points:
 - i. There will be an enclosed, permanent booth at the northwest wall of the Barn Dining facing the stage
 1. The sound and lighting boards will be stored when not in use

Performance Issues Conference Call: Meeting Notes

2. The booth will be raised, have low walls, and will not be covered
3. A temporary ramp or stairs will be brought in as needed to access the booth
 - ii. There will also be a connection point (no enclosure) in the "Dining Seating Area," closer to the stage
 1. Both locations will also have network and power connections
- c. Screen and projector: larger outdoor mechanical screen on the outdoor stage plus a projector
- d. Camera: there will be a truss mounted fixed camera to provide feed to the indoor screen
- e. Dimmers: (one dimmer rack=96 circuits) and multiple amp racks in the storage at the southwest gates into the stage area (west of the WC near the loading dock)
- f. Shade Structure:
 - i. The canopy will need to be 18' to 20' high to support lights and lighting trusses mounted at 16' high
 - ii. Columns will be added to reduce the spans and reduce the column size
 - iii. Canopy will also need to support permanent weatherized loudspeakers
 1. If there are heavier low frequency loudspeakers located as delays (one extra set) in the seating area they can be at the columns.
- g. Stage Canopy:
 - i. Acoustically absorptive underside material. Also on upper walls at back of stage (KUCR exterior walls)
 - ii. Separate structure for stage and canopy from KUCR
- h. Stage Access will be reviewed by F&H to provide for loading from south end of stage
- i. Lighting will be truss mounted to the Shade Structure as noted above
 - i. Provide capability for movable lights but no followspots

4) Indoor Stage

- a. Approximate size of the stage is 12' x 20'
- b. Sound / lighting control for the indoor stage:
 - i. The indoor stage will have a sound board connection point on one side of the stage and a lighting control connection point on the other. Neither will be permanent

Performance Issues Conference Call: Meeting Notes

- ii. Also possible to have connection points for both sound and lighting in the same place, and at two or three locations to accommodate different types of acts and mixing / lighting requirements

- c. Lighting:

- i. Extent of lighting is to be determined
 - 1. Incorporate into existing truss
 - 2. Locations for dimmers are also to be determined
- ii. Provide capability for movable lights but no followspots

- d. Screen and projector: mechanical screen on the stage for viewing live feed from the exterior stage plus a projector

5) Ticket Booth

- a. The Ticket Booth will include the following:
 - i. Terminals for Ticket Master and satellite connection
 - ii. Exterior lighting and canopy overhead
 - iii. Two onsite sales stations (tickets will be preprinted not computer generated)
 - iv. Two sales windows with thick security glass and one safe
 - v. Door to the interior of The Barn, no exterior door

6) Additional Storage

- a. There will need to be additional storage for audio equipment including:
 - i. Mixing boards, mics, stands, cables, and stage monitor cabinets

DBR Presentation: Meeting Notes

UC Riverside Design Review Board Meeting Minutes for April 6, 2010

Board Members		
Professor John Ganim	Academic Senate Chair, Physical Resources Committee	(N)
Professor Stella Nair	History of Art (CHASS)	(A*)
Professor Jerome Schultz	Bioengineering (BCOE)	(A)
Professor Martin Kennedy	Earth Sciences (CNAS)	(N)
Timothy Ralston	Associate VC, Capital & Physical Planning	(A)
Don Caskey	Associate VC/Campus Architect, Design & Construction	(A)
Charles "Duke" Oakley	Steven Ehrlich Architects	(A)
Rob Quigley	Robert Wellington Quigley, FAIA	(A)
Kathleen Garcia	Wallace, Roberts & Todd Architects	(A)
Presenter(s)		
Laura Hartman	Fernau & Hartman	(A)
Jason Wilkinson	Fernau & Hartman	(A)
Other Attendees		
Rich Racicot	Office of Design & Construction	(A)
Mike Delo	Transportation & Parking Services	(N)
Mike Miller	Facilities, Plant Administration	(N)
Jon Harvey	Capital & Physical Planning	(A)
Kieron Brunelle	Capital & Physical Planning	(N)
Tricia Thrasher	Office of Design & Construction	(N)
Nita Bullock	Capital & Physical Planning	(A)
Andy Plumley	Housing Services, Administration	(A)
Susan Marshburn	Housing Services, Administration	(A)
Cheryl Garner	Housing Services, Dining	(A)
Jacqueline Norman	Office of Design & Construction	(A)
Susan Ryan	Office of Design & Construction	(A)
Sandi Evelyn-Veere	Office of Design & Construction	(A)

Attendance (A = Attendance, A* = Arrived After Presentation, N = Not in Attendance)

1.0 Meeting Agenda. The agenda for the April 6th meeting of the Design Review Board (DRB) included:

a. Barn Project Phases 1 & 2, Pre-Design.

Fernau & Hartman presented their pre-design study of the Barn Project Phases 1 & 2 which includes: Barn Dining and Kitchen Addition, Barn Stable, Cottage, KUCR and Barn Theatre.

DBR Presentation: Meeting Notes

2.0 Observations and Recommendations -- Barn Project Phases 1 & 2, Pre-Design.

- a. The DRB provided the following comments:
 1. Encouraged the design development of interior spaces in the Barn Dining area to address acoustics in order to minimize sound transfer. Acoustical improvements over the existing facility will help improve the dining experience.
 2. Recommended that meeting rooms with food service be included in the scope of the project.
 3. The terminus of Eucalyptus and Barn Walks ending in a semi-intersection needs to be addressed in order to provide a more gracious entry into and connection across the campus. This area should be further studied and resolved during design.
 4. If security and fencing of the courtyards areas are necessary, it is suggested they be developed in a seamless way by using transparent materials for fencing with heights kept to a minimum.
 5. The freeway's noise generation is only partially mitigated by the existing sound wall. It will be important to study how to minimize traffic noise in the courtyard spaces and how to utilize the building masses as appropriate sound walls.
 6. Since the project includes old versus new buildings, the design should be balanced in scale and materials. DRB endorsed the concept of older buildings being in the foreground with the new buildings in the background. Material selection should reinforce the concept so new buildings do not overshadow existing.
 7. The incorporation of trellises in the design needs to be in harmony with the buildings.
 8. KUCR facility should explore a stronger relationship with the outdoor entertainment space. It was suggested that one way would be to incorporate the use of a multipurpose digital screen on the stage area showing broadcasts.
 9. The design of potentially five courtyards plays an important role in the development of the site and should be looked at as a series of interrelated courtyards.
 10. The landscape design should take into consideration the campuses agricultural heritage by developing landscape responses that relate to our early California gardens. This could be done not only with plant material, but hardscape, walls and fences. Permeable paving, such as decomposed granite would also evoke this character. This type of approach would make it a rich site and further tie the old

DBR Presentation: Meeting Notes

to the new. It was further suggested the approach to the landscape design be developed in a “less formal” way than typical campus landscapes.

11. The bathroom facility, sited at the entry portal to the north, would be a challenge to design. Sound attenuation and privacy will be concerns. A double-door entry could be considered as well as a water feature in near proximity to the facility.
12. Campus guidelines should be developed for The Barn Group to ensure that the development of future phases is in keeping with the current project’s direction.
13. The west side of The Barn Group needs to be carefully designed, not overlooked or just dealt with in terms of a demanding service function. The concept design for the service road separated from West Campus Drive with a median gives the potential for landscape screening as one, possibly important tool, for the overall design of that face of the project.

The board commended Fernau & Hartman on a well-developed and refined presentation.

Note: Presentation by Fernau & Hartman, available by request.

3.0 School of Medicine Site Change

- a. Nita Bullock informed the DRB that the School of Medicine site has changed from the northeast corner of Chicago Ave. and Martin Luther King Blvd., to the northeast corner of Iowa Ave. and Martin Luther King Blvd. The site change will delay the LRDP Amendment process by one year. Nita will provide updates on the status of the LRDP Amendment at future meetings.

4.0 Follow Up and Next Steps.

- a. DRB’s next meeting is scheduled for May 3, 2009.

Attachments: Barn Project Phases 1 & 2 Area Summary
West Campus Analysis – School of Medicine Site Options C1, C2, C3 & D

The following constitutes a summary of topics presented to or discussed by the DRB on April 6, 2010. Recipients of these minutes are encouraged to apprise Sandi Evelyn-Veere of any errors or omissions.

Workshop #4: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480
fax 510.848-4532

ISSUED: May 19, 2010

MEETING NOTES

Project Management Team Meeting #4

PROJECT: DPP – UCR Barn Project Phases 1 & 2
TIME/DATE: 9:00 AM – 9:30 AM, April 16, 2010
LOCATION: Capital and Physical Planning Offices

ATTENDEES:

Project Management Team

Kieron Brunelle	Director, Capital and Physical Planning
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Andy Plumley	Assistant Vice Chancellor, Housing, Dining and Residential Services
Susan Marshburn	Executive Director of Housing Services

Consultant Team

Laura Hartman	Principal in Charge, Fernau & Hartman Architects
Jason Wilkinson	Project Manager, Fernau & Hartman Architects
Scott Lewis	Cost Estimator, Oppenheim Lewis

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

ACTION BY:	ITEM:
	1. Workshop #4 Goals: The goals for the Workshop #4 are to bring closure to the program and implementation plan.
	2. Performance Issues Conference Call: Reviewed the input of the Theater Consultant and its usefulness for the DPP.
	3. Draft DPP Text: Some of the text in the draft DPP needs work. The text should be clear and concise. It should also focus positive language and avoid negative language whenever possible.
AP	4. Allowable Number of Occupants: AP to meet with the Campus Fire Marshal to discuss allowable number of occupants for indoor and outdoor gathering spaces.
	5. Action Items: <ul style="list-style-type: none"> a. 1.02: JN reported that the Historical resources report will be completed April 26, 2010. The preliminary findings are that the project does not appear to qualify as “historic resources” per CEQA, but the buildings do have cultural significance for the UCR campus and community. b. 2.03: F&H to provide a fee for As-Built drawings after reviewing the recently

DPP - UCR Barn Project Phases 1 & 2 –DRAFT Meeting Notes from PMT #4, 04/16/10
 05/19/10
 Page 1 of 2

Workshop #4: Meeting Notes

ACTION BY:	ITEM:
	<p>found archived drawings:</p> <ul style="list-style-type: none"> i. Original drawings (1916 and 1917) for the Cottage, Barn Stable and The Barn ii. Drawings (1985) for the renovation of The Barn after the north end of the structure burned in a fire. c. 3.36: A single emergency generator for both Kitchen (refrigeration and cooking requirements) and KUCR (emergency broadcast requirements) will be included in the cost plan. Incorporating the generator into the site plan will be a challenge given the limited space.
	<p>6. Schedule: The DPP is currently on schedule and is targeting the upcoming milestones:</p> <ul style="list-style-type: none"> a. 4/28/10 Administrative Draft DPP: F&H to submit the electronic PDF and one printed copy. b. 5/19/10 Pre-CPAC Conference Call (3:00 to 4:00 PM): Review the materials for the CPAC presentation. c. 5/24/10 CPAC Presentation (2:00 to 2:30 PM)

Workshop #4: Meeting Notes

FERNAU & HARTMAN • ARCHITECTS, INC.

2512 Ninth Street No. 2 • Berkeley California 94710

510.848-4480

fax 510.848-4532

ISSUED: May 20, 2010

MEETING NOTES

Workshop #4: Review DPP and Cost Plan

PROJECT: DPP – UCR Barn Project Phases 1 & 2
TIME/DATE: 9:30 AM – 3:45 PM, April 16, 2010
LOCATION: Capital and Physical Planning Offices, Bannockburn, J-102

ATTENDEES:

Project Management Team

Kieron Brunelle	Director, Capital and Physical Planning
Jacqueline Norman	Senior Project Manager, Office of Design and Construction
Jon Harvey	Principal Education Facilities Planner, Capital and Physical Planning
Andy Plumley	Assistant Vice Chancellor, Housing, Dining and Residential Services
Susan Marshburn	Executive Director of Housing Services

Steering Committee

Andy Plumley	Assistant Vice Chancellor, Housing, Dining and Residential Services
Susan Marshburn	Executive Director of Housing Services
Cheryl Garner	Executive Director of Dining Services
Nita Bullock	Director of Physical Planning, Campus Landscape Architect
Professor John Ganmin	Faculty Representative, Academic Senate

Consultant Team

Laura Hartman	Principal in Charge, Fernau & Hartman Architects
Jason Wilkinson	Project Manager, Fernau & Hartman Architects
Ryan Metcalf	Junior Designer, Fernau & Hartman Architects
Scott Lewis	Cost Estimator, Oppenheim Lewis

These notes are meant to summarize the issues raised and directions chosen at the meeting. If they differ from your recollection, please contact Fernau & Hartman immediately.

Workshop #4: Meeting Notes

ACTION BY: ITEM:

	<p>1. Drawings Presented: Two 24" x 36" boards (Composite Site Organization Plan and Outdoor Seating Plan). The draft DPP and illustrations from previous workshops were presented digitally.</p>
	<p>2. Naming Conventions: A clarification was made regarding the name of The Barn. Rather than being divided into two separate spaces and referred to as Barn Dining and Kitchen Addition individually, the building should be referred to as a whole, The Barn, which contains both the Kitchen Addition and Barn Dining.</p> <p>The project will include the following buildings: The Barn, Cottage, Barn Stable, KUCR, Barn Theater, and Restrooms.</p> <p>Outdoor spaces will include West Courtyard, East Courtyard, and Barn Stable Patio.</p>
F&H	<p>3. Cottage: F&H presented an overview of the program for the Cottage.</p>
F&H	<p>a. General Program Discussion</p>
F&H	<p>i. F&H to study frontage seating south of the Cottage as a place for visitors "to see and be seen."</p>
F&H	<p>ii. F&H to combine the Storage and Telecom/Electrical closet into one space. A secure office space is needed to support cash counting and other administrative functions, but overall the square footage may be reduced to accommodate a larger storage/Telecom space.</p>
F&H	<p>iii. Telecom/Electrical was noted as being smaller than suggested by the Communication Services. It was agreed that the size of Telecom/Electrical will be reviewed during design.</p>
	<p>b. Outdoor Seating: F&H to add a column for Programmable Covered Outdoor Space to the "Summary" page of the Project Area Summary.</p>
	<p>4. The Barn: F&H presented an overview of the program for The Barn.</p>
	<p>a. General Program Discussion</p>
F&H	<p>i. The current conceptual layout functions well and seating feels comfortable.</p>
F&H	<p>ii. F&H clarified the function of the three proposed ventilation/light shafts at the indoor dining area. They will bring light into the space and help to move air via the stack effect. A roof monitor at the Kitchen will also help to bring daylight into the Kitchen work area.</p>
F&H	<p>iii. F&H to include the missing double exterior door at the west side of Barn Dining.</p>
	<p>b. Performance Area</p>
F&H	<p>i. F&H will revise the Green Room to be at ground level (on grade with indoor dining), rather than at the level of the stage. The room will have a door exiting into the Barn (to the south) and an exterior door.</p>
F&H	<p>ii. F&H to confirm height of existing stage.</p>
	<p>5. Barn Stable: F&H presented an overview of the program for the Barn Stable.</p>
	<p>a. General Program Discussion</p>
	<p>i. Barn Stable seating (868 SF indoor at the Meeting Room providing 42 seats and 875 SF outdoor at the Barn Stable Patio providing 44 seats) was found to be acceptable. Seat numbers were based on 20 SF/seat. Cheryl Garner (CG) noted that these seating numbers will satisfy the University Club.</p>
	<p>ii. The large, sliding barn door proposed for the west wall of the Meeting Room</p>

Workshop #4: Meeting Notes

ACTION BY:	ITEM:
	<p>allows the Patio to become an extension of the interior space, with service and guests flowing freely between the two spaces.</p> <p>iii. The shower, included in one of the restrooms, will help achieve the LEED credit SS 4.2 "Alternative Transportation: Bicycle Storage and Changing Rooms."</p>
F&H	<p>6. KUCR: F&H presented an overview of the program for KUCR, including the new single story plan.</p> <p>a. General Program Discussion</p> <p>i. As requested, two studio production rooms have been provided.</p> <p>ii. It may be possible to reduce the square footage of the Library, however this issue will require further study during the design phase.</p> <p>iii. F&H to study an informal conference area at the wide hallway near the two Edit/Post-Production Rooms.</p>
F&H F&H F&H	<p>7. Shared Outdoor Spaces: F&H presented an overview of the program for the outdoor spaces, including seat count.</p> <p>a. Seating</p> <p>i. Dining seating areas (indoor at the Barn and outdoor at the East Courtyard and West Courtyard), total 6,695 SF, allowing for 332 seats (based on approximately 20 SF/seat). The seat count was found to be acceptable.</p> <p>b. West Courtyard</p> <p>i. F&H to note in the narrative the option of moving Sound/Lighting control to the back edge of seating in the West Courtyard will be studied further during design.</p> <p>ii. F&H to revise the Outdoor BBQ layout and criteria.</p> <ul style="list-style-type: none"> • It will be a self-contained unit with a BBQ grill, exhaust hood, refrigerator, sink, and POS. • The Outdoor BBQ will not be covered by a roof, however a chimney above the cooking area will be need to direct smoke out of the courtyard. • Its location along the south edge of the West Courtyard is acceptable, but it does not necessarily need to be attached to the north wall of the Kitchen Addition. <p>iii. F&H to revise the site plan to show the Outdoor Condiment Counter and Queuing adjacent to the Outdoor BBQ and Bar.</p>
	<p>8. Materials: The concept presented by F&H for the use of materials to highlight the hierarchy of the existing, new and tertiary structures was found to be acceptable.</p> <p>a. Existing: Materials at the existing buildings will be consistent with the heritage of these buildings.</p> <p>b. New: The new buildings will employ contrasting materials that allow the structures to recede, maintaining the historic structures as the focal point.</p> <p>c. Tertiary: The tertiary structures will be largely landscape type structures that use materials and plantings to knit together the existing and new buildings.</p>
F&H	<p>9. Site Circulation</p> <p>a. Landscape Approach: F&H presented a sketch by Lutsko Associates (Landscape Architect) for the intersection of the Eucalyptus Walk, the Barn Walk and West Campus Drive.</p> <p>i. F&H will incorporate the landscape sketch of southeast corner on a larger</p>

Workshop #4: Meeting Notes

ACTION BY:	ITEM:
F&H	<p>site plan to better illustrate the surrounding context.</p> <p>b. Vehicle Access</p> <ul style="list-style-type: none"> i. The drive aisle near the Barn Loading Dock allows approximately 10 feet of clearance for a car to pass while a truck is unloading. ii. Sproul Loading Dock: A simplified Sproul Loading Dock layout without a truck turnaround was accepted. <ul style="list-style-type: none"> • F&H to revise the wall at the north end of the Sproul Loading Dock to allow for fire truck through access. • The accepted scheme provides a reconfigured area for service cart storage (4 spaces for media services and 2 spaces for service vehicles) and a location for trash and recycling bins. Access will be limited to service vehicles (no public). • Nita Bullock to confirm that an ADA space is not required if these service spaces are considered "cart storage" rather than "parking."
NB	<p>10. Systems</p> <ul style="list-style-type: none"> a. Steam and Chilled Water: There are times when the campus steam and chilled water system is shut down. <ul style="list-style-type: none"> i. Housing to confirm with Physical Plant (between DPP and design) the timing for when steam and chilled water are shut down. ii. Critical services that need to be maintained at the Kitchen Addition are refrigeration and domestic hot water. b. Heating / Cooling <ul style="list-style-type: none"> i. Radiant system proposed for Barn Stable Lobby and KUCR. ii. Forced air system proposed for Barn Kitchen and Cottage. iii. Radiant systems are preferred for the Barn Stable and Barn Dining, However this system will be studied during design for its ability to respond to quick changes for heating and cooling loads. Forced air in these spaces would be the alternative. c. Electrical <ul style="list-style-type: none"> i. Site Lighting: NB to check with Physical Plant to see if (and how many) existing campus streetlights would be available to incorporate into the project. ii. Barn Kitchen and KUCR require backup power from a shared diesel-powered generator. An acoustical cover will not be needed. Location and size of generator to be determined during design. d. Security <ul style="list-style-type: none"> i. UCR Physical Plant to provide infrastructure for security systems (up to points of access), Barn project to carry systems across site and provide all required devices. ii. OLI to include wiring for all systems (assume none will be wireless). iii. Susan Marshburn (SM) and CG to provide electronic door access (card swipe) count and camera count. e. A/V and Internet Access <ul style="list-style-type: none"> i. Speakers at Barn Dining, Cottage, and Barn Stable Meeting Room. ii. An empty conduit will be provided at the Lighting/Sound booth for running coaxial cable to and from KUCR. iii. Wireless internet access to be provided across entire site. JH to confirm who provides wireless nodes.
NB	
OLI SM/CG	
JH	

Workshop #4: Meeting Notes

ACTION BY:	ITEM:
OLI	<p>11. LEED: F&H presented a draft assessment of the project LEED checklist.</p> <ul style="list-style-type: none"> a. LEED Certification Level: While LEED Silver Certification is required by UCR for The Barn Project, LEED Gold is the current target. This level of certification is largely dependent on connection to the campus steam and chilled water system. b. Enhanced Commissioning: OLI will add Enhanced Commissioning to the Cost Plan as a “below the line” item.
F&H	<p>12. Phasing and Implementation</p> <ul style="list-style-type: none"> c. Phase 1 <ul style="list-style-type: none"> i. Initial work in Phase 1 will include items identified as having potential schedule complications or other risks. These include: moving the Barn Stable and the utility work. Ideally this work would begin before Summer 2011. ii. Phase 1A <ul style="list-style-type: none"> • Phase 1A will include: the Kitchen Addition, the Cottage, the Loading Dock Area, and the Drive Aisle along West Campus Drive. • The Kitchen Addition should be up and running before the end of summer. Maintaining a functioning kitchen is critical during the school year. The Kitchen Addition will require at least a 12-month window for completion. • Demolition of the current University Club meeting space can occur in Phase 1A. iii. Phase 1B <ul style="list-style-type: none"> • Phase 1B will include: Barn Dining, the East Courtyard, and the Restrooms east of The Barn. • During the school year when Barn Dining is under construction, the Barn Stable, Cottage, and related seating areas can be used for dining and be served by the Kitchen Addition. d. Phase 2 <ul style="list-style-type: none"> i. Phase 2 will include: the West Courtyard, Stage, and KUCR. ii. The construction fence at the west side of The Barn will be close to along the west side of the building, allowing for exiting only. No West Courtyard seating will be provided during Phase 2. <ul style="list-style-type: none"> • This approach will provide a clean division between Phases 1 and 2. • It was agreed that construction activities would be too disruptive to outdoor dining at the West Courtyard. e. Preliminary Scheduling <ul style="list-style-type: none"> i. F&H to develop a preliminary design and construction schedule. ii. Construction to begin sometime between spring and early summer of 2011. iii. Construction Scheduling will be clarified once design begins and there is a better understanding of project engineering. A Construction Manager at Risk (CMAR) will be hired early in the design phase to help facilitate construction scheduling and implementation. iv. Construction noise will need to be carefully managed during dining hours. Halting construction during the lunch hours, however, will have a significant impact on costs. v. During Phase 2, due to the construction of the West Courtyard, there will be a significant lack of outdoor seating. Overflow seating may be provided at the Barn Stable, Barn Stable Patio, and/or frontage seating to the south of the Cottage.

Workshop #4: Meeting Notes

ACTION BY:	ITEM:

	<p>13. Cost Plan: Scott Lewis (of OLI) presented the cost plan, including assumptions.</p>
	<p>a. General Elements</p> <ul style="list-style-type: none"> i. Site work directly associated with each building was included with that building. ii. Utilities connections associated with each building were included with that building. (Note: the majority of the utility work will occur in Phase 1) iii. Phases run without a break between. iv. Preparation of the ground surface for the Phase 2 staging area will be completed during Phase 1.
OLI	<ul style="list-style-type: none"> v. OLI to revise the Cost Plan so that the 10% design contingency is expressed as a line item and not rolled into the estimate. vi. Estimates were obtained from local contractors for the relocation of the Cottage and the Barn Stable. The estimates were considered very low, and so a multiplier was applied to ensure the item is sufficiently covered in the Cost Plan.
OLI	<ul style="list-style-type: none"> vii. OLI to add a line item for HAZMAT work by owner, per the HAZMAT report dated February 19, 2010. viii. Chillers, boilers, etc. are not included in Mechanical rooms. Estimate assumes that project will tap into existing steam and chilled water system.
OLI	<ul style="list-style-type: none"> ix. OLI to provide an updated version of the Cost Plan.
	<p>b. Structures / Materials</p> <ul style="list-style-type: none"> i. Seismic work for the existing buildings can be done from inside. ii. Masonry: Kitchen Addition, KUCR, Restrooms. iii. Stud framing: additions (Barn Dining and Barn Stable). iv. Interior walls will include curbs at the Kitchen Addition. v. Metal or wood cladding at all new buildings. <ul style="list-style-type: none"> • Wood may be used in place of metal, but pricing for metal allows flexibility for cost plan. vi. Pitched roofs were assumed for all new construction. <ul style="list-style-type: none"> • KUCR will require a metal roof due to the low slope. • Roofs may not be gables, but pricing as such allows for flexibility for the Cost Plan. vii. Light wells and clerestories are included in estimate.
	<p>c. Finishes</p> <ul style="list-style-type: none"> i. Patch/paint existing wood at Theater as a “below the line” item. ii. Allowances were made for polished or colored concrete for floors at Barn Dining and Barn Stable Meeting. iii. Quarry tile or epoxy floor at Barn Served and Kitchen.
	<p>d. Value Engineering: Kieron Brunelle related the project will approach budget constraints through a “value added” approach rather than simply cutting costs.</p>
	<p>e. Cost Plan Revisions/Clarifications</p> <ul style="list-style-type: none"> i. In order to calculate rent for KUCR, the Stage and Backstage will be called out as “Allowance included in the Cost Plan in order to show the cost of these spaces. ii. The Schedule is needed for preparing the business plan.

Workshop #4: Meeting Notes

ACTION BY:	ITEM:
	<ul style="list-style-type: none"> iii. Assume a CMAR will be used. Bid packages are preferred. iv. Cost Plan does not include the Barn Theater. v. It will be determined in design if Sproul Loading Dock will be part of the project. vi. A new UC delivery system allows campus projects under \$60M to proceed at risk. f. “Below the Line” Items: will be treated as alternatives. <ul style="list-style-type: none"> i. Alterations to Sproul Hall Loading Dock ii. On-site chiller and boiler in lieu of campus connection iii. Audio visual equipment as described in DPP report iv. Emergency power for Kitchen Addition and KUCR v. Construction Management Preconstruction Services vi. Enhanced Commissioning / 3rd Party Commissioning vii. Patching and painting the Barn Theater viii. Security Devices
<p>F&H</p> <p>F&H</p> <p>F&H</p> <p>F&H</p> <p>JN</p>	<p>14. Next Steps</p> <p>a. Project</p> <ul style="list-style-type: none"> i. Program and phasing have been approved. ii. Design to be carried through construction documents (on all parts of the project, including KUCR). F&H noted that a year will likely be required for design. iii. Bidding/approval process will take at least two months. iv. Ideally, construction to begin sometime between spring and early summer of 2011. v. CPAC presentation may be deferred until June. <p>b. Materials</p> <p>i. DPP</p> <ul style="list-style-type: none"> • F&H to review discrepancies between project area summary and room data sheets, including the net-to-gross ratio. • F&H to remove dimensions from drawings contained in room data sheets. • F&H to work through literary portions of DPP. • F&H to include backup documentation (important decisions and directives) in Appendix. <p>ii. Documentation</p> <ul style="list-style-type: none"> • JN to provide record drawings of existing Barn structures (dating from 1916-1917 and 1985). • Geotech report also needed early in design. • Site survey to be completed before design begins.

Correspondence

INDEX OF CORRESPONDENCE - 2010

February 5, 2010	UCPD Review (letter)	April 5, 2010	Existing Barn Performances (spreadsheet)
February 8, 2010	Sproul Loading Dock Truck Access (email)	April 5, 2010	Barn Seat Utilization Study (email)
February 12, 2010	Sproul Loading Dock_Cart Storage_Parking (email)	April 8, 2010	Central Plant Utility Connection Costs (email)
February 22, 2010	Electrical Review (letter and diagrams)	April 8, 2010	Stage Equipment Costs (email)
February 23, 2010	Trash Truck Information (email)	April 15, 2010	Seating Count Issues (email)
February 24, 2010	Plumbing Review (letter)	April 19, 2010	Historical Resources Review (email)
March 2, 2010	Kitchen Addition Loading Dock_Truck Length (email)	April 21, 2010	Naming Conventions (email)
March 4, 2010	Telecom Closet Sizes from Communication Services (email)	April 23, 2010	Emergency Generator (email)
March 12, 2010	HVAC Utilities (email including diagrams)	May 10, 2010	Campus Steam Shutdown Schedule (email)
March 12, 2010	Walnut Tree Location (email including diagram)	November 16, 2009	Dining Master Planning Study (spreadsheet)
March 22, 2010	Barn Theatre Study – Performing Arts (letter)		

Correspondence

UNIVERSITY OF CALIFORNIA, RIVERSIDE

BERKELEY § DAVIS § IRVINE § LOS ANGELES § MERCED § RIVERSIDE § SAN DIEGO § SAN FRANCISCO



SANTA BARBARA § SANTA CRUZ

POLICE DEPARTMENT

3500 Canyon Crest Drive
 Riverside, CA 92521-0218
 Phone: (951) 827-5222
 Fax: (951) 683-1639
<http://www.police.ucr.edu>

February 5, 2010

To: Jonathan C. Harvey, Principal Educational Facilities Planner
 Fr: John Freese, Lieutenant, University of California Police Department
 Re: Barn Area Study – Safety & Security Issues

Crime Prevention Through Environmental Design (CPTED)

This project should employ the CPTED concepts to provide a space that is welcoming to patrons and discourages criminal behavior.

Main areas of concerns:

- Adequate lighting in and around the structures that is pedestrian friendly and mitigates dark areas that could provide hiding places for the criminal element.
- Low lying landscaping that eliminates hiding places and keeps an open line of sight between the facilities and parking areas.

Security/Surveillance Cameras

There is a need for a security camera system that is consistent with current campus systems.

- Coverage of at least the cashier, box office, and alcohol service and consumption areas.
- Internet IP address accessibility with pan/tilt/zoom control for UCPD Communications to access in the event of a police response (UCPD will not monitor the system on a routine basis).
- DVR storage of video footage consistent with current campus time frame standards.

Burglary/Panic Alarms

At a minimum, there should be an entry and motion detector alarm for the main buildings, including KUCR. Panic alarms should be installed at the cashier, and box office, and KUCR main desk and DJ areas.

Access Control

Permanent fencing is needed around the alcohol consumption area to prevent patrons from passing alcoholic beverages through to people outside of the area.

Some type of fencing or barricade is needed around the KUCR radio tower to prevent people from climbing and/or tampering with the tower.

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: FW: Barn Project Phase 1 & 2 Loading Dock Question
Date: February 8, 2010 1:10:03 PM PST
To: "Jason Wilkinson" <jw@fernauhartman.com>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

Jason,

FYI

Jon

From: Mike Terry [<mailto:Mike.Terry@ucr.edu>]
Sent: Friday, February 05, 2010 8:49 AM
To: jon.harvey@ucr.edu
Cc: Kieron Brunelle; Susan Marshburn (susan.marshburn@ucr.edu); Mike Miller
Subject: RE: Barn Project Phase 1 & 2 Loading Dock Question

Jon,

Here's an update on your information request.

Per Toshio Ishida, Asst Director Landscape & Refuse Services:
 "The refuse and recycling pick-ups are made with standard refuse trucks. Average size = 13 ft high, 38 ft long, and 9 ft wide. The refuse is picked up everyday Mon-Fri and recycling is twice a week. Recycling will not change as of right now. Refuse may move to a different unit, the length may increase a few feet. I don't have current specs because we have not had a final decision on what we will use. It will require at least the same amount of space as now.

That area is already very tight now. We have to pull in and have a spotter back us all the way out past the lift gate each day. I would not recommend making it any smaller than it is. When cars are present on both sides, we have a very hard time now. If you need more information let me know."

I have not received a reply from Material Management on the size of their vehicles and frequency of use, but they do not have any larger than the P Plant refuse trucks.

Thanks,
 Mike

APPENDIX

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: FW: Barn Project - Student Special Services Parking
Date: February 12, 2010 9:03:19 AM PST
To: "Jason Wilkinson" <jw@fernauhartman.com>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

Jason,

Let me know if you have any questions or require additional information related to the Student Special Services parking requirements by the loading dock.

Thanks

Jon

From: Mike Delo [<mailto:Mike.Delo@ucr.edu>]
Sent: Friday, February 12, 2010 8:59 AM
To: jon.harvey@ucr.edu
Cc: Andy Steward (andrew.stewart@ucr.edu); Kieron Brunelle; marcia.schiffer@ucr.edu; Tammie Pierce; Enci Naghshineh; Lenita Kellstrand
Subject: RE: Barn Project - Student Special Services Parking

Jon,

TAPS and Student Affairs have agreed to transition disabled student transport service to TAPS effective July 1. So, it is likely that Student Special Services will not retain its transport vehicles that now park in the Sproul Hall service area. That demand for the two parking spaces in the Sproul Hall loading dock will go away.

Maybe this factor will increase the likelihood of retaining disabled parking spaces within the loading dock area.

Let me know if other information is required.

Mike

From: Jon Harvey [<mailto:jon.harvey@ucr.edu>]
Sent: Thursday, February 11, 2010 1:52 PM
To: Mike Delo
Cc: Andy Steward (andrew.stewart@ucr.edu); Kieron Brunelle; marcia.schiffer@ucr.edu
Subject: Barn Project - Student Special Services Parking

Mike,

At last week's Barn Project Phase 1 & 2, workshop, parking at the Sproul Hall loading dock was discussed. Student Special Services is one group that parking two transport vans in the area.

As part of the Medical Infrastructure Phase 1 project, Student Special Services completed a survey which described

the Student Mobility Services operation. Transport vans are parked at various locations through out the day, and are parked overnight at dedicated spaces across from Sproul Hall loading dock. Student Special Services is open to finding an alternative overnight parking location for the vans per conversation with Marcia Schiffer, Director, Services for Students with Disabilities Special Services,

Request that you contact Marcia Schiffer to identify another transport vans parking location, which will free space in the Sproul Hall loading dock area.

Please let me know how long it will take to identify the location, and the proposed implementation timeframe.

Thanks

Jon

Jon Harvey
 Capital & Physical Planning
 951-827-6952

APPENDIX

Correspondence

Barn Project Electrical Review

In reviewing the project description for the Barn Project Phase 1 and 2 and relocation of the cottage Physical Plant would like to make the following electrical recommendations. For review, I have attached a copy of the underground electrical drawings, and an outline of the buildings each feeder serves.

- This area is the main thoroughfare for all of the campus electrical utility systems. Any excavations would need to take place with extreme consideration to this fact. If any one of these feeders becomes compromised it would cause significant campus power outages as each feeder serves multiple buildings.
- The Barn is currently fed from the 5kv substation and has an 800 amp service. We recommend upgrading the service to at least 1200 amps to accommodate the described improvements.
- During this improvement Physical Plant would require the new service to be tied in to the 12kv substation. This can be accomplished by tying in to the 12kv in vault 3 next to the parking lot exit for the cottage.
- Additionally the transformer would need to be replaced in order to accommodate the 1200 amp service and to be tied in to the 12kv system.
- Physical Plant would retain the old 800 amp service and transformer. These items should not be disposed of or resold by the contractor.

Because of the sensitivity of this area electrically to the campus I would welcome the opportunity to be involved during the ongoing planning process. Please feel free to contact me directly for any additional information or questions.

Eric Shuler
 Electrical Shop Supervisor
 951-827-3112 Office
 951-827-4596 Fax
 ericshuler@ucr.edu



**Campus Electrical Circuits
4,160 Volt System
10/1/99**

CIRCUIT 2 Humanities/Olmsted D	CIRCUIT 4 Student Health Center D Corporation Yard D
CIRCUIT 3 (The Barn) Barn Theater and Dance Studio O (The Cottage) O Domestic Water Pump Pit D Football Field D Hinderaker Hall D Intramural Fields D Physiatrist Education Bldg. D Riversa Library/Library South D Sprout Hall D Tennis Courts D Underpass Pump Station D Watkins D	CIRCUIT 6 Bell Tower D Geology D Physics D O
	CIRCUIT 7 Greenhouses Pierce Hall
	CIRCUIT 8 Greenhouses 6-10, 11-14, 15-17 Steam Plant

Some list

CIRCUIT 3A Fine Arts New Humanities	CIRCUIT 3B Surge O PE O Bookstore D Stadium O	Costo Hall O SASS D Chess D Arts D
CIRCUIT 4A Satellite Chiller Plant O	CIRCUIT 4B	

Blue Tags
Green

I think Arts is on B

**Campus Electrical Circuits
12,000 Volt System
10/1/999**

**CIRCUIT 1A
Steam Plant 12KV/4160V Substation**


Section 1 A Gary Anderson Batchelor Hall Botanic Gardens Biology Bldg. College Bld. North College Bld. South Custodial/Grounds Bld. Environmental Health & Safety Entomology - Old Fawcett Lab Greenhouse 1 Greenhouse 2a Greenhouse 3 Greenhouses 18-21 Greenhouses	Section 2 Life Science 1500 Life Science Psychology	Section 3 4160 volt Steam Plant chillers 1 & 2
Section 1 Greenhouse 51 Greenhouse 52 Insectary Lynimeter Bldg. Soils Facility SPNV Chapman Hall Stored Products Superintendents Cottage Trailers 1-15 (Surge Facility) University Office Building Upper Still House 800MHz Building	Section 2 Speith Hall	
Circuit 1B New Quarantine Building Insectary UILB New Entomology	Bio Science Bld. D Greenhouses O	
Circuit 2A Lothian Hall Student recreation Center Parking Services SAC/CLC Library Werner	PSI Boyce Com Stat Science Lab1 Rooms A & B D	Aberdeen & Inverness res. Hall D Engineering Sciences D Penland Hills D Geology Addition D
Circuit 2B Modular Building Lot 9 Penland Hills	Glennmor O	

Red

Red

4 cell

4 cell



Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: **FW: Barn Project - Trash Truck Information**
Date: February 23, 2010 4:14:42 PM PST
To: "Jason Wilkinson" <jw@fernauhartman.com>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

Jason,

FYI

Jon

From: Mike Terry [<mailto:mike.terry@ucr.edu>]
Sent: Tuesday, February 23, 2010 4:08 PM
To: jon.harvey@ucr.edu
Cc: Mike Miller; Kieron Brunelle; Toshio Ishida
Subject: RE: Barn Project - Trash Truck Information

Jon,

As discussed earlier today, per Toshio Ishida, Asst. Director Landscape & Refuse Services, the trash truck radius is the same as the large fire truck turning radius identified in the City of Riverside bulletin already supplied to you. Please let me know if you need that info sheet resent.

Thanks,
Mike

APPENDIX

Correspondence

Barn Project Plumbing Review

In reviewing the project description for the Barn Project Phase 1 & 2 and relocation Physical Plant would like to make the following plumbing recommendations.

Barn building utilities:

Water is provided from Campus owned water mains (12" with pressure of 110psi to 135 psi) with 6" domestic supply which supplies 6" Barn fire main and 2" domestic Barn supply followed by second 6" feed (valve) for Stable 2" fire main and Theater 2-1/2" fire main.

Recommend that water system modifications still be provided from Campus owned water mains with addition of Service Protection Backflows.

Gas is provided by Southern California Gas Co. meter with additional 3/4" feed lines underground to the Stable and theater buildings currently capped off. (non use)

Recommend that gas continue to be provided by Southern California Gas Co.

Sewer mains system A has been upgraded in size to 12" and is located in the street area with 4" lateral for Barn sewer system.

Recommend that any Barn sewer system changes include new laterals to new 12" main sewer.

Barn has very little small storm discharge lines from site to street storm drains 18" to 24" in size.

Recommend same use and connections be to 18" and 24" storm drains.

Cottage building utilities:

Water sized is 3/4" domestic connected to the campus 12" water main in the street to Cottage with additional small 1/2" water line from this system 1/2" underground to Cottage garage exist.

Recommend new water supply to campus water main in area with service protection.

Sewer system "A" 12" in street had lateral for Barn 4" and 1-1/2" for garage.

Recommend new sewer to Cottage be connected to Sewer system "B"

Natural gas 3/4" supplied by Southern California Gas Company.

Recommend new service line from Southern California Gas Company extending to new site location.

Cottage has no storm area drains (use of parking lot and street)

Recommend area drain installations for new location be connected to street mains 18"-24" depending on location.

Thanks

Jerry Higgins

UCR Plumbing Supervisor

951-827-7696

Jerry.Higgins@ucr.edu

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: FW: Sysco truck length
Date: March 2, 2010 3:53:10 PM PST
To: "Jason Wilkinson" <jw@fernauhartman.com>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

From: Cheryl Garner [<mailto:Cheryl.Garner@ucr.edu>]
Sent: Tuesday, March 02, 2010 2:00 PM
To: Susan Marshburn; jon.harvey@ucr.edu; llanier@laschobersovich.com
Subject: FW: Sysco truck length

It appears that our primary vendor does deliver in a 54 foot tractor and trailer.

This obviously would be the very largest truck.

Cheryl Garner
 Director of Dining Services
 University of California, Riverside
 Office: (951) 827-5857
 Cell: (951) 333-4700

*If you don't like change, you're going to
 like irrelevance a lot less.*

Tom Feltenstein

From: Gary Burton [<mailto:gary.burton@ucr.edu>]
Sent: Tuesday, March 02, 2010 10:11 AM
To: Cheryl Garner
Subject: Sysco truck length

Cheryl,

The overall length of the tractor and trailer is 54ft.

Sorry to be late in responding but I have been out sick for a few days.

Regards,

Gary

APPENDIX

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: FW: Barn Telecom Closet Sizes
Date: March 4, 2010 10:42:22 AM PST
To: "Jason Wilkinson" <jw@fernauhartman.com>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>
 ▶ 1 Attachment, 4.0 KB

Jason,

The size of telecom closet per communications is below for your information.

Jon

From: Tim Gable [<mailto:timgable@ucr.edu>]
Sent: Thursday, March 04, 2010 10:35 AM
To: jon.harvey@ucr.edu
Subject: RE: Barn

Yes, that is correct...

Regards,
 Tim Gable, RCDD, OSP
 Campus Planner
 Communications Services
 Telephone Building



Voice: 951-827-4584
 Fax: 951-827-5600
 Cell: 951-522-4599

From: Jon Harvey [<mailto:jon.harvey@ucr.edu>]
Sent: Thursday, March 04, 2010 8:14 AM
To: Tim Gable
Subject: RE: Barn

Tim,

Just want to confirm that the space below is for the telecom closets in each building.

Jon

From: Tim Gable [<mailto:timgable@ucr.edu>]
Sent: Thursday, March 04, 2010 6:07 AM
To: jon.harvey@ucr.edu
Subject: Barn

Jon

As a follow up to our discussion this past Friday; The Barn area contains two (2) conduit runs, the current feed on the South side of the Barn and an existing duct bank on the West side of which we would like to feed the new KUCR building from.

Based on the current preliminary information the amount of space required at each facility is as follows;

Barn – 10' X 12'
 KUCR – 10' X 10'
 Barn Annex – 6' X 8'
 Barn Theater – 6' X 8'
 Cottage – 6' X 8'

Please contact me if you have any questions.

Thank you,

Regards,
 Tim Gable, RCDD, OSP
 Campus Planner
 Communications Services
 Telephone Building



Voice: 951-827-4584
 Fax: 951-827-5600
 Cell: 951-522-4599

APPENDIX

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
 Subject: **FW: Barn Project HVAC utilities**
 Date: March 12, 2010 3:20:02 PM PST
 To: "Jason Wilkinson" <jw@fernauhartman.com>
 Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>
 2 Attachments, 1.7 MB

Jason,
 FYI
 Jon

-----Original Message-----

From: Jacqueline Norman [mailto:Jacqueline.Norman@ucr.edu]
 Sent: Friday, March 12, 2010 2:58 PM
 To: jon.harvey@ucr.edu
 Subject: FW: Barn Project HVAC utilities

Jon,

Please find attached additional comments that were sent to Rich, with attachments.

Jacqueline Norman | Office of Design and Construction | University of California, Riverside | 951.827.6316

-----Original Message-----

From: Chris Flanders [mailto:Chris.Flanders@ucr.edu]
 Sent: Friday, February 26, 2010 9:28 AM
 To: Richard Racicot; patrick.simone@ucr.edu; Jacqueline Norman
 Subject: RE: Barn Project HVAC utilities

Rich,

I revisited this, and discussed it with our two veterans (Frank Porter and Steve Benart, who have been here since Anderson Hall was built I think). We all agree that the most likely POC is Vault 15, which I overlooked during Geovision's walk. This high-ceilinged vault contains large services directly from the plant, with blanked-off isolation valves for both services (CHWS/R, steam, condensate return). There is a manhole access located in the sidewalk intersection between Watkins Hall and University Theater. From there the Barn is in your line of sight, with only an access road as an obstacle...distance maybe 250 feet as the crow flies.

Hopefully they will do careful engineering for this connection. While we do not have any direct evidence of capacity problems with condensate return on that particular line, we have had a troubling history with that system where it returns along the Vault 6-9-10 route. We suspect that we are at max capacity over there, so it deserves some attention. At the very least, any new connections should definitely include some gauge ports & service valves etc. for monitoring. Increasing the condensate return line size on that route would be fairly straightforward until you get to the plant...increasing the size from the plant entrance to the receiver looks like a big problem though.

My personal suggestion: if these utilities are tapped for this project, they should be oversized between Vault 15 and the project area POC, to make future upgrades more convenient. We would also be very interested in the plumbing plan at Vault 15 POC, to ensure that maintenance and repair access is not compromised there.

Attached is a schematic of Vault 15 utilities (no sizes shown). FYI, Steve Benart has been surveying the entire tunnel system and producing these schematics. Our goal is to create a schematic of the entire tunnel system, to create a comprehensive valve schedule and try to catch up on thirty years of deferred construction record-keeping. Within a few months I hope to bring Steve's drawings to Jeff Saito's folks for conversion to a CAD master plan.

Chris Flanders
 Climate Control Supervisor
 University of California, Riverside
 Steam Plant
 ph (951)827-6235
 fx (951)827-5404
chris.flanders@ucr.edu

-----Original Message-----


From: Richard Racicot [mailto:Richard.Racicot@ucr.edu]
 Sent: Thursday, February 25, 2010 4:42 PM
 To: Chris Flanders
 Subject: RE: Barn Project HVAC utilities

At this time the proposal for GeoVision was to conduct their survey around the Barn Area. It did not include areas back to the utility tunnels. The survey was outlined to include all areas around the Barn Area up to the face of the surrounding buildings. Yes, if an addition survey is needed to one of the tunnel locations we will conduct an additional survey if needed. During this Phase of the project, we are trying to determine if it is cost effective to supply utilities to the


Barn project from the one of the tunnels. The length of the connection could be the cost breaker. What are your thoughts. As always, that's for your input.

Richard W. Racicot, A.I.A.
 Assistant Vice Chancellor

Facilities - Design & Construction
 3615-A Canyon Crest Drive
 Riverside, California 92507
 951.827.1277 Office
 951.827.3890 Fax



○	Drp Leg Steam Trap 1	3/4" Armstrong 800
⊗	Expansion Joints 1, 2, 3 and 4	12" Ball/Swivel, Chilled Water Return



APPENDIX

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
 Subject: **RE: UCR Barn DPP - Tree Location**
 Date: March 12, 2010 8:56:06 AM PST
 To: "Jason Wilkinson" <jw@fernauhartman.com>
 Cc: "Laura Hartman" <lh@fernauhartman.com>
 Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>
 1 Attachment, 275 KB

Jason,

We are trying to plot the locations and hopefully this will be finished this afternoon. Once completed, the approximate location of the trees (plus or minus three feet) in an around the site will be identified.

Attached is the approximate location of the walnut tree from three campus points, and photos of the tree for your information and use.

We are interested to know the impact to the program by retaining the tree.

Thanks

Jon

From: Jason Wilkinson [mailto:jw@fernauhartman.com]
 Sent: Thursday, March 11, 2010 4:46 PM
 To: Jonathan Harvey
 Cc: Laura Hartman
 Subject: UCR Barn DPP - Tree Location

Hi Jon,

If it is important for us to design KUCR around the Walnut tree, not knowing the location is holding us up. We need this information as soon as possible. Otherwise, please let us know if we should move ahead without trying to save the tree.

Thanks,
 Jason

Jason Wilkinson
 Fernau & Hartman Architects, Inc.
 (t) 510.848.4480
 (f) 510.848.4532
<http://www.fernauhartman.com>



[Barn_Pri_Tre....pdf \(275 KB\)](#)

Barn Project Phases 1 & 2
 March 12, 2010

Approximate diameter of the tree (orange tape) is 30 inches



Barn Project Phases 1 & 2
 March 12, 2010

Approximate location of the Walnut Tree
 Requires field verification



Point	Description	Approximate Distance
A	Light pole, west side of West Campus Drive	89 ft
B	Speed Bump right lane marking	46 ft
C	SW Corner of Barn Stable	34 ft

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
 Subject: **FW: Barn Theatre Project**
 Date: March 22, 2010 8:03:55 AM PDT
 To: "Jason Wilkinson" <jw@fernauhartman.com>
 Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>
 ▶ 1 Attachment, 27.5 KB

Jason,

Per WS-3

Jon

From: Nathaniel Jones [<mailto:natej@ucr.edu>]
Sent: Friday, March 19, 2010 4:42 PM
To: jon.harvey@ucr.edu
Cc: 'Paul Richardson'
Subject: Barn Theatre Project

Hello Jon:

It was good to see you this morning. I also enjoyed chatting with you over lunch. As discussed, please find an electronic copy of the document I provided you today. As I indicated earlier, the gross scaling of the Barn Theatre and related spaces appears to be adequate to support the likely programmatic use of these facilities. The document provided highlights both general and specific programmatic requirements that would need to be taken into account during the design development phase of the project. Also thoughtful consideration needs to be given to issues of phasing, constructability, security, access and programmatic use of shared/multi-user spaces. I look forward to our continued work on this project. If you have any questions, please feel free to contact me. Take care.

Nate

Nathaniel Jones III, Ph.D., MBA
Assistant Dean & Chief Financial & Administrative Officer
College of Humanities, Arts & Social Sciences
University of California at Riverside
900 University Ave
Riverside, CA 92521
951-827-5062 (Office)
951-827-7975 (Fax)
410-952-3652 (Mobile 1)
951-237-2168 (Mobile 2)



[Barn Theatre...oc \(27.5 KB\)](#)

Correspondence

Barn Theatre Study CHASS Performing Arts Programming Analysis

Usage:

Dance Department intends to use the space 15 hours per week for studio courses and MFA project rehearsals. Music Department currently uses the space 38 hours per week for courses, rehearsals and music clubs. They would expect the usage to expand depending on the size expansion. Theatre Department is considering use of the space for student works, rehearsals, performances and coursework. The department chair expects the usage to be up to 36 hours per week. The Department of Theatre expects at least one course per quarter to be scheduled in the Barn Theatre. All departments would expect to benefit from the building transformation. This would allow additional rehearsal and performance space to better support the current academic programs.

Facility Attributes:

A few facility attributes are missing or need to be altered in order to accommodate the three departments. The new construction calls for a basic restroom facility. An expanded restroom facility could include dressing areas and make-up tables. Clothes/costumes racks installed in the restroom areas would be a great benefit. In review of the conceptual estimate, there is not a mention of an installed lighting or sound grid. The lighting grid would need to be included on the interior and exterior portions of the facility. Electrical distribution would have to be included as well as with the proper power requirements. The structural grid will need to support such a lighting system. The existing flooring would have to be extended throughout the facility. Network capabilities have been requested due to the programming from the departments. Three data/communication lines would need to be provided for the office and rehearsal spaces. Adequate HVAC, acoustics, security features, general power and lighting must also be provided. A water fountain should be added as well.

Physical Expansion:

Expanding the physical space is easily the most crucial part of this project. The ability to allow multiple activities and have the capability to perform with an audience is of the most importance. A soundproof wall system between rehearsal 01 and rehearsal 02 is crucial in order to maximize the expected use. Separate exterior entrances would be necessary to both rehearsal areas. Each area must be designed to be usable by all anticipated users. Flooring systems that are flexible enough to be used for dance, music and theatre would be ideal. Alternatively, a flooring system could be installed for the primary use and a protection system provided to cover the floor for the other uses.

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: **FW: Barn Performances**
Date: April 5, 2010 10:11:12 AM PDT
To: "Jason Wilkinson" <jw@fernauhartman.com>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>
 ▶ 2 Attachments, 52.7 KB

Jason,

FYI

Jon

From: Cheryl Garner [<mailto:Cheryl.Garner@ucr.edu>]
Sent: Monday, April 05, 2010 9:52 AM
To: jon.harvey@ucr.edu
Cc: Susan Marshburn; Andy Plumley
Subject: Barn Performances
Importance: High

Jon,

Attached is the information that you requested regarding the types of events that are currently performing at the Barn. I had them add the genre and the size of the group where possible so that you would be able to size the stage – or at least have some information that might assist in sizing it. I also had them identify how many people attended the event – for your purposes this is the number noted under "In". This might assist us in deciding how big the space needs to be in front of the stage.

Please note: They would like to schedule Video Game Tournaments, Movie Nights, Sports Event Viewing and Karaoke inside the Barn, which requires a package of equipment. I will send you a quote of the types of equipment that they are interested in.

Please call if you have questions regarding the information.

Cheryl Garner

Director of Dining Services

University of California, Riverside

Office: (951) 827-5857

Cell: (951) 333-4700

*If you don't like change, you're going to
 like irrelevance a lot less.*

Tom Feltenstein

From: Jonathan Cubos [<mailto:Jonathan.Cubos@ucr.edu>]
Sent: Monday, April 05, 2010 9:07 AM
To: Cheryl Garner; Albert Esqueda; Cedric Martin
Cc: David Sakover; Pam.Trimble@ucr.edu
Subject: Seat Utilization Info & Barn Music Conference call Info
Importance: High

Good Morning,

I have attached the Seat Utilization chart for 3 days of Lunch Service, 3 spread sheets of Past, current and possible future Barn Music Events and the very scaled down version of a Music System for the Barn. If there are any question please contact David or myself.

Thank you,

Jonathan A Cubos

Senior Operations Manager

The Barn, Ivan's and Bear Tracks

3595 Canyon Crest Drive

Riverside, CA 92507

Office (951) 827-2777

email: jonathan.cubos@ucr.edu



[Barn Music 1....xls \(50.0 KB\)](#)

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: FW: Barn Seat Utilization Study
Date: April 5, 2010 10:11:56 AM PDT
To: "Jason Wilkinson" <jw@fernauhartman.com>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

Jason,

FYI

Jon

From: Cheryl Garner [<mailto:Cheryl.Garner@ucr.edu>]
Sent: Monday, April 05, 2010 9:34 AM
To: jon.harvey@ucr.edu
Cc: Susan Marshburn
Subject: Barn Seat Utilization Study

Jon,

We conducted the seat utilization study at the Barn last week and I wanted to share some general information with you that may assist us in determining the mix of tables that will be required. I looked at the interior seating and the exterior seating separately as we frequently find they differ, and they indeed did. It appears the larger parties preferred to sit outside.

Our seat utilization currently is approximately 53% inside and 61% outside. Our average party size is 2.5 customers.

Here is the breakdown for tables:

Interior Patio		Interior %	Required	If 4 tops are ganged
25	2 tops	49.02%	76% - 2 tops	76% - 2 tops
14	1 tops	27.45%	22% - 4 tops	24% - 4 tops
11	3 tops	21.57%	2% - 6 tops	
1	7 tops	1.96%		
Exterior Patio		Exterior %	Required	If 4 tops are ganged
35	2 tops	37.63%	57% - 2 tops	57% 2 tops
18	1 tops	19.35%	31% - 4 tops	43% 4 tops
19	3 tops	20.43%	6% - 6 tops	
9	4 tops	9.68%	6% - 8 tops	
4	5 tops	4.30%		
2	6 tops	2.15%		
4	7 tops	4.30%		
2	8 tops	2.15%		

The 6 tops and 8 tops may also be translated into 4 tops if we use squares and assume that they will be ganged together, so you may adjust those counts as required. I strongly suggest that we do this for the 8 tops. If the decision is made to add 6 tops – it would only be about 6% of the exterior mix and just one or two tables inside.

Cheryl Garner
 Director of Dining Services
 University of California, Riverside
 Office: (951) 827-5857
 Cell: (951) 333-4700

If you don't like change, you're going to like irrelevance a lot less.
 Tom Feltenstein

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: **Barn Project - Central Plant Utility Connection Costs**
Date: April 8, 2010 4:51:33 PM PDT
To: "Jason Wilkinson" <jw@fernauhartman.com>
Cc: "Kieron Brunelle" <kieron.brunelle@ucr.edu>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

Jason,

During WS-3 direction provided was to examine the costs for direct connections to the Central Plant steam and chilled water lines and a stand-alone system.

Assume that the stand-alone system would be a boiler and chiller, which would provide the campus with the capability to connect to central plant steam and chilled water at a later date. It is not clear how the option could be achieved, or where the equipment would be accommodated on the site inside a mechanical room.

Request that the costs for options be clearly identified and that the direct connection be provided above the line, and options below the line.

Thanks

Jon

Jon Harvey
Capital & Physical Planning
951-827-6952

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: RE: UCR Barn DPP - Performance Issues Discussion
Date: April 8, 2010 8:41:04 AM PDT
To: "Jason Wilkinson" <jw@fernauhartman.com>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

Jason,

Stage equipment costs will need reported in the cost estimate as a below the line number. UCR will not furnish any figures.

We will need to get meeting notes for the conference call that shows the outcomes / direction.

Thanks

Jon

From: Jason Wilkinson [<mailto:jw@fernauhartman.com>]
Sent: Wednesday, April 07, 2010 9:20 PM
To: jon.harvey@ucr.edu
Subject: Fwd: UCR Barn DPP - Performance Issues Discussion

Hi Jon,

I wanted to send this as a follow up to the conference call we had on Monday to confirm the direction. There is some outstanding issues that may not need to be resolved for the deliverable on Monday. One question is what portion of the stage equipment should be included in the estimate and what will be provided by UCR?

Thanks,
Jason

APPENDIX

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
 Subject: **FW: Barn Project - Updated Project Area Summary**
 Date: April 15, 2010 1:01:08 PM PDT
 To: "Jason Wilkinson" <jw@fernauhartman.com>, "Laura Hartman" <lh@fernauhartman.com>
 Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

Jason, Laura,

FYI

Jon

From: Cheryl Garner [<mailto:Cheryl.Garner@ucr.edu>]
Sent: Thursday, April 15, 2010 12:12 PM
To: jon.harvey@ucr.edu; Andy Plumley (andy.plumley@ucr.edu); don.caskey@ucr.edu; Jacqueline Norman; John Ganim; Kieron Brunelle; Nita Bullock; nziad001@ucr.edu; richard.racicot@ucr.edu; Susan Marshburn (susan.marshburn@ucr.edu); Timothy Ralston
Cc: Cheryl Garner
Subject: RE: Barn Project - Updated Project Area Summary

I thought I would provide a little information for us to review as we think about seating:

Total Estimated Lunch Transactions	640
Total Estimated Peak Lunch Hour Transactions (50%)	320
Estimated Seat Turnover (45 minutes)	1.333
Net Seats Required (Occupied)	240
Gross Seats Required @ 75% Utilization	320
10% customers take out food	-32
Total seats required	288
Current Seating	301

There are of course some variables that might change the required seating. For example, our current seat utilization is much lower than 75% based on the table sizes. If I use 65% utilization, the required seating would be 332 rather than 288. Also, we have not accounted for seating for those purchasing coffee, so we will need a margin of error for that as well.

You are currently suggesting 276 seats for the Barn interior and the East and West Courtyard which is less than the 288 required at 75% utilization and without the coffee customer seating.

Cheryl Garner
 Director of Dining Services
 University of California, Riverside
 Office: (951) 827-5857
 Cell: (951) 333-4700

*If you don't like change, you're going to
 like irrelevance a lot less.*
 Tom Feltenstein

From: Jon Harvey [<mailto:jon.harvey@ucr.edu>]
Sent: Wednesday, April 14, 2010 4:33 PM
To: Andy Plumley (andy.plumley@ucr.edu); Cheryl Garner (cheryl.garner@ucr.edu); don.caskey@ucr.edu; Jacqueline Norman; John Ganim; jon.harvey@ucr.edu; Kieron Brunelle; Nita Bullock; nziad001@ucr.edu; richard.racicot@ucr.edu; Susan Marshburn (susan.marshburn@ucr.edu); Timothy Ralston
Subject: Barn Project - Updated Project Area Summary

Steering Committee,

Seating capacity in the interior and exterior dining areas was reviewed and updated

Revised figures are provided in the attached Project Area Summary revised April 14, 2010.

Total number of seats was reduced from the previous summary as follows:

Interior
 Barn Dining - from 108 seats to 94 seats
 Barn Stable - from 50 seats to 43 seats

Exterior
 East Courtyard – from 134 seats to 122 seats
 West Courtyard – from 82 seats to 60 seats
 Barn Stable Patio – remains at 44 seats

The updated outdoor seat counts (188) corresponds with the figure presented in WS-1, while the number of interior seats is less (original target was 108 seats).

Please let me know if you have any questions or concerns with the revised figures.

Thanks

Jon

Jon Harvey
 Capital & Physical Planning
 951-827-6952

APPENDIX

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
 Subject: **FW: Barn Group and Cottage**
 Date: April 16, 2010 8:08:29 AM PDT
 To: "Jason Wilkinson" <jw@fernauhartman.com>, "Laura Hartman" <lh@fernauhartman.com>
 Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

Jason, Laura

FYI

Jon

From: Jacqueline Norman [<mailto:Jacqueline.Norman@ucr.edu>]
Sent: Friday, April 16, 2010 8:03 AM
To: jon.harvey@ucr.edu
Subject: FW: Barn Group and Cottage

FYI – update on Cultural Resources Update.

Jacqueline Norman | Office of Design and Construction | University of California, Riverside | 951.827.6316

From: Tricia Thrasher [<mailto:tricia.thrasher@ucr.edu>]
Sent: Wednesday, April 14, 2010 10:55 AM
To: Jacqueline Norman
Subject: FW: Barn Group and Cottage

FYI

Tricia D. Thrasher, ASLA, LEED AP
 Principal Environmental Project Manager
 UCR Office of Design & Construction

From: Casey Tibbet [<mailto:casey.tibbet@lsa-assoc.com>]
Sent: Wednesday, April 14, 2010 10:44 AM
To: Tricia Thrasher
Subject: Barn Group and Cottage

Hi Tricia,

It was very nice meeting you in person this morning. I appreciate all the information you have provided.

As we discussed, based on the field survey and research the barn group and the cottage do not appear to qualify as "historical resources" pursuant to the California Environmental Quality Act (CEQA). However, they are clearly important to the UCR campus and I would strongly urge you to keep the group together and maintain the rustic character that defines these buildings and

gives some sense that they are associated with the earliest history of the campus. If you haven't done so already, it might be nice to have some sort of historical display in the Barn to reinforce its history.

The historical resources assessment will be submitted to you by April 26, 2010. Please let me know if you have any questions.

Casey Tibbet, M.A.
 Senior Architectural Historian/Historian

LSA Associates, Inc.
 1500 Iowa Avenue, Suite 200
 Riverside, CA 92507
 951-781-9310
 951-781-4277 (fax)

APPENDIX

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
Subject: RE: UCR Barn DPP - Schedule
Date: April 21, 2010 8:43:36 AM PDT
To: "Jason Wilkinson" <jw@fernauhartman.com>
Cc: "Laura Hartman" <lh@fernauhartman.com>, "Kieron Brunelle" <kieron.brunelle@ucr.edu>
Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>

Jason,

This morning is open with the exception of a 10:30 meeting.

Naming conventions were reviewed at WS-3 were Barn Dining, Kitchen Addition, Barn Theater, Cottage, and Barn Stable.

Comments on the text have challenged the naming convention associated with the Barn since comments typically remove the word Dining from the name. Discussion following WS-4 concluded that the Barn refers to both Barn Dining and Kitchen Addition. Unfortunately there are also problems with this approach.

The Official Name of the dining facility is "The Barn" per the Campus Space Inventory system, and the name should therefore be used in the report. The balance of the names should follow the naming convention adopted at WS-3. Suggest that the report introduction address the "The Barn" name adjustment.

Thanks

Jon

From: Jason Wilkinson [<mailto:jw@fernauhartman.com>]
Sent: Tuesday, April 20, 2010 5:47 PM
To: Jonathan Harvey
Cc: Laura Hartman
Subject: UCR Barn DPP - Schedule

Hi Jon,

I was not able to complete the schedule today. I apologize for any inconvenience, however there are many considerations and want to feel confident in the draft document. We have some questions that we would like to go over with you tomorrow morning if possible. Please let us know your availability.

Also we were reviewing our notes and were not sure about the naming convention for "The Barn." Should we refer to the new portion as the "Kitchen Addition" or just "(N)" similar to the annotations for the Barn Stable and Barn Theater?

Regards,
 Jason

 Jason Wilkinson
 Fernau & Hartman Architects, Inc.
 (t) 510.848.4480
 (f) 510.848.4532
<http://www.fernauhartman.com>

APPENDIX

Correspondence

From: "Jon Harvey" <jon.harvey@ucr.edu>
 Subject: **FW: Barn Project Phases 1 & 2 Emergency Generator**
 Date: April 23, 2010 2:03:59 PM PDT
 To: "Jason Wilkinson" <jw@fernauhartman.com>
 Reply-To: "jon.harvey@ucr.edu" <jon.harvey@ucr.edu>
 ▶ 1 Attachment, 4.1 KB

Jason,

Information on the emergency generator fuel type and fuel supply requirements are below.

Thanks

Jon

From: Eric Shuler [<mailto:eric.shuler@ucr.edu>]
Sent: Friday, April 23, 2010 1:46 PM
To: Mike Terry; jon.harvey@ucr.edu
Cc: Kieron Brunelle
Subject: RE: Barn Project Phases 1 & 2 Emergency Generator

Our preference is red diesel, and we would require a 3 day capacity.

Eric Shuler

Electrical Shop Supervisor



Department of Physical Plant
 3401 Watkins Drive
 Riverside, California 92521
 951-827-3112 Office
 951-827-4596 Fax
eric.shuler@ucr.edu

From: Mike Terry [<mailto:mike.terry@ucr.edu>]
Sent: Friday, April 23, 2010 1:36 PM
To: jon.harvey@ucr.edu
Cc: Kieron Brunelle; Eric Shuler
Subject: RE: Barn Project Phases 1 & 2 Emergency Generator

Good afternoon!
 I will have a reply sent to you by the end of work Monday 26APR10.
 Thanks,
 Mike

From: Jon Harvey [<mailto:jon.harvey@ucr.edu>]
Sent: Friday, April 23, 2010 9:27 AM
To: Mike Terry
Cc: Kieron Brunelle
Subject: Barn Project Phases 1 & 2 Emergency Generator

Mike,

An emergency generator is being considered for the Barn Project Phases 1 & 2 to supply power to the kitchen refrigeration units, emergency lights, and KUCR. The size of the generator will be determined by the consultant team.

Request preferences for emergency generator fuel supplies, and if diesel, the capacity of the fuel tank in days.

We would appreciate a quick response (no later than Monday) so the information can be incorporated into the draft report.

Thanks

Jon

Jon Harvey
 Capital & Physical Planning
 951-827-6952

APPENDIX

Correspondence

Dear Campus Community:

Due to annual campus maintenance requirements, steam systems serving all campus buildings will be shut down:

Starting
Monday, June 14, 2010 at 8:00 pm
And continue until
Tuesday, June 22, 2010 at 7:00 am

Full steam service will be restored to all buildings by the end of the day,
June 22, 2010.

Impacted services include:
Domestic hot water heating, space heating,
Humidification, soil sterilization,
Autoclave sterilization, cage washers, etc.

Critical repairs must be performed to ensure a reliable and
energy-efficient supply of steam to all campus facilities.

We are aware of the inconvenience this will cause to some operations,
particularly research. The Physical Plant staff is available to help you
determine the effect of this shutdown on your areas, and will work with you to
provide solutions wherever possible.

Thank you for your cooperation.

Any questions or concerns should be addressed to:

Chris Flanders
Climate Control Supervisor
951-827-6235
Chris.flanders@ucr.edu

OR

Pat Simone
Assistant Director of Energy & Utility Services
951-827-6464
Patrick.simone@ucr.edu

APPENDIX

Correspondence

Barn Renovation
Program Statement
 November 16, 2009

Demand Analysis

Number of Classroom Seats within a 3 minute walk of the Barn	3617	
Estimated Future Utilization of Classroom Seats - 11am-2pm	75% Now 69%	
Estimated Potential Student Customers	2713	
Current Ratio of Faculty/Staff to Students	32%	
Estimated Potential Faculty/Staff Customers	868	
Total Potential Customers	<u>3581</u>	
Projected "Design Day" Capture Rate - All Customers	45%	Current Capture Rate is 34.3% Non-Resident Students & 32.3% Faculty/Staff
Projected Transactions of Student Customers within a 3 minute walk of the Barn	1221	
Projected Transactions of Faculty/Staff Customers within a 3 minute walk of the Barn	391	
Total Projected Transactions of Customers within a 3 minute walk of the Barn	<u>1611</u>	
Projected Distribution of Student Transactions between the Barn and the HUB	30% / 70%	30% Barn and 70% HUB
Projected Distribution of Faculty/Staff Transactions between the Barn and the HUB	70% / 30%	70% Barn and 30% HUB
Total Estimated Student Lunch Transactions at the Barn	366	
Total Estimated Faculty/Staff Lunch Transactions at the Barn	273	
Total Estimated Lunch Transactions:	<u>640</u>	Current Average Lunch Transactions are 301

Seating Requirements

Total Estimated Lunch Transactions	640	
Total Estimated Peak Lunch Hour Transactions (50%)	320	
Estimated Seat Turnover in Peak Hour (45 minute occupancy)	1.333333333	
Net Seats Required (Occupied)	240	
Gross Seats Required (@ 75% Seating Efficiency)	320	Current Seating = 183 outdoor seats and 118 indoor seats
Less Estimated Take-Out Factor (10%)	-32	
Total Estimated Seats Required	288	
Indoor Seats	110	
Outdoor Seats	178	

Space Requirements

Program Area	ASF	Notes
Production Kitchen		
Cold Prep	960	Cold Production for Barn, Barn/University Club Catering and 425 pieces packaged grab and go products daily.
Hot Production (Cook Line and Grille Production)	640	Grille Line adjacent to Servery with pass-through window for finished products; Bulk hot production line to include finish baking capability; Ice maker.
Refrigerated Storage - Bulk Food	120	Walk-in Cooler
Refrigerated Storage - Finished Product Cooler	120	Walk-in Cooler
Refrigerated Storage - Beer Cooler	80	Walk-in Cooler; Lockable
Frozen Storage	120	Walk-in Freezer
Dry Storage - Food	360	Wire Rack Shelving
Dry Storage - Liquor	30	Lockable
Dry Storage - Catering Equipment (Barn and University Club)	80	Wire Rack Shelving; Lockable
Receiving, Recycling and Outbound Staging Area	200	Receiving; Outbound Cart Marshalling; Food waste bin; Compostable bin.
	Subtotal:	2710
Warewashing		

APPENDIX

Correspondence

Dishwashing	352	Conveyor Dishmachine; Space includes Chemical Storage
Potwashing	100	Pot Sink; Shelving
Janitor's Closet	48	Mop Sink; Cleaning Equipment Storage
Chemical Storage	Incl. Above	
Subtotal:	500	
Back of House Support		
Unisex Employee Toilet	80	
Unisex Changing Room & Lockers	60	12 Lockers and Changing Bench
Manager's Office	80	
Production Office	120	2 stations shared by - 1 Sr. Mgr.; 1 Entertainment Mgr.; 1 Principle Supervisor (Barn); 1 Principle Cook (Barn); 1 Principle Supervisor (Truck). Includes Safe for cash handling.
Subtotal:	340	
Serving		
Serving Area	480	Exhibition Kitchen and Servery; (4) POS; (2) Exhibition Production Platforms - Salad/Sandwich, Pizza (Woodstone Oven); These Platforms and the Grille Platform all funnel to Expediting/Pick-up Station seperated from POS.
Customer Queuing	400	Serpentine Queue System (next available cashier).
Self-Serve Beverage Counter & Queuing	96	Adjacent to interior Service Bar.
Double-sided Service Bar	96	Opening into interior and exterior; Service Bars on each side (beer taps and bottled wine); (1) bar sink and (1) under counter glass washer.
Self-Serve Condiment Counter & Queuing	48	
Subtotal:	1120	
Indoor Seating & Stage		
Indoor Seating	1760	110 Seats; Café Style Seating
Performance Stage	By Architect	
Subtotal:	1760	
Total Indoor ASF:	6430	
Outdoor Space		
Loading Dock	By Architect	3 Bays - 2 Vehicle; 1 Trash/Recycling (Trash dumpster; Recycling containers for oil waste, paper, compostables); Mat/cart washing area.
Outdoor Seating	2848	178 Seats; Café Style Seating
Outdoor BBQ	100	Outdoor gas BBQ with exterior refrigeration; gas line; (1) POS; hot/cold wells.
Outdoor Condiment Counter & Queuing	48	
Total Outdoor ASF:	2996	
Total Indoor/Outdoor ASF:	9426	

Correspondence

University Club

Design Criteria - Food Service Areas

November 16, 2009

Back of House Pantry

Provide the following:

3 compartment sink with soiled pot shelving and clean pot shelving
Cart parking area with electrical outlets for 4 carts
Cook line with exhaust hood, to include (1) two-basket fryer, (1) 36" griddle with oven below
8-10' work counter with undercounter dishwasher for glassware
Plating table
1 wire rack shelf/lockable cage for liquor storage
1 section roll-in refrigerator
1 hand sink

Bar

Provide the following:

Bar top and die with beer taps, (1) POS, and undercounter ice maker
Back bar to include undercounter refrigeration, undercounter dishwasher and bar sink

Janitor Closet

Provide the following:

Mop sink
Cleaning equipment storage for the facility
Chemical Storage

APPENDIX

Correspondence

Coffee Shop
 Program Statement
 November 16, 2009

Space Requirements

Program Area	ASF	Notes
Back of House Support		
Dry Storage	64	
Refrigerated Storage - Bulk	36	Walk-in Cooler
Office	64	
Potwashing	60	
Unisex Employee Toilet	48	If required by code
Ice Making/Prep/Miscellaneous Support	48	
Janitor's Closet/Chemical Storage	24	
Subtotal:	344	
Serving		
Serving Area	150	Espresso and specialty coffees; Brewed coffee; Blenders; Bakery display case (2 section - ambient & refrigerated); Undercounter dishmachine
Customer Queuing	120	Serpentine Queue System (next available cashier).
Self-Serve Condiment Counter & Queuing	24	
Subtotal:	294	
Total Indoor ASF:	638	
Outdoor Space		
Outdoor Seating	By Architect	36 Seats Desired; Porch Seating in Keeping with the Architectural Integrity of the Historic Structure
Total Outdoor ASF:	By Architect	