

UNIVERSITY OF CALIFORNIA RIVERSIDE

Please consult with Campus Architect or  
Campus Physical Planner prior to specifying  
signage.

Not all sign types herein are still considered  
standards.

Campus logo and specifications for standard  
colors (blue and gold) will change in Fall  
2020.

CAMPUS SIGN PROGRAM  
100% PACKAGE

Section 1: Sign Type Drawings  
Section 2: Sign Location Plans  
Section 3: Building Identification Survey

1.04.08

**LAST UPDATED 09.15.2020**

**INTERIOR SIGNAGE** at interior locations:  
there is some latitude on the panel color and  
material. See MRB submittal as an example.  
Consult with Campus Architect.



- 1.1–1.44 **Section 1**  
Sign Type Drawings
  
- 2.1–2.43 **Section 2**  
Sign Location Plans
  
- 3.1–3.87 **Section 3**  
Building Identification Sign Survey

1.1 Typefaces & Color

**Electronic Message Boards**

- 1.2 W10 Site ID, Freeway
- 1.3 W11 Campus ID

**Campus Entry Monument**

- 1.4 W15 Primary ID
- 1.5 W16 Secondary ID

**Vehicular Directional**

- 1.6 W20 Primary
- 1.7 W20.1 Primary, Engineering
- 1.8 W21 Secondary
- 1.9 W21.1 Secondary, Engineering
- 1.10 W22 Pole Mounted
- 1.11 W22.1 Pole Mounted, Engineering

**Pedestrian Directional**

- 1.12 W30 Blade Sign
- 1.13 W30.1 Blade Sign, Engineering
- 1.14 W35 Wall Mounted
- 1.15 W36 Accessible Pathway

**Pedestrian Information**

- 1.16 W40 Freestanding Directory, primary
- 1.17 W40.1 Freestanding Directory, primary, Engineering
- 1.18 W40.2 Freestanding Directory, primary, Engineering
- 1.19 W41 Wall Mounted Directory
- 1.20 W41.1 Wall Mounted Directory, Engineering
- 1.21 W42 Freestanding Directory, secondary
- 1.22 W42.1 Freestanding Directory, secondary Engineering
- 1.23 W42.2 Freestanding Directory, secondary Engineering
- 1.24 W46 Info Kiosk, Posted Messages
- 1.25 W46.1 Info Kiosk, Engineering
- 1.26 W46.2 Info Kiosk, Engineering
- 1.27 W48 Interactive Kiosk
- 1.28 W48.1 Interactive Kiosk

**Building Identity**

- 1.29 W50 Primary, Vehicular
- 1.30 W50.1 Primary, Vehicular
- 1.31 W50.2 Primary, Vehicular
- 1.32 W50.3 Primary, Vehicular, Engineering
- 1.33 W51 Freestanding, Ped
- 1.34 W51.1 Freestanding, Ped
- 1.35 W51.2 Freestanding, Ped
- 1.36 W52 Wall Mounted
- 1.37 W53 Vinyl Letters on Door
- 1.38 W54 Parapet Letters
- 1.39 W55 Building ID, small  
(Refer to sheet 1.66 for Loading Dock Identification)

**Parking Lot Identity & Information**

- 1.40 W70 Primary ID
- 1.41 W70.1 Primary ID
- 1.42 W71 Secondary ID
- 1.43 W71.1 Secondary ID
- 1.44 W72 Pole Mounted ID
- 1.45 W72.1 Pole Mounted ID
- 1.46 W97 Street Sign

**Building Interior Identity Program**


- 1.47 B20 Ceiling Mounted Department Area ID
- 1.48 B22 Blade Sign ID
- 1.49 B30 Wall Mounted Changeable Room ID **ADDED B31**
- 1.50 B32 Wall Mounted Room ID (Paper Holder) **ADDED B32A**
- 1.51 B36 Wall Mounted Restroom ID (ADA)
- 1.52 B42 Wall Mounted Directional
- 1.53 B50 Wall Mounted Building Directory
- 1.54 B52 Wall Mounted Floor Directory
- 1.55 B60 Wall Mounted Secondary Information
- 1.56 B64 Wall Mounted Bulletin Board
- 1.57 B70 Wall Mounted Permanent Room ID
- 1.58 B75 Wall Mounted Evacuation Map
- 1.59 B80 Wall Mounted Restroom ID
- 1.60 B81 Wall Mounted Stair Level ID (ADA)
- 1.61 B82 Wall Mounted Stair Level ID
- 1.62 B86 Wall Mounted Maximum Occupancy
- 1.63 B90 Door Entry / Exit Information
- 1.64 B92 Wall Mounted Accessible ID
- 1.65 B94 Wall Mounted Accessible Information
- 1.66 B95 Wall Mounted Loading Dock Parking Regulatory Information




**Key Plan**


2.1 Overall Campus Map

Sign Location Plans:  
includes the following sign types

 **Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID


 **Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID

 **Pedestrian Information**  
W36 Accessible Pathway

 **Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk


 **Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped

 **Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID

 W97 Street Signs

- 2.2 Section A
- 2.3 Section B
- 2.4 Section C
- 2.5 Section D
- 2.6 Section E
- 2.7 Section F
- 2.8 Section G
- 2.9 Section H
- 2.10 Section I
- 2.11 Section J
- 2.12 Section K
- 2.13 Section L
- 2.14 Section M
- 2.15 Section N
- 2.16 Section O
- 2.17 Section P
- 2.18 Section R
- 2.19 Section S

Vehicular Directionals  
includes the following sign types

 **Vehicular Directional**  
W20 Primary  
W21 Secondary  
W22 Pole Mounted

- 2.20 Introduction
- 2.21 Section B
- 2.22 Section C
- 2.23 Section E
- 2.24 Section F
- 2.25 Section G
- 2.26 Section H
- 2.27 Section I
- 2.28 Section J
- 2.29 Section K
- 2.30 Section M
- 2.31 Section N
- 2.32 Section Q
- 2.33 Section R
- 2.34 Section S

Pedestrian Directionals  
includes the following sign types

 **Pedestrian Directional**  
W30 Blade Sign  
W35 Wall Mounted

- 2.35 Introduction
- 2.36 Section E
- 2.37 Section F
- 2.38 Section H
- 2.39 Section I
- 2.40 Section J
- 2.41 Section M
- 2.42 Section N
- 2.43 Section S



**A**

- 3.1 Aberdeen-Inverness Residence Hall (343)
- 3.2 Agricultural Operations (489)
- 3.3 Anderson Hall 1 & 2 (325 & 357)
- 3.4 Arts Building (411)

**B**

- 3.5 The Barn, Theater Workshop, & Barn Stable (358)
- 3.6 Bannockburn Village *Bldgs A-V* (590–611)
- 3.7 Batchelor Hall (501 & 501a)
- 3.8 Biological Sciences (186)
- 3.9 Biomedical Teaching Complex  
& Biomedical Trailers 2 & 3 (385 & 561)
- 3.10 Bookstore (224)
- 3.11 Botanical Gardens (254)
- 3.12 Bourns Hall (261)
- 3.13 Boyce Hall (341)
- 3.14 Boyden Laboratory (482)

**C**

- 3.15 California Museum of Photography (720) downtown
- 3.16 Campus Surge (380)
- 3.17 Canyon Crest Family Student Housing (000–183)
- 3.18 Central Utility Plant (295)
- 3.19 Chapman Hall (215)
- 3.20 Chemical Sciences (414)
- 3.21 Child Development Center A (396)
- 3.22 College Building North (517)  
& College Building South (231)
- 3.23 Computing & Communications Center (381)
- 3.24 Corporation Yard A–C (485–487)
- 3.25 Costo Hall (311)
- 3.26 The Cottage (218)
- 3.27 Culver Center for the Arts (757) downtown
- 3.28 Custodial & Grounds Building (507)

**E**

- 3.29 Engineering Building Unit 2 (194)
- 3.30 Entomology (417)
- 3.31 Entomology Museum (256)
- 3.32 Environmental Health & Safety (241)

**F**

- 3.33 Fawcett Laboratory (503)

**G**

- 3.34 Geology Building (335)
- 3.35 Greenhouses 6–10 (200, & 275–278)
- 3.36 Greenhouses 11–14 (279–281, & 481)
- 3.37 Greenhouses 15–21  
(210, 284, 483, 513–515, & 202)

**H**

- 3.38 Headhouse Greenhouses 1–3 (378, 259, & 374)
- 3.39 Health Services Building (495)
- 3.40 Herbarium (319)
- 3.41 Highlander Hall (716)
- 3.42 Hinderaker Hall (480)
- 3.43 Housing Administration (581)
- 3.44 Human Resources Building (788)
- 3.45 Humanities Building (498)
- 3.46 Humanities & Social Sciences Building (307)

**I**

- 3.47 East Campus Insectary  
& Quarantine Facility (289)
- 3.48 International Village Apartments (998)

**K**

- 3.49 KUCR Radio Station (176)

**L**

- 3.50 Life Science Building (316)
- 3.51 Lothian Residence Hall (502)

**O**

- 3.52 Olmsted Hall (497)

**P**

- 3.53 Parking Services Building (272)
- 3.54 Pentland Hills Residence Hall A–Q  
(365, 369, 636–648)
- 3.55 Physics Building (504)
- 3.56 Physics 2000 Lecture Hall (504A)
- 3.57 Physical Education Building (334)
- 3.58 Pierce Hall (508)
- 3.59 Police Building (566)

**R**

- 3.60 Rivera Library (322)

**S**

- 3.61 Satellite Chiller Plant (367)
- 3.62 Science Laboratories 1 (416)
- 3.63 Science Library (418)
- 3.64 Spieth Hall (323)
- 3.65 Sproul Hall (523)
- 3.66 Statistics Computer Building (588)
- 3.67 Stonehaven Apartments (991)
- 3.68 Student Recreation Center (511)

**U**

- 3.69 UCR/City Athletic Complex (285)
- 3.70 UCR Extension Center (722)
- 3.71 University Laboratory Building (263)
- 3.72 University Lecture Hall (383)
- 3.73 University Office Building (205)
- 3.74 University Office Building A (987)
- 3.75 University Plaza Apartments (715)

**W**

- 3.76 Watkins Hall (354)
- 3.77 Webber Hall (342)

**Not included:**

- Alumni & Visitors Center (197)
- Belltower (530)
- Child Development Center B (190)
- Chancellor's Residence (488)
- CHASS Interdisciplinary  
North & South (403 & 372)
- Commons Expansion (404)
- Falkirk Apartments 1–19 (671–689)
- Genomics (196)
- Glen Mor Housing A–E (470–475)
- SASS (614)
- School of Education Clinic (397)

**PLEASE NOTE:**

Sign types W50 and W51 are shown both in the Building Identity Survey and the sign location plan.



### CAMPUS WIDE SIGNAGE

The hundreds of signs on the UCR campus not only provide important information; they collectively form powerful and lasting impressions of the University and campus environment. Each sign should be considered a direct message from the administration and each is an opportunity to communicate clearly and present a positive image to students, faculty, staff and visitors.

#### Intent

*Signage and graphics design guidelines seek to unify and improve all signage on the campus by:*

- Organizing campus signs into useful, integrated categories
- Standardizing materials, colors and type styles
- Setting scale and size formats
- Creating appropriate relationships to landscape, architectural and lighting elements
- Selecting appropriate design details
- Organize wayfinding

*Campus signage has been organized into the following functional groups:*

#### Monument & Entry Signs

Substantial monument signs will be designed and located at key entrances to the campus. Those entrances are identified as

- [1] University Avenue & West Campus Drive
- [2] Martin Luther King Boulevard & Chicago Avenue
- [3] Canyon Crest Drive & Martin Luther King Boulevard
- [4] Big Springs Road & Valencia Hill Drive

For the main entrance signs, permanent, monumental materials such as natural stone and metal will be used to present a formal, welcoming appearance. The signs will be illuminated by remotely mounted fixtures. Letters may be fabricated of metals or incised into the surface of the monument.

In addition to the monument signs, a pylon sign of significant height and visibility will be located adjacent to the freeway. The purpose of this sign is to identify the UCR campus to freeway drivers and to provide an opportunity for University announcements of events. A high resolution LED screen will be incorporated into the pylon, providing a methodology by which the University can communicate directly with the community.

#### Vehicular Directional Signs and Parking Identification

A system of vehicular signage will be designed and deployed throughout the campus roadways and parking areas. The vehicular sign system will be comprised of directional signs, parking identification signs and street name signs. These signs will display important and “reachable-by-car” campus destinations, and adjacent parking areas, with directional arrows. The signs

will be highly visible and recognizable from over 150 ft. where sight lines allow. *(Drivers should always be able to see at least one directional sign from anywhere on the campus roadways, thus providing substantial driver reassurance.)* The type style should be Trade Gothic Bold No.2 for clarity and easy reading by drivers with reflective qualities for night reading.

#### Pedestrian Directional Signs

A system of pedestrian-directional signage will be designed and deployed throughout the campus. The directional signs should display important and frequented campus destinations with directional arrows. The directional signs will be a “finger-sign” or pointer style design that features pointed slats for each destination. Signs of this style are very pedestrian friendly and are less prone to vandalism. The height of these signs will be eight to ten feet. The type style should be a simple, bold sans-serif font for clarity and easy reading. Wording on the signs should be simple and use the shortest messages possible. The formal names of some destinations may need to be shortened for effective display on signs.

#### Pedestrian Map Directories

A system of map directories with lighting for night reading will be designed and deployed throughout the campus presenting an illustrated campus map and detailed listing of all destinations. The directories will present a clear, colorful map, matching that of printed hand-out maps. Maps will be easily changeable to allow for regularly updating campus information.

#### Information Kiosks

Interactive kiosks will be installed for the display of campus information. Information links within the kiosk software can help foster communication, student interest and help build community on the campus.

#### Freestanding Building Signage

A system of free-standing building identification signage will be designed and deployed throughout the campus. Each sign will display the formal name of a campus building and be located near the main building entry door. The signs should be highly visible and recognizable from over 200 feet where sight lines allow. These signs will reflect the University’s blue and gold coloration, but will feature a more architecturally sensitive neutral background color. A letter size of approximately two to three inches will be used. The type style should be Trade Gothic Bold No.2 for clarity and easy reading.

#### Building-Mounted Signage

Building-mounted signs will be comprised of three categories; architectural letter signs, panel signs and door mounted signs. These signs are to be used in a variety of configurations in order to provide adequate visibility and identification for the building. Architectural letter signs are to be used to prominently identify buildings, generally at or near the top of the structure. Letter size and location should be appropriately scaled and proportioned to the overall

building. Panel signs usually at eye level or slightly above, should be used to supplement the architectural letter signs where building identification is required closer to the entry path. Door mounted signs shall be applied to all main building entry doors. These signs shall be applied vinyl letters applied subsurface to clear glass.

#### Design Considerations

A wide variety of design approaches and opportunities exist for the signage at UCR. However, while the designs can be simple and understated, or play a more dramatic role, a contemporary, clean-line approach should be used. The buildings of the University are an eclectic mix of architectural and design styles. Signage will be designed to compliment and help unify the campus’s diversity of styles.

#### Interior Signage

A system of interior signs has been developed to give consistency to the location, size, materials and color of the graphic elements within buildings. Directional signage, room number identification, building and floor directories, and all code required signs shall be laid out and located in accordance with the UCR Interior Signage Guidelines

#### Color and Contrast

With its large scale, open spaces and long sight lines, the campus needs highly visible and recognizable signs. The use of bold and high contrast colors and materials will help signage elements stand out in the environment. Directional signage will reflect the University’s school colors of blue and gold with sign messages in white. Monument signage will be constructed using a more architectural palette of natural stone and metal finishes.

*For more details, please consult the Campus Sign Program, posted on the UCR Capital and Physical Planning website. ([www.ucrapb.ucr.edu](http://www.ucrapb.ucr.edu))*

**PROJECT TYPESTYLES:**

**ABCDEFGHIJKLMNOPQRSTUVWXYZ 1234567890**

**abcdefghijklmnopqrstuvwxyz**

Times Bold

ABCDEFGHIJKLMNOPQRSTUVWXYZ 1234567890

abcdefghijklmnopqrstuvwxyz

Times Regular

**ABCDEFGHIJKLMNOPQRSTUVWXYZ 1234567890**

**abcdefghijklmnopqrstuvwxyz**

Trade Gothic Bold

**ABCDEFGHIJKLMNOPQRSTUVWXYZ 1234567890**

**abcdefghijklmnopqrstuvwxyz**

Trade Gothic Bold No. 2

ABCDEFGHIJKLMNOPQRSTUVWXYZ 1234567890

abcdefghijklmnopqrstuvwxyz

Din Medium



Project Symbols and Arrow

Note:  
Times (Bold/Regular) is not to be used on any sign required to be ADA compliant. Use only sans serif font on any sign complying with accessibility code.

**GUIDELINES FOR TEXT KERNING:**

**Letter Spacing**


Spacing "0 pt." Minimum

**Letter Spacing**

Spacing "20 pt." Maximum (Recommended Standard)

**Line Spacing**

Spacing Between Lines In Paragraph Format 116.67 % Of Letter Height.



**COLOR SCHEDULE: EXTERIOR SIGNAGE**

No.	Color No.	Color Name	Finish
1	MP10273	Blue	Semi gloss
2	MP04516	Gold	Semi gloss
3	Davis Concrete Color	Mesa Buff 2lbs. 5447	
4	3M Scotchlite EGR 3290	White Reflective Vinyl	
5	MP-White	White	Semi gloss
6	3M Scotchcal 7125-10	White	
7	MP18100	Light Silver	Semi gloss
8	MP20140	Gray	Semi gloss
9	MP07694	Light Blue	Semi gloss
10	3M Scotchcal 7125-13	Red	
11	3M Scotchlite EGR 3275	Blue Reflective Vinyl	
12	MP04705	Terra Cotta	Semi gloss
13	3M Scotchlite EGR 3271	Yellow	
14	3M Scotchlite EGR 3272	Red	
15	3M Scotchcal 7125-12	Black	


**COLOR SCHEDULE: BUILDING INTERIOR SIGNAGE**


No.	Color No.	Color Name	Finish
1	MP13915	Gray	Satin Finish
2	MP 06668	Light Gray	Satin Finish
3	3M Scotchcal Vinyl	7125-10 White	
4	3M Scotchcal Vinyl	7125-13 Red	
5	MP White	White	Satin Finish
6	Gravoply II 21927	Gray/white	
7	Aluminum		Light Sandblast Finish

MP = Matthews Paint

EGR = 3M Engineering Grade Reflective Vinyl







W11 SINGLE SIDE SIGN ORIENTATION: Not To Scale

- Single Faced - (Location sheet 2.6) Linden St. @ Canyon Crest Dr.
- Single Faced - (Location sheet 2.12) Valencia Hills Dr. @ Big Springs Rd.
- Single Faced - (Location sheet 2.14) Campus Dr. @ Canyon Crest Dr.



Not Used

Flat cut out horizontally brushed stainless steel letters with 1/4" stainless steel spacer sleeves and blind studs.

Fabricated 2" thick stainless steel "shield" with light horizontal brushed finish. Graphics to be etched 1/32" deep and paint filled.


1" deep Incised letters with painted finish inside of letters. Paint color Matthews MP10217 Brown.


Full colored L.E.D. video board with high resolution picture quality remote computer controlled display. Manufacturer and model specifications to be determined. Opening dimensions to be determined video display manufacturer.

Fabricated aluminum frame structure with stone facing. Dark red / brown facing to be morning glory stone with oil rubbed finish. Light ochre / brown facing to be sunflower stone with oil rubbed finish.

Arida fluorescent outdoor architectural lighting. Sign Contractor to minimize fixture above grade as possible. (or equivalent lighting product)

Concrete footing / integral colored mow pad to be determined by Sign Contractor's engineering.






PLAN 1/2" = 1'-0"



ELEVATION 1/2" = 1'-0"




W11 DOUBLE SIDED SIGN ORIENTATION: Not To Scale  
 Double Faced - (Location sheet 2.6) Linden St. @ Flower St.  
 Double Faced - (Location sheet 2.10) University Dr. @ W. Campus Dr.



SIDE 1/2" = 1'-0"

NOT USED




For single faced displays cover message display opening with stone panel and eliminate exterior lighting on back side only.

Flush aluminum service access for message display controller. Venting for excess heat to be determined by message display manufacturer. Use tamperproof fastening or locking device for panel access.

PLAN 1/2" = 1'-0"

- General Notes:
1. Sign construction details conceptual only, sign contractor's engineering to take precedence over any drawing details.
  2. Stone and or color matches can be purchased through Contractor's Tile Mart, 1063 E. Las Tunas Dr., San Gabriel, Calif. 91776 - Tel. (626) 287-6483 - Attn. Albert Maloof



Not Used

Flat cut out horizontally brushed stainless steel letters with 1/4" stainless steel spacer sleeves and blind studs.

Fabricated aluminum frame structure with stone facing. stone facing. Light ochre / brown facing to be sunflower stone with oil rubbed finish.

Full colored L.E.D. video board with high resolution picture quality remote computer controlled display. Manufacturer and model specifications to be determined. Opening dimensions to be determined video display manufacturer.

Fabricated aluminum frame structure with stone facing. Dark red / brown facing to be morning glory stone with oil rubbed finish.

Threaded stainless steel studs / anchor pins with masonry holes filled with epoxy sealant.

3" square steel tubes with 3/8" thick bottom plate. Verify with Sign Contractor's engineering.

Perforated aluminum around display for venting painted black.

Stainless steel "Z" clips / brackets with fasteners to support stone.


2" x 2" x 1/4" steel angle welded frame structure to support stone and electronic message display.

Arida fluorescent outdoor architectural lighting. Sign Contractor to minimize fixture above grade as possible. (or equivalent lighting product)


Concrete footing / integral colored mow pad to be determined by Sign Contractor's engineering.


Primary power to sign location by UCR.

ELEVATION 1/2" = 1'-0"




DOUBLE SIDED SECTION 1/2" = 1'-0" A






Not used



- 3/4" thick flat cut out horizontally brushed stainless steel letters with 1/4" stainless steel spacer sleeves and blind studs.
- 1" deep Incised letters with painted Matthews MP10217 Brown.
- Exterior lighting.
- Primary power to location by UCR.
- Concrete footing / integral colored mow pad to be determined by Sign Contractor's engineering.




Not used



East side of Canyon Crest Dr. - (1) single faced sign

Fabricated 2" thick stainless steel "shield" with light horizontal brushed finish. Graphics to be etched 1/32" deep and paint filled.

ELEVATION 3/16" = 1'-0" W16 Single Faced - (Location sheet 2.18) MLK Jr. Blvd. @ Canyon Crest Dr.




PLAN 3/16" = 1'-0"

Fabricated aluminum frame structure with stone facing. Dark red / brown facing to be Morning Glory stone with oil rubbed finish. Light ochre / brown facing to be Sunflower stone with oil rubbed finish.

Integral colored concrete pad / footing with internal rebar and sign support structure as required by Sign Contractors Engineering. (Davis Concrete color Mesa Buff 2 lbs. 5447.

Arida fluorescent outdoor architectural lighting. Sign Contractor to minimize fixture above grade as possible. (or equivalent lighting product)



West side of Canyon Crest Dr. - (1) single faced sign

3/4" thick flat cut out horizontally brushed stainless steel letters with 1/4" stainless steel spacer sleeves and blind studs.


1" deep Incised letters with painted Matthews MP10217 Brown.

Exterior lighting.

Concrete footing / integral colored mow pad to be determined by Sign Contractor's engineering.

Primary power to sign location by UC Riverside.


ELEVATION 3/16" = 1'-0" W16 Single Faced - (Location sheet 2.18) MLK Jr. Blvd. @ Canyon Crest Dr.





SIDE 3/16" = 1'-0"

Not Used











GENERAL NOTES:


1. SIGN CONSTRUCTION DETAILS CONCEPTUAL ONLY, SIGN CONTRACTOR'S ENGINEERING TO TAKE PRECEDENCE OVER ANY DRAWING DETAILS.
2. STONE AND OR COLOR MATCHES CAN BE PURCHASED THROUGH CONTRACTOR'S TILE MART, 1063 E. LAS TUNAS DR., SAN GABRIEL, CALIF. 91776 - TEL. (626) 287-6483 - ATTN. ALBERT MALOOF





GENERAL NOTES:

1. SIGN CONSTRUCTION DETAILS CONCEPTUAL ONLY, SIGN CONTRACTOR'S ENGINEERING TO TAKE PRECEDENCE OVER ANY DRAWING DETAILS.
2. STONE AND OR COLOR MATCHES CAN BE PURCHASED THROUGH CONTRACTOR'S TILE MART, 1063 E. LAS TUNAS DR., SAN GABRIEL, CALIF. 91776 - TEL. (626) 287-6483 - ATTN. ALBERT MALOOF




PARTIAL PLAN DETAIL

1" = 1'-0"

CONCRETE FOOTING AND REBARS AS PER SIGN CONTRACTOR'S ENGINEERING WITH INTEGRAL COLORED CONCRETE MOW PAD.

ARIDA FLUORESCENT OUTDOOR ARCHITECTURAL LIGHTING OR EQUIVALENT. SIGN CONTRACTOR TO MINIMIZE FIXTURES ABOVE GRADE AND STILL SECURE EVEN ILLUMINATION. RECOMMENDED LIGHTING CONSULTANT, MARGIE CHAVEZ, PRUDENTIAL LIGHTING PRODUCTS, (213) 746-0360.

PRIMARY POWER BY UCR.



FABRICATED HORIZONTALLY BRUSHED STAINLESS STEEL LETTERS WITH 1/4" STAINLESS STEEL SPACER SLEEVES AND BLIND STUDS. FILL WALL MOUNTING HOLES WITH EPOXY ADHESIVE.

CAST CONCRETE MONUMENT WITH SCOFIELD COMPANY CHROMIX CORAL RED INTEGRAL ADMIX COLOR AND SURFACE APPLIED CHEMSTAIN PADRE BROWN. (FACES TO HAVE ROUGH STONE APPEARANCE)

CAST UNCOLORED CONCRETE MONUMENT WITH SCOFIELD COMPANY SURFACE APPLIED CHEMSTAIN ANTIQUE AMBER. (FACES TO HAVE ROUGH STONE APPEARANCE)

1" DEEP INCISED LETTERS WITH PAINTED FINISH.

DETERMINED BY SIGN CONTRACTOR TO ACHIEVE MAXIMUM ILLUMINATION

FABRICATED ± 2" THICK STAINLESS STEEL "SHIELD" WITH HORIZONTAL BRUSHED FINISH. GRAPHICS TO BE ETCHED 1/32" DEEP AND PAINT FILLED.

STAINLESS STEEL "Z" CLIPS WITH WELDED STAINLESS STEEL SUPPORT BARS.

MECHANICAL STAINLESS STEEL TENSERS.

ADD 2-PART EPOXY INTO CONCRETE MOUNTING HOLES.

"SHIELD" SECTION 1 1/2" = 1'-0"

RECESSED STAINED CONCRETE REVEAL ON ALL VISIBLE SIDES.



STEEL REBAR CONCRETE REINFORCEMENT AS REQUIRED BY ENGINEERING.

45° BEVELED EDGES.




TO VARY WITH SIGN TYPE


SECTION 1" = 1'-0"

A



Not Used






PARTIAL PLAN DETAIL | 1" = 1'-0" | (B)

GENERAL NOTES:  
 1. SIGN CONSTRUCTION DETAILS CONCEPTUAL ONLY, SIGN CONTRACTOR'S ENGINEERING TO TAKE PRECEDENCE OVER ANY DRAWING DETAILS.  
 2. STONE AND OR COLOR MATCHES CAN BE PURCHASED THROUGH CONTRACTOR'S TILE MART, 1063 E. LAS TUNAS DR., SAN GABRIEL, CALIF. 91776 - TEL. (626) 287-6483 - ATTN. ALBERT MALOOF

ARIDA FLUORESCENT OUTDOOR ARCHITECTURAL LIGHTING OR EQUIVALENT. SIGN CONTRACTOR TO MINIMIZE FIXTURES ABOVE GRADE AND STILL SECURE EVEN ILLUMINATION. RECOMMENDED LIGHTING CONSULTANT, MARGIE CHAVEZ, PRUDENTIAL LIGHTING PRODUCTS, (213) 746-0360.

CONCRETE FOOTING AND REBARS AS PER SIGN CONTRACTOR'S ENGINEERING WITH INTEGRAL COLORED CONCRETE MOW PAD. PRIMARY POWER BY OTHERS.



FABRICATED HORIZONTALLY BRUSHED STAINLESS STEEL LETTERS WITH 1/4" STAINLESS STEEL SPACER SLEEVES AND BLIND STUDS. FILL WALL MOUNTING HOLES WITH EPOXY ADHESIVE.

CAST CONCRETE MONUMENT WITH SCOFIELD COMPANY CHROMIX CORAL RED INTEGRAL ADMIX COLOR AND SURFACE APPLIED CHEMSTAIN PADRE BROWN. (FACES TO HAVE ROUGH STONE APPEARANCE)

CAST UNCOLORED CONCRETE MONUMENT WITH SCOFIELD COMPANY SURFACE APPLIED CHEMSTAIN ANTIQUE AMBER. (FACES TO HAVE ROUGH STONE APPEARANCE)

1" DEEP INCISED LETTERS WITH PAINTED FINISH.

3/8" THICK FLAT CUT OUT HORIZONTALLY BRUSHED STAINLESS STEEL LETTERS. FLUSH MOUNTED TO CONCRETE WITH CONCEALED STUDS. FILL WALL MOUNTING HOLES WITH EPOXY ADHESIVE.

RECESSED STAINED CONCRETE REVEAL ON ALL VISIBLE SIDES.

45° BEVELED EDGES

SECTION | 1" = 1'-0" | (A)

6 1/2" 10" 6 1/2"  
 1/2" 1/4" 1/4" 1/2"

FABRICATED 1 1/2" THICK STAINLESS STEEL "SHIELD" WITH HORIZONTAL BRUSHED FINISH. GRAPHICS TO BE ETCHED 1/32" DEEP AND PAINT FILLED.

STAINLESS STEEL "Z" CLIPS WITH WELDED STAINLESS STEEL SUPPORT BARS.


MECHANICAL STAINLESS STEEL FASTENERS.

ADD 2-PART EPOXY INTO CONCRETE MOUNTING HOLES.

"SHIELD" SECTION | 1 1/2" = 1'-0" | (C)

STEEL REBAR CONCRETE REINFORCEMENT AS REQUIRED BY ENGINEERING.

NOT USED



PARTIAL PLAN DETAIL

1" = 1'-0"



GENERAL NOTES:

1. SIGN CONSTRUCTION DETAILS CONCEPTUAL ONLY, SIGN CONTRACTOR'S ENGINEERING TO TAKE PRECEDENCE OVER ANY DRAWING DETAILS.
2. STONE AND OR COLOR MATCHES CAN BE PURCHASED THROUGH CONTRACTOR'S TILE MART, 1063 E. LAS TUNAS DR., SAN GABRIEL, CALIF. 91776 - TEL. (626) 287-6483 - ATTN. ALBERT MALOOF


ARIDA FLUORESCENT OUTDOOR ARCHITECTURAL LIGHTING OR EQUIVALENT. SIGN CONTRACTOR TO MINIMIZE FIXTURES ABOVE GRADE AND STILL SECURE EVEN ILLUMINATION. RECOMMENDED LIGHTING CONSULTANT, MARGIE CHAVEZ, PRUDENTIAL LIGHTING PRODUCTS, (213) 746-0360.

CONCRETE FOOTING AND REBARS AS PER SIGN CONTRACTOR'S ENGINEERING WITH INTEGRAL COLORED CONCRETE MOW PAD. PRIMARY POWER BY OTHERS.

45° BEVELED EDGES

SECTION

1" = 1'-0"



FABRICATED HORIZONTALLY BRUSHED STAINLESS STEEL LETTERS WITH 1/4" STAINLESS STEEL SPACER SLEEVES AND BLIND STUDS. FILL WALL MOUNTING HOLES WITH EPOXY ADHESIVE.

FABRICATED .090 ALUMINUM CABINET WITH TEXCOTE FINISH TO MATCH SCOFIELD COMPANY RED INTEGRAL ADMIX COLOR AND SURFACE APPLIED CHEMSTAIN PADRE BROWN. (FACES TO HAVE ROUGH STONE APPEARANCE)

FABRICATED .090 ALUMINUM CABINET WITH TEXCOTE FINISH TO MATCH SCOFIELD COMPANY SURFACE APPLIED CHEMSTAIN ANTIQUE AMBER. (FACES TO HAVE ROUGH STONE APPEARANCE)

WELDED 2" x 2" x 1/4" ALUMINUM ANGLE FRAMING STRUCTURE WITH PRIMED FINISH.

1" DEEP INCISED LETTERS WITH PAINTED FINISH. REFER TO SHEET 1.6 FOR COLORS.

3/8" THICK FLAT CUT OUT HORIZONTALLY BRUSHED STAINLESS STEEL LETTERS. FLUSH MOUNTED TO CONCRETE WITH CONCEALED STUDS. FILL WALL MOUNTING HOLES WITH EPOXY ADHESIVE.

RECESSED ALUMINUM REVEAL. REVEAL WRAPPED AROUND ALL VISIBLE SIDES AND PAINTED.

6 1/2" 10" 6 1/2"  
1/2" 1/4" 1/4" 1/2"

FABRICATED 1 1/2" THICK STAINLESS STEEL "SHIELD" WITH HORIZONTAL BRUSHED FINISH. GRAPHICS TO BE ETCHED 1/32" DEEP AND PAINT FILLED.

STAINLESS STEEL "Z" CLIPS WITH WELDED STAINLESS STEEL SUPPORT BARS.

MECHANICAL STAINLESS STEEL FASTENERS.

ADD 2-PART EPOXY INTO CONCRETE MOUNTING HOLES.

1 1/2"

2'-5" Ø

"SHIELD" SECTION

1 1/2" = 1'-0"



(4)-3" SQUARE HEAVY WALL ALUMINUM TUBING WITH WELDED 1/2" THICK ALUMINUM PLATED ON BURIED END. COAT BURIED TUBING WITH ALKALI - RESISTANT BITUMINOUS PAINT. VERIFY WITH SIGN CONTRACTOR'S ENGINEERING.

1'-8 3/4"

1'-8 3/4"

3/4"

C

C





HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPE W20.0  
A= 4.83' \* 4.29' = 20.7 S.F.

WIND CBC-'01 80 MPH, EXP. C  
CBC-1613  $p=Cq*Ce*Qs*I$  I=1.0  
 $Qs = 16.4$   $Cq = 1.4$   
25.94 LBS/S.F. @ 20'  $Ce = 1.13$   
24.34 LBS/S.F. < 15'  $Ce = 1.06$   
S.F. LBS FT. FT. LBS  
AREA !PRESS! X-DIST ! MOM-XX

TOTAL 504 2.42 1219  
(AVE.)

DOUBLE COLUMN  
MOM. 'K 0.61

ALUM  $Fb = 12$  K/SQ. IN.  
 $S = M/Fb$  WIND 1/3 INCR.  
 $S = 0.75 * M$  (INCL 1.33 WIND)  
 $S = 0.46$  IN<sup>3</sup>


$S = (bd^3 - b1*d1^3)/(6*d)$   
 $d = 2$   $d1 = 1.75$   
 $b = 2$   $b1 = 1.75$   
USING 2"x2"x 1/8" ALUM. TUBE  
 $S = 0.55$  IN<sup>3</sup> > 0.46  
O.K.

COAT ALUM. SURFACES EMBEDDED IN  
CONC. WITH ONE HEAVY COAT OF  
ALKALI-RESISTANT BITUMINOUS  
(BITUMASTIC) PAINT TO 2" MIN.  
ABOVE GRADE  
8"x8"x 3/8" ALUM. PLATE - W/4000  
WT. OF SIGN = 220 LBS +/-  
AXIAL STRESS IS NEGLIGIBLE

SEE PAGE 2 FOR FOOTING DETAILS



JOB NO. HUNT-142



HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI


SINGLE FOOTING - STRAIGHT

DESIGN OF EMBEDDED POLE FOOTINGS


DESCRIPTION	>>	57" WIDE	>>	>>
		57" WIDE		
		12" THK		
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	504	0	0
LOAD HT.	ft	2.42	0.00	0.00
DIST. LOAD	#/ft	0	0	0
START HT.	ft	0.00	0.00	0.00
END HT.	ft	0.00	0.00	0.00
WIDTH/DIAMETER	in	57"	0	0
CIRCULAR ?	y/n	N	N	N
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surface:				
Point Load	ft-#	1,220	0	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	1,220	0	0
Total Lateral Load	#	504	0	0
NON-RESTRAINED RESULTS				
Min. Req'd Embedment		2'-3"		
$A(1+(1+4.36h/A)^.5)/2$	ft	2.11	0.00	0.00
$A=2.34P/(S 1 b)$				
Press @ 1/3 Embed.:				
Actual	psf	188	0	0
Allowable	psf	187	0	0
RESTRAINED				
Min. Req'd Embedment		0.00	0.00	0.00
$(4.25 P h/S3 b)^.5$	ft			
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint				
Force	lbs	0	0	0

PER CBC TABLE 18-1-A  
POLE 2X ALLOWABLE







LOCATION ELEVATION | 1/4" = 1'-0"





Note: All sign surfaces to be sprayed with semi gloss anti graffiti clear coating.

COLORS | 1/4" = 1'-0"



Single face sign with graphics to be applied on (1) - one side only.



MODIFIED | MATCH EXISTING INSTALLED SIGNAGE

HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPE W21.0  
A= 4.29' \* 2.79' = 12.0 S.F.

WIND CBC-'01 80 MPH, EXP. C  
CBC-1613  $p=Cq*Ce*Qs*I$  I=1.0  
 $Qs = 16.4$   $Cq = 1.4$   
25.94 LBS/S.F. @ 20'  $Ce = 1.13$   
24.34 LBS/S.F. < 15'  $Ce = 1.06$   
S.F. LBS FT. FT. LBS  
AREA | PRESS | X-DIST | MOM-XX

12.0	292	2.15	628
0.0	0	0.00	0
0.0	0	0.00	0
0.0	0	0.00	0

TOTAL 292 2.15 628  
(AVE.)  
DOUBLE COLUMN  
MOM.'K 0.31



ALUM  $F_b = 12$  K/SQ. IN.  
 $S = M/F_b$  WIND 1/3 INCR.  
 $S = 0.75 * M$  (INCL 1.33 WIND)  
 $S = 0.24$  IN<sup>3</sup>

$S = (bd^3 - b1*d1^3)/(6*d)$   
 $d = 2$   $d1 = 1.75$   
 $b = 2$   $b1 = 1.75$   
USING 2"x2"x 1/8" ALUM. TUBE  
 $S = 0.55$  IN<sup>3</sup> > 0.24

8" x 8" x 3/8" ALUM PLATE - WRAPPED  
COAT ALUM. SURFACES EMBEDDED IN  
CONC. WITH ONE HEAVY COAT OF  
ALKALI-RESISTANT BITUMINOUS  
(BITUMASTIC) PAINT TO 2" MIN.  
ABOVE GRADE

WT. OF SIGN = 130 LBS +/-  
AXIAL STRESS IS NEGLIGIBLE

SEE PAGE 2 FOR FOOTING DETAILS



JOB NO. HUNT-143

HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI







SINGLE FOOTING - SORRIGED

DESIGN OF EMBEDDED POLE FOOTINGS

DESCRIPTION	>>	39" WIDE x 12" THK.		
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	292	0	0
LOAD HT.	ft	2.15	0.00	0.00
DIST. LOAD	#/ft	0	0	0
START HT.	ft	0.00	0.00	0.00
END HT.	ft	0.00	0.00	0.00
WIDTH/DIAMETER	in	39"	0	0
CIRCULAR ?	y/n	N	N	N
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surface:				
Point Load	ft-#	628	0	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	628	0	0
Total Lateral Load	#	292	0	0
NON-RESTRAINED RESULTS				
Min. Req'd Embedment				
$A(1+(1+4.36h/A)^.5)/2$	ft	2'-0"		
$A=2.34P/(S 1 b)$	ft	1.93'	0.00	0.00
Press @ 1/3 Embed.:				
Actual	psf	171	0	0
Allowable	psf	171	0	0
RESTRAINED RESULTS				
Min. Req'd Embedment				
$(4.25 P h/S 3 b)^.5$	ft	0.00	0.00	0.00
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0

PER CBC TABLE 18-1-A  
POLE 2x ALLOWABLE






COAST SIGN, INC.  
1345 S. ALLEC STREET  
ANAHEIM, CA 92805

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-3-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPE W22.0  
A = 2.25' \* 2.42' = 5.4 S.F.  
A = 8.17' \* 0.25' = 2.0 S.F.



WIND	CBC-'01	80 MPH, EXP. C
CBC-1613	$p=Cq*Ce*Qs*I$	$I=1.0$
$Qs =$	$16.4 Cq =$	$1.4$
	$25.94 \text{ LBS/S.F. @ } 20'$	$Ce = 1.13$
	$24.34 \text{ LBS/S.F. } < 15'$	$Ce = 1.06$
S.F.	LBS	FT.
AREA	!PRESS!	X-DIST
		MOM-XX
5.4	131	9.05
2.0	49	4.17
0.0	0	0.00
0.0	0	0.00
TOTAL	180	7.73
	(AVE.)	1392

SINGLE COLUMN  
MOM.'K 1.39

ALUM  $F_y = 12 \text{ K/SQ. IN.}$   
 $S = M/F_b$  WIND 1/3 INCR.  
 $S = 0.75 * M$  (INCL 1.33 WIND)  
 $S = 1.04 \text{ IN}^3$   
 $t = 0.216 \text{ IN. (MIN. THK.)}$   
 $S = .0982*(d^4-d1^4)/d$   
 $d = 3.5 \quad d1 = 3.068$   
USE MIN. 3" DIA. x 0.216 ALUM. PIPE #40  
 $S = 1.72 \text{ IN}^3 > 1.04$   
O.K.

WT. OF SIGN = 80 LBS +/-  
AXIAL STRESS IS NEGLIGIBLE

COAT ALUM. SURFACES EMBEDDED IN CONC. WITH ONE HEAVY COAT OF ALKALI-RESISTANT BITUMINOUS (BITUMASTIC PAINT -- SUCH AS HENRY'S OR EQUIVALENT).

SEE PAGE 2 FOR FOOTING DETAILS



JOB NO. HUNT-145

HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106


PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI




SINGLE COLUMN

DESIGN OF EMBEDDED POLE FOOTINGS

DESCRIPTION	>>	12" DIA.	18" DIA.	24" SQ.
CHOOSE ONE		OPTIMUM 1	OPTIMUM 2	OPTIMUM 3
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	180	180	180
LOAD HT.	ft	7.73	7.73	7.73
DIST. LOAD	#/ft	0	0	0
START HT.	ft	0.00	0.00	0.00
END HT.	ft	0.00	0.00	0.00
WIDTH/DIAMETER	in	12"	18"	24"
CIRCULAR ?	y/n	Y	Y	Y
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surface:				
Point Load	ft-#	1,391	1,391	1,391
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	1,391	1,391	1,391
Total Lateral Load	#	180	180	180
NON-RESTRAINED				
Min. Req'd Embedment		4'-0"	3'-5"	3'-1"
$A(1+(1+4.36h/A)^.5)/2$		3.88'	3.34'	3.01'
$A=2.34P/(S 1 b)$		DEPTH	DEPTH	DEPTH
Press. @ 1/3 Embed.:				
Actual	psf	345	296	266
Allowable	psf	344	296	267
RESTRAINED				
Min. Req'd Embedment		0.00	0.00	0.00
$(4.25 P h/S3 b)^.5$	ft			
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint				
Force	lbs	0	0	0

PER CBC TABLE 18-  
POLE 2 ALLOWABLE





COAST SIGN, INC.  
1345 S. ALLEC STREET  
ANAHEIM, CA 92805

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-3-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPE W32.0 - DIRECTIONALS  
A = 1.8' \* 5.47' = 9.8 S.F. (MAX. AREA)  
A = 7.86' \* 0.25' = 2.0 S.F. (COL.)  
A = 0.67' \* 1.0' = 0.7 S.F. (BASE)

NOTE: 2-WAY DIRECTIONAL GOVERNS  
FOR WIND -- OTHER CONFIGURATIONS  
ARE O.K. BY INSPECTION.

WIND CBC-'01 80 MPH EXP. C

CBC-1613  $p=Cq*Ce*Qs*I$  I=1.0  
 $Qs = 16.4$   $Cq = 1.4$   
 25.94 LBS/S.F. @ 20'  $Ce = 1.13$   
 24.34 LBS/S.F. < 15'  $Ce = 1.06$   
 S.F. LBS FT. FT. LBS  
 AREA | PRESS | X-DIST | MOM-XX

9.8	239	9.00	2147
2.0	49	4.00	195
0.7	17	0.34	6
0.0	0	0.00	0

TOTAL 304 7.72 2347  
(AVE.)

SINGLE COLUMN  
MOM. 'K 2.35


ALUM  $F_y = 12$  K/SQ. IN.  
 $S = M/P_b$  WIND 1/3 INCR.  
 $S = 0.75 * M$  (INCL 1.33 WIND)  
 $S = 1.76$  IN<sup>3</sup>

$t = 0.216$  IN. (MIN. THK.)  
 $S = .0982 * (d^4 - d_1^4) / d$   
 $d = 4$   $d_1 = 3.568$   
 USE MIN. 3.5" DIA. x 0.216 ALUM. PIPE  
 $S = 2.31$  IN<sup>3</sup> > 1.76  
 O.K.

WT. OF SIGN = 130 LBS +/-  
AXIAL STRESS IS NEGLIGIBLE

COAT ALUM. SURFACES EMBEDDED IN  
CONC. WITH ONE HEAVY COAT OF  
ALKALI-RESISTANT BITUMINOUS  
(BITUMASTIC PAINT -- SUCH AS  
HENRY'S OR EQUIVALENT).

SEE PAGE 2 FOR FOOTING DETAILS



SOB No. HUNT-1A7


HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI



SINGLE COLUMN  
DESIGN OF EMBEDDED POLE FOOTINGS

DESCRIPTION	>>	10" DIA.	12" DIA.	
CHOOSE ONE	→	OPTIONAL	OPTIONAL	
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	304	304	304
LOAD HT.	ft	7.72	7.72	7.72
DIST. LOAD	#/ft	0	0	0
START HT.	ft	0.00	0.00	0.00
END HT.	ft	0.00	0.00	0.00
WIDTH/DIAMETER	in	10"	12"	0
CIRCULAR ?	y/n	Y	Y	Y
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surface:				
Point Load	ft-#	2,347	2,347	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	2,347	2,347	0
Total Lateral Load	#	304	304	0
NON-RESTRAINED				
Min. Req'd Embedment		5'-2"	4'-9"	RESULTS
$A(1+(1+4.36h/A)^.5)/2$	ft	5.06	4.72	0.00
Press @ 1/3 Embed.:				
Actual	psf	449	419	0
Allowable	psf	449	419	0
RESTRAINED				
Min. Req'd Embedment		0.00	0.00	0.00
$(4.25 P h / S^3 b)^.5$	ft	0.00	0.00	0.00
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint				
Force	lbs	0	0	0


PER CBC TABLE 18-1-  
POLE 2x ALLOWABLE








Note: All sign surfaces to be sprayed with semi gloss anti graffiti clear coating.






ELEVATION | 1" = 1'-0" ——— "ARROW" CONFIGURATIONS





ELEVATION | 1" = 1'-0" ——— LAYOUT OPTION "A"




ELEVATION | 1" = 1'-0" ——— LAYOUT OPTION "B"


Note:  
This sign cannot be used within any path of travel.  
The height from the ground to the bottom of the sign is less than the minimum 80 inches ADA requirement for signs located in a path of travel.



SIDE VIEW | 1 1/2" = 1'-0"




PLAN VIEW 1/2" = 1'-0"




FINIAL DETAIL 1" = 1'-0"


Exterior grade transparent colored digital print with U.V. inhibitors for exterior use and adhesive backing applied to #7238 white acrylic panel.



ELEVATION 1/2" = 1'-0"







SIDE VIEW 1/2" = 1'-0"



COLORS N.T.S.





Not Used


COAST SIGN, INC.  
1345 S. ALLEC STREET  
ANAHEIM, CA 92805

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-3-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPE W40.0 & W42.0  
A = 3.5' \* 5.25' = 18.4 S.F.  
A = 6.88' \* 0.25' \* 2 COL. = 3.4 S.F.

NOTE: SIGN TYPE W42.0 IS SLIGHTLY  
SMALLER IN SIZE THAN W40.0 -  
COLUMN & FOOTING DESIGN FOR BOTH  
IS O.K. BY INSPECTION



WIND	CBC-'01	80 MPH, EXP. C
CBC-1613	$p=Cq*Ce*Qs*I$	$I=1.0$
Qs =	16.4	Cq = 1.4
	25.94 LBS/S.F. @ 20'	Ce = 1.13
	24.34 LBS/S.F. < 15'	Ce = 1.06
S.F.	LBS	FT. FT. LBS
AREA	!PRESS!	X-DIST ! MOM-XX
18.4	448	4.26 1908
3.4	83	3.44 285
0.0	0	0.00 0
0.0	0	0.00 0

TOTAL 531 4.13 2192  
(AVE.)

DOUBLE COLUMN  
MOM. 'K 1.10

ALUM  $F_y = 12$  K/SQ. IN.  
 $S = M/F_b$  WIND 1/3 INCR.  
 $S = 0.75 * M$  (INCL 1.33 WIND)  
 $S = 0.82$  IN<sup>3</sup>

$t = 0.216$  IN. (MIN. THK.)  
 $S = .0982*(d^4-d1^4)/d$   
 $d = 3.5$   $d1 = 3.068$

USE MIN. 3" DIA. x 0.216 ALUM. PIPE #40

$S = 1.72$  IN<sup>3</sup> > 0.82  
O.K.

WT. OF SIGN = 220 LBS +/-  
AXIAL STRESS IS NEGLIGIBLE

COAT ALUM. SURFACES EMBEDDED IN  
CONC. WITH ONE HEAVY COAT OF  
ALKALI-RESISTANT BITUMINOUS  
(BITUMASTIC PAINT -- SUCH AS  
HENRY'S OR EQUIVALENT).

SEE PAGE 2 FOR FOOTING DETAILS



JOB NO. HUNT-146

HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

SINGLE FOOTING - STRAIGHT





DESIGN OF EMBEDDED POLE FOOTINGS

DESCRIPTION	>>	64" WIDE		
	>>	X 12" THK.		
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	31	0	0
LOAD HT.	ft	4	0.00	0.00
DIST. LOAD	#/ft	0	0	0
START HT.	ft	0.00	0.00	0.00
END HT.	ft	0.00	0.00	0.00
WIDTH/DIAMETER	in	64"	0	0
CIRCULAR ?	N	N	N	N
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surf				
Point	ft-#	2,193	0	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	2,193	0	0
Total Lateral Load	#	531	0	0
NON RESTRAINED				
Req'd Embedment		2'-5"		
$A(1+(1+4.36h/A)^.5)/2$		2.34'	0.00	0.00
$A=2.34P/(S 1 b)$	ft	MIN.		
Press @ 1/3 Embed.:				
Actual	psf	207	0	0
Allowable	psf	207	0	0
RESTRAINED				
Min. Req'd Embedment		0.00	0.00	0.00
$(4.25 P h/S3 b)^.5$	ft			
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint				
Force	lbs	0	0	0


PER CBC TABLE 18-1-A  
POLE 2x ALLOWABLE

Not Used











Exterior grade transparent colored digital print with U.V. inhibitors and adhesive backing applied to #7238 white acrylic panel.







Not Used

4 1/4" Ø, 1/2" thick aluminum cap drilled and tapped for assembly. Cap to have painted finish.

1/4" thick welded aluminum clip drilled and tapped for mounting decorative cap.

Ease edges ±3/16" radius.

Finished grade

4 1/4" Ø

3 1/2" Ø aluminum sphere with 1/4" Ø all thread steel stud for attaching to top base cap. Sphere to be painted.

3" Ø x .216" wall aluminum pipe with 6 1/2" Ø, 3/4" thick welded decorative aluminum base plate. Pipe and plate with painted finish.

6 1/2" Ø

3/4"

3" Ø x .216" wall aluminum pipe with 8" x 8" x 3/8" welded aluminum plate. Coat embedded aluminum with alkali resistant bituminous paint.

Concrete footing with integral colored concrete mow pad as per sign engineering.

1/4" thick header panel with side returns with painted finish.

Fabricated .090 aluminum cabinet with painted finish. Seams welded, grounded and filled smooth or hairline seams. Cabinet interior to be painted.

Welded 1/4" wall aluminum angle door frame with seams welded, grounded and filled smooth or hairline seams. All visible of door framing to be painted.


Stainless steel countersunk mechanical fasteners.

1/4" thick clear lexan door face

3/8" thick #7328 white acrylic with surface applied translucent colored digital map and copy with U.V. inhibitors. Use translucent vinyl diffuser on back if necessary to achieve even illumination.

Internal back light fluorescent lamps with interior wireway. Cabinet interior not visible from outside to be painted white.

1" x 1 1/2" aluminum flat bar lexan retainer frame fastened to back of aluminum door facing with countersunk screws.



Conduit with primary power to sign by others.

± 4" O.D. aluminum collar mechanically fastened to pole with countersunk tamperproof stainless steel screws.

End of sign cabinet

1" x 2 1/2", 2 1/4" long, rectangular aluminum tubing welded to pole collar.

Stainless steel mechanical fasteners.

1/4" thick aluminum clip welded inside of tubing and drilled and tapped for mechanical fasteners.

2"

2 1/2"

SECTION 1 1/2" = 1'-0" (D)

SECTION 1 1/2" = 1'-0" (C)

SECTION 1 1/2" = 1'-0" (B)


COAST SIGN, INC.  
1345 S. ALLEC STREET  
ANAHEIM, CA 92805

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-3-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPE W40.0 & W42.0  
A = 3.5' \* 5.25' = 18.4 S.F.  
A = 6.88' \* 0.25' \* 2 COL. = 3.4 S.F.

NOTE: SIGN TYPE W42.0 IS SLIGHTLY  
SMALLER IN SIZE THAN W40.0 -  
COLUMN & FOOTING DESIGN FOR BOTH  
IS O.K. BY INSPECTION



WIND	CBC-'01	80 MPH, EXP. C		
CBC-1613	$p=Cq*Ce*Qs*I$	$I=1.0$		
Qs =	16.4	Cq =	1.4	
	25.94 LBS/S.F. @ 20'	Ce =	1.13	
	24.34 LBS/S.F. < 15'	Ce =	1.06	
S.F.	LBS	FT.	FT.	LBS
AREA	!PRESS!	X-DIST	!	MOM-XX
18.4	448	4.26		1908
3.4	83	3.44		285
0.0	0	0.00		0
0.0	0	0.00		0

TOTAL	531	4.13	2192
		(AVE.)	
DOUBLE COLUMN			
MOM. 'K	1.10		

ALUM  $F_y = 12$  K/SQ. IN.  
S = M/Fb WIND 1/3 INCR.  
S = 0.75 \* M (INCL 1.33 WIND)  
S = 0.82 IN<sup>3</sup>  
t = 0.216 IN. (MIN. THK.)  
S = .0982\*(d<sup>4</sup>-d1<sup>4</sup>)/d  
d = 3.5 d1 = 3.068  
USE MIN. 3" DIA. x 0.216 ALUM. PIPE #  
S = 1.72 IN<sup>3</sup> > 0.82

WT. OF SIGN = 220 LBS +/-  
AXIAL STRESS IS NEGLIGIBLE  
COAT ALUM. SURFACES EMBEDDED IN  
CONC. WITH ONE HEAVY COAT OF  
ALKALI-RESISTANT BITUMINOUS  
(BITUMASTIC PAINT -- SUCH AS  
HENRY'S OR EQUIVALENT).  
SEE PAGE 2 FOR FOOTING DETAILS



JOB NO. HUNT-146

HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106



PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI


SINGLE FOOTING - STRAIGHT  
DESIGN OF EMBEDDED POLE FOOTINGS

DESCRIPTION	>>	64" WIDE		
	>>	X 12" THK.		
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	531	0	0
LOAD HT.	ft	4.13	0.00	0.00
DIST. LOAD	#/ft	0	0	0
START HT	ft	0.00	0.00	0.00
END HT	ft	0.00	0.00	0.00
WIND METER	in	64"	0	0
REMAINED?	y/n	N	N	N
REMAINED?	y/n	N	N	N
--- SUMMARY ---				
Moments @ Surface:				
Point Load	ft-#	2,193	0	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	2,193	0	0
Total Lateral Load	#	531	0	0
--- NON-RESTRAINED ---				
Min. Req'd Embedment		2'-5"		
$A(1+(1+4.36h/A)^.5)/2$				
A=2.34P/(S 1 b)	ft	2.34'	0.00	0.00
Press @ 1/3 Embed.:		MIN.		
Actual	psf	207	0	0
Allowable	psf	207	0	0
--- RESTRAINED ---				
Min. Req'd Embedment		0.00	0.00	0.00
$(4.25 P h/S3 b)^.5$	ft			
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint				
Force	lbs	0	0	0

PER CBC TABLE 18-1-A  
POLE 2x ALLOWABLE







Not used

Welded 1/4" wall aluminum angle cabinet wrap with welds ground and filled smooth or hairline seams.

Welded 1/4" wall aluminum door frame face trim with welds ground and filled smooth.

3/4" x 1 1/4" aluminum flat bar retainer frame mechanically fastened to door face trim. Drilled and tapped using countersunk stainless steel screws.




1/4" thick clear lexan.

Fabricated .080 aluminum cabinet pan with all inside and outside painted surfaces.

Tan Nucork bulletin board with hardwood backer RAL 1003 Signal Yellow powder coat finish.

Welded 1 1/2", 1/4" thick, aluminum flat support framing welded to back of cabinet. Drill and tap to fasten graphic panel.

Countersunk mechanical fasteners around perimeter concealed behind door trim.




COAST SIGN, INC.  
1345 S. ALLEC STREET  
ANAHEIM, CA 92805

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-3-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPE W40.0 & W42.0  
A = 3.5' \* 5.25' = 18.4 S.F.  
A = 6.88' \* 0.25' \* 2 COL. = 3.4 S.F.

NOTE: SIGN TYPE W42.0 IS SLIGHTLY  
SMALLER IN SIZE THAN W40.0 -  
COLUMN & FOOTING DESIGN FOR BOTH  
IS O.K. BY INSPECTION



WIND	CBC-'01	80 MPH, EXP. C
CBC-1613	$p=Cq*Ce*Qs*I$	$I=1.0$
Qs =	16.4	Cq = 1.4
	25.94 LBS/S.F. @ 20'	Ce = 1.13
	24.34 LBS/S.F. < 15'	Ce = 1.06
S.F.	LBS	FT. FT. LBS
AREA	!PRESS!	X-DIST ! MOM-XX
18.4	448	4.26 1908
3.4	83	3.44 285
0.0	0	0.00 0
0.0	0	0.00 0

TOTAL	531	4.13	2192
		(AVE.)	
DOUBLE COLUMN			
MOM. 'K	1.10		

ALUM  $F_y = 12$  K/SQ. IN.  
S = M/Fb WIND 1/3 INCR.  
S = 0.75 \* M (INCL 1.33 WIND)  
S = 0.82 IN<sup>3</sup>  
t = 0.216 IN. (MIN. THK.)  
S = .0982\*(d<sup>4</sup>-d1<sup>4</sup>)/d  
d = 3.5 d1 = 3.068  
USE MIN. 3" DIA. x 0.216 ALUM. PIPE #40  
S = 1.72 IN<sup>3</sup> > 0.82  
O.K.

WT. OF SIGN = 220 LBS  
AXIAL STRESS IS NEGLIGIBLE

COAT ALUM. SURFACES EMBEDDED IN  
CONC. WITH ONE HEAVY COAT OF  
ALKALI-RESISTANT BITUMINOUS  
(BITUMASTIC PAINT -- SUCH AS  
HENRY'S OR EQUIVALENT).

SEE PAGE 2 FOR FOOTING DETAILS



JOB NO. HUNT-146

HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106


PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

SINGLE FOOTING - STRAIGHT  
DESIGN OF EMBEDDED POLE FOOTINGS

DESCRIPTION	>>	64" WIDE		
	>>	X 12" THK.		
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	531	0	0
LOAD H	ft	4.13	0.00	0.00
DIST. L	#/ft	0	0	0
ST. H	ft	0.00	0.00	0.00
E	ft	0.00	0.00	0.00
DIAMETER	in	64"	0	0
CIRCULAR ?	y/n	N	N	N
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surface:				
Point Load	ft-#	2,193	0	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	2,193	0	0
Total Lateral Load	#	531	0	0
--- NON-RESTRAINED ---				
Min. Req'd Embedment		2'-5"		
$A(1+(1+4.36h/A)^.5)/2$				
A=2.34P/(S 1 b)	ft	2.34'	0.00	0.00
Press @ 1/3 Embed.:		MIN.		
Actual	psf	207	0	0
Allowable	psf	207	0	0
--- RESTRAINED ---				
Min. Req'd Embedment		0.00	0.00	0.00
$(4.25 P h/S3 b)^.5$	ft			
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint				
Force	lbs	0	0	0

PER CBC TABLE 18-1-A  
POLE 2x ALLOWABLE





Not Used




Product Name: Sliivr (sli-ver) Type: Floorstanding



**DESCRIPTION:**  
 Proof that true beauty is more than skin deep. The standard 19" LCD display is highlighted by the architecture of the surrounding steel enclosure. The internal peripherals are designed for quick cold swapping and easy, unobtrusive maintenance. Designed to be the perfect informational kiosk, the Sliivr is the choice for free standing directory, way-finding and in-store cataloging applications.

**DIMENSIONS:**






**INCLUDED W/ BASE MODEL:**  
 19" LCD Display  
 Powder Coated Steel Side Accent Blades  
 Large Access Doors with Tubular Locks/Keys  
 Tempered Glass Display Overlay (Certain UI Options Only)  
 Cooling Fan  
 Industrial Power Strip  
 2.5 Watt Speakers / 8 Ohm Impedance

**SPECIFICATIONS:**  
 Precision cut, 16 gauge steel enclosure  
 Full Interior MIG Welds / Custom Brackets & Mounts  
 Cardinal Industrial Powder Coat Finish  
 Kiosk Temp Range:  
 Operating: 42-90° F  
 Stored: 33-100° F


**OPTIONS:**  
 Installation / Warranty  
 Custom & Off The Shelf Software  
 PC & PC Upgrades  
 Branding & Graphics  
 Accent Blade Color Options  
 Multimedia  
 Custom Finishes  
 User Input Devices  
 Card Readers / Scanners  
 Custom Component Integration  
 Shipping & Delivery

**WEIGHT:**  
 Kiosk Base Weight: \*\* 120lbs  
 \*\* Shipping weight and cost will vary depending on options selected


Not Used








Double faced sign perpendicular to roadway



Double faced sign perpendicular to roadway





Double faced sign perpendicular to roadway

LAYOUT CONDITIONS

1" = 1'-0"

See Sheet 1.27, Sign Type W50, for Specifications



LAYOUT CONDITIONS

1" = 1'-0"

See Sheet 1.27, Sign Type W50, for Specifications


HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPES W50.0 & W70.0  
A = 5.29' \* 2.96' = 15.7 S.F. (TYPE W70.0)

NOTE: SIGN TYPE W50.0 IS SLIGHTLY  
SMALLER IN SIZE THAN TYPE W70.0 -  
COLUMN & FOOTING DESIGN FOR BOTH  
IS O.K. BY INSPECTION



JOB NO. HUNT-144

WIND	CBC-'01	80 MPH, EXP. C
CBC-1613	$p=Cq \cdot Ce \cdot Qs \cdot I$	$I=1.0$
$Qs =$	16.4	$Cq = 1.4$
	25.94 LBS/S.F. @ 20'	$Ce = 1.13$
	24.34 LBS/S.F. < 15'	$Ce = 1.06$
S.F.	LBS	FT.
AREA	!PRESS!	X-DIST
15.7	382	2.65
0.0	0	0.00
0.0	0	0.00
0.0	0	0.00

TOTAL	382	2.65	1013
		(AVE.)	
DOUBLE COLUMN			
MOM.'K	0.51		

ALUM  $F_b = 12$  K/SQ. IN.  
 $S = M/F_b$  WIND 1/3 INCR.  
 $S = 0.75 \cdot M$  (INCL 1.33 WIND)  
 $S = 0.38$  IN<sup>3</sup>

$S = (bd^3 - b1 \cdot d1^3) / (6 \cdot d)$   
 $d = 2$   $d1 = 1.75$   
 $b = 2$   $b1 = 1.75$

USING 2"x2"x 1/8" ALUM. TUBE  
 $S = 0.55$  IN<sup>3</sup> > 0.38  
O.K.

COAT ALUM. SURFACES EMBEDDED IN  
CONC. WITH ONE HEAVY COAT OF  
ALKALI-RESISTANT BITUMINOUS  
(BITUMASTIC) PAINT TO 2" MIN.  
ABOVE GRADE

WT. OF SIGN = 175 LBS +/-  
AXIAL STRESS IS NEGLIGIBLE

SEE PAGE 2 FOR FOOTING DETAILS



HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

SINGLE FOOTING - STRAIGHT

DESIGN OF EMBEDDED POLE FOOTINGS



DESCRIPTION	>>	42" WIDE	>>	PER CBC TABLE 18-1-A POLE 2x ALLOWABLE
		+ 12" THK.		
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	382	0	0
LOAD HT.	ft	2.65	0.00	0.00
DIST. LOAD	#/ft	0	0	0
START HT.	ft	0.00	0.00	0.00
END HT.	ft	0.00	0.00	0.00
WIDTH/DIAMETER	in	42	0	0
CIRCULAR ?	y/n	N	N	N
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surface:				
Point Load	ft-#	1,012	0	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	1,012	0	0
Total Lateral Load	#	382	0	0
NON-RESTRAINED				
Min. Req'd Embedment				
$A(1+(1+4.36h/A)^{.5})/2$	ft	2'-3"		
$A=2.34P/(S \cdot 1 \cdot b)$	ft	2.18'	0.00	0.00
Press @ 1/3 Embed.:		DEPTH		
Actual	psf	194	0	0
Allowable	psf	193	0	0
RESTRAINED				
Min. Req'd Embedment				
$(4.25 P h / S3 b)^{.5}$	ft	0.00	0.00	0.00
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint Force	lbs	0	0	0







Not used



LAYOUT CONDITIONS | 1" = 1'-0" ————— See Sheet 1.31, Sign Type W51, for Specifications


HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPES W50.0 & W70.0  
A = 5.29' \* 2.96' = 15.7 S.F. (TYPE W70.0)

NOTE: SIGN TYPE W50.0 IS SLIGHTLY  
SMALLER IN SIZE THAN TYPE W70.0 -  
COLUMN & FOOTING DESIGN FOR BOTH  
IS O.K. BY INSPECTION



JOB NO. HUNT-144

WIND CBC-'01 80 MPH, EXP. C

CBC-1613  $p=Cq \cdot Ce \cdot Qs \cdot I$   $I=1.0$   
 $Qs = 16.4$   $Cq = 1.4$   
 25.94 LBS/S.F. @ 20'  $Ce = 1.13$   
 24.34 LBS/S.F. < 15'  $Ce = 1.06$

S.F.	LBS	FT.	FT.	LBS
AREA	!PRESS!	X-DIST	MOM-XX	
15.7	382	2.65	1013	
0.0	0	0.00	0	
0.0	0	0.00	0	
0.0	0	0.00	0	

TOTAL 382 2.65 1013 (AVE.)

DOUBLE COLUMN  
MOM.'K 0.51

ALUM  $F_b = 12$  K/SQ. IN.  
 $S = M/F_b$  WIND 1/3 INCR.  
 $S = 0.75 \cdot M$  (INCL 1.33 WIND)  
 $S = 0.38$  IN<sup>3</sup>

$S = (bd^3 - b1 \cdot d1^3) / (6 \cdot d)$   
 $d = 2$   $d1 = 1.75$   
 $b = 2$   $b1 = 1.75$

USING 2"x2"x 1/8" ALUM. TUBE  
 $S = 0.55$  IN<sup>3</sup> > 0.38  
 O.K.

COAT ALUM. SURFACES EMBEDDED IN  
 CONC. WITH ONE HEAVY COAT OF  
 ALKALI-RESISTANT BITUMINOUS  
 (BITUMASTIC) PAINT TO 2" MIN.  
 ABOVE GRADE

WT. OF SIGN = 175 LBS +/-  
 AXIAL STRESS IS NEGLIGIBLE

SEE PAGE 2 FOR FOOTING DETAILS



HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI


SINGLE FOOTING - STRAIGHT

DESIGN OF EMBEDDED POLE FOOTINGS


DESCRIPTION	>>	42" WIDE		
	>>	+ 12" THK.		
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	382	0	0
LOAD HT.	ft	2.65	0.00	0.00
DIST. LOAD	#/ft	0	0	0
START HT.	ft	0.00	0.00	0.00
END HT.	ft	0.00	0.00	0.00
WIDTH/DIAMETER	in	42	0	0
CIRCULAR ?	y/n	N	N	N
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surface:				
Point Load	ft-#	1,012	0	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	1,012	0	0
Total Lateral Load	#	382	0	0
NON-RESTRAINED				
Min. Req'd Embedment				
$A(1+(1+4.36h/A)^{.5})/2$	ft	2'-3"		
$A=2.34P/(S \cdot 1 \cdot b)$	ft	2.18'	0.00	0.00
Press @ 1/3 Embed.:				
Actual	psf	194	0	0
Allowable	psf	193	0	0
RESTRAINED				
Min. Req'd Embedment				
$(4.25 P h / S3 b)^{.5}$ ft		0.00	0.00	0.00
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint Force	lbs	0	0	0

PER CBC TABLE 18-1-A  
POLE 2X ALLOWABLE







ELEVATION | 3/4" = 1'-0"






TWO LINE LAYOUT | 1 1/2" = 1'-0"



ONE LINE LAYOUT | 1 1/2" = 1'-0"



1 1/8" deep fabricated aluminum panel with painted finish. Graphics surface applied 3M Scotchlcal computer cut vinyl.







Exact placement to be determined in field.

Font: Frutiger 65 (BOLD) • Cast Aluminum • Letters with horizontally brushed finish • 10" high, wall mounted • 1/2" stand-offs from wall, preferably affixed to monolithic facade material (depending on building design)

Depending on height of letter location on the building, confer with PD&C on correct letter height. 3 digit

Fire address required per code (3 digits of Capital Asset Account No. (CAAN) - contact Campus Space Manager and Campus Fire Marshall)

**TWO SETS** of building identification and fire address are required for each building

LOCATION ELEVATION | N.T.S. \_\_\_\_\_




ELEVATION | 3/4" = 1'-0" \_\_\_\_\_


Standard Times Bold cast bronze letters with 1/2" stainless steel stand-offs from wall.

Bold cast bronze letters with 1/2" stainless steel stand-offs from wall.


Stainless steel all thread studs with wall mounting holes filled with 2-part epoxy adhesive.




TYPICAL LETTER SECTION | 3/4" = 1'-0" \_\_\_\_\_




ELEVATION | 3/4" = 1'-0"



LAYOUT | 1 1/2" = 1'-0"






HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPES W50.0 & W70.0  
A = 5.29' \* 2.96' = 15.7 S.F. (TYPE W70.0)

NOTE: SIGN TYPE W50.0 IS SLIGHTLY  
SMALLER IN SIZE THAN TYPE W70.0 -  
COLUMN & FOOTING DESIGN FOR BOTH  
IS O.K. BY INSPECTION



JOB NO. HUNT-144

WIND CBC-'01 80 MPH, EXP. C

CBC-1613  $p=Cq \cdot Ce \cdot Qs \cdot I$   $I=1.0$   
 $Qs = 16.4$   $Cq = 1.4$   
 25.94 LBS/S.F. @ 20'  $Ce = 1.13$   
 24.34 LBS/S.F. < 15'  $Ce = 1.06$

S.F.	LBS	FT.	FT.	LBS
AREA	PRESS	X-DIST	MOM-XX	
15.7	382	2.65	1013	
0.0	0	0.00	0	
0.0	0	0.00	0	
0.0	0	0.00	0	
<b>TOTAL</b>	<b>382</b>	<b>2.65</b>	<b>1013</b>	

(AVE.)

DOUBLE COLUMN  
MOM. 'K 0.51

ALUM  $F_b = 12$  K/SQ. IN.  
 $S = M/F_b$  WIND 1/3 INCR.  
 $S = 0.75 \cdot M$  (INCL 1.33 WIND)  
 $S = 0.38$  IN<sup>3</sup>

$S = (bd^3 - b1 \cdot d1^3) / (6 \cdot d)$   
 $d = 2$   $d1 = 1.75$   
 $b = 2$   $b1 = 1.75$

USING 2" x 2" x 1/8" ALUM. TUBE  
 $S = 0.55$  IN<sup>3</sup> > 0.38  
 O.K.

COAT ALUM. SURFACES EMBEDDED IN  
 CONC. WITH ONE HEAVY COAT OF  
 ALKALI-RESISTANT BITUMINOUS  
 (BITUMASTIC) PAINT TO 2" MIN.  
 ABOVE GRADE

WT. OF SIGN = 175 LBS +/-  
 AXIAL STRESS IS NEGLIGIBLE

SEE PAGE 2 FOR FOOTING DETAILS



HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI




SINGLE FOOTING - STRAIGHT

DESIGN OF EMBEDDED POLE FOOTINGS

DESCRIPTION	>>	42" WIDE		
	>>	+ 12" THK.		
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	382	0	0
LOAD HT.	ft	2.65	0.00	0.00
DIST. LOAD	#/ft	0	0	0
START HT.	ft	0.00	0.00	0.00
END HT.	ft	0.00	0.00	0.00
WIDTH/DIAMETER	in	42	0	0
CIRCULAR ?	y/n	N	N	N
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surface:				
Point Load	ft-#	1,012	0	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	1,012	0	0
Total Lateral Load	#	382	0	0
NON-RESTRAINED				
Min. Req'd Embedment				
$A(1+(1+4.36h/A)^{.5})/2$	ft	2'-3"		
$A=2.34P/(S \cdot 1 \cdot b)$	ft	2.18'	0.00	0.00
Press @ 1/3 Embed.:		DEPTH		
Actual	psf	194	0	0
Allowable	psf	193	0	0
RESTRAINED				
Min. Req'd Embedment				
$(4.25 P h / S3 b)^{.5}$ ft		0.00	0.00	0.00
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint Force	lbs	0	0	0

PER CBC TABLE 18-1-A  
POLE 2X ALLOWABLE





Note:  
All sign panel surfaces to be sprayed with semi gloss anti graffiti clear coating.



Permanent fabricated aluminum cabinet with painted finish. Surface applied 3M scotchlite white engineering grade reflective graphics.

Double sided changeable aluminum panel with painted finish on all surfaces. Surface applied 3M Scotchlite white engineering grade reflective vinyl graphics.

Permanent silkscreened logo. (Refer to sheet 1.6 for colors)

Ease edges ±3/16" radius.

Concrete footing and mow pad with integral colored concrete as per engineering.




HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106

PAGE: 1 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

FOR COLUMN & FOOTING DESIGN

AREA -- SIGN TYPES W50.0 & W70.0  
A = 5.29' \* 2.96' = 15.7 S.F. (TYPE W70.0)

NOTE: SIGN TYPE W50.0 IS SLIGHTLY  
SMALLER IN SIZE THAN TYPE W70.0 -  
COLUMN & FOOTING DESIGN FOR BOTH  
IS O.K. BY INSPECTION



JOB NO. HUNT-144

WIND CBC-'01 80 MPH, EXP. C

CBC-1613	$p=Cq \cdot Ce \cdot Qs \cdot I$	$I=1.0$
$Qs =$	$16.4$	$Cq = 1.4$
	$25.94 \text{ LBS/S.F. @ } 20'$	$Ce = 1.13$
	$24.34 \text{ LBS/S.F. } < 15'$	$Ce = 1.06$
S.F.	LBS	FT.
AREA	!PRESS!	X-DIST
15.7	382	2.65
0.0	0	0.00
0.0	0	0.00
0.0	0	0.00

TOTAL 382 2.65 1013 (AVE.)

DOUBLE COLUMN MOM.'K 0.51

ALUM  $F_b = 12 \text{ K/SQ. IN.}$   
 $S = M/F_b$  WIND 1/3 INCR.  
 $S = 0.75 \cdot M$  (INCL 1.33 WIND)  
 $S = 0.38 \text{ IN}^3$

$S = (bd^3 - b1 \cdot d1^3) / (6 \cdot d)$   
 $d = 2$   $d1 = 1.75$   
 $b = 2$   $b1 = 1.75$

USING 2"x2"x 1/8" ALUM. TUBE  
 $S = 0.55 \text{ IN}^3 > 0.38$   
O.K.

COAT ALUM. SURFACES EMBEDDED IN  
CONC. WITH ONE HEAVY COAT OF  
ALKALI-RESISTANT BITUMINOUS  
(BITUMASTIC) PAINT TO 2" MIN.  
ABOVE GRADE

WT. OF SIGN = 175 LBS +/-  
AXIAL STRESS IS NEGLIGIBLE

SEE PAGE 2 FOR FOOTING DETAILS



HUNT DESIGN  
25 N. MENTOR AVE.  
PASADENA, CA 91106


PAGE: 2 of 2  
PROJECT: UC RIVERSIDE  
SUBJECT: RIVERSIDE, CA  
SIGN STRUCTURAL CALCS.  
BY: DVM DATE: 10-1-07  
P.O.# DWGS. FROM PERRY SHIMOJI

SINGLE FOOTING - STRAIGHT

DESIGN OF EMBEDDED POLE FOOTINGS



DESCRIPTION	>>	42" WIDE	>>	PER CBC TABLE 18-1-A POLE 2X ALLOWABLE
		+ 12" THK.		
ALLOW PASSIVE	psf	200	200	200
MAX PASSIVE	psf	1,500	1,500	1,500
LOAD DURATION FACTOR		1.33	1.33	1.33
POINT LOAD	lbs	382	0	0
LOAD HT.	ft	2.65	0.00	0.00
DIST. LOAD	#/ft	0	0	0
START HT.	ft	0.00	0.00	0.00
END HT.	ft	0.00	0.00	0.00
WIDTH/DIAMETER	in	42	0	0
CIRCULAR ?	y/n	N	N	N
RESTRAINED ?	y/n	N	N	N
SUMMARY				
Moments @ Surface:				
Point Load	ft-#	1,012	0	0
Uniform Load	ft-#	0	0	0
... Total Moment	ft-#	1,012	0	0
Total Lateral Load	#	382	0	0
NON-RESTRAINED				
Min. Req'd Embedment				
$A(1+(1+4.36h/A)^{.5})/2$	ft	2'-3"		
$A=2.34P/(S \cdot 1 \cdot b)$	ft	2.18'	0.00	0.00
Press @ 1/3 Embed.:		DEPTH		
Actual	psf	194	0	0
Allowable	psf	193	0	0
RESTRAINED				
Min. Req'd Embedment				
$(4.25 P h / S3 b)^{.5}$	ft	0.00	0.00	0.00
Pressure @ Bottom				
Actual	psf	0	0	0
Allowable	psf	0	0	0
Surface Restraint Force	lbs	0	0	0









ELEVATION (NEW POLE) | 1/2" = 1'-0"

BACK VIEW | 1/2" = 1'-0"




ELEVATION (EXISTING POLE) | 1/2" = 1'-0"







5-LINE CONDITION | 1" = 1'-0"








2-LINE CONDITION W/ LARGE NUMERAL | 1" = 1'-0"






Double faced 1/8" thick aluminum panel with painted finish on all surfaces and surface applied 3M scotchlite white engineering grade reflective vinyl graphics.

Note: All sign panel surfaces to be sprayed with semi gloss anti graffiti clear coating.






(A) SECTION | 3"=1'-0"


GENERAL NOTES:

1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.




ELEVATION | 1 1/2"=1'-0"

SIDE VIEW | 1 1/2"=1'-0"




LOCATION ELEVATION | 1/2"=1'-0"

**INTERIOR SIGNAGE**  
 interior locations, there is some latitude on the panel color and material. See MRB submittal as an example. Consult with Campus Architect.




ELEVATION | HALF SIZE



SIDE VIEW | HALF SIZE

GENERAL NOTES:

1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.




LOCATION ELEVATION | 1/2"=1'-0"


GENERAL NOTES:

1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.
3. Braille shall be Calif Grade 2 (Contracted Braille).
4. An inverted "L" shall precede all numbers in Braille.


**INTERIOR SIGNAGE**  
 interior locations, there is some latitude on the panel color and material. See MRB submittal as an example. Consult with Campus Architect.



LOCATION ELEVATION | 1/4"=1'-0"



ALTERNATE GLASS MOUNTING | 1/4"=1'-0"




ELEVATION | HALF SIZE

1/4" thick photopolymer etched panel with 1/32" raised copy, California grade 2 braille.


1/4" x 1/4" square aluminum bar raised 1/8" above etched background and eased edges. Attached with concealed fasteners threaded and taped from back light sandblast finish.

Separate changeable bottom panel 1/16" thick New Hermes Gravoply II panel laminated to 1/8" acrylic panel. Copy to be engraved and panel sides to be painted to match slate gray.

1/16" thick acrylic backer panel permanently mounted to wall with 3M VHB tape and silicone. Paint sides to match adjacent sides.



SIDE VIEW | HALF SIZE




SIDE VIEW (GLASS MOUNT) | HALF SIZE


Updated 11/02/09

**GENERAL NOTES:**


1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.
3. Braille shall be Calif Grade 2 (Contracted Braille)
4. An inverted "L" shall precede all numbers in Braille.




LOCATION ELEVATION | 1/4"=1'-0"




ALTERNATE GLASS MOUNTING | 1/4"=1'-0"




ELEVATION | HALF SIZE




SIDE VIEW | HALF SIZE




SIDE VIEW (GLASS MOUNT) | HALF SIZE




- GENERAL NOTES:
1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
  2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.
  3. Braille shall be Calif Grade 2 (Contracted Braille).
  4. 1/16" tolerance provided at top and bottom for paper insert




**CORRECTION TO CAMPUS SIGN PROGRAM**  
 DRAWING 1.63X (REPLACES DRAWING 1.63)

AUTHORIZED BY:  
  
 JULY 12, 2011

**TIMOTHY RALSTON**  
 ASSOCIATE VICE CHANCELLOR  
 CAPITAL RESOURCE MANAGEMENT  
 UNIVERSITY OF CALIFORNIA, RIVERSIDE





**GENERAL NOTES:**

1. This sign is to be fabricated identical to sign type B32 in all respects with the exception of the following:
  - a. Overall width will be 11"
  - b. Overall height will be 11 5/8"
2. For all additional details refer to DWG. 1.63X of the 2008 CAMPUS SIGN PROGRAM

ELEVATION | HALF SIZE

**AMENDMENT TO CAMPUS SIGN PROGRAM**  
 DRAWING 1.63A FOR SIGN TYPE B32A


AUTHORIZED BY:

*Timothy Ralston*  
 JULY 12, 2011

**TIMOTHY RALSTON**  
 ASSOCIATE VICE CHANCELLOR  
 CAPITAL RESOURCE MANAGEMENT  
 UNIVERSITY OF CALIFORNIA, RIVERSIDE

GENERAL NOTES:

1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.
3. Braille shall be Calif Grade 2 (Contracted Braille).
4. An inverted "L" shall precede all numbers in Braille.





Mens Room




Unisex Restroom

ADDITIONAL LAYOUTS




Womens Room






GENERAL NOTES:


1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.




ELEVATION | 3"=1'-0"



SIDE VIEW | 3"=1'-0"



LOCATION ELEVATION | 1/2"=1'-0"



**(3) COLUMN ELEVATION** | 1 1/2"=1'-0"

3'-2" (Total Height)

3'-2" (Total Width)

1 (Section Reference)

<b>Directory</b>		
Chemistry Computer Lab 123	Chemistry Computer Lab 123	Chemistry Computer Lab 123
Organic Composition Lab 321	Organic Composition Lab 321	Organic Composition Lab 321
Stock Room 456	Stock Room 456	Stock Room 456
Graduate Students Office 654	Graduate Students Office 654	Graduate Students Office 654
Instrumentation Room 415	Instrumentation Room 415	Instrumentation Room 415
Chemistry Computer Lab 123	Chemistry Computer Lab 123	Chemistry Computer Lab 123
Organic Composition Lab 321	Organic Composition Lab 321	Organic Composition Lab 321
Stock Room 456	Stock Room 456	Stock Room 456
Graduate Students Office 654	Graduate Students Office 654	Graduate Students Office 654
Instrumentation Room 415	Instrumentation Room 415	Instrumentation Room 415
Chemistry Computer Lab 123	Chemistry Computer Lab 123	Chemistry Computer Lab 123
Organic Composition Lab 321	Organic Composition Lab 321	Organic Composition Lab 321
Stock Room 456	Stock Room 456	Stock Room 456
Graduate Students Office 654	Graduate Students Office 654	Graduate Students Office 654
Instrumentation Room 415	Instrumentation Room 415	Instrumentation Room 415
Chemistry Computer Lab 123	Chemistry Computer Lab 123	Chemistry Computer Lab 123
Organic Composition Lab 321	Organic Composition Lab 321	Organic Composition Lab 321
Stock Room 456	Stock Room 456	Stock Room 456
Graduate Students Office 654	Graduate Students Office 654	Graduate Students Office 654
Instrumentation Room 415	Instrumentation Room 415	Instrumentation Room 415

1, 3, 7 (Section References)

6 (Section Reference)

Fabricated aluminum cabinet with clear tempered glass face. Hinged door to be locked mechanically with concealed captured screws/pins top and bottom on side of cabinet. Cabinet to be painted on all visible surfaces.

Changeable New Hermes Gravoply II name strips.


**(2) COLUMN ELEVATION** | 1 1/2"=1'-0"

2'-2" (Total Width)

1 (Section Reference)





<b>Directory</b>	
Chemistry Computer Lab 123	Chemistry Computer Lab 123
Organic Composition Lab 321	Organic Composition Lab 321
Stock Room 456	Stock Room 456
Graduate Students Office 654	Graduate Students Office 654
Instrumentation Room 415	Instrumentation Room 415
Chemistry Computer Lab 123	Chemistry Computer Lab 123
Organic Composition Lab 321	Organic Composition Lab 321
Stock Room 456	Stock Room 456
Graduate Students Office 654	Graduate Students Office 654
Instrumentation Room 415	Instrumentation Room 415
Chemistry Computer Lab 123	Chemistry Computer Lab 123
Organic Composition Lab 321	Organic Composition Lab 321
Stock Room 456	Stock Room 456
Graduate Students Office 654	Graduate Students Office 654
Instrumentation Room 415	Instrumentation Room 415
Chemistry Computer Lab 123	Chemistry Computer Lab 123
Organic Composition Lab 321	Organic Composition Lab 321
Stock Room 456	Stock Room 456
Graduate Students Office 654	Graduate Students Office 654
Instrumentation Room 415	Instrumentation Room 415

3, 7 (Section References)





GENERAL NOTES:

1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.




GENERAL NOTES:

1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.



ELEVATION | HALF SIZE



SIDE VIEW | HALF SIZE

NO FOOD OR DRINK

NO FOOD OR DRINK in building

ACADEMIC STUDY AREA





Sleeping, laying down, shoes/feet on furniture are not permitted

Assistive Listening Device available from (location T.B.D.)

ADDITIONAL LAYOUTS | HALF SIZE


GENERAL NOTES:

1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.




GENERAL NOTES:


1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.
3. Braille shall be Calif Grade 2 (Contracted Braille).
4. An inverted "L" shall precede all numbers in Braille.





ELEVATION | HALF SIZE




SIDE VIEW | HALF SIZE




LOCATION ELEVATION | 1/2"=1'-0"




C



Horizontal Map Layout





Vertical Map Layout








GENERAL NOTES:


1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition

3. Contact UCR Capital Programs for template artwork in Adobe Illustrator format.










PLAN VIEW

HALF SIZE




ELEVATION

HALF SIZE

SIDE VIEW

HALF SIZE



LOCATION ELEVATION


1/2"=1'-0"

GENERAL NOTES:


1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.
3. Braille shall be Calif Grade 2 (Contracted Braille).
4. An inverted "L" shall precede all numbers in Braille.

GENERAL NOTES:


1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.



ELEVATION | 3"=1'-0"




SIDE VIEW | 3"=1'-0"




LOCATION ELEVATION | 1/2"=1'-0"

GENERAL NOTES:


1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.



ELEVATION | HALF SIZE



SIDE VIEW | HALF SIZE




LOCATION ELEVATION | 1/2"=1'-0"



Computer cut 3M Scotchcal vinyl copy with color being gray or white as determined by existing surface color.


ELEVATION

3"=1'-0"




LOCATION ELEVATION


3/4"=1'-0"




ELEVATION | HALF SIZE



SIDE VIEW | HALF SIZE



ALTERNATE GLASS MOUNTING | 1/4"=1'-0"




LOCATION ELEVATION | 1/4"=1'-0"

GENERAL NOTES:


1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.
3. Braille shall be Calif Grade 2 (Contracted Braille).



ELEVATION HALF SIZE




SIDE VIEW HALF SIZE




LOCATION ELEVATION 1/4"=1'-0"

GENERAL NOTES:


1. Copy shown as typical layouts only, actual layouts to be determined and or verified prior to fabrication.
2. Sign installer to verify existing mounting conditions and use appropriate attachment method as per condition.




(A) DETAIL | FULL SIZE



ELEVATION | 1 1/2"=1'-0"



SIDE VIEW | 1 1/2"=1'-0"



LOCATION ELEVATION | 1/2"=1'-0"

# UCR Campus Process: Gender Inclusive Facilities 2015

**ISSUING OFFICER:** Associate Vice Chancellor/ Campus Architect

**RESPONSIBLE OFFICE:** Architects & Engineers    **EFFECTIVE DATE:** November 01, 2015

## I. Background

UCR is strongly committed to creating and sustaining a campus environment that supports and values all members of our community, including visitors. This Gender Inclusive Facilities process focuses on providing a safe environment, consistent with UCR principles of community and efforts aimed at civility and respect. Gender inclusion should provide access and equality by creating an environment that is safe, accessible and respectful of all individuals. One aspect of creating an inclusive environment is the availability of safe, accessible and convenient restroom facilities. Many people may experience difficulty, inconvenience or harassment when using gender specific restrooms and facilities. Additionally, parents with children of a different gender, as well as caregivers to persons of different genders, face difficulties in accompanying them. UCR aims to implement best practices for gender inclusive facilities.

## II. Goals of the UCR Gender Inclusive Process

In accordance with the University's nondiscrimination policies, these guidelines seek to create an inclusive campus environment for transgender and gender variant people and provide direction on the implementation of gender inclusive facilities in UCR-owned buildings.

## III. Definitions:

**Changing Room:** a room in which one or more persons partially or fully disrobe and re-dress. Locker rooms fall under this definition. Gender inclusive changing rooms shall provide privacy and security.

**Gender Identity:** an individual's sense of oneself as male, female or transgender, including an individual's self-image, appearance, expression or behavior, whether or not that self-image, appearance, expression or behavior is different from the individual's sex assigned at birth.

**Gender Inclusive facility** (sometimes referred to as Gender Neutral facility): a facility, including but not limited to restrooms, showers, locker rooms and changing rooms, that is



usable by persons of all gender identities and expressions and that is not gender specific. The facility shall provide privacy and security for the individual user. Gender inclusive facilities shall include spaces and fixtures equivalent to gender specific facilities.

**Gender Specific:** designated for use by one gender (i.e. male or female).

**Restroom:** any facility equipped with toilets, urinals and other similar facilities, in a public facility for use of the public for personal hygiene and comfort. “In a public facility” and “for use by the public” in this context covers essentially all UCR facilities and restrooms, except for facilities located within private residences or apartments, within dormitory suites, or in areas not accessible to the public.

**Shower:** a space in which one or more persons bathe or shower. Gender inclusive showers shall provide privacy and security for the individual user.

#### IV. **Applicability**

This process applies to UCR-owned facilities including new construction, existing and renovated facilities. While the process does not extend to UCR-leased facilities at this time, evaluation of the availability of gender inclusive facilities shall occur when beginning or renewing leases, especially when UCR leases more than 50% of a building, or for leases 10 years or longer. Privatized projects developed on UCR-owned land where the project is to be used for University-related purposes shall comply with the requirements for inclusive facilities.

#### V. **Process**

- a. **Existing Facilities: Capital Asset Strategies (CAS)** shall maintain an accurate list of Gender Inclusive Facilities in the campus space data found within the Facilities Management System (FMS). CAS will also maintain the locational listing in the Geographic Information System database, and transmit that information to Strategic Communications, for inclusion on the interactive campus map.

**The Campus Architect** will ensure the conversion of existing, single-occupancy or single-stall restrooms in UCR-owned buildings from gender specific to gender inclusive with privacy and security as noted in the definitions, such that all UCR-owned buildings with existing single stall restrooms will either contain a Gender Inclusive Restroom (GIRR) or be served by an identified GIRR in a “nearby” facility. “Nearby” is commonly defined as being within two minutes of pedestrian travel time between building entrances. Conversions will usually be limited to revised signage. Conversions that are accomplished by signage changes alone shall not be considered renovations. In cases

where conversions do not satisfy the goal of having a GIRR in every UCR-owned building or in a nearby building, construction or renovation of a GIRR must be considered.

- b. *New Construction or Renovation:*** UCR-owned buildings beginning design, for either new construction or renovation, on or after July 1, 2015, shall include at least one GIRR on each floor where restrooms are required or provided in a building. GIRRs on each floor shall be accessible consistent with the California Building Code (CBC). “UCR-owned” includes buildings designed and/or built by third parties that are to become the property of UCR upon completion.
- c. *Restroom Renovations:*** When extensive renovations are made to existing restrooms (i.e. when the construction cost for the renovation exceeds 50% of the restroom replacement cost) or when extensive renovations are made to one or more floors of an existing building (i.e. more than 50% of the replacement cost of the area being renovated) in buildings that do not already have at least one GIRR, the project shall provide a GIRR in the same building.
- d. *Changing Rooms:*** The design of new buildings shall provide for at least one gender-inclusive changing room in each location in the building where locker rooms or changing rooms are provided. The gender-inclusive changing room shall be located within the locker room/changing room facility so the user need not leave the locker room/changing room to use the gender-inclusive changing room. For major renovations, the Campus shall construct at least one gender inclusive private changing room in each location in any building where locker rooms or changing rooms are provided (major renovation is defined as renovation exceeding 50% of the replacement cost of the area being renovated) or when the locker room or changing room is renovated.
- e. *Showers:*** The design of new buildings shall provide for at least one gender-inclusive shower in buildings where showers are provided. If the shower or showers are located within a locker room/changing room facility, the gender inclusive shower(s) shall be located so that the user need not leave the locker room/changing room facility to use the shower. The Campus shall construct at least one gender inclusive shower in each location in any building where showers are provided when a major renovation occurs (major renovation is defined as renovation exceeding 50% of the replacement cost of the area being renovated) or when existing showers are renovated. The shower(s) shall be located within the locker room/changing room facility so that the user need not leave the locker room/changing room facility to use the shower(s).
- f. *Signage:*** Gender inclusive facilities will be identified in a simple manner, utilizing the minimum signage required by the CBC and the 2010 ADA Standards for Accessible Design (ADA). For GIRRs, the required sign on the door shall be a triangle within a circle

of contrasting color, without gender pictograms. The international convention is a white triangle on a blue circle, but ADA-compliant and CBC-compliant signs/colors are acceptable. The CBC-required room identification sign shall provide the minimum required information, including the pictogram for access, if applicable. For GIRRs, the room identification shall be “Restroom”. Signs for changing rooms and shower rooms shall also follow this guidance, as applicable.

- g. Directional signs:** In existing buildings where gender inclusive facilities are not or cannot be provided, the Campus Architect shall direct the installation of at least one directional sign in a conspicuous location, normally near the building’s main entrance and the building restrooms, indicating the location of the nearest gender inclusive facilities.
- h. Hardship:** In instances where hardship may preclude full compliance with this process, campus entities may request that a waiver from the process be approved. Approval authority for these waivers has been delegated in writing from the Chancellor to the Campus Building Official (Campus Architect). The waiver request form is included as Attachment A.
- i. Feedback:** Any concerns, suggestions, or recommendations associated with UCR’s provision of gender inclusive facilities should be submitted to the Campus Architect, via the Office of Architects & Engineers.

## **VI. References**

1. University of California Guidelines for Providing Gender Inclusive Facilities: Effective 7/1/15
2. University of California Facilities Manual RD4.1: Providing Gender Inclusive Facilities
3. UCR Gender Inclusive Facilities Hardship Waiver Request (Attachment A)
4. Model Template for Signs (Attachment B)

## UCR Gender Inclusive Facilities Hardship Waiver Request

### PROCESS

1. Project proponent completes Waiver Request Form. The Project Manager will provide technical support, as needed.
2. Request is submitted to Campus Building Official (Campus Architect) through the Architects & Engineers office.
3. Review of Request and application of criteria to be completed by “Working Group” consisting of:
  - a. Code Enforcement Representative
  - b. Capital Finance Representative
  - c. A&E Project Team member
  - d. CAS Project Team member
4. “Working Group” makes recommendation with justification to Campus Building Official for approval or denial.
5. Campus Building Official renders decision.
6. CBO decision may be appealed to VC-BAS, whose ruling will be final, and without further appeal.

### CRITERIA

- **Building Code Compliance:** Waiver may be considered for instances where, in the judgement of the Campus Building Official (CBO), compliance with GIF provision would unduly compromise provisions of the California Building Code or other applicable provision of law.
  - Access
  - Life/Safety
  - Security
  - Fixture unit requirements(Plumbing Code)
- **Program impacts** – Waiver may be considered upon project proponent’s application where, in the judgement of the CBO, compliance with GIF provision would unduly compromise the core mission of the University by adverse impact on space or functional requirements of the facility.
- **Cost:** Waiver may be considered upon project proponent’s application where, in the judgement of the CBO, compliance with GIF provision would entail consumption of fiscal resources to a degree that would unduly compromise the core mission of the University.
  - Quantitative criteria:
    - For projects with a total budget (GIF compliance not included) of \$100,000 or less, cost impact >10%.
    - For projects with a total budget (GIF compliance not included) of >\$100,000 cost impact >5%.
- **Location:** Waiver may be considered upon application where, in the judgement of the CBO, compliance with GIF provision is unnecessary based on availability of convenient access to existing GIF facility.

**Gender Inclusive Facilities in Renovation Projects  
REQUEST FOR WAIVER BASED ON HARDSHIP**

Submit completed form to UCR Architects and Engineers office

**LEGEND**

Input cell
Calculation

Campus

Project

Date

**PROJECT COST**

Construction cost of overall project  
 Construction cost of inclusive restroom work (new or remodeled single-occupancy restroom or remodeled multi-occupancy restroom)  
 Percentage of restroom cost/overall project construction cost

\$

\$

**OCCUPANT LOAD & FIXTURE COUNTS**

Occupant load of building

Occupants

MEN		WOMEN	
TOILETS & URINALS	LAVATORIES	TOILETS	LAVATORIES
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

<sup>1,2,4</sup> **Required** number of gender specific toilet/urinal fixtures  
**Existing** number of gender specific toilet/urinal fixtures  
 Number of gender specific fixtures inc. new inclusive restroom(s)  
 Deficit (if any) with new inclusive restrooms and fixtures

**PROXIMITY**

Are there other inclusive restrooms in this building?  
 If YES, indicate distance to nearest inclusive restroom in building

<sup>3</sup> If NO, indicate location of nearest inclusive restroom

YES or NO			
<input type="text"/>	Travel distance in feet	<input type="text"/>	Travel distance--number of floors
<input type="text"/>	Travel distance in feet between building entries	<input type="text"/>	Pedestrian travel time between building entries

**HARDSHIP**

If space will be reassigned from programmatic or other dedicated use to construct the inclusive restroom(s), describe secondary effects of constructing restroom in this location

(Describe)

**INTENT**

If inclusive restroom cannot be provided in this location, describe the proposed alternate solution and how it meets the spirit and intent of the inclusive restrooms guidelines?

(Describe)

**NOTES**

<sup>1</sup> "Separate" refers to California Code of Regulations, Title 24, Part 6--California Plumbing Code, Section 422.2, Separate Facilities: "Separate toilet facilities shall be provided for each sex." See also Table 422.1 of the plumbing code for fixture count requirements.  
<sup>2</sup> Include additional code-triggered required separate fixtures that must be added by the work of the new project, if any.  
<sup>3</sup> Pedestrian travel time is encouraged to be less than 2 minutes between building entrances to avoid extending break times and provide equivalent facilities  
<sup>4</sup> Modify form as needed if assessing changing rooms or showers

# Signage Guidelines - Gender Inclusive Facilities

Updated 6/23/2020



Directional Signage – to be used if no gender inclusive facilities are available in a building.



Restroom Door Sign – Details on Page 2



Restroom Room Sign – Details on Page 3

All signs shall meet ADA and CBC Standards.

# CBC/ADA Door Signage

## SIGN SPECIFICATIONS

### 1. SIGN PANEL SUBSTRATE

Finish Size: 9"H x 10 1/2"W  
 Material: 1/4" Plaskolite Non-Glare Clear Acrylic (P99)  
 Backpaint: Matthews Paint to Match 311-307 Charcoal Grey (Satin Finish)  
 Edge Finish: Milled & Unpainted

### 2. SIGN PANEL SUBSTRATE

Finish Size: 12"H x 12"W  
 Material: 1/4" Plaskolite Non-Glare Clear Acrylic (P99)  
 Backpaint: Matthews MAP-LVS202 White (Satin Finish)  
 Edge Finish: Milled & Unpainted

### 3. SYMBOL

Material: Second-Surface Vinyl To Match 311-307 Charcoal Grey (Opaque)  
 Height: 5 1/2" Tall

### 4. SYMBOL

Material: Second-Surface 3M #7725-10 Opaque White Vinyl  
 Height: 5 1/2" Tall

### 5. ADHESIVE / TAPE FOR COMPONENTS


Tape: Thin DT Tape

### 6. MOUNTING

Tape: 1/16" Thick Double Sided Foam Tape & Silicone Adhesive

### INSTALLATION PLACEMENT

Height: 60" Bottom of Highest Tactile Letters / 48" AFF Min. to Bottom of Braille  
 Placement: 9" OC of Tactile Characters From Opening of Door  
 Location: Adjacent to Latch Side of Door. Refer to CSB Installation Standards



SIGN TYPE - GENDER INCLUSIVE  
RESTROOM

**B** SIDE VIEW  
SCALE: 3" = 1'-0"

**COLOR LEGEND**

	<b>WHITE</b> - MATTHEWS PAINT MAP-LVS202 (SATIN FINISH) / 3M #7725-10 OPAQUE WHITE VINYL
	<b>CHARCOAL GREY</b> - 311-307 CHARCOAL GREY - VINYL / MATTHEWS PAINT TO MATCH (SATIN FINISH)

# Restroom Signage (Wall Mt.)

## SIGN SPECIFICATIONS

### 1. SIGN PANEL SUBSTRATE

Finish Size: 6 1/4"H x 10"W  
 Material: 1/4" Plaskolite Non-Glare Clear Acrylic (P99)  
 Backpaint: Matthews MAP-LVS202 White (Satin Finish)  
 Edge Finish: Milled & Unpainted

### 2. TACTILE APPLIQUE

Material: Modified Acrylic  
 Font Height: 5/8" Tall  
 Symbol Heights: 4 1/2" / 2 7/8"  
 Depth: 1/32" Thick  
 Font: DIN Medium  
 Color: 311-307 Charcoal Grey

### 3. BRAILLE

Type: Clear Grade II Braille

### 4. DECORATIVE METAL BAR

Material: 6063 Aluminum Square 1/4" x 10"  
 Finish: #4 Brushed Finish (Horizontal Grain)  
 Fastener: Thin DT Tape

### 5. ADHESIVE / TAPE FOR COMPONENTS

Tape: Thin DT Tape

### 6. MOUNTING

Tape: 1/16" Thick Double Sided Foam Tape & Silicone Adhesive

### INSTALLATION PLACEMENT

Height: 60" Bottom of Highest Tactile Letters / 48" AFF Min. to Bottom of Braille  
 Placement: 9" OC of Tactile Characters From Opening of Door  
 Location: Adjacent to Latch Side of Door. Refer to CSB Installation Standards



QTY. : 2

TOTAL QTY. : 8

**A** ELEVATION  
SCALE: HALF-SIZE

SIGN TYPE - GENDER INCLUSIVE  
RESTROOM




**B** SIDE VIEW  
SCALE: HALF-SIZE


### COLOR LEGEND

White	WHITE - MATTHEWS PAINT MAP-LVS202 (SATIN FINISH)
Charcoal Grey	CHARCOAL GREY - TACTILE: 311-307 CHARCOAL GREY / MATTHEWS PAINT TO MATCH (SATIN FINISH)
#4 Brushed Finish	#4 BRUSHED FINISH (HORIZONTAL GRAIN)





**A FRONT ELEVATION**  
SCALE 1:3



**B SIDE SECTION**  
SCALE 1:5


**SIGN SPECIFICATIONS**

- 1. SIGN PANEL SUBSTRATE**  
Finish Sizes:  
- 12" H x 18" W  
Material: Cast Bronze (horizontal grain)  
Return: 5/16"
- 2. TEXT**  
Finish: Natural Satin (horizontal grain)  
Clear Coat: Semi-Gloss  
Recessed Texture: Sand  
Recessed Paint Fill: 0312 Medium Bronze  
Fonts: DIN Medium  
Brushed Bronze = Raised  
Text = Recessed
- 3. MOUNTING**  
Studs: 10/24 Blind Stud - 2" length  
Standoffs: 1/2"  
Border: 1/8" Outline  
Edges: Square  
Mounting Pattern: Yes
- 4. MOUNTING SURFACE**  
Brick

**Cast Bronze with Recessed Text.  
Paint filled medium bronze text.**



**Material**  
Grain Runs Horizontal  
On Finish Product




**Paint Fill**


**C FINISH**  
SCALE: NTS

FILE PATH Q:\UCR MRB1\20180426 UCR Contract\Renderings, Submittals & PDFs\Submittals\UCR MRB1\_SignSubmittal

CONTACT	DRAWN BY	CLIENT / PROJECT	DATE	SHEET TITLE	SHEET
Albuquerque / Phoenix P 505.888.2901 ext 109 F 505.888.2902 csbsigns.com	Lawrence Spingola Lawrence Spingola@csbsigns.com <small>This artwork and design is owned by Century Sign Builders unless expressly stated. Use of this document or the design shown here without permission is prohibited.</small>	Client / GC: Hensel Phelps Project: University of California, Riverside - MRB1 <b>APPROVAL REQUIRED FOR PRODUCTION</b>	Modification Date: November 29, 2018 9:10 AM  SIGNATURE / DATE	Sign Type PLQ Building Dedication Plaque	<b>27</b>







A ◀



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - ★ Information Kiosk
  - ▲ Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

▶ C  
E ▼

B ◀




Universi

- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - ★ Information Kiosk
  - ▲ Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

F ▼

▲ A



H ▼ E

- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - Information Kiosk
  - Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

▲ B  
D ◀




- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - ★ Information Kiosk
  - ▲ Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs
















**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

▶ F  
I ▼

E



**Legend**


-  Off campus vehicular circulation
-  On campus primary veh. circulation
-  On campus secondary veh. circulation
-  Primary Pedestrian Circulation
-  Secondary Pedestrian Circulation
-  Parking Lot Permit Zones
-  Information Kiosk
-  Existing Postings
-  **Electronic Message Boards**
- W10 Site ID, Freeway
- W11 Campus ID
-  **Campus Entry Monument**
- W15 Primary ID
- W16 Secondary ID
-  **Pedestrian Information**
- W36 Accessible Pathway
-  **Pedestrian Information**
- W40 Freestanding Directory, primary
- W41 Wall Mounted Directory
- W42 Freestanding Directory, secondary
- W46 Info Kiosk, Posted Messages
- W48 Interactive Kiosk
-  **Building Identity**
- W50 Primary, vehicular
- W51 Freestanding, Ped
-  **Parking Lot Id/Info**
- W70 Primary ID
- W71 Secondary ID
- W72 Pole Mounted ID
-  W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

J



F ◀



**Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Primary Pedestrian Circulation
- Secondary Pedestrian Circulation
- Parking Lot Permit Zones
- Information Kiosk
- Existing Postings
- Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
- Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
- Pedestrian Information**  
W36 Accessible Pathway
- Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
- Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
- Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
- W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

K ▼

▲ D



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - Information Kiosk
  - Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

▶ I  
L ▼


H ▲ E  
H ◀



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - ★ Information Kiosk
  - ▲ Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs


**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

▶ J  
M ▼



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - Information Kiosk
  - Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs


**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - ★ Information Kiosk
  - ▲ Existing Postings
  - Electronic Message Boards**  
 W10 Site ID, Freeway  
 W11 Campus ID
  - Campus Entry Monument**  
 W15 Primary ID  
 W16 Secondary ID
  - Pedestrian Information**  
 W36 Accessible Pathway
  - Pedestrian Information**  
 W40 Freestanding Directory, primary  
 W41 Wall Mounted Directory  
 W42 Freestanding Directory, secondary  
 W46 Info Kiosk, Posted Messages  
 W48 Interactive Kiosk
  - Building Identity**  
 W50 Primary, vehicular  
 W51 Freestanding, Ped
  - Parking Lot Id/Info**  
 W70 Primary ID  
 W71 Secondary ID  
 W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

▲ H



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - Information Kiosk
  - Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

▶ M  
P ▼



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - Information Kiosk
  - Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

J  
M



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - Information Kiosk
  - Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

S 0



▲ K




T ▼

**Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Primary Pedestrian Circulation
- Secondary Pedestrian Circulation
- Parking Lot Permit Zones
- Information Kiosk
- Existing Postings
- Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
- Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
- Pedestrian Information**  
W36 Accessible Pathway
- Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
- Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
- Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
- W97 Street Signs


**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - Information Kiosk
  - Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.


Q ▲ M



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - Information Kiosk
  - Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

▶ S



- Legend**
- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - Parking Lot Permit Zones
  - ★ Information Kiosk
  - ▲ Existing Postings
  - Electronic Message Boards**  
W10 Site ID, Freeway  
W11 Campus ID
  - Campus Entry Monument**  
W15 Primary ID  
W16 Secondary ID
  - Pedestrian Information**  
W36 Accessible Pathway
  - Pedestrian Information**  
W40 Freestanding Directory, primary  
W41 Wall Mounted Directory  
W42 Freestanding Directory, secondary  
W46 Info Kiosk, Posted Messages  
W48 Interactive Kiosk
  - Building Identity**  
W50 Primary, vehicular  
W51 Freestanding, Ped
  - Parking Lot Id/Info**  
W70 Primary ID  
W71 Secondary ID  
W72 Pole Mounted ID
  - W97 Street Signs


**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Location Plans and Messages**


In order to provide clarity to the vehicular sign type locations, the following plans only show Vehicular Directional sign types.

Included are the following sign types:

W20  
W21  
W22



A ◀



**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- ★ Information Kiosk
- Vehicular Directional
  - W20 Primary
  - W21 Secondary
  - W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

**Direct from Perimeter of Campus**

- Info Kiosk
- Botanical Gardens
- University Theater

**Direct from 2-3 decision points away**

- Child Dev. Center
- Corporation Yard
- East Campus
- Lothian Hall
- Parking Lot 10
- Parking Lot 13
- Parking Lot 24
- Parking Lot 30
- Parking Services
- Res. Halls
- Sports Complex
- Student Rec Center
- Health Services
- West Campus

**Direct from 1 decision point away**

- Ag. Operations
- Bannockburn
- Biomedical Teaching C omplex
- Riviera Library Parking
- USDA Lab

▶ C  
E ▼

B ◀

**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- ★ Information Kiosk

- Vehicular Directional**
- W20 Primary
- W21 Secondary
- W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

**Direct from Perimeter of Campus**  
Info Kiosk  
Botanical Gardens  
University Theater

**Direct from 2-3 decision points away**  
Child Dev. Center  
Corporation Yard  
East Campus  
Lothian Hall  
Parking Lot 10  
Parking Lot 13  
Parking Lot 24  
Parking Lot 30  
Parking Services  
Res. Halls  
Sports Complex  
Student Rec Center  
Health Services  
West Campus

**Direct from 1 decision point away**  
Ag. Operations  
Bannockburn  
Biomedical Teaching C omplex  
Riviera Library Parking  
USDA Lab



Universi

F ▼

▲ B  
D ◀



**Vehicular Legend**

- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Parking Lot Permit Zones
  - ★ Information Kiosk
- Vehicular Directional**
- W20 Primary
  - W21 Secondary
  - W22 Pole Mounted


**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

- Direct from Perimeter of Campus**
- Info Kiosk
  - Botanical Gardens
  - University Theater
- Direct from 2-3 decision points away**
- Child Dev. Center
  - Corporation Yard
  - East Campus
  - Lothian Hall
  - Parking Lot 10
  - Parking Lot 13
  - Parking Lot 24
  - Parking Lot 30
  - Parking Services
  - Res. Halls
  - Sports Complex
  - Student Rec Center
  - Health Services
  - West Campus
- Direct from 1 decision point away**
- Ag. Operations
  - Bannockburn
  - Biomedical Teaching C omplex
  - Riviera Library Parking
  - USDA Lab

▶ F  
I ▼





**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- Information Kiosk
- Vehicular Directional**
- W20 Primary
- W21 Secondary
- W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

**Direct from Perimeter of Campus**

- Info Kiosk
- Botanical Gardens
- University Theater


**Direct from 2-3 decision points away**

- Child Dev. Center
- Corporation Yard
- East Campus
- Lothian Hall
- Parking Lot 10
- Parking Lot 13
- Parking Lot 24
- Parking Lot 30
- Parking Services
- Res. Halls
- Sports Complex
- Student Rec Center
- Health Services
- West Campus

**Direct from 1 decision point away**

- Ag. Operations
- Bannockburn
- Biomedical Teaching C omplex
- Riviera Library Parking
- USDA Lab

F ◀



**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- ★ Information Kiosk

- Vehicular Directional
- W20 Primary
- W21 Secondary
- W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**


- Direct from Perimeter of Campus**
- Info Kiosk
  - Botanical Gardens
  - University Theater

- Direct from 2-3 decision points away**
- Child Dev. Center
  - Corporation Yard
  - East Campus
  - Lothian Hall
  - Parking Lot 10
  - Parking Lot 13
  - Parking Lot 24
  - Parking Lot 30
  - Parking Services
  - Res. Halls
  - Sports Complex
  - Student Rec Center
  - Health Services
  - West Campus

- Direct from 1 decision point away**
- Ag. Operations
  - Bannockburn
  - Biomedical Teaching C omplex
  - Riviera Library Parking
  - USDA Lab

K ▼

▲ D



**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- ★ Information Kiosk
- Vehicular Directional**
- W20 Primary
- W21 Secondary
- W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

**Direct from Perimeter of Campus**

- Info Kiosk
- Botanical Gardens
- University Theater

**Direct from 2-3 decision points away**


- Child Dev. Center
- Corporation Yard
- East Campus
- Lothian Hall
- Parking Lot 10
- Parking Lot 13
- Parking Lot 24
- Parking Lot 30
- Parking Services
- Res. Halls
- Sports Complex
- Student Rec Center
- Health Services
- West Campus

**Direct from 1 decision point away**

- Ag. Operations
- Bannockburn
- Biomedical Teaching C omplex
- Riviera Library Parking
- USDA Lab

▶ I  
L ▼

H ▲ E



**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- Information Kiosk
- Vehicular Directional**
- W20 Primary
- W21 Secondary
- W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

**Direct from Perimeter of Campus**

- Info Kiosk
- Botanical Gardens
- University Theater


**Direct from 2-3 decision points away**

- Child Dev. Center
- Corporation Yard
- East Campus
- Lothian Hall
- Parking Lot 10
- Parking Lot 13
- Parking Lot 24
- Parking Lot 30
- Parking Services
- Res. Halls
- Sports Complex
- Student Rec Center
- Health Services
- West Campus

**Direct from 1 decision point away**

- Ag. Operations
- Bannockburn
- Biomedical Teaching C omplex
- Riviera Library Parking
- USDA Lab

▲ J  
M ▼



**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- Information Kiosk
- Vehicular Directional**
- W20 Primary
- W21 Secondary
- W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

**Direct from Perimeter of Campus**

- Info Kiosk
- Botanical Gardens
- University Theater

**Direct from 2-3 decision points away**

- Child Dev. Center
- Corporation Yard
- East Campus
- Lothian Hall
- Parking Lot 10
- Parking Lot 13
- Parking Lot 24
- Parking Lot 30
- Parking Services
- Res. Halls
- Sports Complex
- Student Rec Center
- Health Services
- West Campus

**Direct from 1 decision point away**

- Ag. Operations
- Bannockburn
- Biomedical Teaching C omplex
- Riviera Library Parking
- USDA Lab



**Vehicular Legend**

- Off campus vehicular circulation
  - On campus primary veh. circulation
  - On campus secondary veh. circulation
  - Parking Lot Permit Zones
  - Information Kiosk
- 
- Vehicular Directional**
  - W20 Primary
  - W21 Secondary
  - W22 Pole Mounted


**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

- Direct from Perimeter of Campus**
- Info Kiosk
  - Botanical Gardens
  - University Theater

- Direct from 2-3 decision points away**
- Child Dev. Center
  - Corporation Yard
  - East Campus
  - Lothian Hall
  - Parking Lot 10
  - Parking Lot 13
  - Parking Lot 24
  - Parking Lot 30
  - Parking Services
  - Res. Halls
  - Sports Complex
  - Student Rec Center
  - Health Services
  - West Campus

- Direct from 1 decision point away**
- Ag. Operations
  - Bannockburn
  - Biomedical Teaching C omplex
  - Riviera Library Parking
  - USDA Lab



**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- ★ Information Kiosk
- Vehicular Directional
  - W20 Primary
  - W21 Secondary
  - W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**


**Direct from Perimeter of Campus**  
Info Kiosk  
Botanical Gardens  
University Theater

**Direct from 2-3 decision points away**  
Child Dev. Center  
Corporation Yard  
East Campus  
Lothian Hall  
Parking Lot 10  
Parking Lot 13  
Parking Lot 24  
Parking Lot 30  
Parking Services  
Res. Halls  
Sports Complex  
Student Rec Center  
Health Services  
West Campus

**Direct from 1 decision point away**  
Ag. Operations  
Bannockburn  
Biomedical Teaching C omplex  
Riviera Library Parking  
USDA Lab



J  
M



S  
O

**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- Information Kiosk
- Vehicular Directional**  
 W20 Primary  
 W21 Secondary  
 W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

- Direct from Perimeter of Campus**
  - Info Kiosk
  - Botanical Gardens
  - University Theater
- Direct from 2-3 decision points away**
  - Child Dev. Center
  - Corporation Yard
  - East Campus
  - Lothian Hall
  - Parking Lot 10
  - Parking Lot 13
  - Parking Lot 24
  - Parking Lot 30
  - Parking Services
  - Res. Halls
  - Sports Complex
  - Student Rec Center
  - Health Services
  - West Campus
- Direct from 1 decision point away**
  - Ag. Operations
  - Bannockburn
  - Biomedical Teaching C omplex
  - Riviera Library Parking
  - USDA Lab



P ▲ L



**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- ★ Information Kiosk

**Vehicular Directional**

- W20 Primary
- W21 Secondary
- W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.


**Vehicular Destinations**

**Direct from Perimeter of Campus**  
Info Kiosk  
Botanical Gardens  
University Theater

**Direct from 2-3 decision points away**  
Child Dev. Center  
Corporation Yard  
East Campus  
Lothian Hall  
Parking Lot 10  
Parking Lot 13  
Parking Lot 24  
Parking Lot 30  
Parking Services  
Res. Halls  
Sports Complex  
Student Rec Center  
Health Services  
West Campus

**Direct from 1 decision point away**  
Ag. Operations  
Bannockburn  
Biomedical Teaching C omplex  
Riviera Library Parking  
USDA Lab

▶ R



**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- Information Kiosk
- Vehicular Directional**
- W20 Primary
- W21 Secondary
- W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

**Direct from Perimeter of Campus**


- Info Kiosk
- Botanical Gardens
- University Theater

**Direct from 2-3 decision points away**

- Child Dev. Center
- Corporation Yard
- East Campus
- Lothian Hall
- Parking Lot 10
- Parking Lot 13
- Parking Lot 24
- Parking Lot 30
- Parking Services
- Res. Halls
- Sports Complex
- Student Rec Center
- Health Services
- West Campus

**Direct from 1 decision point away**

- Ag. Operations
- Bannockburn
- Biomedical Teaching Complex
- Riviera Library Parking
- USDA Lab



**Vehicular Legend**

- Off campus vehicular circulation
- On campus primary veh. circulation
- On campus secondary veh. circulation
- Parking Lot Permit Zones
- Information Kiosk

- Vehicular Directional**
- W20 Primary
- W21 Secondary
- W22 Pole Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Vehicular Destinations**

**Direct from Perimeter of Campus**  
Info Kiosk  
Botanical Gardens  
University Theater

**Direct from 2-3 decision points away**  
Child Dev. Center  
Corporation Yard  
East Campus  
Lothian Hall  
Parking Lot 10  
Parking Lot 13  
Parking Lot 24  
Parking Lot 30  
Parking Services  
Res. Halls  
Sports Complex  
Student Rec Center  
Health Services  
West Campus

**Direct from 1 decision point away**  
Ag. Operations  
Bannockburn  
Biomedical Teaching Complex  
Riviera Library Parking  
USDA Lab

**Location Plans and Messages**

In order to provide clarity to the pedestrian sign type locations, the following plans only show Pedestrian Directional sign types.


Included are the following sign types:

W30

W35



▲ B  
D ◀



**Pedestrian Legend**

- Primary Pedestrian Circulation
- Secondary Pedestrian Circulation
- ★ Existing Directory (new directories to replace existing)
- ▲ Existing Postings
- ■ ■ ■ ■ Parking Lot Permit Zones

**Pedestrian Directional**

- W30 Blade Sign
- W35 Wall Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Pedestrian Destinations**

**Direct from Perimeter of Campus**

- Commons
- Hinderacker Hall
- Humanities 1500
- Life Sciences 1500
- Physics 2000
- Univ. Lecture Hall
- Watkins 1000

**Direct from Parking Lots**

- Alumni Visitor Center
- Barn Group (Lots 1, 2, 24)
- P.E. Building (Lots 1, 24)
- Studio Theater (Lots 1, 2, 24)
- University Theater (Lot 30)

**Direct from 2 - 3 decisions points away**

- Bookstore
- College Bldg North and South
- Env. Health & Safety
- Extension/East Campus
- Lot 1, 2
- Lot 10, 13
- Lot 24
- Lot 30
- Police Dept.
- Student Recreation Center
- P.E. Building
- Health Services
- West Campus

- ↑ Police Dept
- ↑ Lot 24
- ↓ Commons
- ↓ Studio Theater
- ↓ Barn Group
- ↓ Phys. Ed. Building
- ↓ Student Rec Center

- ↓ Univ. Lecture Hall
- ↓ Commons
- Student Rec Center
- ← Police Dept

▶ F  
I ▼

E C



**Pedestrian Legend**

- Primary Pedestrian Circulation
- Secondary Pedestrian Circulation
- ★ Existing Directory (new directories to replace existing)
- ▲ Existing Postings
- ■ ■ ■ ■ Parking Lot Permit Zones

- Pedestrian Directional**
- W30 Blade Sign
- W35 Wall Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Pedestrian Destinations**

**Direct from Perimeter of Campus**

- Commons
- Hinderacker Hall
- Humanities 1500
- Life Sciences 1500
- Physics 2000
- Univ. Lecture Hall
- Watkins 1000

**Direct from Parking Lots**

- Alumni Visitor Center
- Barn Group (Lots 1, 2, 24)
- P.E. Building (Lots 1, 24)
- Studio Theater (Lots 1, 2, 24)
- University Theater (Lot 30)

**Direct from 2 - 3 decisions points away**

- Bookstore
- College Bldg North and South
- Env. Health & Safety
- Extension/East Campus
- Lot 1, 2
- Lot 10, 13
- Lot 24
- Lot 30
- Police Dept.
- Student Recreation Center
- P.E. Building
- Health Services
- West Campus

J G

▲ D



**Pedestrian Legend**

- Primary Pedestrian Circulation
- Secondary Pedestrian Circulation
- ★ Existing Directory (new directories to replace existing)
- ▲ Existing Postings
- ■ ■ ■ ■ Parking Lot Permit Zones

- Pedestrian Directional**
- W30 Blade Sign
- W35 Wall Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Pedestrian Destinations**

**Direct from Perimeter of Campus**

- Commons
- Hinderaker Hall
- Humanities 1500
- Life Sciences 1500
- Physics 2000
- Univ. Lecture Hall
- Watkins 1000

**Direct from Parking Lots**

- Alumni Visitor Center
- Barn Group (Lots 1, 2, 24)
- P.E. Building (Lots 1, 24)
- Studio Theater (Lots 1, 2, 24)
- University Theater (Lot 30)

**Direct from 2 - 3 decisions points away**

- Bookstore
- College Bldg North and South
- Env. Health & Safety
- Extension/East Campus
- Lot 1, 2
- Lot 10, 13
- Lot 24
- Lot 30
- Police Dept.
- Student Recreation Center
- P.E. Building
- Health Services
- West Campus

▶ I  
L ▼

H ▲ E



**Pedestrian Legend**

- Primary Pedestrian Circulation
- Secondary Pedestrian Circulation
- ★ Existing Directory (new directories to replace existing)
- ▲ Existing Postings
- ■ ■ ■ ■ Parking Lot Permit Zones

**Pedestrian Directional**

- W30 Blade Sign
- W35 Wall Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Pedestrian Destinations**

**Direct from Perimeter of Campus**

- Commons
- Hinderaker Hall
- Humanities 1500
- Life Sciences 1500
- Physics 2000
- Univ. Lecture Hall
- Watkins 1000

**Direct from Parking Lots**


- Alumni Visitor Center
- Barn Group (Lots 1, 2, 24)
- P.E. Building (Lots 1, 24)
- Studio Theater (Lots 1, 2, 24)
- University Theater (Lot 30)

**Direct from 2 - 3 decisions points away**

- Bookstore
- College Bldg North and South
- Env. Health & Safety
- Extension/East Campus
- Lot 1, 2
- Lot 10, 13
- Lot 24
- Lot 30
- Police Dept.
- Student Recreation Center
- P.E. Building
- Health Services
- West Campus

▲ J  
M ▼





- Pedestrian Legend**
- Primary Pedestrian Circulation
  - Secondary Pedestrian Circulation
  - ★ Existing Directory (new directories to replace existing)
  - ▲ Existing Postings
  - ■ ■ ■ ■ Parking Lot Permit Zones

- Pedestrian Directional**
- W30 Blade Sign
  - W35 Wall Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Pedestrian Destinations**

**Direct from Perimeter of Campus**


- Commons
- Hinderaker Hall
- Humanities 1500
- Life Sciences 1500
- Physics 2000
- Univ. Lecture Hall
- Watkins 1000

**Direct from Parking Lots**

- Alumni Visitor Center
- Barn Group (Lots 1, 2, 24)
- P.E. Building (Lots 1, 24)
- Studio Theater (Lots 1, 2, 24)
- University Theater (Lot 30)

**Direct from 2 - 3 decisions points away**

- Bookstore
- College Bldg North and South
- Env. Health & Safety
- Extension/East Campus
- Lot 1, 2
- Lot 10, 13
- Lot 24
- Lot 30
- Police Dept.
- Student Recreation Center
- P.E. Building
- Health Services
- West Campus



**Pedestrian Legend**

- Primary Pedestrian Circulation
- Secondary Pedestrian Circulation
- Existing Directory (new directories to replace existing)
- Existing Postings
- Parking Lot Permit Zones
- Pedestrian Directional
  - W30 Blade Sign
  - W35 Wall Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Pedestrian Destinations**

**Direct from Perimeter of Campus**

- Commons
- Hinderaker Hall
- Humanities 1500
- Life Sciences 1500
- Physics 2000
- Univ. Lecture Hall
- Watkins 1000


**Direct from Parking Lots**

- Alumni Visitor Center
- Barn Group (Lots 1, 2, 24)
- P.E. Building (Lots 1, 24)
- Studio Theater (Lots 1, 2, 24)
- University Theater (Lot 30)

**Direct from 2 - 3 decisions points away**

- Bookstore
- College Bldg North and South
- Env. Health & Safety
- Extension/East Campus
- Lot 1, 2
- Lot 10, 13
- Lot 24
- Lot 30
- Police Dept.
- Student Recreation Center
- P.E. Building
- Health Services
- West Campus

J  
M



**Pedestrian Legend**

- Primary Pedestrian Circulation
- Secondary Pedestrian Circulation
- Existing Directory (new directories to replace existing)
- Existing Postings
- Parking Lot Permit Zones

**Pedestrian Directional**

- W30 Blade Sign
- W35 Wall Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Pedestrian Destinations**

**Direct from Perimeter of Campus**

- Commons
- Hinderaker Hall
- Humanities 1500
- Life Sciences 1500
- Physics 2000
- Univ. Lecture Hall
- Watkins 1000

**Direct from Parking Lots**

- Alumni Visitor Center
- Barn Group (Lots 1, 2, 24)
- P.E. Building (Lots 1, 24)
- Studio Theater (Lots 1, 2, 24)
- University Theater (Lot 30)

**Direct from 2 - 3 decisions points away**

- Bookstore
- College Bldg North and South
- Env. Health & Safety
- Extension/East Campus
- Lot 1, 2
- Lot 10, 13
- Lot 24
- Lot 30
- Police Dept.
- Student Recreation Center
- P.E. Building
- Health Services
- West Campus

S O



**Pedestrian Legend**

- Primary Pedestrian Circulation
- Secondary Pedestrian Circulation
- ★ Existing Directory (new directories to replace existing)
- ▲ Existing Postings
- ■ ■ ■ Parking Lot Permit Zones

- Pedestrian Directional**
- W30 Blade Sign
- W35 Wall Mounted

**Note:**  
Lozenge orientation does not necessarily represent accurate sign placement.

**Pedestrian Destinations**

- Direct from Perimeter of Campus**
- Commons
  - Hinderacker Hall
  - Humanities 1500
  - Life Sciences 1500
  - Physics 2000
  - Univ. Lecture Hall
  - Watkins 1000

- Direct from Parking Lots**
- Alumni Visitor Center
  - Barn Group (Lots 1, 2, 24)
  - P.E. Building (Lots 1, 24)
  - Studio Theater (Lots 1, 2, 24)
  - University Theater (Lot 30)

- Direct from 2 - 3 decisions points away**
- Bookstore
  - College Bldg North and South
  - Env. Health & Safety
  - Extension/East Campus
  - Lot 1, 2
  - Lot 10, 13
  - Lot 24
  - Lot 30
  - Police Dept.
  - Student Recreation Center
  - P.E. Building
  - Health Services
  - West Campus


Aberdeen Inverness (343)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign




Replace with W50 Vehicular Bldg ID



SEE PLAN J

Agricultural Operations		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Replace with W50 Vehicular Bldg ID



Keep existing sign

Anderson Hall I & II (325 & 357)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	0
W53	Vinyl Letters on Door	4
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign




Add W51 Freestanding Bldg ID



Add W53 Vinyl Letters on Door



Keep existing sign



Add W53 Vinyl Letters on Door




Add W53 Vinyl Letters on Door



Add W53 Vinyl Letters on Door

Arts (411)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	2
B95	Loading Dock ID	1





The Barn, Theater Workshop & Barn Stable (358, 251, & 271)

	qty
W50 Vehicular Bldg ID	1
W51 Freestanding, Ped	1
W52 Wall Mounted	6
W53 Vinyl Letters on Door	0
W54 Parapet Letters	0
B95 Loading Dock ID	0



Add W52 Wall Mounted Bldg ID




Replace with W52 Wall Mounted Bldg ID



Add W51 Freestanding Bldg ID



Add W52 Wall Mounted Bldg ID



Add W52 Wall Mounted Bldg ID



Replace with W50 Vehicular Bldg ID





Add W52 Wall Mounted Bldg ID




Replace with W52 Wall Mounted Bldg ID


Bannockburn Village Buildings A-V (590-611)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Remove Sign  
 Note: A Parking Sign (W70) with bldg name has been included in the sign location plan



Replace with  
 W51 Bldg ID



Remove Sign  
 Note: A Parking Sign (W70) with bldg name has been included in the sign location plan

Batchelor Hall (501)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	2
W52	Wall Mounted	2
W53	Vinyl Letters on Door	5
W54	Parapet Letters	0
B95	Loading Dock ID	1



Replace existing sign with  
W52 Wall Mounted  
Add  
W53 Vinyl Letters on Door



Keep existing sign


Add  
W51 Freestanding Building ID



Add  
W52 Wall Mounted Bldg ID  
W53 Vinyl Letters on Door



Add  
W50 Vehicular Building ID



Keep existing sign



Add  
W53 Vinyl Letters on Door




Keep existing sign  
Add  
W53 Vinyl Letters on Door



Keep existing sign  
Add B95 Loading Dock



Add  
W53 Vinyl Letters on Door



Add  
W51 Freestanding Building ID

Biological Sciences (186)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	1
W53	Vinyl Letters on Door	3
W54	Parapet Letters	0
B95	Loading Dock ID	0



Add W53 Vinyl Letters on Door




Add W53 Vinyl Letters on Door




Add W52 Wall Mounted Building ID



Add W53 Vinyl Letters on Door



Keep existing sign



Keep existing sign

Add W50 Vehicular Bldg ID


Biomed Teaching Center (385)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	3
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
W55	Building ID, small	1
B95	Loading Dock ID	0



Replace with W52 Wall Mounted Bldg ID



Replace with W52 Wall Mounted Bldg ID



Add W55 Building ID, small




Add W52 Wall Mounted Bldg ID



Replace with W50 Vehicular Bldg ID

Bookstore (224)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	2
W53	Vinyl Letters on Door	1
W54	Parapet Letters	2
B95	Loading Dock ID	1




Keep Existing Sign

Add  
W54 Parapet Letters



Add  
W54 Parapet Letters



Add  
W52 Wall Mounted Bldg ID



Add  
W53 Vinyl Letters on Doors




Add  
B95 Loading Dock ID



Add  
W52 Wall Mtd Bldg ID

Botanical Gardens (254)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0
*Entry Sign—exception to Master Plan		1



Bourns Hall (261)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	1
W52	Wall Mounted	5
W53	Vinyl Letters on Door	4
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign



Keep existing sign



Keep existing sign





Add W52 Wall Mounted Bldg ID



Keep existing sign  
Add W53 Vinyl Letters on Door



Add W52 Wall Mounted Bldg ID



Add W52 Wall Mounted Bldg ID




Add W53 Vinyl Letters on Door




Add W52 Wall Mounted Bldg ID




Add W51 Freestanding, Ped Bldg ID



Add W53 Vinyl Letters on Door



Add W52 Wall Mounted Bldg ID



Keep existing sign




Add W53 Vinyl Letters on Door



Boyce Hall (341)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	4
W53	Vinyl Letters on Door	4
W54	Parapet Letters	0
B95	Loading Dock ID	1



Keep existing sign




Replace with W53 Vinyl Letters on Door



Add W52 Wall Mounted Bldg ID

Replace with W53 Vinyl Letters on Door


Add W51 Ped. Bldg ID




Replace with W53 Vinyl Letters on Door



Add W52 Wall Mounted Bldg ID



Replace with B95 Loading Dock ID



Add W52 Wall Mounted Bldg ID



Keep existing sign




Add W52 Wall Mounted Bldg ID




Replace with W53 Vinyl Letters on Door


Boyden Laboratory (482)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	2
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Remove existing sign




Keep existing sign




Add  
W51 Freestanding Bldg ID




Add  
W52 Wall Mounted Bldg ID




California Museum of Photography (720)		qty
W50	Vehicle Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0




Keep existing Vinyl Letters on Door and Banners



Campus Surge (380)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	4
W53	Vinyl Letters on Door	2
W54	Parapet Letters	1
B95	Loading Dock ID	0



Canyon Crest Family Student Housing (000-183)		qty
W50	Vehicular Bldg ID	4
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Add  
W50 Vehicular Building ID



Replace with  
W50 Vehicular Building ID



Add  
W50 Vehicular Building ID



Replace with  
W50 Vehicular Building ID

Central Utility Plant (295)		qty
W50	Vehicular Bldg ID	2
W51	Freestanding, Ped	0
W52	Wall Mounted	2
W53	Vinyl Letters on Door	0
W54	Parapet Letters	1
B95	Loading Dock ID	0



Replace with W52 WallMounted Bldg ID




Replace with W50 Vehicular Bldg ID



Replace with W52 WallMounted Bldg ID



Replace with W54 Parapet Letters




Add W50 Vehicular Bldg ID

Chapman Hall (215)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	2
W52	Wall Mounted	0
W53	Vinyl Letters on Door	2
W54	Parapet Letters	0
B95	Loading Dock ID	0


Replace with W53 Vinyl Letters on Door



Add  
W51 Freestanding, Ped



Add  
W53 Vinyl Letters on Door




Add  
W51 Freestanding Bldg ID

Chemical Sciences (414)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	5
W54	Parapet Letters	0
B95	Loading Dock ID	1



Replace with  
W53 Vinyl Letters on Door



Keep existing sign




Keep existing sign  
Add  
B95 Loading Dock Sign



Add  
W53 Vinyl Letters on Door



Add  
W50 Vehicular Bldg ID



Add  
W53 Vinyl Letters on Door



Replace with  
W53 Vinyl Letters on Door




Add  
W53 Vinyl Letters on Door



Keep existing sign




Child Dev Center (396)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Add  
W50 Vehicular Bldg ID



Remove existing sign



Note:  
A Parking Sign (W71) with the bldg name  
has been included in the sign location plan

College Bldg North (231)		College Bldg South (517)		qty
W50	Vehicular Bldg ID			1
W51	Freestanding, Ped			1
W52	Wall Mounted Bldg ID			3
W53	Vinyl Letters on Door			2
W54	Parapet Letters			2
B95	Loading Dock ID			0



Add  
W53 Vinyl Letters on Door




Add  
W53 Vinyl Letters on Door



Replace with W52 Wall Mounted Bldg ID



Replace with W52 Wall Mounted Bldg ID



Replace with  
W50 Vehicular Building ID



Add  
W54 Parapet Letters



Add  
W54 Parapet Letters



Add  
W52 Wall Mounted Bldg ID




Keep existing sign

Computing/Comm. (381)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign  
Add  
W50 Vehicular Bldg ID




Note:  
A Parking Sign (W71)  
with the building name  
has been included in the sign  
location plan



Add  
W53 Vinyl Letters on Door

Corporation Yard A-C (485-487)		qty
W50	Vehicular Bldg ID	2
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Note:  
A Parking Sign (W71)  
with the building name  
has been included on the  
sign location plan.




Add  
W50 Vehicular Bldg ID

Costo Hall (311)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0


Note:  
 Building should be surveyed again  
 once the Commons Expansion  
 is 100% complete.



Keep existing sign




University Cottage (118)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0




Replace with  
W50 Vehicular Bldg ID


Culver Center of the Arts (757)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0



See UC Riverside ArtsBlock Signage Package for Building Identification recommendations.



Custodial & Grounds (507)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Replace with W50 Vehicular Bldg ID



Keep existing sign




Engineering Building Unit 2 (194)		qty
W50	Freestanding, Vehicular	1
W51	Freestanding, Ped	0
W52	Wall Mounted	6
W53	Vinyl Letters on Door	5
W54	Parapet Letters	0
B95	Loading Dock ID	1




Add  
W52 Wall Mounted Building ID  
W53 Vinyl Letters on Door




Add  
W52 Wall Mounted Building ID




Keep existing sign  
Add W53 Vinyl Letters on Door



Add  
W52 Wall Mounted Building ID




Add  
W52 Wall Mounted Building ID  
W53 Vinyl letters on door



Add  
B95 Loading Dock ID




Add  
W52 Wall Mounted Building ID



Add  
W53 Vinyl letters on door



Add  
W52 Wall Mounted Building ID



Keep existing sign  
Add  
W53 Vinyl letters on door

Entomology (417)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	3
W53	Vinyl Letters on Door	3
W54	Parapet Letters	0
B95	Loading Dock ID	1




Add  
W52 Wall Mounted Bldg ID




Add  
B95 Loading Dock ID



Keep existing sign



Keep existing sign



Add  
W52 Wall Mounted Bldg ID  
W53 Vinyl Letters on Door



Add  
W50 Vehicular Bldg ID  
W53 Vinyl Letters on Door



Add  
W52 Wall Mounted Bldg ID



Add  
W53 Vinyl Letters on Door

Entomology Museum (256)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted Bldg ID	1
W53	Vinyl Letters on Door	2
W54	Parapet Letters	0
B95	Loading Dock ID	0


Keep existing sign



Add W53 Vinyl Letters on Door



Add W51 Freestanding Bldg ID



Replace with W52 Wall Mounted Bldg ID




Add W53 Vinyl Letters on Door

Env. Health & Safety (241)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	1
W54	Parapet Letters	1
B95	Loading Dock ID	0

Keep existing sign



Add W54 Parapet Letters



Replace with W53 Vinyl Letters on Door


Fawcett Laboratory (503)		qty
W50	Vehicular Bldg ID	2
W51	Freestanding, Ped	1
W52	Wall Mounted	1
W53	Vinyl Letters on Door	2
W54	Parapet Letters	0
B95	Loading Dock ID	1



Replace with W50 Vehicular Bldg ID





Replace with W52 Wall Mounted Bldg ID  
Add W53 Vinyl Letters on Door



Keep existing sign

Add B95 Loading Dock ID



Add W53 Vinyl Letters on Door



Keep existing sign



Replace with W50 Vehicular Bldg ID

**Geology (335)**

	qty
W50 Vehicular Bldg ID	0
W51 Freestanding, Ped	4
W52 Wall Mounted	3
W53 Vinyl Letters on Door	4
W54 Parapet Letters	0
B95 Loading Dock ID	1




Keep existing sign  
Add W53 Vinyl Letters on Door




Add  
W51 Freestanding Bldg ID



Add  
W51 Freestanding Bldg ID



Keep existing sign




Replace  
W53 Vinyl Letters on Door



Add  
W51 Freestanding Bldg ID

Add  
Loading Dock Info




Replace  
W53 Vinyl Letters on Door




Add  
W52 Wall Mounted Bldg ID



Add  
W52 Wall Mounted Bldg ID  
W51 Freestanding Bldg ID



Add  
W52 Wall Mounted Bldg ID



Replace  
W53 Vinyl Letters on Door

Greenhouses 6-10 (200, & 275-278)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	1
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
W55	Building ID, small	10
B95	Loading Dock ID	0



Add W55 Building ID, small



Add W55 Building ID, small



Add W55 Building ID, small




Add W55 Building ID, small



Add W55 Building ID, small



Add W55 Building ID, small



Replace with W52 Wall Mounted Bldg ID



Add W55 Building ID, small



Add W55 Building ID, small



Add W55 Building ID, small



Add W55 Building ID, small

**Greenhouses 11-14  
(279-281, 481)**

	qty
W50 Vehicular Bldg ID	0
W51 Freestanding, Ped	0
W52 Wall Mounted	0
W53 Vinyl Letters on Door	0
W54 Parapet Letters	0
W55 Building ID, small	11
B95 Loading Dock ID	0



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small




Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small




Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small





Greenhouses 15 - 21 (210, 284, 483, 513-515, & 202)		
		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	4
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
W55	Building ID, small	8
B95	Loading Dock ID	0



Replace with  
W52 Wall Mounted Bldg ID



Replace with  
W55 Building ID, small



Replace with  
W52 Wall Mounted Bldg ID



Replace with  
W52 Wall Mounted Bldg ID



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small




Replace with  
W55 Building ID, small



Replace with  
W55 Building ID, small



Replace with  
W52 Wall Mounted Bldg ID




Headhouse greenhouses 1-3 (378, 259, 374)

	qty
W50 Vehicular Bldg ID	0
W51 Freestanding, Ped	0
W52 Wall Mounted	6
W53 Vinyl Letters on Door	1
W54 Parapet Letters	0
W55 Building ID, small	4
B95 Loading Dock ID	0



Replace with W52 Wall Mounted Bldg ID



Replace with W55 Building ID, small



Replace with W55 Building ID, small





Replace with W55 Building ID, small

Note: A Parking Sign (W71) with the building name is included in the sign location plan

Replace with W52 Wall Mounted Bldg ID



Replace with W52 Wall Mounted Bldg ID



Replace with W52 Building ID, wall mounted



Replace with W52 Building ID, wall mounted



Replace with W53 Vinyl Letters on Door



Replace with W52 Building ID, wall mounted



Add W55 Building ID, small


Health Services Building (495)		qty
W50	Vehicular Bldg ID	2
W51	Freestanding, Ped	0
W52	Wall Mounted	1
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign



Replace with W53 Vinyl Letters on Door



Add W50 Vehicular Bldg ID




Add W52 Wall Mounted Bldg ID

Add W50 Vehicular Building ID

Herbarium (319)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Replace with  
W51 Freestanding Bldg ID



Keep existing sign

Highlander Hall (716)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	3
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	0





Replace with W52 Wall Mounted Bldg ID



Replace with W53 Vinyl Letters on Door



Replace with W52 Wall Mounted Bldg ID



Replace with W52 Wall Mounted Bldg ID

Hinderaker Hall (480)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	0
W53	Vinyl Letters on Door	2
W54	Parapet Letters	0
B95	Loading Dock ID	1
* (2) sets of letters to match existing		



Add  
W53 Vinyl Letters on Door




Keep existing sign



Keep existing sign



Keep existing sign



Note:  
A Parking sign (W72) with the building name is included in the sign location plan.



Keep existing sign  
Add  
B95 Loading Dock ID




Add additional letters to match other existing sign



Add  
W53 Vinyl Letters on Door

Housing Admin (581)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign  
Add  
W50 Vehicular Bldg ID



Add  
W53 Vinyl Letters on Door


Human Resources (788)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign




Replace with W50 Vehicular Bldg ID





Humanities (498)		
		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	1
W53	Vinyl Letters on Door	0
W54	Parapet Letters	2
B95	Loading Dock ID	1



Replace with  
W54 Parapet Letters  
(University Theater)



Add  
B51 Freestanding Bldg ID




Add  
W54 Parapet Letters  
Keep existing sign



Add  
B95 Loading Dock ID

B95  
Add loading dock info




Add  
W52 Wall Mounted Bldg ID

Humanities & Social Sciences (307)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	1
W52	Wall Mounted	10
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Add B52 Wall Mounted Bldg ID




Keep existing sign



Add B52 Wall Mounted Bldg ID




Add B51 Freestanding Bldg ID




Add B52 Wall Mounted Bldg ID



Add B52 Wall Mounted Bldg ID



Add B52 Wall Mounted Bldg ID



Keep existing sign

Add B50 Vehicular Bldg ID




Add B52 Wall Mounted Bldg ID



Keep existing sign




Add B52 Wall Mounted Bldg ID



Add B52 Wall Mounted Bldg ID



Add B52 Wall Mounted Bldg ID





Add B52 Wall Mounted Bldg ID

East Campus Insectary & Quarantine (289)		
		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	1



Add W53 Vinyl Letters on Door



Keep existing sign

International Village (998)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	0


\* Replace wall monument sign with new sign with current brand



Replace with  
New sign to match current brand



Add  
W50 Vehicular Bldg ID




Keep existing sign




Add  
W53 Vinyl Letters on Door

KUCR Radio Station (176)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	1
B95	Loading Dock ID	0



Replace existing sign with  
W50 Vehicular Building ID  
W54 Parapet Letters

Life Sciences (316)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	3
W53	Vinyl Letters on Door	6
W54	Parapet Letters	2
B95	Loading Dock ID	1



Add  
W52 Wall Mounted Bldg ID  
W53 Vinyl Letters on Door



Replace with  
W53 Vinyl Letters on Door



Replace with  
W53 Vinyl Letters on Door




Add  
W53 Vinyl Letters on Sidelight

Add  
B95 Loading Dock ID



Add  
W54 Parapet Letters




Add  
W54 Parapet Letters



Add  
W53 Vinyl Letters on Door



Add  
W52 Wall Mounted Bldg ID



Keep existing sign



Add  
W52 Wall Mounted Bldg ID




Replace with  
W53 Vinyl Letters on Door

Lothian Res. Hall (502)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	1
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Add  
W52 Wall Mounted Bldg ID




Remove Existing sign  
Note: A Parking Sign (W70) with the bldg name is included in the sign location plan

Olmsted Hall (497)		
		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	3
W53	Vinyl Letters on Door	5
W54	Parapet Letters	0
B95	Loading Dock ID	0



Add W53 Vinyl Letters on Door



Keep existing sign



Add W51 Freestanding Bldg ID




Add W52 Wall Mounted Bldg ID



Replace with W53 Vinyl Letters on Door



Add W52 Wall Mounted Bldg ID



Add W53 Vinyl Letters on Door



Keep existing sign



Add W53 Vinyl Letters on Door





Replace with W53 Vinyl Letters on Door



Add W52 Wall Mounted Bldg ID




Parking Services Building (272)		
		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	
W52	Wall Mounted	0
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	0



Replace with W50 Vehicular Bldg ID

Pentland Hills Residence Hall A-Q (365, 369, 636-648)(365)		
		qty
W50	Vehicular Bldg ID	2
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0

No additional signs



Physics (504)

	qty
W50 Vehicular Bldg ID	1
W51 Freestanding, Ped	0
W52 Wall Mounted	7
W53 Vinyl Letters on Door	3
W54 Parapet Letters	0
B95 Loading Dock ID	1




Physics 2000 Lecture Hall(504a)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	4
W53	Vinyl Letters on Door	0
W54	Parapet Letters	1
B95	Loading Dock ID	0





Add  
W52 Wall Mounted Bldg ID



Add  
W52 Wall Mounted Bldg ID



Add  
W51 Freestanding Bldg ID



Add  
W52 Wall Mounted Bldg ID



Add  
W54 Parapet Letters




Add  
W52 Wall Mounted Bldg ID



Phys Ed Bldg (334)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	0
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	0

Building Signage should be reviewed once construction is completed in this area.

Keep existing sign



Keep existing sign



Add B51 Freestanding Bldg ID



Replace

Pierce Hall (508)		
		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	3
W53	Vinyl Letters on Door	3
W54	Parapet Letters	0
B95	Loading Dock ID	1



Add  
W51 Freestanding Bldg ID




Add  
B95 Loading Dock ID




Add  
W52 Wall Mounted Bldg ID



Add  
W52 Wall Mounted Bldg ID



Keep existing sign  
Add  
W53 Vinyl Letters on Door




Add  
W53 Vinyl Letters on Door



Add  
W52 Wall Mounted Bldg ID



Keep existing sign



Add  
W51 Freestanding Bldg ID




Keep existing sign "Pierce Hall"  
Remove "Chemistry"  
Add W53 Vinyl Letters on Door

Police Building (566)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign

Note:  
A Monument Sign for the Campus is included on the sign location plan



Add  
W50 Vehicular Bldg ID



Keep existing sign

Riviera Library (322)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	2
W52	Wall Mounted	2
W53	Vinyl Letters on Door	2
W54	Parapet Letters	0
B95	Loading Dock ID	1




Keep existing sign



Add W51 Freestanding Bldg ID




Add W52 Wall Mounted Bldg ID (ceiling hung)



Replace with B95 Loading Dock ID


Add W51 Freestanding Bldg ID



Add W53 Vinyl Letters on Door



Add W53 Vinyl Letters on Door




Add W52 Wall Mounted Bldg ID




Satellite Chiller Plant (367)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0

No signs proposed



Science Laboratories 1 (416)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	2
W53	Vinyl Letters on Door	5
W54	Parapet Letters	0
B95	Loading Dock ID	0



Science Library (418)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	1
W52	Wall Mounted	4
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	1





Add  
W52 Wall Mounted Bldg ID




Add  
B95 Loading Dock Info



Add  
W52 Wall Mounted Bldg ID



Add  
W52 Wall Mounted Bldg ID  
W53 Vinyl Letters on Door



Keep existing sign

Speith Hall (323)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	5
W53	Vinyl Letters on Door	3
W54	Parapet Letters	0
B95	Loading Dock ID	0



Replace with W53 Vinyl Letters on Door




Keep existing sign




Add W51 Freestanding Bldg ID



Add W52 WallMounted Bldg ID




Keep existing sign




Add W52 WallMounted Bldg ID



Add W52 WallMounted Bldg ID



Replace with W52 WallMounted Bldg ID



Replace with W53 Vinyl Letters on Door




Replace with W53 Vinyl Letters on Door



Add W52 WallMounted Bldg ID

Sproul Hall (523)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	3
W53	Vinyl Letters on Door	4
W54	Parapet Letters	0
B95	Loading Dock ID	1




Keep existing sign  
Add  
W52 Wall Mounted Bldg ID



Keep existing sign



Replace with  
W53 Vinyl Letters on Door




Add  
W51 Freestanding  
Bldg ID



Keep existing sign  
Add  
W52 Wall Mounted Bldg ID



Add  
B95 Loading Dock ID




Add  
W53 Vinyl Letters on Door



Add  
W52 Wall Mounted Bldg ID



Add  
W53 Vinyl Letters on Door



Keep existing sign



Add  
W53 Vinyl Letters on Door

Statistic Computer Building (588)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	1
W52	Wall Mounted	3
W53	Vinyl Letters on Door	3
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign



Add W52 Wall Mounted Bldg ID



Replace with W53 Vinyl Letters on Door



Add W52 Wall Mounted Bldg ID

Add W51 Freestanding Bldg ID

Add W50 Vehicular Bldg ID



Add W53 Vinyl Letters on Door




Add W52 Wall Mounted Bldg ID  
W53 Vinyl Letters on Door


Add B95 Loading Dock ID



Keep existing sign



Stonehaven Apts. (991)		qty
W50	Vehicular Bldg ID	2
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0




Keep existing sign



Replace with W50 Vehicular Bldg ID


Add W50 Vehicular Bldg Sign

Student Rec Center (511)		qty
W50	Vehicle Bldg ID	0
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0






UCR Athletic Complex (285)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	2
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Replace with W50 Vehicular Bldg ID



Note:  
A Parking Sign (W70)  
with the bldg name  
has been included  
in the sign location plan

UCR Extension Center (722)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	1
W54	Parapet Letters	0
B95	Loading Dock ID	0


\* Replace Face of large freestanding sign



Keep existing sign



Keep existing sign



Replace face of sign to match current brand



Keep existing sign



Keep existing sign  
Add  
W53 Vinyl Letters on Door

University Lab Bldg (263)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	2
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



University Lecture Hall (383)		qty
W50	Vehicular Bldg ID	0
W51	Freestanding, Ped	1
W52	Wall Mounted	4
W53	Vinyl Letters on Door	2
W54	Parapet Letters	0
B95	Loading Dock ID	0



Add  
W52 Wall Mounted Bldg ID



Add  
W52 Wall Mounted Bldg ID




Add  
W52 Wall Mounted Bldg ID



Add  
W53 Vinyl Letters on Door




Add  
W52 Wall Mounted Bldg ID  
W53 Vinyl Letters on Door  
W51 Freestanding Bldg ID




University Office Bldg (205)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	1
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Keep existing sign



Keep existing sign  
Add W53 Vinyl Letters on Door




W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0


B95	Loading Dock ID	0
-----	-----------------	---

No Signs Recommended at this Time

Not UCR property - Leased



University Plaza Apts. (715)		qty
W50	Vehicular Bldg ID	1
W51	Freestanding, Ped	0
W52	Wall Mounted	0
W53	Vinyl Letters on Door	0
W54	Parapet Letters	0
B95	Loading Dock ID	0



Replace with W50 Vehicular Bldg ID

**Watkins Hall (354)**

	qty
W50 Vehicular Bldg ID	0
W51 Freestanding, Ped	2
W52 Wall Mounted	6
W53 Vinyl Letters on Door	4
W54 Parapet Letters	0
B95 Loading Dock ID	0



Possible Banner Location



Add W52 Wall Mounted Bldg ID



Possible Banner Location




Add W52 Wall Mounted Bldg ID





Add W51 Freestanding Bldg ID



Replace with W53 Vinyl Letters on Door



Add W52 Wall Mounted Bldg ID



Add W51 Freestanding Bldg ID



Keep existing parapet sign  
Add W52 Wall Mounted Bldg




Add W52 Wall Mounted Bldg ID




Keep existing sign




Replace with W53 Vinyl Letters on Door



Replace with W53 Vinyl Letters on Door



Add W52 Wall Mounted Bldg ID



Replace with W53 Vinyl Letters on Door





